

Doddridge County Sheriff  
Flood Plain Ordinance Fund

1030  
69-217/515

DATE August 8, 2013

PAY TO THE ORDER OF ANTERO \$ 941.75

Nine Hundred Fourty-One Dollars and 75/100----- DOLLARS

Security features included. Details on back.



West Union, WV 26456

*Rachel Sanderson*  
*Beth A. Rogers*

*MP*

MEMO #13-038 Reimburse Bldg Permit  
Re-Submit NM Compress

⑈001030⑈ ⑈051502175⑈ ⑈119649⑈9⑈


BLUE TRADITIONAL

U.S. Postal Service  
**CERTIFIED MAIL™ RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at www.usps.com

**OFFICIAL USE**

Postage	\$ .46
Certified Fee	3.10
Return Receipt Fee (Endorsement Required)	2.55
Restricted Delivery Fee (Endorsement Required)	
<b>Total Postage &amp; Fees</b>	<b>\$ 6.11</b>



Sent To Denver Cox  
Street, Apt. No., or PO Box No. 2753 Smithton Rd  
City, State, ZIP+4 Smithburg, WV 26436

PS Form 3800, August 2006 See Reverse for Instructions

U.S. Postal Service  
**CERTIFIED MAIL™ RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at www.usps.com

**OFFICIAL USE**

Postage	\$ 0.46	0522
Certified Fee	3.10	04
Return Receipt Fee (Endorsement Required)	2.55	Postmark Here
Restricted Delivery Fee (Endorsement Required)	\$0.00	
<b>Total Postage &amp; Fees</b>	<b>\$ 6.11</b>	07/19/2013

Sent To Louis R. Enlow  
Street, Apt. No., or PO Box No. 191 Saddletree Dr.  
City, State, ZIP+4 Kala Point, Port Townsend, WA 98368


PS Form 3800, August 2006 See Reverse for Instructions

U.S. Postal Service  
**CERTIFIED MAIL™ RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at www.usps.com

**OFFICIAL USE**

Postage	\$ .46
Certified Fee	3.10
Return Receipt Fee (Endorsement Required)	2.55
Restricted Delivery Fee (Endorsement Required)	
<b>Total Postage &amp; Fees</b>	<b>\$ 6.11</b>



Sent To Robert C. Taylor  
Street, Apt. No., or PO Box No. 7289 WV Rt. 18 S  
City, State, ZIP+4 New Milton, WV 26411

PS Form 3800, August 2006 See Reverse for Instructions

7012 1010 0001 4282 8126

7012 1010 0001 4282 8126

7012 1010 0001 4282 8126

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

## 1. Article Addressed to:

Louis R. Enlow  
 191 Saddletree Dr.  
 Kala Point, Port Townsend, WA  
 98368

## 2. Article Number

(Transfer from service label)

7012 1010 0001 4282 8133

**COMPLETE THIS SECTION ON DELIVERY**

## A. Signature


 Agent Addressee

## B. Received by (Printed Name)



## C. Date of Delivery

D. Is delivery address different from item 1?  YesIf YES, enter delivery address below:  No

## 3. Service Type

 Certified Mail Express Mail Registered Return Receipt for Merchandise Insured Mail C.O.D.

## 4. Restricted Delivery? (Extra Fee)

 Yes

UNITED STATES POSTAL SERVICE



First-Class Mail  
Postage & Fees Paid  
USPS  
Permit No. G-10

• Sender: Please print your name, address, and ZIP+4 in this box •

BETH A. ROGERS  
DODDRIDGE COUNTY CLERK  
118 E. COURT ST., RM 102  
WEST UNION, WV 26456

56129799



**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

## 1. Article Addressed to:

Robert C. Taylor  
7289 WV Rt. 18 S  
New Milton, WV 26411

## 2. Article Number

(Transfer from service label)

7012 1010 0001 4282 8126

**COMPLETE THIS SECTION ON DELIVERY**

## A. Signature

*Danna R. McCook*

 Agent Addressee

## B. Received by (Printed Name)

*Danna R. McCook*

## C. Date of Delivery

*7-20-13*

D. Is delivery address different from item 1?  Yes

If YES, enter delivery address below:

 No

## 3. Service Type

 Certified Mail Express Mail Registered Return Receipt for Merchandise Insured Mail C.O.D.

## 4. Restricted Delivery? (Extra Fee)

 Yes




UNITED STATES POSTAL SERVICE



First-Class Mail  
Postage & Fees Paid  
USPS  
Permit No. G-10

• Sender: Please print your name, address, and ZIP+4 in this box •



BETH A. ROGERS  
DODDRIDGE COUNTY CLERK  
118 E. COURT ST., RM 102  
WEST UNION, WV 26456



**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

## 1. Article Addressed to:

Denver Cox  
 2753 Smithton Rd  
 Smithburg, WV 26436

## 2. Article Number

(Transfer from service label)

7012 1010 0001 4282 8119

**COMPLETE THIS SECTION ON DELIVERY**

## A. Signature


 Agent Addressee

## B. Received by (Printed Name)

Denver Cox

## C. Date of Delivery

7-20-13

D. Is delivery address different from item 1?  YesIf YES, enter delivery address below:  No

## 3. Service Type

 Certified Mail Express Mail Registered Return Receipt for Merchandise Insured Mail C.O.D.

## 4. Restricted Delivery? (Extra Fee)

 Yes

UNITED STATES POSTAL SERVICE



First-Class Mail  
Postage & Fees Paid  
USPS  
Permit No. G-10

• Sender: Please print your name, address, and ZIP+4 in this box •

BETH A. ROGERS  
DODDRIDGE COUNTY CLERK  
118 E. COURT ST., RM 102  
WEST UNION, WV 26456



By: BH - MEH - AML  
Asst. Chief Tax Deputy

W. C .Underwood Jr.  
Sheriff of Doddridge County

The Person paying Money into the Treasury shall forthwith file one of these Receipts with the County Clerk

## Doddridge County, West Virginia

No. 113

Date: July 19, 2013

\*\*\*Customer copy\*\*\*

Received: #13-038 ANTERO NEW MILTON COMPRESSOR STATION \$2,938.25

In Payment For: 318 Building Permits (LP)

For: 12-Flood Plain Ordinance #20 Fund

By: BH - MEH - AML  
Asst. Chief Tax Deputy

W. C .Underwood Jr.  
Sheriff of Doddridge County



**ANTERO RESOURCES CORPORATION**  
1625 17th STREET, SUITE 300  
DENVER, COLORADO 80202

Vendor Name	Vendor No.	Date	Check Number	Check Total
DODDRIDGE COUNTY CLERK	45582	Jul-17-2013	33814	\$2,938.25

VOUCHER	VENDOR INV #	INV DATE	TOTAL AMOUNT	PRIOR PMTS & DISCOUNTS	NET AMOUNT
07-AP-7334	COMPRESSORST	07/17/13	2,938.25	0.00	2,938.25
FLOOD PLAIN PERMIT - NEW MILTON COMPRESSOR STATION					
TOTAL INVOICES PAID					2,938.25

DETACH AND RETAIN FOR TAX PURPOSES

**Doddridge County Flood Plain Application Fee Calculator (if in Flood Plain)****New Milton Compressor Station**

Estimated Construction Costs	\$287,650.00
Amount over \$100,000	\$187,650.00
Drilling Oil and Gas Well Fee	\$1,000.00
Deposit for additional charges	\$1,000.00
\$5 per \$1,000 over \$100,000	\$938.25
Amount Due with application	\$2,938.25

Legal Advertisement:  
Doddridge County  
Floodplain Permit Application

Please take notice that on the 19<sup>th</sup> day of July, 2013

**ANTERO RESOURCES APPALACHIAN CORP**, re-filed an  
application for a Floodplain Permit to develop land re- located at or  
about: **Kathryn H. Marshall, Clinton D & Kevin Means, Marvin L. Phillips, Ruth  
E. Phillips, William C. Phillips, and Laverne AH. Williams, Surface Owners, 147.86 acres,  
New Milton District, Tax Map 8, Parcel 37.**

The Application is on file with the Clerk of the County Court and  
may be inspected or copied during regular business hours.

Any interested persons who desire to comment shall present  
the same in writing by **August 8, 2013.**

Delivered to the:  
Clerk of the County Court  
118 E. Court Street, West Union, WV 26456.

Beth A Rogers, Doddridge County Clerk  
Dan Wellings, Doddridge County Flood Plain Manager

\*\*\*\*\*  
\* P. 01 \*  
\* TRANSACTION REPORT \*  
\* JUL-19-2013 FRI 04:06 PM \*  
\* FOR: DODDRIDGE CO. CLERK 304 873 1840 \*  
\* SEND \*  
\* DATE START RECEIVER TX TIME PAGES TYPE NOTE M# DP \*  
\* JUL-19 04:05 PM 93048731600 39" 2 FAX TX OK 521 \*  
\* TOTAL : 39S PAGES: 2 \*  
\*\*\*\*\*

Legal Advertisement:

Doddridge County

Floodplain Permit Application

Please take notice that on the 19<sup>th</sup> day of July, 2013

**ANTERO RESOURCES APPALACHIAN CORP**, re-filed an

application for a Floodplain Permit to develop land re- located at or

about: Kathryn H. Marshall, Clinton D & Kevin Means, Marvin L. Phillips, Ruth  
E. Phillips, William C. Phillips, and Laverne AH. Williams, Surface Owners, 147.86 acres,

**New Milton District, Tax Map 8, Parcel 37.**

The Application is on file with the Clerk of the County Court and  
may be inspected or copied during regular business hours.

Any interested persons who desire to comment shall present  
the same in writing by **August 8, 2013.**

Delivered to the:

Clerk of the County Court

118 E. Court Street, West Union, WV 26456.

Beth A Rogers, Doddridge County Clerk

Dan Wellings, Doddridge County Flood Plain Manager





PERMIT NO. 13-038

**DODDRIDGE COUNTY**  
**FLOODPLAIN DEVELOPMENT**  
**PERMIT**

PURPOSE FOR PERMIT: BRIDGE CROSSING

ISSUED TO ANTERO

ADDRESS: 1625 17TH STREET  
Denver, CO. 80202

PROJECT ADDRESS: TOM'S FORK, RT. 18  
ACROSS FROM MEANS HOLLOW

ISSUED BY: Dan Wellings

DATE: 08/09/2013

THIS PERMIT MUST BE POSTED ON THE PREMISES IN A CONSPICUOUS PLACE SO AS TO BE CLEARLY  
VISIBLE FROM THE STREET.



July 17, 2013

Antero Resources  
1625 17th Street  
Denver, Colorado 80202  
Office 303.357.7310  
Fax 303.357.7315

Doddridge County Commission  
Attn: Dan Wellings, Doddridge County Floodplain Manager  
118 East Court Street, Room 102  
West Union, WV 26456

Mr. Wellings:

Please find enclosed revisions to supplement the original New Milton Compressor Station Floodplain permit package which was submitted to your office on June 27<sup>th</sup>, 2013. This project is located in Doddridge County, New Milton District and Antero Resources Corporation (Antero) is submitting two options for the New Milton Compressor Station Access Road stream crossing.

Attached you will find the following:

- Doddridge County Floodplain Permit Application
- Two Floodplain Study Reports for the Access Road Stream Crossing. (One report for the dual culvert option and one report for the 60' span bridge option).
- Two Stream Crossing Reports for both crossing options
- A detailed set of plans signed by a WV licensed professional engineer
- Revised FIRM Map

If you have any questions please feel free to contact me at (303) 357-6820.

Thank you in advance for your consideration.

Sincerely,

Shauna Redican  
Permit Representative  
Antero Resources Corporation

Enclosures

2013 JUL 18 AM 9:18  
DODDRIDGE COUNTY, WV  
FILED

FILED

**DODDRIDGE COUNTY**

2013 JUL 18 AM 9:18


**FLOODPLAIN DEVELOPMENT PERMIT APPLICATION**

CLERK  
COUNTY CLERK  
DODDRIDGE COUNTY, WV

**SECTION 1: GENERAL PROVISIONS (APPLICANT TO READ AND SIGN)**

1. No work may start until a permit is issued.
2. The permit may be revoked if any false statements are made herein.
3. If revoked, all work must cease until permit is re-issued.
4. Development shall not be used or occupied until a Certificate of Compliance is issued.
5. The permit will expire if no work is commenced within six months of issuance.
6. Applicant is hereby informed that other permits may be required to fulfill local, state, and federal requirements.
7. Applicant hereby gives consent to the Floodplain Administrator/Manager or his/her representative to make inspections to verify compliance.
8. **I, THE APPLICANT CERTIFY THAT ALL STATEMENTS HEREIN AND IN ATTACHMENTS TO THIS APPLICATION ARE, TO THE BEST OF MY KNOWLEDGE, TRUE AND ACCURATE.**

APPLICANT'S SIGNATURE



DATE July 17th, 2013

**SECTION 2: PROPOSE DEVELOPMENT (TO BE COMPLETED BY APPLICANT).**

**IF THE APPLICANT IS NOT A NATURAL PERSON, THE NAME, ADDRESS, AND TELEPHONE NUMBER OF A NATURAL PERSON WHO SHALL BE APPOINTED BY THE APPLICANT TO RECEIVE NOTICE PURSUANT TO ANY PROVISION OF THE CURRENT DODDRIDGE COUNTY FLOODPLAIN ORDINANCE.**

Antero Resources Appalachian Corporation - Shauna Redican, Permit Representative

**APPLICANT'S NAME:**

**ADDRESS:** 1625 17th Street, Denver, CO 80202

**TELEPHONE NUMBER:** Contact Shauna Redican: 303-357-6820

**BUILDER'S NAME:** Antero Resources Corporation  
**ADDRESS:** 1625 17th Street, Denver, CO 80202  
**TELEPHONE NUMBER:** (303) 357-7310

**ENGINEER'S NAME:** Navitus Engineering - Cyrus S, Kump  
**ADDRESS:** 151 Windy Hill Lane, Winchester, VA 22602  
**TELEPHONE NUMBER:** 888-662-1485

**PROJECT LOCATION:**

**NAME OF SURFACE OWNER/OWNERS (IF NOT THE APPLICANT)**  
PLEASE SEE ATTACHED EXHIBIT A

**ADDRESS OF SURFACE OWNER/OWNERS (IF NOT THE APPLICANT)**  
PLEASE SEE ATTACHED EXHIBIT A

**DISTRICT:** New Milton

**DATE/FROM WHOM PROPERTY PURCHASED:** N/A

**LAND BOOK DESCRIPTION:** PLEASE SEE ATTACHED EXHIBIT A

**DEED BOOK REFERENCE:** PLEASE SEE ATTACHED EXHIBIT A

**TAX MAP REFERENCE:** PLEASE SEE ATTACHED EXHIBIT A

**EXISTING BUILDINGS/USES OF PROPERTY:** N/A

**NAME OF AT LEAST ONE ADULT RESIDING IN EACH RESIDENCE LOCATED UPON THE SUBJECT PROPERTY** N/A

**ADDRESS OF AT LEAST ONE ADULT RESIDING IN EACH RESIDENCE LOCATED UPON THE SUBJECT PROPERTY** N/A

To avoid delay in processing the application, please provide enough information to easily identify the project location.

**DESCRIPTION OF WORK (CHECK ALL APPLICABLE BOXES)**

**A. STRUCTURAL DEVELOPMENT**

**ACTIVITY**

**STRUCTURAL TYPE**

- |                                     |                         |                          |                                  |
|-------------------------------------|-------------------------|--------------------------|----------------------------------|
| <input checked="" type="checkbox"/> | New Structure           | <input type="checkbox"/> | Residential (1 – 4 Family)       |
| <input type="checkbox"/>            | Addition                | <input type="checkbox"/> | Residential (more than 4 Family) |
| <input type="checkbox"/>            | Alteration              | <input type="checkbox"/> | Non-residential (floodproofing)  |
| <input type="checkbox"/>            | Relocation              | <input type="checkbox"/> | Combined Use (res. & com.)       |
| <input type="checkbox"/>            | Demolition              | <input type="checkbox"/> | Replacement                      |
| <input type="checkbox"/>            | Manufactured/Mobil Home |                          |                                  |

**B. OTHER DEVELOPMENT ACTIVITIES:**

- |                                     |   |                          |        |                          |          |                                     |            |
|-------------------------------------|---|--------------------------|--------|--------------------------|----------|-------------------------------------|------------|
| <input type="checkbox"/>            | Fill  | <input type="checkbox"/> | Mining | <input type="checkbox"/> | Drilling | <input checked="" type="checkbox"/> | Pipelining |
| <input checked="" type="checkbox"/> | Grading   |                          |        |                          |          |                                     |            |
| <input type="checkbox"/>            | Excavation (except for STRUCTURAL DEVELOPMENT checked above)          |                          |        |                          |          |                                     |            |
| <input type="checkbox"/>            | Watercourse Altercation (including dredging and channel modification) |                          |        |                          |          |                                     |            |
| <input type="checkbox"/>            | Drainage Improvements (including culvert work)                        |                          |        |                          |          |                                     |            |
| <input checked="" type="checkbox"/> | Road, Street, or Bridge Construction                                  |                          |        |                          |          |                                     |            |
| <input type="checkbox"/>            | Subdivision (including new expansion)                                 |                          |        |                          |          |                                     |            |
| <input type="checkbox"/>            | Individual Water or Sewer System                                      |                          |        |                          |          |                                     |            |
| <input type="checkbox"/>            | Other (please specify)  |                          |        |                          |          |                                     |            |
- 

**C. STANDARD SITE PLAN OR SKETCH**

- 1. SUBMIT ALL STANDARD SITE PLANS, IF ANY HAVE BEEN PREPARED.**
- 2. IF STANDARD SITE PLANS HAVE NOT BEEN PREPARED:**  
SKETCH ON A SEPARATE 8 ½ X 11 INCH SHEET OF PAPER THE SHAPE AND LOCATION OF THE LOT. SHOW THE LOCATION OF THE INTENDED CONSTRUCTION OR LAND USE INDICATING BUILDING SETBACKS, SIZE & HEIGHT. IDENTIFY EXISTING BUILDINGS, STRUCTURES OR LAND USES ON THE PROPERTY.
- 3. SIGN AND DATE THE SKETCH.**

**ACTUAL TOTAL CONSTRUCTION COSTS OF THE COMPLETE DEVELOPMENT IRRESPECTIVE OF WHETHER ALL OR ANY PART OF THE SUBJECT PROPOSED CONSTRUCTION PROJECT IS WITHIN THE FLOODPLAIN \$ 287,650.00**

**D. ADJACENT AND/OR AFFECTED LANDOWNERS:**

**1. NAME AND ADDRESS OF ALL OWNERS OF SURFACE TRACTS ADJACENT TO THE AREA OF THE SURFACE TRACT (UP & DOWN STREAM) UPON WHICH THE PROPOSED ACTIVITY WILL OCCUR AND ALL OTHER SURFACE OWNERS UP & DOWN STREAM) WHO OWN PROPERTY THAT MAY BE AFFECTED BY FLOODING AS IS DEMONSTRATED BY A FLOODPLAIN STUDY OR SURVEY (IF ONE HAS BEEN COMPLETED).**

**NAME:** Sandra McKinney  
**ADDRESS:** Rt 1 Box 229  
New Milton, WV 26411

**NAME:** John McClain  
**ADDRESS:** HC 67 Box 125  
West Union, WV 26456

**NAME:** Joey McKinney  
**ADDRESS:** 1635 Meathouse Fork Road  
New Milton, WV 26411

**NAME:** Charles James  
**ADDRESS:** PO Box 81  
New Milton, WV 26411  
Timothy R Crislip  
Rt 1 Box 228  
New Milton, WV 26411

**1. NAME AND ADDRESS OF AT LEAST ONE ADULT RESIDING IN EACH RESIDENCE LOCATED UPON ANY ADJACENT PROPERTY AT THE TIME THE FLOODPLAIN PERMIT APPLICATION IS FILED AND THE NAME AND ADDRESS OF AT LEAST ONE ADULT RESIDING IN ANY HOME ON ANY PROPERTY THAT MAY BE AFFECTED BY FLOODING AS IS DEMONSTRATED BY A FLOODPLAIN STUDY OR SURVEY.**

**NAME:** Sandra McKinney  
**ADDRESS:** Rt 1 Box 229  
New Milton, WV 26411

**NAME:** John McClain  
**ADDRESS:** HC 67 Box 125  
West Union, WV 26456

**NAME:** Joey McKinney  
**ADDRESS:** 1635 Meathouse Fork Road  
New Milton, WV 26411

**NAME:** Charles James  
**ADDRESS:** PO Box 81  
New Milton, WV 26411


Timothy R Crislip  
Rt 1 Box 228  
New Milton, WV 26411

**E. CONFIRMATION FORM**

**THE APPLICANT ACKNOWLEDGES, AGREES, AND CONFIRMS THAT HE/IT WILL PAY WITHIN 30 DAYS OF RECEIPT OF INVOICE BY THE COUNTY FOR ALL EXPENSES RELATIVE TO THE PERMIT APPLICATION PROCESS GREATER THAN THE REQUIRED DEPOSIT FOR EXPENSES INCLUDING:**

- (A) PERSONAL SERVICE OF PROCESS BY THE DODDRIDGE COUNTY SHERIFF AT THE RATES PERMITTED BY LAW FOR SUCH SERVICE.
- (B) SERVICE BY CERTIFIED MAIL RETURN RECEIPT REQUESTED.
- (C) PUBLICATION.

- (D) COURT REPORTING SERVICES AT ANY HEARINGS REQUESTED BY THE APPLICANT.
- (E) CONSULTANTS AND/OR HEARING EXPERTS UTILIZED BY DODDRIDGE COUNTY FLOODPLAIN ADMINISTRATOR/MANAGER OR FLOODPLAIN APPEALS BOARD FOR REVIEW OF MATERIALS AND/OR TESTIMONY REGARDING THE EFFICACY OF GRANTING OR DENYING THE APPLICANT'S FLOODPLAIN PERMIT.

NAME (PRINT): Shauna Redican  
 SIGNATURE:  DATE: 7/17/13

After completing SECTION 2, APPLICANT should submit form to Floodplain Administrator/Manager or his/her representative for review.

**SECTION 3: FLOODPLAIN DETERMINATION (to be completed by Floodplain Administrator/Manager or his/her representative)**

**THE PROPOSED DEVELOPMENT:**

THE PROPOSED DEVELOPMENT IS LOCATED ON:

FIRM Panel: Panel 0220C, 0235C  
 Dated: Oct 4, 2011

Is **NOT** located in a Specific Flood Hazard Area (Notify applicant that the application review is complete and **NO FLOODPLAIN DEVELOPMENT PERMIT IS REQUIRED**).

Is located in Special Flood Hazard Area.  
 FIRM zone designation \_\_\_\_\_  
 100-Year flood elevation is: \_\_\_\_\_ NGVD (MSL)

Unavailable

The proposed development is located in a floodway.  
 FBFM Panel No. \_\_\_\_\_ Dated \_\_\_\_\_

See section 4 for additional instructions.



SIGNED *Dan Drilling*

DATE 08/09/2003

**SECTION 4: ADDITIONAL INFORMATION REQUIRED (To be completed by Floodplain Administrator/Manager or his/her representative)**

The applicant must submit the documents checked below before the application can be processed.

- A plan showing the location of all existing structures, water bodies, adjacent roads, lot dimensions and proposed development.
- Development plans, drawn to scale, and specifications, including where applicable: details for anchoring structures, storage tanks, proposed elevation of lowest floor, (including basement or crawl space), types of water resistant materials used below the first floor, details of flood proffing of utilities located below the first floor and details of enclosures below the first floor. Also \_\_\_\_\_
- Subdivision or other development plans (If the subdivision or development exceeds 50 lots or 5 acres, whichever is the lesser, the applicant must provide 100-year flood elevations if they are not otherwise available).
- Plans showing the extent of watercourse relocation and/or landform alterations.
- Top of new fill elevation \_\_\_\_\_ Ft. NGVD (MSL).  
For floodproofing structures applicant must attach certification from registered engineer or architect.
- Certification from a registered engineer that the proposed activity in a regulatory floodway will not result in any increase in the height of the 100-year flood. A copy of all data and calculations supporting this finding must also be submitted.
- Manufactured homes located in a floodplain area must have a West Virginia Contractor's License and a Manufactured Home Installation License as required by the Federal Emergency Management Agency (FEMA).

Other:

---

---

---

**SECTION 5: PERMIT DETERMINATION (To be completed by Floodplain Administrator/Manager or his/her representative)**

I have determined that the proposed activity (**type is or is not**) in conformance with provisions of the Floodplain Ordinance adopted by the County Commission of Doddridge County on May 21, 2013. The permit is issued subject to the conditions attached to and made part of this permit.

SIGNED \_\_\_\_\_ DATE \_\_\_\_\_

If the Floodplain Administrator/Manager found that the above was not in conformance with the provisions of the Doddridge County Floodplain Ordinance and/or denied that application, the applicant may complete an appealing process below.

APPEALS:   Appealed to the County Commission of Doddridge County?  Yes  No  
Hearing Date: \_\_\_\_\_  
County Commission Decision - Approved    Yes    No

CONDITIONS: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**SECTION 6: AS-BUILT ELEVATIONS (To be submitted by APPLICANT before Certificate of Compliance is issued).**

The following information must be provided for project structures. This section must be completed by a registered professional engineer or a licensed land surveyor (or attach a certification to this application).

COMPLETE 1 OR 2 BELOW:

- 1 Actual (As-Built) Elevation of the top of the lowest floor (including basement or crawl space is \_\_\_\_\_ FT. NGVD (MSL)
- 2 Actual (As Built) elevation of floodproofing is \_\_\_\_\_ FT. NGVD (MSL)

**Note:** Any work performed prior to submittal of the above information is at risk of the applicant.

**SECTION 7: COMPLIANCE ACTION (To be completed by the Floodplain Administrator/Manager or his/her representative).**

The Floodplain Administrator/Manager or his/her representative will complete this section as applicable based on inspection of the project to ensure compliance with the Doddridge County Floodplain Ordinance.

**INSPECTIONS:**

DATE: 12/04/13 BY: Dan Melton  
DEFICIENCIES? Y/N

COMMENTS Bridge in reclamation remaining  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**SECTION 8: CERTIFICATE OF COMPLIANCE (To be completed by Floodplain Administrator/Manager or his/her representative).**

Certificate of Compliance issued: DATE: \_\_\_\_\_ BY: \_\_\_\_\_

**CERTIFICATE OF COMPLIANCE  
FOR DEVELOPMENT IN SPECIAL FLOOD HAZARD AREA  
(OWNER MUST RETAIN)**

**PERMIT NUMBER:** \_\_\_\_\_

**PERMIT DATE:** \_\_\_\_\_

**PURPOSE –**

**CONSTRUCTION LOCATION:** \_\_\_\_\_

**OWNER'S ADDRESS:** \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**THE FOLLOWING MUST BE COMPLETED BY THE FLOODPLAIN  
ADMINISTRATOR/MANAGER OR HIS/HER AGENT.**

**COMPLIANCE IS HEREBY CERTIFIED WITH THE REQUIREMENT OF THE  
FLOODPLAIN ORDINANCE ADOPTED BY THE COUNTY COMMISSION OF  
DODDRIDGE COUNTY ON MAY 21, 2013.**

**SIGNED** \_\_\_\_\_ **DATE** \_\_\_\_\_

**ANTERO RESOURCES CORPORATION**  
**SCHEDULE OF QUANTITIES**  
**NEW MILTON**  
**COMPRESSOR STATION ACCESS ROAD**

**CLEARING & GRUBBING; EROSION & SEDIMENT CONTROLS**

	QUANTITY	UNIT	UNIT COST	COST
MOBILIZATION	1.0	EA	\$19,257.00	\$19,257.00
CONSTRUCTION ENTRANCE	1.0	EA	\$3,170.00	\$3,170.00
CLEARING & GRUBBING	0.9	AC	\$3,688.00	\$3,392.96
TREE REMOVAL	0.4	AC	\$4,460.00	\$1,962.40
12" COMPOST FILTER SOCK DIVERSION	41.0	LF	\$4.00	\$164.00
SUPER SILT FENCE	186.2	LF	\$9.00	\$1,675.80
<b>TOTAL</b>				<b>\$29,622.16</b>

**SITE**

	QUANTITY	UNIT	UNIT COST	COST
ACCESS ROADS EXCAVATION	15.8	CY	\$5.00	\$79.00
TOPSOIL	328.3	CY	\$4.00	\$1,313.20
<b>TOTAL</b>				<b>\$1,392.20</b>

**AGGREGATE SURFACING - SPREADING, COMPACTION, and/or INSTALLATION**

	QUANTITY	UNIT	UNIT COST	COST
ACCESS ROADS 6" OR 4" MINUS CRUSHER RUN AGGREGATE (8" THICK)	493.8	TON	\$3.00	\$1,481.40
ACCESS ROAD 1 1/2" OR 3/4" CRUSHER RUN STONE (2" THICK)	123.6	TON	\$3.00	\$370.80
ACCESS ROADS GEOTEXTILE FABRIC (US 200)	1480.7	SY	\$1.00	\$1,480.70
<b>TOTAL</b>				<b>\$3,332.90</b>

**ROAD CULVERTS**

	QUANTITY	UNIT	UNIT COST	COST
35' 10" x 11' 4" Contech Bridgecor #25A5 Arch Culvert	80.0	LF	\$1,000.00	\$80,000.00
GABION BASKET	100.0	EA	\$170.00	\$17,000.00
<b>TOTAL</b>				<b>\$97,000.00</b>

**SEEDING**

	QUANTITY	UNIT	UNIT COST	COST
SITE SEEDING (LIME, FERTILIZER, SEEDING, AND HYDRO-MULCH w/TACK (HYC-2 OR EQUAL))	0.6	AC	\$3,136.00	\$1,944.32
<b>TOTAL</b>				<b>\$1,944.32</b>

**UNFORESEEN SITE CONDITIONS**

	QUANTITY	UNIT	UNIT COST	COST
*ROCK CLAUSE - BLASTING		CY		\$0.00
*ROCK CLAUSE - HOE RAMMING		CY		\$0.00
*FRENCH DRAINS		FT		\$0.00
*PHASE 1 FENCING - STEEL CORRUGATED PANELS w/"T" POST (10 FT CENTERS) - WETLAND PROTECTION		LF		\$0.00
*PHASE 2 FENCING - SILT FENCE AND OR FILTER SOCK OUTSIDE OF PHASE 3 FENCING - WETLAND PROTECTION		LF		\$0.00
*PHASE 3 FENCING - ORANGE SAFETY FENCE w/"T" POST (10FT CENTERS) - WETLAND PROTECTION		LF		\$0.00
*SILT FENCE		LF		\$0.00
*TEMPORARY SEEDING		AC		\$0.00
*CONSTRUCTION STAKEOUT		HOUR		\$0.00
GUARD RAIL	240.0	LF	\$12.00	\$2,880.00
* JUTE MATTING - SLOPE MATTING	739.3	SY	\$2.00	\$1,478.60
<b>TOTAL</b>				<b>\$4,358.60</b>

**GRAND TOTAL + Estimated 150,000 for Bridge \$287,650.18**

Antero


13-038



Rt. 18 South  
near Mean's Hollow

12/04/2013

W.J. W



July 16, 2013

Doddridge County Commission  
118 East Court Street  
West Union, WV 26456

Attn: Dan Wellings, Doddridge County Floodplain Administrator

Re: New Milton Compressor Station Access Road ~~Bridge~~ Stream Crossing - Floodplain Analysis

Dear Mr. Wellings:

Navitus Engineering has completed a floodplain analysis of the proposed New Milton Compressor Station Access Road stream crossing over Toms Fork located south of West Union, along State Route 18 in Doddridge County, West Virginia. This site is located within a FEMA Flood Zone "AE", as shown on the Flood Insurance Rate Map (FIRM) from the National Flood Insurance Program (NFIP), Map Number 54017C0230C dated October 4, 2011. Being that the site is located in a Flood Zone "AE", base flood elevations for this area have been established and detailed study information was found in the Flood Insurance Study for Doddridge County, dated October 4, 2011.

In order to establish base flood elevations for this site, a hydrologic and hydraulic analysis was performed as outlined in the current Doddridge County Floodplain Ordinance, enacted May 21st, 2013. Using field shot data, 10-foot interval topography converted from 3 meter West Virginia GIS Technical Center DEM data, and information taken from USGS 7.5 Minute Series Topographic Maps, a drainage analysis was performed for the Toms Fork drainage shed. Upon establishing the peak flow drainage calculations for the 100-year storm event, a HEC-RAS river analysis was conducted for a section of Toms Fork adjacent to the New Milton Compressor Station Access Road and Base Flood Elevations (BFE) were established. The established BFEs were compared to those found in the Flood Insurance Study as shown on the Summary of Computed Elevations found in the attached report. The established BFEs were similar to the BFEs found in the Flood Insurance Study, with the greatest difference in elevation being approximately 0.7'. The resulting BFEs were used to establish adjusted floodplain boundaries for the segment of Toms Fork being studied. These boundaries are shown on the attached Existing Conditions Plan. In addition to establishing BFEs, a proposed conditions analysis was performed to determine the impacts of the proposed entrance road and stream crossing over Toms Fork. The proposed grading and bridge were added into the cross sections and the manning's "n" values were adjusted where necessary. The model was run with these changes to determine the impacts of the proposed access road and bridge. The results of this analysis indicate that the proposed improvement will cause a maximum increase of 0.3' in the BFEs in this area and no upstream or downstream properties will be adversely impacted. The maximum increase in the BFE occurs at River Stations 17+26.403 and 18+11.557. The cross section at River Station 17+26.403 has an existing BFE of 831.4 and a proposed BFE of 831.7 and the cross section at River Station 18+11.557 has an existing BFE of 831.7 and a proposed BFE of 832.0. The New Milton Compressor Station Access Road Site

Engineering Dedicated to the Development and Transmission of Energy  
Serving PA-WV-OH-NY  
Engineering Surveying Environmental GIS  
www.navituseng.com

Plan (attached) contains a FEMA FIRM Map exhibit showing the proposed access road site overlaid on the FIRM Map. This map contains approximate property lines and owner information.

Attached are the following documents associated with this submission:

- A Floodplain Analysis of Toms Fork documenting the methods used for the analysis, drainage computations, cross sections, and a narrative to describe the analysis. Included with this analysis are exhibits that identify the existing and proposed 100-year floodplain.
- The New Milton Compressor Station Access Road Site Plan, prepared by Navitus Engineering, Inc. which includes additional site design and construction specifications.
- Project Cost Estimate
- Floodplain Permit Application Fee
- Doddridge County Improvement Location Permit Application

Should any questions or comments arise during the review, please let us know and we will work to address them. Copies of all permits required for this site will be provided by the operator. Please let me know if you should need additional information. You can reach me by phone (540) 336-9486 or email: [dmurphy@navituseng.com](mailto:dmurphy@navituseng.com).

Sincerely,  
Navitus Engineering, Inc.



Daniel E. Murphy, CFM





July 16, 2013

Doddridge County Commission  
118 East Court Street  
West Union, WV 26456

Attn: Dan Wellings, Doddridge County Floodplain Administrator

Re: New Milton Compressor Station Access Road Culvert Stream Crossing - Floodplain Analysis

Dear Mr. Wellings:

Navitus Engineering has completed a floodplain analysis of the proposed New Milton Compressor Station Access Road stream crossing over Toms Fork located south of West Union, along State Route 18 in Doddridge County, West Virginia. This site is located within a FEMA Flood Zone "AE", as shown on the Flood Insurance Rate Map (FIRM) from the National Flood Insurance Program (NFIP), Map Number 54017C0230C dated October 4, 2011. Being that the site is located in a Flood Zone "AE", base flood elevations for this area have been established and detailed study information was found in the Flood Insurance Study for Doddridge County, dated October 4, 2011.

In order to establish base flood elevations for this site, a hydrologic and hydraulic analysis was performed as outlined in the current Doddridge County Floodplain Ordinance, enacted May 21st, 2013. Using field shot data, 10-foot interval topography converted from 3 meter West Virginia GIS Technical Center DEM data, and information taken from USGS 7.5 Minute Series Topographic Maps, a drainage analysis was performed for the Toms Fork drainage shed. Upon establishing the peak flow drainage calculations for the 100-year storm event, a HEC-RAS river analysis was conducted for a section of Toms Fork adjacent to the New Milton Compressor Station Access Road and Base Flood Elevations (BFE) were established. The established BFEs were compared to those found in the Flood Insurance Study as shown on the Summary of Computed Elevations found in the attached report. The established BFEs were similar to the BFEs found in the Flood Insurance Study, with the greatest difference in elevation being approximately 0.7'. The resulting BFEs were used to establish adjusted floodplain boundaries for the segment of Toms Fork being studied. These boundaries are shown on the attached Existing Conditions Plan. In addition to establishing BFEs, a proposed conditions analysis was performed to determine the impacts of the proposed entrance road and stream crossing over Toms Fork. The proposed grading and culverts were added into the cross sections and the manning's "n" values were adjusted where necessary. The model was run with these changes to determine the impacts of the proposed access road and culverts. The results of this analysis indicate that the proposed improvement will cause a maximum increase of 0.5' in the BFEs in this area and no upstream or downstream properties will be adversely impacted. The maximum increase in the BFE occurs at River Station 17+26.403 and has an existing BFE of 831.4 and a proposed BFE of 831.9. The New Milton Compressor Station Access Road Site Plan (attached) contains a FEMA FIRM Map exhibit showing the proposed access road site overlaid on the FIRM Map. This map contains approximate property lines and owner information.

Engineering Dedicated to the Development and Transmission of Energy  
**Serving PA-WV-OH-NY**  
Engineering Surveying Environmental GIS  
[www.navituseng.com](http://www.navituseng.com)

Attached are the following documents associated with this submission:

- A Floodplain Analysis of Toms Fork documenting the methods used for the analysis, drainage computations, cross sections, and a narrative to describe the analysis. Included with this analysis are exhibits that identify the existing and proposed 100-year floodplain.
- The New Milton Compressor Station Access Road Site Plan, prepared by Navitus Engineering, Inc. which includes additional site design and construction specifications.
- Project Cost Estimate
- Floodplain Permit Application Fee
- Doddridge County Improvement Location Permit Application

Should any questions or comments arise during the review, please let us know and we will work to address them. Copies of all permits required for this site will be provided by the operator. Please let me know if you should need additional information. You can reach me by phone (540) 336-9486 or email: [dmurphy@navituseng.com](mailto:dmurphy@navituseng.com).

Sincerely,  
Navitus Engineering, Inc.



Daniel E. Murphy, CFM



151 Windy Hill Lane  
Winchester, Virginia 22602  
Telephone: (888) 662-4185

July 16, 2013

Doddridge County Commission  
118 East Court Street  
West Union, WV 26456

Attn: Dan Wellings, Doddridge County Floodplain Administrator

Re: New Milton Compressor Station Access Road Culvert Stream Crossing - Floodplain Analysis

Dear Mr. Wellings:

Navitus Engineering has completed a floodplain analysis of the proposed New Milton Compressor Station Access Road stream crossing over Toms Fork located south of West Union, along State Route 18 in Doddridge County, West Virginia. This site is located within a FEMA Flood Zone "AE", as shown on the Flood Insurance Rate Map (FIRM) from the National Flood Insurance Program (NFIP), Map Number 54017C0230C dated October 4, 2011. Being that the site is located in a Flood Zone "AE", base flood elevations for this area have been established and detailed study information was found in the Flood Insurance Study for Doddridge County, dated October 4, 2011.

In order to establish base flood elevations for this site, a hydrologic and hydraulic analysis was performed as outlined in the current Doddridge County Floodplain Ordinance, enacted May 21st, 2013. Using field shot data, 10-foot interval topography converted from 3 meter West Virginia GIS Technical Center DEM data, and information taken from USGS 7.5 Minute Series Topographic Maps, a drainage analysis was performed for the Toms Fork drainage shed. Upon establishing the peak flow drainage calculations for the 100-year storm event, a HEC-RAS river analysis was conducted for a section of Toms Fork adjacent to the New Milton Compressor Station Access Road and Base Flood Elevations (BFE) were established. The established BFEs were compared to those found in the Flood Insurance Study as shown on the Summary of Computed Elevations found in the attached report. The established BFEs were similar to the BFEs found in the Flood Insurance Study, with the greatest difference in elevation being approximately 0.7'. The resulting BFEs were used to establish adjusted floodplain boundaries for the segment of Toms Fork being studied. These boundaries are shown on the attached Existing Conditions Plan. In addition to establishing BFEs, a proposed conditions analysis was performed to determine the impacts of the proposed entrance road and stream crossing over Toms Fork. The proposed grading and culverts were added into the cross sections and the manning's "n" values were adjusted where necessary. The model was run with these changes to determine the impacts of the proposed access road and culverts. The results of this analysis indicate that the proposed improvement will cause a maximum increase of 0.5' in the BFEs in this area and no upstream or downstream properties will be adversely impacted. The maximum increase in the BFE occurs at River Station 17+26.403 and has an existing BFE of 831.4 and a proposed BFE of 831.9. The New Milton Compressor Station Access Road Site Plan (attached) contains a FEMA FIRM Map exhibit showing the proposed access road site overlaid on the FIRM Map. This map contains approximate property lines and owner information.

Engineering Dedicated to the Development and Transmission of Energy  
Serving PA-WV-OH-NY  
Engineering Surveying Environmental GIS  
www.navituseng.com

Attached are the following documents associated with this submission:


- A Floodplain Analysis of Toms Fork documenting the methods used for the analysis, drainage computations, cross sections, and a narrative to describe the analysis. Included with this analysis are exhibits that identify the existing and proposed 100-year floodplain.
- The New Milton Compressor Station Access Road Site Plan, prepared by Navitus Engineering, Inc. which includes additional site design and construction specifications.
- Project Cost Estimate
- Floodplain Permit Application Fee
- Doddridge County Improvement Location Permit Application

Should any questions or comments arise during the review, please let us know and we will work to address them. Copies of all permits required for this site will be provided by the operator. Please let me know if you should need additional information. You can reach me by phone (540) 336-9486 or email: [dmurphy@navituseng.com](mailto:dmurphy@navituseng.com).


Sincerely,  
Navitus Engineering, Inc.



Daniel E. Murphy, CFM



**STREAM CROSSING "A"  
STORMWATER COMPUTATIONS  
NEW MILTON COMPRESSOR STATION  
ACCESS ROAD WITH CULVERTS**



VICINITY MAP  
1" = 2,000'



**NAVITUS**  
ENGINEERING INC.

151 Windy Hill Lane  
Winchester, VA 22602  
Telephone: (888) 662-4185  
[www.navituseng.com](http://www.navituseng.com)

Engineering — Survey — Environmental — GIS

Prepared For:



981 East Washington Avenue  
Ellenboro, WV 26346  
(304) 869-3405

Contacts:  
Bill Prehm, Project Manager  
(303) 807-4436  
Anthony Smith, Field Engineer  
(304) 673-6196  
Mike Heaster, Land Agent  
(304) 871-0085



Designed By:  
Navitus Engineering Inc.

Project Manager:  
Dan Murphy, CFM  
[dmurphy@navituseng.com](mailto:dmurphy@navituseng.com)

Tax Parcel:  
Map 8 Parcel 37

Location:  
New Milton District, Doddridge County  
West Virginia

Date: July 16, 2013

**FN#** ANT096

New Milton Compressor Station  
Access Road with Culverts

STREAM CROSSING "A"

**STORMWATER COMPUTATIONS**

**Sections**

Overview and Narrative	Section 1
NRCS Soils Report	Section 2
Drainage Calculations	Section 3
HY-8 Culvert Analysis Report	Section 4
Stream Crossing "A" Details	Section 5

## SECTION 1

### Overview

The intent of this project is to construct a gravel access road to a compressor station and associated facilities. This project design will include a permanent stream crossing and access. The compressor station was designed by others. Toms Fork which has been classified as a Perennial stream per the wetlands report conducted by Kleinfelder dated July 15, 2013, will be crossed at station 01+92.735 of the proposed access road.

### Drainage Narrative

Using the SCS Method and HEC-HMS, we determined the 1, 10, and 100-year rainfall events at the stream crossing study point. We then used HY-8 to design the culvert and to determine the base flow water surface elevation for each rainfall event. Stream Crossing "A" has a drainage area of 9345.7 Acres. Design flows are provided in the drainage calculations in Section 3.

The permanent stream crossing was designed per the West Virginia Department of Environmental Protection Erosion and Sediment Control Best Management Practice Manual 2006 edition, Section 3.21-21. Per this manual, any structure that will remain in place 6 months or longer shall be large enough to convey the flow from a 10-year frequency, 24 hour duration storm. This culvert is sized to handle the computed 10-year storm event flow of 1,790.5 cfs.


The stream crossing was also designed as a permanent structure in accordance with the U.S. Army Corps of Engineering Nationwide 14 Permit. The structure is two (2) 35'-10" x 11'-4" Contech Bridgecor #25A5 Arch Culverts that shall be bottomless to allow for aquatic passage. The culverts are 40.0 LF with a slope of 0.7%. The stream crossing will contain clean rock fill made of 2-4" aggregate 50 feet on each side of the culvert with large angular rock below. No green concrete shall be used in the crossing. The permanent stream crossing will impact 98.5' of the perennial stream, Toms Fork.

**SECTION 2**

**NRCS Soils Report**




Hydrologic Soil Group—Doddridge County, West Virginia  
(Stream Crossing A)



Hydrologic Soil Group—Doddridge County, West Virginia  
(Stream Crossing A)

### MAP LEGEND

#### Area of Interest (AOI)

 Area of Interest (AOI)

#### Soils

 Soil Map Units

#### Soil Ratings

 A

 A/D

 B

 B/D

 C

 C/D


 D

 Not rated or not available

#### Political Features

 Cities

#### Water Features

 Streams and Canals

#### Transportation

 Rails

 Interstate Highways

 US Routes

 Major Roads

### MAP INFORMATION

Map Scale: 1:34,100 if printed on B size (11" × 17") sheet.

The soil surveys that comprise your AOI were mapped at 1:24,000.

Please rely on the bar scale on each map sheet for accurate map measurements.

Source of Map: Natural Resources Conservation Service  
Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>  
Coordinate System: UTM Zone 17N NAD83

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Doddridge County, West Virginia  
Survey Area Data: Version 8, Apr 2, 2009

Date(s) aerial images were photographed: 8/25/2007

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Hydrologic Soil Group

Hydrologic Soil Group— Summary by Map Unit — Doddridge County, West Virginia (WV017)				
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
Ch	Chagrin silt loam	B	149.2	1.6%
Co	Cotaco silt loam	C	7.3	0.1%
GpE	Gilpin-Peabody complex, 25 to 35 percent slopes	D	5.2	0.1%
GsE	Gilpin-Peabody complex, 15 to 35 percent slopes, very stony	C	1,903.9	20.4%
GsF	Gilpin-Peabody complex, 35 to 70 percent slopes, very stony	C	5,505.4	58.9%
GuC	Gilpin-Upshur complex, 8 to 15 percent slopes	D	167.9	1.8%
GuD	Gilpin-Upshur complex, 15 to 25 percent slopes	D	814.4	8.7%
Ka	Kanawha loam	B	32.2	0.3%
Me	Melvin silt loam	D	4.6	0.0%
Se	Sensabaugh silt loam	B	188.9	2.0%
SeB	Sensabaugh silt loam, 3 to 8 percent slopes, rarely flooded	B	451.6	4.8%
VaC	Vandalia silt loam, 8 to 15 percent slopes	D	3.2	0.0%
VaD	Vandalia silt loam, 15 to 25 percent slopes	D	48.9	0.5%
VaE	Vandalia silt loam, 25 to 35 percent slopes	D	7.9	0.1%
VsE	Vandalia silt loam, 15 to 35 percent slopes, very stony	D	54.9	0.6%
<b>Totals for Area of Interest</b>			<b>9,345.7</b>	<b>100.0%</b>

## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

**SECTION 3**

**SCS TR-55  
Drainage Computations**

Project: New Milton

Simulation Run: Existing

Start of Run: 11Jul2013, 00:00  
End of Run: 12Jul2013, 00:05  
Compute Time: 11Jul2013, 08:20

Basin Model: Existing  
Meteorologic Model: 2 YR  
Control Specifications: Control 1

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
Upper Toms Fork	12.832	696	11Jul2013, 14:25	304.9
Reach-1	12.832	696	11Jul2013, 14:55	299.7
Middle Toms Fork	1.77	167.5	11Jul2013, 13:00	44.2
Junction-1	14.602	753.3	11Jul2013, 14:50	343.9
Reach-2	14.602	753.2	11Jul2013, 15:10	340
Lower Toms Fork	0.944	116.4	11Jul2013, 12:40	23.9
Downstream	15.546	775.9	11Jul2013, 15:10	363.9

Project: New Milton

Simulation Run: Existing

Start of Run: 11Jul2013, 00:00

Basin Model: Existing

End of Run: 12Jul2013, 00:05

Meteorologic Model: 10 YR

Compute Time: 11Jul2013, 08:20

Control Specifications: Control 1

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
Upper Toms Fork	12.832	1668.9	11Jul2013, 14:15	659.9
Reach-1	12.832	1668.7	11Jul2013, 14:45	650.7
Middle Toms Fork	1.77	417.2	11Jul2013, 12:55	94.8
Junction-1	14.602	1790.6	11Jul2013, 14:40	745.5
Reach-2	14.602	1790.5	11Jul2013, 15:00	738.6
Lower Toms Fork	0.944	293.8	11Jul2013, 12:35	51.1
Downstream	15.546	1835.4	11Jul2013, 15:00	789.7

Project: New Milton

Simulation Run: Existing

Start of Run: 11Jul2013, 00:00

Basin Model: Existing

End of Run: 12Jul2013, 00:05

Meteorologic Model: 100 YR

Compute Time: 11Jul2013, 08:20

Control Specifications: Control 1

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
Upper Toms Fork	12.832	3765.8	11Jul2013, 14:10	1397
Reach-1	12.832	3765	11Jul2013, 14:40	1380.7
Middle Toms Fork	1.77	949.1	11Jul2013, 12:55	199.5
Junction-1	14.602	4015.3	11Jul2013, 14:35	1580.2
Reach-2	14.602	4015.1	11Jul2013, 14:55	1567.8
Lower Toms Fork	0.944	666.8	11Jul2013, 12:35	107.3
Downstream	15.546	4101.3	11Jul2013, 14:55	1675.1



**SECTION 4**


**HY-8 Culvert Analysis Report**

# HY-8 Culvert Analysis Report

Headwater Elevation (ft)	Total Discharge (cfs)	Culvert 1 Discharge (cfs)	Roadway Discharge (cfs)	Iterations
826.03	753.30	753.30	0.00	1
826.99	1079.50	1079.50	0.00	1
827.76	1405.70	1405.70	0.00	1
828.39	1731.90	1731.90	0.00	1
828.50	1790.60	1790.60	0.00	1
829.53	2384.30	2384.30	0.00	1
830.03	2710.50	2710.50	0.00	1
830.51	3036.70	3036.70	0.00	1
830.96	3362.90	3362.90	0.00	1
831.40	3689.10	3689.10	0.00	1
831.83	4015.30	4015.30	0.00	1
838.58	8121.08	8121.08	0.00	Overtopping

**Table 1 - Summary of Culvert Flows at Crossing: Stream Crossing "A"**

## Total Rating Curve Crossing: Stream Crossing "A"



**Rating Curve Plot for Crossing: Stream Crossing "A"**

Inlet Depression: NONE

Flow (cfs)	Water Surface Elev (ft)	Depth (ft)	Velocity (ft/s)	Shear (psf)	Froude Number
753.30	825.70	3.43	4.54	0.71	0.50
1079.50	826.60	4.33	4.69	0.89	0.50
1405.70	827.26	4.99	4.79	1.03	0.50
1731.90	827.78	5.51	4.93	1.13	0.51
1790.60	827.86	5.59	4.96	1.15	0.51
2384.30	828.66	6.39	5.06	1.32	0.51
2710.50	829.01	6.74	5.13	1.39	0.51
3036.70	829.31	7.04	5.21	1.45	0.52
3362.90	829.59	7.32	5.29	1.51	0.52
3689.10	829.84	7.57	5.38	1.56	0.52
4015.30	830.07	7.80	5.48	1.61	0.52

**Table 3 - Downstream Channel Rating Curve (Crossing: Stream Crossing "A")**

**Tailwater Channel Data - Stream Crossing "A"**

Tailwater Channel Option: Irregular Channel

Channel Slope: 0.0033

User Defined Channel Cross-Section:

Coord No.	Station (ft)	Elevation (ft)	Manning's n
1	0.00	830.62	0.0350
2	9.95	830.00	0.0350
3	93.44	828.00	0.0350
4	149.89	826.00	0.0350
5	152.58	824.00	0.0350
6	154.39	822.27	0.0350
7	177.13	822.38	0.0350
8	194.49	822.46	0.0350
9	199.90	824.00	0.0350
10	216.57	826.00	0.0350
11	220.16	828.00	0.0350
12	223.64	830.00	0.0350
13	235.94	832.00	0.0000

**Roadway Data for Crossing: Stream Crossing "A"**

Roadway Profile Shape: Irregular Roadway Shape (coordinates)

Irregular Roadway Cross-Section:

Coord No.	Station (ft)	Elevation (ft)
0	0.00	838.58
1	50.00	838.58
2	100.00	838.58
3	150.00	838.58


Roadway Surface: Gravel

Roadway Top Width: 25.00 ft

Crossing Front View (Roadway Profile): Stream Crossing "A"

Crossing Front View

(Not to scale)



**SECTION 5**

**Stream Crossing "A" Details**

**GENERAL STREAM CROSSING NOTES:**

- 1) 2" to 4" COARSE AGGREGATE OR LARGER SHALL BE USED TO FORM THE FIRST 6" OF FILL FOR THE CROSSING. THE REMAINDER OF MATERIAL SHALL BE ONLY LARGE ANGULAR DURABLE ROCK. DO NOT USE ERODIBLE MATERIAL FOR CONSTRUCTION OF THE CROSSING.
- 2) IF MULTIPLE CULVERTS ARE USED, THEY SHALL BE SEPARATED BY AT LEAST 18 INCHES OF COMPACTED AGGREGATE FILL.
- 3) CLEARING AND EXCAVATION OF THE STREAMBED AND BANKS SHALL BE KEPT TO A MINIMUM.
- 4) APPROPRIATE PERIMETER CONTROLS SUCH AS COMPOST FILTER SOCK, SUPER SILT FENCE AND/OR SEDIMENT TRAPS SHALL BE EMPLOYED ALONG THE BANKS AND PARALLEL TO THE STREAMBED.
- 5) GABION WALLS ON THE UPSTREAM AND DOWNSTREAM SIDS OF THE CULVERT INSTALLATION SHALL BE INSTALLED TO REDUCE STRUCTURAL DAMAGE DURING HIGH VELOCITY WATER OVERFLOW PERIODS.
- 6) STREAMBED MATERIAL IS NOT TO BE USED AS FILL.
- 7) CEMENT CONCRETE SHALL NOT BE PLACED IN CONTACT WITH FLOWING WATER.
- 8) WHEN THE CROSSING HAS SERVED ITS PURPOSE, ALL STRUCTURES INCLUDING CULVERTS, BEDDING, AND FILTER CLOTH SHALL BE REMOVED. REMOVAL OF THE STRUCTURE AND CLEAN UP OF THE AREA SHOULD BE ACCOMPLISHED WITHOUT CONSTRUCTION EQUIPMENT WORKING IN THE WATERWAY CHANNEL. UPON REMOVAL OF THE STRUCTURE, THE STREAM BANK SHALL IMMEDIATELY BE STABILIZED.
- 9) DURING ROUTINE MAINTENANCE DO NOT GRADE MUD AND DEBRIS OVER THE SIDES OF THE CROSSING INTO THE STREAM.
- 10) THE CROSSING MUST BE INSPECTED AFTER EVERY RAIN EVENT OF 0.5 INCHES OR MORE AND ONCE A WEEK TO ENSURE THAT THE CULVERTS, STREAMBED, AND STREAM BANKS ARE MAINTAINED AND NOT DAMAGED. NEVER ALLOW THE CULVERTS TO BECOME CLOGGED WITH DEBRIS AND REMOVE ANY OBSTRUCTIONS IMMEDIATELY.
- 11) FLUSHING IS NOT AN APPROVED METHOD TO BE UTILIZED FOR CULVERT CLEANOUT.


**PUMP AND DEWATERING NOTES:**

- 1) CONSTRUCTION SHOULD BE PERFORMED DURING LOW FLOW PERIODS.
- 2) PUMP(S) AND DEWATERING BAG SHOULD BE SUFFICIENTLY LARGE TO CONTAIN THE ENTIRE STREAM AREA BEING DAMMED.
- 3) THE COFFERDAM CONSTRUCTED MUST BE IMPERVIOUS TO WATER.
- 4) THE SILEY OF THE PUMPS IS TO BE SUSPENDED ABOVE THE STREAMBED IN ORDER TO PREVENT SUCKING MUD AND SEDIMENT.

**STREAM CROSSING "A" DETAILS**




**STREAM CROSSING "A" SECTIONS**



**CROSS SECTION "A-A"**

SCALE: HORIZ. 1" = 50' VERT. 1" = 10'




**CROSS SECTION "B-B"**

SCALE: HORIZ. 1" = 50' VERT. 1" = 10'

- NOTE:**
1. SEE STREAM CROSSING REPORT AND FLOODPLAIN ANALYSIS OF TOMS FORK BY NAVITUS ENGINEERING FOR CULVERT AND DRAINAGE COMPUTATIONS.
  2. ANTERO RESOURCES SHALL OBTAIN A STREAM ACTIVITY PERMIT THROUGH THE PUBLIC LAND CORPORATION OFFICE OF LAND AND STREAMS FOR STREAM CROSSING "A".

**LEGEND**

EX. INDEX CONTOUR	--- 100 ---	PROP. INDEX CONTOUR	--- 100 ---
EX. INTERMEDIATE CONTOUR	--- 100 ---	PROP. INTERMEDIATE CONTOUR	--- 100 ---
EX. PROPERTY LINE	---	PROP. INDEX CONTOUR (ROAD)	---
EX. ROAD EDGE OF GRAVEL/DIRT	---	PROP. INTERMEDIATE CTR. (ROAD)	---
EX. ROAD EDGE OF PAVEMENT	---	PROP. LIMITS OF DISTURBANCE	---
EX. ROAD CENTERLINE	---	PROP. WELL HEAD	---
EX. EROSION	---	PROP. FORECASTER SAFETY FENCE	---
EX. CULVERT	---	PROP. ACCESS SLATS WITH EMERGENCY LIFELINE	---
EX. FENCELINE	---	PROP. ROAD EDGE OF GRAVEL	---
EX. OVERHEAD UTILITY	---	PROP. ROAD CENTERLINE	---
EX. POWER POLE/GUY WIRE	---	PROP. T-SLOT W/ CHECK DAM	---
EX. GASLINE	---	PROP. CULVERT W/ SFP-SAP	---
EX. TRENCH	---	PROP. COMPOST FILTER SOCK	---
EX. DELINEATED STREAM	---	PROP. SUPER SILT FENCE	---
EX. DELINEATED WETLAND	---	MATCHLINE	---
EX. BUILDING	---	BRUSH PILE SEDIMENT BARRIER	---
100' WETLAND/STREAM BUFFER DELINEATION STUDY AREA	---		



**GABION CAGE WALL**


15'

10'

SOIL COMPACTED TO 95% SWEDEMARK PROCTOR

UNDISTURBED SOIL


3 X 6" (3 INCHES HIGH) TUBES AND FILL WITH 4" STONE IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS



**COFFERDAM CROSSING**

PLAN VIEW

**SECTION "A-A"**



**COFFERDAMS**

**JERSEY BARRIER COFFERDAM**

**SAND or GRAVEL BAG COFFERDAM**

**ROCK COFFERDAM**

**NAVITUS ENGINEERING INC.**  
 Survey Engineering  
 Environmental GIS

114 Newby Mill Lane, Suite 2100  
 Tallahassee, Florida 32304  
 Telephone: 904-888-1414  
 Fax: 904-888-1415  
 Email: info@navituseng.com

REVISION	DATE

**ANTERO RESOURCES**  
 Environmental Engineering  
 114 Newby Mill Lane, Suite 2100  
 Tallahassee, Florida 32304  
 Telephone: 904-888-1414  
 Fax: 904-888-1415  
 Email: info@anteroresources.com


**STREAM CROSSING "A" DETAILS**

**NEW MILTON**  
 COMPRESSOR STATION ACCESS ROAD  
 NEW MILTON DISTRICT  
 DODDRIIDGE COUNTY, WEST VIRGINIA

DATE: 07/16/2013  
 SCALE: AS SHOWN  
 SHEET 14 OF 20



**STREAM CROSSING "A"  
STORMWATER COMPUTATIONS  
NEW MILTON COMPRESSOR STATION  
ACCESS ROAD WITH BRIDGE**



VICINITY MAP

1" = 2,000'



151 Windy Hill Lane  
Winchester, VA 22602  
Telephone: (888) 662-4185  
[www.navituseng.com](http://www.navituseng.com)

Engineering ◀ Survey ◀ Environmental ◀ GIS

Prepared For:



981 East Washington Avenue  
Ellenboro, WV 26346  
(304) 869-3405

Contacts:

Bill Prehm, Project Manager  
(303) 807-4436  
Anthony Smith, Field Engineer  
(304) 673-6196  
Mike Heaster, Land Agent  
(304) 871-0085



Designed By:  
Navitus Engineering Inc.

Project Manager:  
Dan Murphy, CFM  
[dmurphy@navituseng.com](mailto:dmurphy@navituseng.com)

Tax Parcel:  
Map 8 Parcel 37

Location:  
New Milton District, Doddridge County  
West Virginia

Date: July 16, 2013

**FN# ANT096**

New Milton Compressor Station  
Access Road with Bridge

STREAM CROSSING "A"

**STORMWATER COMPUTATIONS**

**Sections**

Overview and Narrative	Section 1
NRCS Soils Report	Section 2
Drainage Calculations	Section 3
HY-8 Culvert Analysis Report	Section 4
Stream Crossing "A" Details	Section 5



## SECTION 1

### Overview

The intent of this project is to construct a gravel access road to a compressor station and associated facilities. This project will include a permanent stream crossing. Toms Fork which has been classified as a Perennial stream per the wetlands report conducted by Kleinfelder dated July 15, 2013, will be crossed at station 01+92.735 of the proposed access road.

### Drainage Narrative

Using the SCS Method and HEC-HMS, we determined the 1, 10, and 100-year rainfall events at the stream crossing study point. We then used HEC-RAS to design the bridge and to determine the existing and proposed water surface elevations. The Floodplain Analysis conducted by Navitus Engineering shows the complete HEC-RAS model and computations including the base flood elevations and the impacts to the associated water surface elevations. Stream Crossing "A" has a drainage area of 9345.7 Acres. Design flows are provided in the drainage calculations in Section 3.

The permanent stream crossing was designed per the West Virginia Department of Environmental Protection Erosion and Sediment Control Best Management Practice Manual 2006 edition, Section 3.21-21. Per this manual, any structure that will remain in place 6 months or longer shall be large enough to convey the flow from a 10-year frequency, 24 hour duration storm. This bridge is sized to handle the computed 10-year storm event flow of 1,790.5 cfs and the 100 year storm event.


The stream crossing was also designed as a permanent structure in accordance with the U.S. Army Corps of Engineering Nationwide 14 Permit. The structure is a 60' span steel beam bridge with concrete abutments and a clear width of 57'. The bridge shall span the existing stream bed to allow for aquatic passage. No green concrete shall be used in the crossing. The permanent stream crossing will impact 98.5' of the perennial stream, Toms Fork to allow room for construction activities. The structural components of the bridge are being designed by others.

A complete copy of the Floodplain Analysis for Toms Fork on the proposed bridge can be provided upon request.

**SECTION 2**

**NRCS Soils Report**

Hydrologic Soil Group—Doddridge County, West Virginia  
(Stream Crossing A)



Hydrologic Soil Group—Doddridge County, West Virginia  
(Stream Crossing A)

### MAP LEGEND

#### Area of Interest (AOI)

 Area of Interest (AOI)

#### Soils

 Soil Map Units

#### Soil Ratings

 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available





#### Political Features

 Cities

#### Water Features

 Streams and Canals

#### Transportation

 Rails  
 Interstate Highways  
 US Routes  
 Major Roads

### MAP INFORMATION

Map Scale: 1:34,100 if printed on B size (11" × 17") sheet.

The soil surveys that comprise your AOI were mapped at 1:24,000.

Please rely on the bar scale on each map sheet for accurate map measurements.

Source of Map: Natural Resources Conservation Service  
Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>  
Coordinate System: UTM Zone 17N NAD83

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Doddridge County, West Virginia  
Survey Area Data: Version 8, Apr 2, 2009

Date(s) aerial images were photographed: 8/25/2007

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Hydrologic Soil Group

Hydrologic Soil Group— Summary by Map Unit — Doddridge County, West Virginia (WV017)				
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
Ch	Chagrin silt loam	B	149.2	1.6%
Co	Cotaco silt loam	C	7.3	0.1%
GpE	Gilpin-Peabody complex, 25 to 35 percent slopes	D	5.2	0.1%
GsE	Gilpin-Peabody complex, 15 to 35 percent slopes, very stony	C	1,903.9	20.4%
GsF	Gilpin-Peabody complex, 35 to 70 percent slopes, very stony	C	5,505.4	58.9%
GuC	Gilpin-Upshur complex, 8 to 15 percent slopes	D	167.9	1.8%
GuD	Gilpin-Upshur complex, 15 to 25 percent slopes	D	814.4	8.7%
Ka	Kanawha loam	B	32.2	0.3%
Me	Melvin silt loam	D	4.6	0.0%
Se	Sensabaugh silt loam	B	188.9	2.0%
SeB	Sensabaugh silt loam, 3 to 8 percent slopes, rarely flooded	B	451.6	4.8%
VaC	Vandalia silt loam, 8 to 15 percent slopes	D	3.2	0.0%
VaD	Vandalia silt loam, 15 to 25 percent slopes	D	48.9	0.5%
VaE	Vandalia silt loam, 25 to 35 percent slopes	D	7.9	0.1%
VsE	Vandalia silt loam, 15 to 35 percent slopes, very stony	D	54.9	0.6%
<b>Totals for Area of Interest</b>			<b>9,345.7</b>	<b>100.0%</b>

## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

**SECTION 3**

**SCS TR-55  
Drainage Computations**

Project: New Milton

Simulation Run: Existing

Start of Run: 11Jul2013, 00:00  
End of Run: 12Jul2013, 00:05  
Compute Time: 11Jul2013, 08:20

Basin Model: Existing  
Meteorologic Model: 2 YR  
Control Specifications: Control 1

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
Upper Toms Fork	12.832	696	11Jul2013, 14:25	304.9
Reach-1	12.832	696	11Jul2013, 14:55	299.7
Middle Toms Fork	1.77	167.5	11Jul2013, 13:00	44.2
Junction-1	14.602	753.3	11Jul2013, 14:50	343.9
Reach-2	14.602	753.2	11Jul2013, 15:10	340
Lower Toms Fork	0.944	116.4	11Jul2013, 12:40	23.9
Downstream	15.546	775.9	11Jul2013, 15:10	363.9



Project: New Milton

Simulation Run: Existing

Start of Run: 11Jul2013, 00:00

Basin Model: Existing

End of Run: 12Jul2013, 00:05

Meteorologic Model: 10 YR

Compute Time: 11Jul2013, 08:20

Control Specifications: Control 1

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
Upper Toms Fork	12.832	1668.9	11Jul2013, 14:15	659.9
Reach-1	12.832	1668.7	11Jul2013, 14:45	650.7
Middle Toms Fork	1.77	417.2	11Jul2013, 12:55	94.8
Junction-1	14.602	1790.6	11Jul2013, 14:40	745.5
Reach-2	14.602	1790.5	11Jul2013, 15:00	738.6
Lower Toms Fork	0.944	293.8	11Jul2013, 12:35	51.1
Downstream	15.546	1835.4	11Jul2013, 15:00	789.7

Project: New Milton

Simulation Run: Existing

Start of Run: 11Jul2013, 00:00

Basin Model: Existing

End of Run: 12Jul2013, 00:05

Meteorologic Model: 100 YR

Compute Time: 11Jul2013, 08:20

Control Specifications: Control 1

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
Upper Toms Fork	12.832	3765.8	11Jul2013, 14:10	1397
Reach-1	12.832	3765	11Jul2013, 14:40	1380.7
Middle Toms Fork	1.77	949.1	11Jul2013, 12:55	199.5
Junction-1	14.602	4015.3	11Jul2013, 14:35	1580.2
Reach-2	14.602	4015.1	11Jul2013, 14:55	1567.8
Lower Toms Fork	0.944	666.8	11Jul2013, 12:35	107.3
Downstream	15.546	4101.3	11Jul2013, 14:55	1675.1

**SECTION 4**

**HEC-RAS Bridge Table**

Reach	River Sta	Profile	Plan	E.G. Elev (ft)	W.S. Elev (ft)	Crit W.S. (ft)	Frctn Loss (ft)	C & E Loss (ft)	Top Width (ft)	Q Left (cfs)	Q Channel (cfs)	Q Right (cfs)	Vel Chnl (ft/s)
Toms Fork	1726.403	PF 1	Existing	832.6	831.35		0.25	0.21	185.33	459.43	3496.9	58.97	9.61
Toms Fork	1726.403	PF 1	Bridge	832.8	831.71		0.23	0.15	188.95	525.18	3428.63	61.49	9.04
Toms Fork	1580.979	PF 1	Existing	832.14	831.59		0.14	0.02	292.23	383.83	3292.34	339.13	6.58
Toms Fork	1580.979	PF 1	Bridge	832.42	831.84	828.27	0.08	0.05	296.04	257.07	3395.6	362.63	6.59
Toms Fork	1528.223BR U	PF 1	Bridge	832.28	831.16	828.2	0.04	0.07	58.04	13.92	4001.38		8.52
Toms Fork	1528.223BR D	PF 1	Bridge	832.17	831.27	828.43	0.06	0.13	218.16	391.9	3603.86	19.55	8.03
Toms Fork	1483.221	PF 1	Existing	831.98	831.51		0.06	0.05	384.11	903.2	2954.38	157.72	6.4
Toms Fork	1483.221	PF 1	Bridge	831.99	831.51	828.49	0.06	0.05	384.06	886.99	2969.85	158.46	6.44
Toms Fork	1421.67	PF 1	Existing	831.87	831.56		0.12	0.02	373.8	1016.45	2990.82	8.03	5.19
Toms Fork	1421.67	PF 1	Bridge	831.87	831.56		0.12	0.02	373.8	1016.45	2990.82	8.03	5.19


Total Discharge (cfs)	Culvert Discharge (cfs)	Headwater Elevation (ft)	Inlet Control Depth (ft)	Outlet Control Depth (ft)	Flow Type	Normal Depth (ft)	Critical Depth (ft)	Outlet Depth (ft)	Tailwater Depth (ft)	Outlet Velocity (ft/s)	Tailwater Velocity (ft/s)
753.30	753.30	826.03	2.565	3.371	3-M1t	1.988	1.493	3.325	3.435	3.271	4.538
1079.50	1079.50	826.99	3.246	4.332	3-M1t	2.474	1.936	4.215	4.325	3.719	4.688
1405.70	1405.70	827.76	3.875	5.099	3-M1t	2.939	2.308	4.884	4.994	4.211	4.789
1731.90	1731.90	828.39	4.459	5.730	3-M1t	3.358	2.648	5.398	5.508	4.734	4.930
1790.60	1790.60	828.50	4.559	5.836	3-M1t	3.429	2.709	5.481	5.591	4.828	4.956
2384.30	2384.30	829.53	5.505	6.870	3-M1t	4.145	3.293	6.277	6.387	5.720	5.060
2710.50	2710.50	830.03	6.002	7.371	3-M1t	4.518	3.578	6.626	6.736	6.219	5.133
3036.70	3036.70	830.51	6.500	7.846	3-M1t	4.892	3.863	6.933	7.043	6.719	5.213
3362.90	3362.90	830.96	6.998	8.297	3-M1t	5.269	4.148	7.210	7.320	7.217	5.295
3689.10	3689.10	831.40	7.492	8.736	3-M1t	5.660	4.388	7.464	7.574	7.714	5.376
4015.30	4015.30	831.83	7.915	9.168	3-M1t	6.052	4.627	7.686	7.796	8.219	5.476

**Table 2 - Culvert Summary Table: Culvert 1**

\*\*\*\*\*  
 Inlet Elevation (invert): 822.66 ft,    Outlet Elevation (invert): 822.38 ft  
 Culvert Length: 40.00 ft,    Culvert Slope: 0.0070  
 \*\*\*\*\*

### Performance Curve

Culvert: Culvert 1




**Culvert Performance Curve Plot: Culvert 1**

### Water Surface Profile Plot for Culvert: Culvert 1

Crossing - Stream Crossing "A", Design Discharge - 1790.6 cfs

Culvert - Culvert 1, Culvert Discharge - 1790.6 cfs



### Site Data - Culvert 1

Site Data Option: Culvert Invert Data

Inlet Station: 0.00 ft

Inlet Elevation: 822.66 ft

Outlet Station: 40.00 ft

Outlet Elevation: 822.38 ft

Number of Barrels: 2

### Culvert Data Summary - Culvert 1

Barrel Shape: User Defined

Barrel Span: 34.89 ft

Barrel Rise: 10.38 ft

Barrel Material: Corrugated Metal Riveted or Welded

Embedment: 0.00 in

Barrel Manning's n: 0.0240 (top and sides)

Manning's n: 0.0350 (bottom)

Inlet Type: Conventional

Inlet Edge Condition: Square Edge with Headwall

## **SECTION 5**

### **Stream Crossing "A" Details**

# STREAM CROSSING "A" ALTERNATE DETAILS

## GENERAL STREAM CROSSING NOTES:



- 1) 8" TO 4" COARSE AGGREGATE OR LARGER SHALL BE USED TO FORM THE FIRST 6" OF FILL FOR THE CROSSING, THE REMAINDER OF MATERIAL SHALL BE ONLY LARGE ANGULAR DURABLE ROCK. DO NOT USE ERODIBLE MATERIAL FOR CONSTRUCTION OF THE CROSSING.
- 2) CLEARING AND EXCAVATION OF THE STREAMBED AND BANKS SHALL BE KEPT TO A MINIMUM.
- 3) APPROPRIATE PERIMETER CONTROLS SUCH AS COMPOST FILTER SOCK, SUPER SILT FENCE AND/OR SEDIMENT TRAPS SHALL BE EMPLOYED ALONG THE BANKS AND PARALLEL TO THE STREAMBED.
- 4) ABUTMENTS AND WEIRWALLS ON THE UPSTREAM AND DOWNSTREAM SIDE OF THE BRIDGE INSTALLATION SHALL BE INSTALLED TO REDUCE STRUCTURAL DAMAGE DURING HIGH VELOCITY WATER OVERFLOW PERIODS.
- 5) STREAMBED MATERIAL IS NOT TO BE USED AS FILL.
- 6) GREEN CONCRETE SHALL NOT BE PLACED IN CONTACT WITH FLOWING WATER.
- 7) DURING ROUTINE MAINTENANCE DO NOT GRADE MUD AND DEBRIS OVER THE SIDES OF THE CROSSING INTO THE STREAM.
- 8) THE CROSSING MUST BE INSPECTED AFTER EVERY RAIN EVENT OF 0.5 INCHES OR MORE AND ONCE A WEEK TO ENSURE THAT THE CULVERTS, STREAMBED, AND STREAM BANKS ARE MAINTAINED AND NOT DAMAGED. NEVER ALLOW THE CULVERTS TO BECOME CLOGGED WITH DEBRIS AND REMOVE ANY OBSTRUCTIONS IMMEDIATELY.

## PUMP AND DEWATERING NOTES:



- 1) CONSTRUCTION SHOULD BE PERFORMED DURING LOW FLOW PERIODS.
- 2) PUMPS AND DEWATERING BAG SHOULD BE SUFFICIENTLY LARGE TO CONTAIN THE ENTIRE STREAM AREA BEING DAMMED.
- 3) THE COFFERDAM CONSTRUCTED MUST BE IMPERVIOUS TO WATER.
- 4) THE INLET OF THE PUMP(S) IS TO BE SUSPENDED ABOVE THE STREAMBED IN ORDER TO PREVENT SUCKING MUD AND SEDIMENT.



# STREAM CROSSING "A" ALTERNATE SECTIONS



- NOTE:
1. SEE STREAM CROSSING REPORT AND FLOODPLAIN ANALYSIS OF TOM'S FORK BY NAVITUS ENGINEERING FOR CULVERT AND DRAINAGE COMPUTATIONS.
  2. ANTERO RESOURCES SHALL OBTAIN A STREAM ACTIVITY PERMIT THROUGH THE PUBLIC LAND CORPORATION OFFICE OF LAND AND STREAMS FOR STREAM CROSSING "A".



LEGEND		LEGEND	
EX. INDEX CONTOUR	---	PROP. INDEX CONTOUR	---
EX. INTERMEDIATE CONTOUR	---	PROP. INTERMEDIATE CONTOUR	---
EX. PROPERTY LINE	---	PROP. INDEX CONTOUR (ROAD)	---
EX. ROAD EDGE OF GRAVEL/DIRT	---	PROP. INTERMEDIATE CTR (ROAD)	---
EX. ROAD EDGE OF PAVEMENT	---	PROP. LIMITS OF DISTURBANCE	---
EX. ROAD CENTERLINE	---	PROP. WELL HEAD	---
EX. DITCHLINE	---	PROP. PERIMETER SAFETY FENCE	---
EX. CULVERT	---	PROP. ACCESS GATE WITH EMERGENCY LIFELINE	---
EX. FENCELINE	---	PROP. ROAD EDGE OF GRAVEL	---
EX. OVERHEAD UTILITY	---	PROP. ROAD CENTERLINES	---
EX. POWER POLE/OUT WIRE	---	PROP. V-DITCH W/ CHECK DAM	---
EX. GASLINE	---	PROP. CULVERT W/ SUP-SUP	---
EX. TELELINE	---	PROP. COMPOST FILTER SOCK	---
EX. DELINEATED STREAM	---	PROP. SUPER SILT FENCE	---
EX. DELINEATED WETLAND	---	MATCHLINE	---
EX. BUILDING	---	BRUSH PILE SEDIMENT BARRIER	---
EX. 100' WETLAND/STREAM BUFFER	---		
EX. DELINEATION STUDY AREA	---		

**NAVITUS ENGINEERING INC.**  
131 W. Main St. Suite 207C  
Winchester, Virginia 24392  
www.navituseng.com

Engineering  
Surveying  
Environmental  
GIS

REVISION

DATE


ANTERO RESOURCES  
2013  
ANTERO RESOURCES  
2013

STREAM CROSSING "A" ALTERNATE DETAILS  
NEW MILTON  
COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA

DATE: 07/16/2013  
SCALE: AS SHOWN  
SHEET 15 OF 20



**FLOODPLAIN ANALYSIS OF  
TOMS FORK  
NEW MILTON COMPRESSOR STATION  
ACCESS ROAD WITH CULVERTS**



VICINITY MAP  
1" = 2,000'



Engineering     Survey     Environmental     GIS

Prepared For:



981 East Washington Avenue  
Ellenboro, WV 26346  
(304) 869-3405

Contacts:  
Bill Prehm, Project Manager  
(303) 807-4436  
Anthony Smith, Field Engineer  
(304) 673-6196  
Mike Heaster, Land Agent  
(304) 871-0085



Designed By:  
Navitus Engineering Inc.

Project Manager:  
Dan Murphy, CFM  
[dmurphy@navituseng.com](mailto:dmurphy@navituseng.com)

Tax Parcel:  
Map 8 Parcel 37

Location:  
New Milton District, Doddridge County  
West Virginia

Date: July 16, 2013

**FN# ANT096**

## 1. Objective

The objective of this floodplain analysis was to establish boundaries for the existing and proposed conditions of the 100 year base flood elevations (BFE). The proposed condition includes the installation of two (2) 35'-10"x11'-4" Contech Bridgecor #25A5 Arch Culverts and an access road to provide access to a compressor station site where the entrance off of State Route 18 is within the FEMA Flood Zone "AE".

## 2. Existing Conditions

### 2.1. *Property Description*

This site is located in Doddridge County, West Virginia along Toms Fork and State Route 18 south of West Union in the New Milton District. The proposed access road entrance is located on the east side of State Route 18.

### 2.2. *Floodplain Delineation*

The approximate limit of the 100-year floodplain (a flood event that has a 1% chance of being equaled or exceeded in any given year) is shown on FEMA Flood Insurance Rate Map (FIRM) for Doddridge County on panels 54017C0230C effective October 4, 2011. This floodplain is located in flood zone designation "AE" and base flood elevations have been established. Detailed study information was found in the Flood Insurance Study for Doddridge County, dated October 4, 2011.

### 2.3. *Floodplain Ordinance*

This site is administered under the Doddridge County Floodplain Ordinance, enacted May 31st, 2013.

Per Section 4.3 of the ordinance, when a site is located in FEMA Flood Zone designation "AE" without Floodway Area, the Floodplain Administrator shall require the applicant to demonstrate that the cumulative effect of the proposed development, when combined with all other existing and anticipated development, will not increase the elevation of the 100-year flood more than one (1) foot at any point.

Per Section 4.5.A of the ordinance, any developer shall notify in writing, by certified mail, Doddridge County's Floodplain Administrator, the State Coordinating Office, and adjacent communities and any adjacent property owners of all such intended activities prior to the alteration of the stream. Copies of all required notifications must be submitted to the Federal Insurance Administration. In addition prior to issuing the local permit the Floodplain Administrator shall require copies of all necessary permits from those government agencies from which Federal or State Law requires approval.

Per Section 4.5.B a stream crossing analysis for the proposed permanent crossing of Toms Fork has been provided under separate cover and includes a cover letter signed by the

responsible professional, a detailed report, hydraulic and hydrologic computations and a sitemap detailing the planned construction.

Per Section 4.5.C of this ordinance the stream crossing has been designed with "best practice" techniques in mind. Two (2) 35'-10"x11'-4" Contech Bridgecor #25A5 Arch Culverts were selected to pass the base flow and 10 year storm events. The culverts will be bottomless to allow for aquatic passage and preservation of the existing stream channel. The culverts were designed to be a permanent stream crossing. All fill utilized will be 2-4" clean rock aggregate with a 4-6" large angular durable rock base to minimize erosion during storm events. Gabion basket wing walls will be utilized to minimize scour around the culvert. Sandbag cofferdams and a dewatering bag system will be utilized during construction to minimize erosion and allow for construction in the stream channel.

Per Section 4.5.D of this ordinance the culverts will be properly anchored as required.

Per Section 4.5.E of this ordinance the Developer shall provide Doddridge County with all required legal agreements detailing inspections and maintenance.

Per Section 5.1 of this ordinance Permits are required for the construction of the permanent stream crossing. The format of the permit will coincide with the requirements set forth in Section 5.2 of the ordinance.

Per Section 6.1E of this ordinance the fill associated with this plan has been designed to not adversely affect adjacent properties. The access road and culverts were located to minimize floodway constriction and the height above the existing grade was minimized to allow as much flow as possible to be unimpeded. Impacts to the 100 year base flood elevation are demonstrated later in this report, however, increases to the 100 year base flood elevations were limited to approximately 1,337' upstream of the proposed culvert and returned to 0.0' of impact approximately 1,337' upstream of the proposed culvert. Impacts downstream of the proposed culvert were limited approximately 45' downstream and returned to 0.0' of impact immediately. Fill as stated above shall consist of 2-4" clean rock aggregate with a 4-6" large angular durable rock base. No less than 2:1 slopes will be utilized in the construction of the proposed crossing.

Per Section 6.1F the structure has been placed with the longitudinal axis parallel to the direction of flood flow and to maintain the same flood-flow lines of the adjoining structures.

Per Section 6.1.I of this ordinance, no material or equipment storage shall be allowed within the vicinity of the entrance. The storage of all material and equipment shall be onsite and away from the entrance.

Per Section 6.1.K of this ordinance, a flow line is proposed adjacent to State Route 18 along the entrance to allow adequate drainage across the proposed entrance.

All other specific requirements covered in Section 6.1 of this ordinance are not applicable to this design. (Sections 6.1.A, 6.1.B, 6.1.C, 6.1.D, 6.1.F, 6.1.G, 6.1.H, 6.1.J, and 6.1.L)

The developer shall conform with all administrative procedures as outline in Article 7 of this ordinance.

#### 2.4. *Toms Fork Characteristics*

Toms Fork is located in the New Milton District of Doddridge County and flows in a northern direction. The drainage area flowing to Toms Fork at the stream crossing is approximately 14.602 square miles of forested and agricultural land with an average basin slope of 36.04%.

### 3. Analysis Information

#### 3.1. *HEC-RAS*

A HEC-RAS hydraulic analysis was performed for the portion of the Toms Fork that has an impact on the BFE's across the property. HEC-RAS is designed to perform one-dimensional hydraulic calculations for a full network of natural and constructed channels. The steady flow system is designed for applications in floodplain management and flood insurance studies.

#### 3.2. *Analysis Limits*

The analysis information is based upon two foot interval aerial shot topography by Blue Mountain Aerial Mapping. The upstream analysis limit for Toms Fork is located approximately 1,337 feet upstream from the proposed stream crossing and represents the 28+65.327 section. The downstream analysis limit for Toms Fork is located approximately 1,564 feet downstream of the proposed stream crossing and represents the 10+00.000 section. These limits were selected so that the HEC-RAS model would accurately determine the base flood elevations on site and off site.

#### 3.3. *Flow Data*

The hydrologic analysis utilized USDA soil surveys for computation of drainage shed curve numbers, aerial topography and 3 meter West Virginia GIS Technical Center DEM to determine the drainage area(s) and time of concentration path(s). The peak 100-year discharge within the inundation area was determined through TR-55 SCS methodology. Time of concentration paths were calculated utilizing the SCS lag method. The hydrologic calculations for the drainage area were performed using HEC-HMS. See the table below for a summary of the flow conditions, and see Supplement 1 for the complete Drainage Computations.

<b>Stream</b>	<b>Drainage Area</b>	<b>Flow (cfs)</b>	<b>Note</b>
Upper Toms Fork	8,212.48 Ac.	3765.8	Upper Reach
Middle Toms Fork	1,132.16 Ac.	949.4	Middle Reach
Lower Toms Fork	604.16 Ac.	666.8	Lower Reach

### 3.4. Cross Section Data

The cross sections were employed at significant changes in site features. This includes major bends in the stream channel, areas of major contraction and expansion of the floodplain area, upstream and downstream of existing culverts, and at building obstructions (cross sections were compiled using Aerial Mapping by Blue Mountain Aerial Mapping).

### 3.5. Manning's n-value

The channel and overbank areas were assigned manning's n-values based on field review, site photographs, and close inspection of existing aerial photography. The chart below describes the manning's n values used in this study.

<b>Manning's n value</b>	<b>Description</b>	<b>Portion Used</b>
.035	Clean, straight, full, no rifts or deep pools, stones and weeds	Main Channel
.1	Heavy stand of timber, few down trees, little undergrowth, flow below branches	Floodplains (Normal)
.013	Asphalt	Floodplains
.035	High grass	Floodplains
.033	Rip Rap Dry Rubble	Floodplains
.06	Light Brush and trees, in summer	Floodplains
.08	Heavy stand of timber, few down trees, little undergrowth, flow below branches	Floodplains (Minimum)

## 4. Results

### 4.1. Existing Conditions

Since the site is in Zone "AE" floodplain area as shown on the FIRM, there has been a detailed study analysis with one foot interval base flood elevations established within the Doddridge County Flood Insurance Study (FIS) effective October 4, 2011. An existing conditions model was prepared based upon aerial topography and existing drainage computations. This information was processed in HEC-RAS to determine the existing conditions of the Base Flood Elevations and then compared with the FIS for accuracy.

### 4.2. Proposed Conditions

The proposed conditions model was based on the proposed topography for the site access road and proposed culverts in the stream. This information was added into the existing conditions cross sections, and then was processed in HEC-RAS to determine the proposed conditions of the Base Flood Elevations. A summary of elevation changes showing the

existing and proposed BFEs at the various cross sections has been provided below. As shown in the table, the proposed development will not increase the existing BFEs more than 0.5' throughout the project area and return to 0.0' at the upstream and downstream termini of the study area.

<b>NEW MILTON COMPRESSOR STATION ACCESS ROAD FLOODPLAIN STUDY SUMMARY OF COMPUTED ELEVATIONS</b>					
<b>CROSS SECTION STATION</b>	<b>RIVER NAME</b>	<b>100 YEAR BASE FLOOD ELEVATION</b>			
		<b>DODDRIDGE COUNTY FIS MODEL*</b>	<b>EXISTING CONDITIONS MODEL</b>	<b>PROPOSED CONDITIONS MODEL</b>	<b>PROPOSED DIFFERENCE</b>
2865.327	Toms Fork	833.5	833.9	833.9	0.0
2579.832	Toms Fork	833.0	833.7	833.8	+ 0.1
2372.941	Toms Fork	832.8	833.2	833.3	+ 0.1
2123.812	Toms Fork	832.5	833.2	833.4	+ 0.2
2002.134	Toms Fork	832.3	832.8	832.9	+ 0.1
1929.868	Toms Fork	832.2	832.1	832.3	+ 0.2
1811.557	Toms Fork	832.1	831.7	832.1	+ 0.4
1726.403	Toms Fork	832.0	831.4	831.9	+ 0.5
1580.979	Toms Fork	831.8	831.6	832.0	+ 0.4
1528.223	Toms Fork	Culvert			
1483.221	Toms Fork	831.7	831.5	831.5	0.0
1421.670	Toms Fork	831.6	831.6	831.6	0.0
1293.596	Toms Fork	831.4	831.5	831.5	0.0
1000.000	Toms Fork	831.0	831.1	831.1	0.0

\* ELEVATIONS ARE INTERPOLATED FROM DODDRIDGE COUNTY FIS EFFECTIVE OCTOBER 4, 2011.

## 5. Conclusion

The results of this floodplain analysis indicate that there will be minimal changes in the 100 year base flood elevation and no impacts to upstream and downstream adjacent properties along Toms Fork. The largest increase in base flood elevation is 0.5' and is located on site directly upstream of the stream crossing.


**APPENDIX**

Exhibit A	FIRM Panel 54017C0230C
Exhibit B	Overall Plan
Exhibit C	Existing Conditions Plan
Exhibit D	Proposed Conditions Plan
Supplement 1	Drainage Computations
Supplement 2	HEC-RAS Analysis –Existing Conditions Summary
Supplement 3	HEC-RAS Analysis –Proposed Conditions Summary w/ Cross Sections

**Exhibit A**

**FIRM Panel 54017C0230C**





**PANEL 0230C**

**FIRM**  
**FLOOD INSURANCE RATE MAP**  
**DODDRIDGE COUNTY,**  
**WEST VIRGINIA**  
**AND INCORPORATED AREAS**

**PANEL 230 OF 325**  
 (SEE MAP INDEX FOR FIRM PANEL LAYOUT)

**CONTAINS:**

COMMUNITY	SUBRECS	PANEL	SHEET
DODDRIDGE COUNTY	540024	0230	C

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

**MAP NUMBER**  
**54017C0230C**  
**MAP REVISED**  
**OCTOBER 4, 2011**

Federal Emergency Management Agency





JOINS PANEL 0235


This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at [www.fmsc.fema.gov](http://www.fmsc.fema.gov).

**Exhibit B**  
**Overall Plan**



**LEGEND**

-  EX. DELINEATED STREAM
-  HEC-RAS STUDY CROSS SECTION
-  FEMA FLOOD ZONE "AE" PER FIRM #54017C0230C
-  EXISTING STRUCTURE



**NAVITUS ENGINEERING INC.**

151 Wady Hill Lane  
Winchester, Virginia 22602  
Telephone: (888) 662-4185  
www.navituseng.com

Engineering Survey Environmental GIS

CIRUS S. KUMP  
REGISTERED  
1978  
STATE OF  
WEST VIRGINIA  
PROFESSIONAL ENGINEER

07/16/2013

**ANTERO RESOURCES**

THIS DOCUMENT WAS PREPARED FOR:  
ANTERO RESOURCES CORPORATION

OVERALL PLAN


**NEW MILTON  
COMPRESSOR STATION  
ACCESS ROAD**

NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WV

SCALE: 1" = 200'


NEW MILTON  
JOB NO. ANT096

DATE: 07/16/2013






**Exhibit C**  
**Existing Conditions Plan**



**LEGEND**

	EXISTING 100-YR FLOODPLAIN
	FEMA FLOODPLAIN ZONE 'AE'
	HEC-RAS STUDY CROSS SECTION
	EX. DELINEATED STREAM

SCALE: 1" = 50'  
 NEW MILTON  
 JOB NO. ANT098  
 DATE: 07/16/2013



**EXISTING CONDITIONS PLAN**  
**NEW MILTON**  
**COMPRESSOR STATION**  
**ACCESS ROAD**  
 NEW MILTON DISTRICT  
 DODDRIDGE COUNTY, WV

ANTERO RESOURCES  
 CORPORATION  
 FOR:  
 THIS DOCUMENT  
 WAS PREPARED

07/16/2013






NAVITUS  
 ENGINEERING INC.  
 151 Windy Hill Lane, 2nd Fl.  
 Winchester, Virginia 22602  
 Telephone: (800) 662-4183  
 Fax: (540) 428-0658  
 www.navituseng.com


Engineering — Survey — Environmental — GIS

**Exhibit D**  
**Proposed Conditions Plan**



**LEGEND**

-  EX. DELINEATED STREAM
-  HEC-RAS STUDY CROSS SECTION
-  FEMA FLOODPLAIN ZONE "AE"
-  EXISTING 100-YR FLOODPLAIN
-  PROPOSED 100-YR WSE



GRID NORTH AND ELEVATIONS SHOWN  
HEREON WERE ESTABLISHED BY SURVEY

**NAVITUS**  
ENGINEERING INC.

151 Wandy Hill Lane  
Winchester, Virginia 25002  
Telephone: (889) 662-4185  
www.navituseng.com


Engineering Survey Environmental GIS



**ANTERO RESOURCES**  
THIS DOCUMENT  
WAS PREPARED  
FOR:  
ANTERO RESOURCES  
CORPORATION

PROPOSED CONDITIONS PLAN  
**NEW MILTON  
COMPRESSOR STATION  
ACCESS ROAD**  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WV

SCALE: 1" = 50'  
NEW MILTON  
JOB NO. ANT096  
DATE: 07/16/2013





**Supplement 1**  
**Drainage Computations**



# DRAINAGE MAP


USGS 7.5 OXFORD QUAD MAP



USGS 7.5 NEW MILTON QUAD MAP

KEY	HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)
A	UPPER TOMS FORK	12.832
B	MIDDLE TOMS FORK	1.769
C	LOWER TOMS FORK	0.944
TOTAL		15.545


WEST VIRGINIA STATE PLANE  
 COORDINATE SYSTEM  
 NORTH ZONE, NAD83  
 ELEVATION BASED ON NAVD88  
 ESTABLISHED BY SURVEY GRADE GPS  
 & OPUS POST-PROCESSING



DRAINAGE MAP  
**NEW MILTON**  
**COMPRESSOR STATION**  
**ACCESS ROAD**  
 NEW MILTON DISTRICT  
 DODDRIDGE COUNTY, WV

SCALE: 1" = 4000'  
 NEW MILTON  
 JOB NO. ANT096  
 DATE: 07/16/2013

**ANTERO RESOURCES**  
 THIS DOCUMENT  
 WAS PREPARED  
 FOR:  
 ANTERO RESOURCES  
 CORPORATION



**NAVITUS**  
 ENGINEERING INC.

131 Windy Hill Lane  
 Winchester, Virginia 25602  
 Telephone: (688) 662-4183  
 www.navituseng.com

Engineering Survey Environmental GIS

Project: New Milton

Simulation Run: Existing

Start of Run: 11Jul2013, 00:00

Basin Model: Existing

End of Run: 12Jul2013, 00:05

Meteorologic Model: 100 YR

Compute Time: 11Jul2013, 08:20

Control Specifications: Control 1

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
Upper Toms Fork	12.832	3765.8	11Jul2013, 14:10	1397
Reach-1	12.832	3765	11Jul2013, 14:40	1380.7
Middle Toms Fork	1.77	949.1	11Jul2013, 12:55	199.5
Junction-1	14.602	4015.3	11Jul2013, 14:35	1580.2
Reach-2	14.602	4015.1	11Jul2013, 14:55	1567.8
Lower Toms Fork	0.944	666.8	11Jul2013, 12:35	107.3
Downstream	15.546	4101.3	11Jul2013, 14:55	1675.1

**Supplement 2**  
**HEC-RAS Analysis –Existing Conditions Summary**

HEC-RAS Version 4.1.0 Jan 2010  
U.S. Army Corps of Engineers  
Hydrologic Engineering Center  
609 Second Street  
Davis, California

```
X      X  XXXXXX   XXXX       XXXX       XX       XXXX
X      X  X       X   X       X   X       X   X       X
X      X  X       X       X       X   X       X   X       X
XXXXXXXX XXXX     X       XXX XXXX     XXXXXX     XXXX
X      X  X       X       X   X       X   X       X       X
X      X  X       X   X       X   X       X   X       X
X      X  XXXXXX   XXXX       X   X       X   X       XXXXX
```

\*\*\*\*\*

PROJECT DATA

Project Title: Saddle2  
Project File : Saddle2.prj  
Run Date and Time: 7/16/2013 7:49:15 PM

Project in English units

\*\*\*\*\*

PLAN DATA

Plan Title: Existing  
Plan File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.p01

Geometry Title: Existing  
Geometry File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.g01

Flow Title : Existing-Revised  
Flow File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.f02

Plan Summary Information:

Number of:	Cross Sections =	13	Multiple Openings =	0
	Culverts =	0	Inline Structures =	0
	Bridges =	0	Lateral Structures =	0

Computational Information

water surface calculation tolerance	=	0.001
Critical depth calculation tolerance	=	0.001
Maximum number of iterations	=	20
Maximum difference tolerance	=	0.3

Flow tolerance factor = 0.001

Computation Options

Critical depth computed only where necessary
Conveyance Calculation Method: At breaks in n values only
Friction Slope Method: Average Conveyance
Computational Flow Regime: Subcritical Flow

\*\*\*\*\*

FLOW DATA

Flow Title: Existing-Revised
Flow File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing
Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.f02

Flow Data (cfs)

\*\*\*\*\*
\* River Reach RS \* PF 1 \*
\* Toms Fork Toms Fork 2865.327\* 4015.3 \*
\*\*\*\*\*

Boundary Conditions

\*\*\*\*\*
\* River Reach Profile \* Upstream Downstream \*
\* Toms Fork Toms Fork PF 1 \* Known WS = 833.5 Known WS = 831.1 \*
\*\*\*\*\*

\*\*\*\*\*

GEOMETRY DATA

Geometry Title: Existing
Geometry File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage
Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.g01

CROSS SECTION

RIVER: Toms Fork
REACH: Toms Fork RS: 2865.327

INPUT

Description:

Station Elevation Data num= 100
Table with 10 columns: Sta, Elev, Sta, Elev, Sta, Elev, Sta, Elev, Sta, Elev. Data rows include values like 0, 850, 2.89, 848, 3.73, 847.42, 5.78, 846, 8.24, 844.95.

Saddle2.rep

44.6	841.93	49.67	841.3	52.98	840.89	54.84	840.66	56.84	840.4
56.98	840.39	59.93	840	62.2	838.99	64.42	838	66.42	837.11
68.93	836	77.13	835.38	80.1	835.15	89.55	834.48	91.63	834.33
96.42	834	96.46	834	103.31	833.74	108.11	833.57	115.2	833.31
120.18	833.17	144.96	832.42	149.19	832.28	158.3	832	161.69	831.77
162.91	831.7	163.61	831.66	172.16	831.13	177.1	830.87	181.93	830.59
192.98	830.03	193.14	830.02	193.52	830	195.11	829.63	202.28	828
203.58	827.9	204.23	827.86	205.83	827.75	208.78	827.55	218.92	826.86
225.69	826.43	226.36	826.39	227.77	826.3	228.45	826.25	232.59	826
233.5	824.89	234.03	824.24	234.61	823.57	239.85	823.64	241.59	823.67
250.02	823.8	269.19	824.13	281.09	824.36	281.53	824.87	281.9	825.29
282.64	826	283.77	827.33	285.69	827.68	287.35	828	290.48	828
292.08	828.23	293.87	828.48	299.55	829.32	303.22	829.8	304.12	830
305.84	831.05	306.98	831.74	307.38	832	309.66	833.4	310.6	834
312.52	835.18	313.8	836	315.48	837.04	316.99	838	318.62	839.12
319.93	840	321.46	841.28	322.33	842	324.02	843.41	324.73	844
326.6	845.56	327.13	846	329.22	847.75	329.52	848	331.9	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	232.59	.035	287.35	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	232.59	287.35		212.2	282.13	186.24	.1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 834.43	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.57	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.86	* Reach Len. (ft)	* 212.20	* 282.13	* 186.24
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 409.12	* 522.91	* 97.01
* E.G. Slope (ft/ft)	*0.001252	* Area (sq ft)	* 409.12	* 522.91	* 97.01
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 455.58	* 3431.24	* 128.48
* Top width (ft)	* 210.17	* Top width (ft)	* 132.39	* 54.76	* 23.03
* Vel Total (ft/s)	* 3.90	* Avg. vel. (ft/s)	* 1.11	* 6.56	* 1.32
* Max Chl Dpth (ft)	* 10.29	* Hydr. Depth (ft)	* 3.09	* 9.55	* 4.21
* Conv. Total (cfs)	*113459.8	* Conv. (cfs)	* 12873.3	* 96955.9	* 3630.5
* Length wtd. (ft)	* 268.25	* Wetted Per. (ft)	* 132.76	* 57.29	* 24.27
* Min Ch El (ft)	* 823.57	* Shear (lb/sq ft)	* 0.24	* 0.71	* 0.31
* Alpha	* 2.43	* Stream Power (lb/ft s)	* 331.90	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.27	* Cum Volume (acre-ft)	* 19.22	* 20.54	* 6.95
* C & E Loss (ft)	* 0.05	* Cum SA (acres)	* 5.62	* 2.27	* 1.59

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 2579.832

INPUT

Saddle2.rep

Description:

Station Elevation Data		num= 93		Sta		Elev		Sta		Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	2.44	848	2.66	847.82	4.89	846	5.28	845.68		
7.32	844	7.99	843.55	10.04	842	12.78	841.08	16.18	840		
20.07	838.81	22.77	838	31.3	838	32.34	838.23	36.84	839.24		
45.36	839.17	54.84	838.89	61	838.03	61.18	838	62.93	837.73		
65.72	837.27	73.51	836	74.45	835.56	77.9	834	80.43	832.85		
82.31	832	84.12	831.18	87.67	829.59	88.79	829.09	90.47	828.4		
91.43	828	93.28	827.16	95.87	826	99.12	824.4	99.91	824		
100.45	823.72	100.69	823.6	100.92	823.47	143.75	823.47	144.94	823.92		
145.14	824	151.82	825.23	155.09	825.97	155.22	826	157.83	826		
174.68	826.59	176.96	826.69	179.05	826.72	180.73	826.74	182.27	826.82		
183.75	826.84	185.06	826.91	186.58	826.95	188.92	827.07	190.49	827.12		
195.23	827.34	196.43	827.39	197.44	827.44	206.09	827.82	206.63	827.85		
210.34	828	214.91	828.57	218.82	829.06	221.21	829.36	222.27	829.51		
225.8	830	227.87	830.31	228.23	830.38	230.19	830.82	233.42	831.47		
235.56	832	238.7	832.97	242.37	834	244.36	834.61	248.21	835.78		
248.76	835.95	248.94	836	254.04	837.23	256.99	838	257.34	838		
262.74	838.68	270.79	839.6	273.44	840	283.77	841.65	285.91	842		
289.24	842.78	294.7	844	303.19	845.52	305.76	846	310.28	847.08		
313.75	847.86	314.38	848	323.1	850						

Manning's n Values		num= 3		Sta		n Val	
Sta	n Val	Sta	n Val	Sta	n Val	Sta	n Val
0	.1	95.87	.035	155.09	.1		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	95.87	155.09		271.1	188.24	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 834.11	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.41	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.70	* Reach Len. (ft)	* 271.10	* 188.24	* 66.66
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 67.00	* 584.27	* 480.81
* E.G. slope (ft/ft)	* 0.000851	* Area (sq ft)	* 67.00	* 584.27	* 480.81
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 67.42	* 3295.57	* 652.31
* Top Width (ft)	* 162.73	* Top width (ft)	* 17.31	* 59.22	* 86.20
* Vel Total (ft/s)	* 3.55	* Avg. Vel. (ft/s)	* 1.01	* 5.64	* 1.36
* Max chl Dpth (ft)	* 10.23	* Hydr. Depth (ft)	* 3.87	* 9.87	* 5.58
* Conv. Total (cfs)	* 137645.8	* Conv. (cfs)	* 2311.1	* 112973.3	* 22361.4
* Length Wtd. (ft)	* 183.85	* Wetted Per. (ft)	* 18.94	* 60.11	* 86.83
* Min ch El (ft)	* 823.47	* Shear (lb/sq ft)	* 0.19	* 0.52	* 0.29
* Alpha	* 2.10	* Stream Power (lb/ft s)	* 323.10	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	* 18.06	* 16.95	* 5.71
* C & E Loss (ft)	* 0.03	* Cum SA (acres)	* 5.26	* 1.90	* 1.35

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than

1.4. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 2372.941

INPUT

Description:

Station Elevation Data num= 105

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	1.82	848	2.33	847.47	3.36	846.39	3.78	846
6.59	844.33	7.14	844	10.17	842.28	10.68	842	13.68	840.29
14.22	840	17.19	838.31	17.76	838	19.76	837.02	21.03	837.71
30.82	836.97	45.33	836.96	53.11	837.04	58.14	836.39	62.87	836
70.69	835.06	78.76	834	82.37	833.41	90.69	832	92.24	831.76
95.46	831.2	102.19	830	104.15	829.57	105.93	829.26	108.63	828.71
111.2	828.33	113.43	828	114.56	827.83	114.6	827.82	114.66	827.81
114.94	827.78	118.37	827.27	120.84	826.94	122.59	826.68	127.81	826
128.07	825.95	128.15	825.95	128.23	825.93	131.37	825.41	132.07	825.31
133.39	825.14	134.95	824.85	136.9	824.63	140.69	824	140.95	824
141.56	823.88	142.39	823.69	142.76	823.59	143.18	823.47	161.64	823.47
162.23	823.66	162.96	823.86	163.49	824	170.49	824.97	178.34	826
184.38	826.66	190.63	827.37	196.22	828	204.78	828.89	209.26	829.26
213.01	829.61	214.44	829.73	215.21	829.78	215.72	829.81	218.51	830
221.09	830.31	222.16	830.45	226.82	831.04	233.45	832	259.72	833.51
267.46	833.9	270.43	834	277.5	834	293.51	834.86	300.19	835.16
303.03	835.27	310.96	835.62	312.48	835.69	319.76	836	323.88	836.36
332.03	837.03	340.66	837.87	342.02	838	347.21	839.1	350.16	839.67
350.48	839.73	351.82	840	353.9	840.42	357.17	841.11	360.16	841.74
361.41	842	366.93	843.14	371.51	844	376.07	845.15	379.47	846
382.67	846.77	388.2	848	388.9	848.16	389.32	848.25	397.14	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.035	136.9	.035	170.49	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 136.9 170.49 494.68 209.34 278.69 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 833.87	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.66	* Wt. n-Val.	* 0.035	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.21	* Reach Len. (ft)	* 494.68	* 209.34	* 278.69
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 239.21	* 315.42	* 309.90
* E.G. Slope (ft/ft)	* 0.001691	* Area (sq ft)	* 239.21	* 315.42	* 309.90
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 1126.07	* 2438.45	* 450.78



Saddle2.rep

* Top Width (ft)	* 170.84	* Top Width (ft)	* 53.32	* 33.59	* 83.93
* Vel Total (ft/s)	* 4.64	* Avg. Vel. (ft/s)	* 4.71	* 7.73	* 1.45
* Max Chl Dpth (ft)	* 9.74	* Hydr. Depth (ft)	* 4.49	* 9.39	* 3.69
* Conv. Total (cfs)	* 97647.1	* Conv. (cfs)	* 27384.5	* 59300.1	* 10962.5
* Length Wtd. (ft)	* 267.77	* Wetted Per. (ft)	* 54.02	* 33.85	* 84.37
* Min Ch El (ft)	* 823.47	* Shear (lb/sq ft)	* 0.47	* 0.98	* 0.39
* Alpha	* 1.98	* Stream Power (lb/ft s)	* 397.14	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.25	* Cum Volume (acre-ft)	* 17.10	* 15.01	* 5.11
* C & E Loss (ft)	* 0.12	* Cum SA (acres)	* 5.04	* 1.70	* 1.22

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
 This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork      RS: 2123.812

INPUT  
 Description:

Station Elevation Data		num= 145							
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	7.61	848.12	8.1	848	11.48	846.85	14.02	846
17.32	844.89	20.19	844	29.09	842.54	32.44	842	39.97	840.57
41	840.36	41.44	840.27	41.87	840.18	42.76	840	44.29	839.85
44.87	839.81	45.61	839.77	58.05	838.76	60.93	838.66	73.97	838
80.16	838	86.28	837.78	88.03	837.76	89.01	837.75	89.33	837.75
96.23	837.46	96.83	837.47	114.62	837.25	123.08	837.03	153.21	836.5
165.6	836.24	167.39	836.2	176.66	836	183.88	836	185.94	835.94
186.45	835.92	193.78	835.74	197.53	835.66	200.81	835.61	203.09	835.51
207.46	835.41	211.32	835.23	215.79	835.06	217.31	834.99	218.58	834.93
219.59	834.88	221.23	834.79	225.89	834.56	228.39	834.42	237.61	834
240.15	833.94	250.89	833.92	251.23	833.98	252.74	834.04	256.18	834.13
266.1	834.44	276.79	834.81	279.36	834.6	282	834.51	292.41	834.43
302.29	834.14	305	834	306.65	834	318.72	833.83	322.62	833.82
326.83	833.77	349.34	833.52	366.28	833.31	381.19	833.17	409.51	832.76
442.18	832	458.66	832	459.09	831.91	460.58	831.67	467.09	830.52
470.93	830	472.47	829.86	473.63	829.73	474.35	829.63	476.54	829.59
478.33	829.44	480.51	829.24	482.35	829.05	484.53	829.08	493.14	828.72
510.22	828	540.14	828	541.2	827.11	542.5	826	543.18	825.38
544.61	824	544.96	823.68	545.31	822.47	562.34	822.47	590.93	822.47
591.34	823.26	591.75	823.47	592.68	823.87	592.98	824	596.16	824.59
597.7	824.75	600.18	825.16	601.92	825.29	603.14	825.47	603.8	825.56
606.61	825.79	609.14	825.89	609.21	825.89	611.75	826	618.47	826
623.51	826.14	623.89	826.15	627.54	826.26	629.08	826.31	634.67	826.43
637.3	826.52	638.18	826.54	665.48	826.98	667.38	826.96	668.91	827.09
670.46	827.22	674.09	827.49	676.03	827.52	680.97	828	682.63	828.93
684.49	830	686.81	831.3	688.03	832	689.62	832.9	691.61	834

Saddle2.rep

693.43	834.9	695.67	836	699.67	837.95	699.76	838	699.9	838.07
703.8	840	708.04	841.9	708.27	842	708.74	842.21	712.7	844
716.95	845.96	717.03	846	717.11	846.04	721.13	848	725.2	850

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 540.14 .035 611.75 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 540.14 611.75 4.85 111.36 132.72 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

```

*****
* E.G. Elev (ft) * 833.50 * Element * Left OB * Channel * Right OB *
* Vel Head (ft) * 0.26 * Wt. n-Val. * 0.100 * 0.035 * 0.100 *
* W.S. Elev (ft) * 833.24 * Reach Len. (ft) * 4.85 * 111.36 * 132.72 *
* Crit W.S. (ft) * * * Flow Area (sq ft) * 414.05 * 700.28 * 477.75 *
* E.G. Slope (ft/ft) * 0.000581 * Area (sq ft) * 414.05 * 700.28 * 477.75 *
* Q Total (cfs) * 4015.30 * Flow (cfs) * 271.80 * 3179.77 * 563.73 *
* Top width (ft) * 316.78 * Top Width (ft) * 166.68 * 71.61 * 78.49 *
* Vel Total (ft/s) * 2.52 * Avg. Vel. (ft/s) * 0.66 * 4.54 * 1.18 *
* Max Chl Dpth (ft) * 10.77 * Hydr. Depth (ft) * 2.48 * 9.78 * 6.09 *
* Conv. Total (cfs) * 166543.1 * Conv. (cfs) * 11273.4 * 131887.8 * 23381.9 *
* Length wtd. (ft) * 100.93 * Wetted Per. (ft) * 166.93 * 74.95 * 79.93 *
* Min Ch El (ft) * 822.47 * Shear (lb/sq ft) * 0.09 * 0.34 * 0.22 *
* Alpha * 2.60 * Stream Power (lb/ft s) * 725.20 * 0.00 * 0.00 *
* Frctn Loss (ft) * 0.08 * Cum Volume (acre-ft) * 13.40 * 12.57 * 2.59 *
* C & E Loss (ft) * 0.03 * Cum SA (acres) * 3.79 * 1.45 * 0.70 *
*****
  
```

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 2002.134

INPUT

Description:

Station Elevation Data num= 120

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	5.75	848.69	9.25	848	12.54	847.07	14.98	846.36
16.39	846	21.54	844.57	23.9	844	28.14	843.37	29.49	843.11
31.27	842.82	35.31	842	36.84	841.71	44.09	840.36	45.66	840.07
46.05	840	58.46	838.43	59.73	838.27	60.32	838.19	61.51	838
68.14	838	84.71	837.13	87.17	837.04	90.91	836.93	93.76	836.87
96.92	836.74	102.52	836.63	109.38	836.49	117.27	836.33	120.05	836.28

Saddle2.rep

121.42	836.22	123.9	836.21	135.46	836	152.3	836	152.93	835.97
153.56	835.95	175.95	834.99	193.37	834.28	196.51	834.15	200.1	834
205.39	833.72	210.34	833.1	210.74	833.15	211.69	833.31	213.96	833.36
216.02	833.45	235.66	834	252.32	834	256.05	833.9	257.04	833.88
276.33	833.31	279.34	833.28	281.75	833.27	295.27	832.92	301.58	832.91
307.93	832.77	318.74	832.74	323.19	832.66	337.48	832.62	342.49	832.54
382.49	832.24	402.49	832	443.94	832	448.99	831.31	452.91	830.94
462.54	830	463.53	829.84	463.96	829.78	467.24	829.24	468.14	829.14
470.59	828.79	471.7	828.67	472.1	828.64	472.57	828.59	474.78	828.35
475.89	828.26	476.06	828.26	477.8	828	488.57	828	491.73	827.76
492.21	827.75	494.02	827.72	494.54	827.71	527.7	826.75	553.46	826
561.05	826	561.73	825.49	563.27	824	563.54	823.79	564.49	822.87
577.19	822.74	603.13	822.47	605.42	823.91	605.57	824	609.95	825.19
612.91	826	613.85	826.72	615.51	828	616.81	828.98	618.12	830
619.93	831.36	620.77	832	623.33	833.91	623.44	834	623.55	834.08
625.99	836	626.03	836.04	628.31	838	629.29	838.81	630.68	840
632.39	841.41	633.09	842	635.36	843.87	635.52	844	636.52	844.78
637.1	845.24	638.07	846	640.63	847.87	640.8	848	643.54	850

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 561.05 .035 612.91 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 561.05 612.91 5.33 72.27 84.5 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 833.38	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.58	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 832.80	* Reach Len. (ft)	* 5.33	* 72.27	* 84.50
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 644.97	* 500.64	* 30.24
* E.G. Slope (ft/ft)	* 0.001269	* Area (sq ft)	* 644.97	* 500.64	* 30.24
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 634.08	* 3350.23	* 30.98
* Top Width (ft)	* 315.31	* Top width (ft)	* 254.52	* 51.86	* 8.93
* Vel Total (ft/s)	* 3.41	* Avg. Vel. (ft/s)	* 0.98	* 6.69	* 1.02
* Max chl Dpth (ft)	* 10.33	* Hydr. Depth (ft)	* 2.53	* 9.65	* 3.38
* Conv. Total (cfs)	* 112718.3	* Conv. (cfs)	* 17800.2	* 94048.5	* 869.7
* Length Wtd. (ft)	* 64.92	* Wetted Per. (ft)	* 254.81	* 53.79	* 11.23
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.20	* 0.74	* 0.21
* Alpha	* 3.22	* Stream Power (lb/ft s)	* 643.54	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.11	* Cum Volume (acre-ft)	* 13.34	* 11.03	* 1.81
* C & E Loss (ft)	* 0.06	* Cum SA (acres)	* 3.77	* 1.29	* 0.57

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

Saddle2.rep

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 1929.868

INPUT

Description:

Station Elevation Data		num= 127		Sta Elev		Sta Elev		Sta Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	9.69	848.14	10.44	848	16.57	846.52	19	846
22.06	845.27	23.4	844.99	28.18	844	28.7	843.91	29.27	843.8
34.05	842.91	38.56	842	39.24	841.89	39.57	841.83	44.23	841.11
46.52	840.64	48.15	840.39	49.88	840	53.06	839.56	57.34	839.03
62.7	838	63.49	838	95.81	836.27	101.33	836.06	101.57	836.05
103.51	836	104.46	836	106.48	835.94	113.45	835.8	113.98	835.79
120.44	835.67	140.38	835.62	141.17	835.63	142.8	835.61	144.74	835.58
147.99	835.47	148.7	835.47	152.05	835.32	153.09	835.29	166.02	834.72
167.81	834.65	171.79	834.47	182.48	834	186.18	832.37	186.98	832
189.63	832	190.59	832.17	191.57	832.36	193.59	832.72	211.11	833.08
214.56	833.17	215.19	833.21	215.57	833.24	217.58	833.36	229.11	834
235.48	834	243.03	833.47	247.63	833.34	262.04	832.65	276.26	832.35
277.28	832.32	293.07	832	355.46	832	360.25	831.81	388.23	831.91
390.46	831.9	394.56	832	411.75	832	413.92	831.91	418.69	831.72
420.02	831.67	421.45	831.61	434.07	831.52	435.68	831.52	435.95	831.61
436.19	831.7	437.05	832	451.01	832	457.66	831.46	460.43	831.24
464.27	830.93	466.72	830.73	472.68	830	477.88	828.1	478.17	828
487.76	826.55	489.16	826.33	495.7	826	497.25	826	519.34	826
520.31	825.28	522.18	824	522.87	823.57	523.4	823.17	523.76	822.87
527.6	822.84	528.89	822.83	532.08	822.8	552.31	822.57	560.43	822.47
561.98	823.63	562.39	824	563.46	824.74	565.18	826	566.72	827.13
568.04	828	569.7	829.21	570.9	830	572.63	831.25	573.74	832
575.53	833.28	576.58	834	577.39	834.76	578.84	836	579.87	837.17
580.64	838	581.81	839.35	582.42	840	583.77	841.56	584.18	842
585.76	843.84	585.91	844	586.04	844.16	586.72	844.95	587.6	846
589.67	848	591.96	850						

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
0	.1	519.34	.035
		565.18	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	519.34	565.18		5.86	118.14	110.15	
						.1	.3

Ineffective Flow		num= 1	
Sta L	Sta R	Elev	Permanent
0	235.48	834	F

CROSS SECTION OUTPUT Profile #PF 1

\*\*\*\*\*  
 \* E.G. Elev (ft) \* 833.21 \* Element \* Left OB \* Channel \* Right OB \*

Saddle2.rep

* Vel Head (ft)	* 1.16	* Wt. n-val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 832.05	* Reach Len. (ft)	* 5.86	* 118.14	* 110.15
* Crit W.S. (ft)	* 829.15	* Flow Area (sq ft)	* 294.11	* 414.19	* 25.96
* E.G. Slope (ft/ft)	* 0.002530	* Area (sq ft)	* 294.26	* 414.19	* 25.96
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 259.41	* 3720.50	* 35.39
* Top width (ft)	* 286.29	* Top width (ft)	* 231.82	* 45.84	* 8.63
* Vel Total (ft/s)	* 5.47	* Avg. vel. (ft/s)	* 0.88	* 8.98	* 1.36
* Max Chl Dpth (ft)	* 9.58	* Hydr. Depth (ft)	* 1.29	* 9.04	* 3.01
* Conv. Total (cfs)	* 79822.8	* Conv. (cfs)	* 5156.9	* 73962.3	* 703.6
* Length Wtd. (ft)	* 106.42	* Wetted Per. (ft)	* 229.45	* 48.01	* 10.54
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.20	* 1.36	* 0.39
* Alpha	* 2.50	* Stream Power (lb/ft s)	* 591.96	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.25	* Cum Volume (acre-ft)	* 13.28	* 10.27	* 1.76
* C & E Loss (ft)	* 0.01	* Cum SA (acres)	* 3.74	* 1.21	* 0.55

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water

surface that had the least amount of error between computed and assumed values.

Warning: Divided flow computed for this cross-section.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 1811.557

INPUT

Description:

Station	Elevation	Data	num=	127	Sta	Elev	Sta	Elev	Sta	Elev
0	850	8.09	848.68	9.6	848.44	12.25	848	15.63	847.32	
17.53	847.03	22.85	846.14	23.34	846.05	23.62	846	29.14	845.01	
29.7	844.93	31.77	844.59	35.22	844	38.73	843.44	40.77	843.25	
44.36	842.76	49.7	842.06	50.03	842	54.63	840.79	58.16	840	
60.2	839.66	63.13	839.24	66.64	838.88	68.31	838.67	72.99	838.13	
73.95	838	87.5	836.44	90.85	836	91.66	836	100.94	835.61	
101.33	835.59	110.34	835.25	110.4	835.24	121.22	834.87	124.68	834.79	
125.19	834.78	128.31	834.73	131.18	834.66	139.14	834.59	139.43	834.59	
145.89	834.47	154.04	834.29	161.88	834	163.25	834	165.31	833.16	
168	832	173.5	832	173.52	832	175.04	832.3	193.36	832.94	
194.25	832.97	194.4	832.96	194.97	833.03	195.62	833.08	208.04	834	
229.9	834	238.7	833.13	240.06	833.08	246.53	832	265.48	832	
303.93	831.45	312.8	831.4	332.62	831	353.67	831.77	354.78	831.72	
359.46	831.02	369.02	830.99	369.43	831	369.91	830.99	370.02	830.99	
370.53	830.98	370.91	830.97	389.65	830.53	394.54	830.38	401.08	830.18	
406.7	830	407.31	829.79	412.33	828	413.45	827.6	414.68	827.16	
417.14	826.3	417.99	826	443.82	826	444.09	825.85	445.72	825.04	
447.77	824	447.95	823.91	449.82	822.87	459.79	822.8	489.1	822.47	

Saddle2.rep

489.21	822.59	489.36	822.75	490.51	824	490.88	824.38	492.37	826
493.93	827.55	494.37	828	497.57	830.56	499.37	832	499.82	832.35
501.88	834	503.33	835.14	504.41	836	505.89	837.68	506.17	838
506.24	838.08	507.77	840	508.33	840.71	509.35	842	510.56	843.55
510.91	844	511.55	844.84	512.54	846	513.19	846.66	514.51	848
516.01	849.18	517.12	850	518.94	851.43	519.47	851.82	519.7	852
521.72	853.59	522.26	854	524.41	855.7	524.8	856	527.06	857.79
527.34	858	530.07	860						

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 443.82 .035 492.37 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 443.82 492.37 17.98 85.13 75.99 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 832.78	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 1.04	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.74	* Reach Len. (ft)	* 17.98	* 85.13	* 75.99
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 268.92	* 424.04	* 18.26
* E.G. Slope (ft/ft)	* 0.002415	* Area (sq ft)	* 268.92	* 424.04	* 18.26
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 356.05	* 3637.59	* 21.66
* Top width (ft)	* 214.39	* Top Width (ft)	* 159.16	* 48.55	* 6.68
* Vel Total (ft/s)	* 5.65	* Avg. Vel. (ft/s)	* 1.32	* 8.58	* 1.19
* Max Chl Dpth (ft)	* 9.27	* Hydr. Depth (ft)	* 1.69	* 8.73	* 2.73
* Conv. Total (cfs)	* 81703.8	* Conv. (cfs)	* 7245.0	* 74018.2	* 440.6
* Length Wtd. (ft)	* 78.20	* Wetted Per. (ft)	* 159.93	* 50.86	* 8.82
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.25	* 1.26	* 0.31
* Alpha	* 2.10	* Stream Power (lb/ft s)	* 530.07	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	* 13.24	* 9.14	* 1.70
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 3.71	* 1.08	* 0.53

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.  
 Warning: Divided flow computed for this cross-section.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1726.403

INPUT

Description:

Station Elevation Data num= 111  
 Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
 \*\*\*\*\*

Saddle2.rep

0	850	7.69	848.75	12.67	848	13.53	847.86	13.88	847.81
14.58	847.69	23.99	846	24.2	845.96	24.7	845.87	35.04	844
35.58	844	35.72	843.97	36.71	843.76	44.45	842	50.81	840.91
56.16	840	62.16	839.16	70.39	838	76.77	836.99	82.9	836
107.43	834.59	111.92	834.32	113.55	834.23	114.44	834.18	115.04	834.14
118.29	834	133.54	833	145.97	832	153.68	832	153.78	832.03
154.17	832.11	170.85	832.35	172.32	832.36	172.33	832.36	172.33	832.35
172.36	832.35	172.46	832.35	172.61	832.34	172.88	832.33	173.84	832.26
177.54	832	261.15	832	263.09	831.66	263.15	831.66	264.41	831.43
264.73	831.44	265.31	831.48	266.23	831.31	267.04	831.34	274.24	831.18
277.67	831.06	279.87	830.91	303.11	830.11	303.13	830.11	303.2	830.11
313.87	830.99	332.27	830.68	338.82	830.44	346.78	830.13	350.22	830
354.85	828.9	358.99	828	361.29	827.15	364.99	826	368.69	826
374.3	826	386.59	824.73	394.79	824.26	396.56	824.16	399.37	824
400.62	823.5	401.24	823.25	402.13	822.87	415.76	822.73	440.37	822.47
441.28	823.54	441.62	824	442.72	825.29	443.28	826	446.77	827.59
447.66	828	451.15	831.19	452.07	832	453.87	833.62	454.27	834
454.56	834.26	456.73	836	458.44	837.72	458.72	838	459.92	839.21
460.72	840	461.32	840.61	462.7	842	463.86	843.24	464.51	844
465.71	845.39	466.11	845.85	466.23	846	466.54	846.24	468.77	848
470.01	848.97	471.31	850	472.48	850.91	473.86	852	474.93	852.84
476.4	854	477.37	854.77	478.94	856	481.17	857.79	481.43	858
485.12	860								

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 399.37 .035 441.62 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 399.37 441.62 25.62 144.25 127.32 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 832.60	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 1.25	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.35	* Reach Len. (ft)	* 25.62	* 144.25	* 127.32
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 318.03	* 363.95	* 35.79
* E.G. Slope (ft/ft)	* 0.002988	* Area (sq ft)	* 318.03	* 363.95	* 35.79
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 459.43	* 3496.90	* 58.97
* Top Width (ft)	* 185.33	* Top width (ft)	* 133.37	* 42.25	* 9.71
* Vel Total (ft/s)	* 5.59	* Avg. Vel. (ft/s)	* 1.44	* 9.61	* 1.65
* Max chl Dpth (ft)	* 8.88	* Hydr. Depth (ft)	* 2.38	* 8.61	* 3.68
* Conv. Total (cfs)	* 73457.0	* Conv. (cfs)	* 8404.9	* 63973.3	* 1078.8
* Length wtd. (ft)	* 130.95	* Wetted Per. (ft)	* 134.08	* 43.20	* 12.39
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.44	* 1.57	* 0.54
* Alpha	* 2.58	* Stream Power (lb/ft s)	* 485.12	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.25	* Cum Volume (acre-ft)	* 13.12	* 8.37	* 1.66
* C & E Loss (ft)	* 0.21	* Cum SA (acres)	* 3.65	* 0.99	* 0.52

sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 1580.979

INPUT

Description:

Station Elevation Data num= 105									
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	9.68	848	15.17	846.8	15.87	846.64	18.77	846
20.81	845.56	28	844	35.76	842.18	36.54	842	36.96	841.92
47.38	840	47.87	839.9	56.87	838	68.15	836.06	68.41	836.01
77.1	834.66	80.22	834.43	85.29	834	85.35	834	89.24	833.81
92.24	833.63	92.64	833.63	93.17	833.63	94.58	833.62	97.89	833.46
100.76	833.32	133.45	832	138.56	832	141.4	831.74	147.18	831.31
158.75	831.48	165.31	831.53	185.18	831.5	191.55	831.44	193.11	831.6
206.25	831.02	217.47	830.66	227.63	830.24	231.61	830.09	236.83	830
237.47	829.75	238.59	829.37	245.76	829.63	249.16	829.77	253.95	830
253.96	830	253.97	830	260.61	830	272.1	829.31	290.5	828
293.32	828	298.88	827.16	303.61	826.89	315.57	826	316.11	826
317.58	826	317.83	825.95	322.94	825.12	323.18	825.12	328.6	824.28
328.79	824.25	330.08	824	334.79	823.2	336.76	822.74	337.42	822.86
337.84	822.87	365.19	822.64	382.75	822.47	382.79	822.67	383	822.67
386.52	823.76	387.12	824	389.83	824.32	390.64	824.42	395.83	825.08
400.52	825.66	403.1	826	409.08	826.75	412.02	827.12	419.58	827.98
419.67	827.99	419.74	827.99	419.75	827.99	419.78	828	427.07	828
428.22	828.41	434.02	830	434.67	830.39	436.52	832	439.1	833.98
441.66	836	442.29	836.49	444.2	838	446.24	839.6	446.78	840
447.35	840.4	449.74	842	451.59	843.1	453.32	844	456.03	845.43
457.1	846	457.93	846.44	460.96	848	463.4	849.33	464.87	850

Manning's n Values num= 3					
Sta	n Val	Sta	n Val	Sta	n Val
0	.1	330.08	.035	387.12	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	330.08	387.12		123.76	97.42	118.65	.1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 832.14	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.56	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.59	* Reach Len. (ft)	* 123.76	* 97.42	* 118.65
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 371.62	* 500.61	* 227.20



* E.G. Slope (ft/ft)	*0.001341	* Area (sq ft)	* 371.62	* 500.61	* 227.20	*
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 383.83	* 3292.34	* 339.13	*
* Top width (ft)	* 292.23	* Top width (ft)	* 186.26	* 57.04	* 48.93	*
* Vel Total (ft/s)	* 3.65	* Avg. Vel. (ft/s)	* 1.03	* 6.58	* 1.49	*
* Max Chl Dpth (ft)	* 9.12	* Hydr. Depth (ft)	* 2.00	* 8.78	* 4.64	*
* Conv. Total (cfs)	*109636.6	* Conv. (cfs)	* 10480.5	* 89896.3	* 9259.8	*
* Length Wtd. (ft)	* 102.95	* Wetted Per. (ft)	* 186.77	* 57.55	* 50.01	*
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.17	* 0.73	* 0.38	*
* Alpha	* 2.68	* Stream Power (lb/ft s)	* 464.87	* 0.00	* 0.00	*
* Frctn Loss (ft)	* 0.14	* Cum Volume (acre-ft)	* 12.92	* 6.93	* 1.27	*
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 3.56	* 0.83	* 0.43	*

Warning: Divided flow computed for this cross-section.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1483.221

INPUT

Description:

Station Elevation Data		num= 119		Sta		Elev		Sta		Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	5.81	848	7.38	847.46	9.29	846.8	11.59	846		
12.45	845.72	17.64	844	22	842.63	23.96	842	28.51	840.53		
30.08	840	35.58	838.12	35.95	838	37.05	837.65	42.19	836		
46.82	834.38	47.91	834	52.05	832.41	53.12	832	53.33	831.92		
58.38	830	59.39	830	69.2	829.64	77.21	829.39	84.78	829.19		
91.53	828.99	94.05	828.92	103.42	828.67	104.03	828.65	110.46	828.46		
112.7	828.4	114.09	828.37	119.86	828.27	120.77	828.25	122.62	828.22		
123.19	828.21	132.4	828.09	132.67	828.09	133.01	828.08	134.54	828.07		
135.22	828.07	135.64	828.07	139.19	828.09	139.28	828.09	139.61	828.09		
139.88	828.09	140.15	828.09	143.01	828.18	152.35	828.3	153.73	828.36		
156.58	828.49	168.1	828.8	176.97	829.32	188.61	830	189.36	830.1		
191.09	830.42	197.36	830.41	210.1	830.63	218.76	830.09	220.05	830		
220.87	830	270.1	828.71	272.93	828.65	299.31	828	302.7	827.77		
303.52	827.77	306.38	827.68	320.02	827.07	325.65	826.82	326.24	826.81		
328.46	826.79	353.75	826	356.58	826	357.24	825.45	359.31	824		
360.1	823.52	362.29	822.03	382.46	822.33	401.54	822.42	405.94	823.87		
406.29	824	408.51	824.33	415.99	825.23	420.95	825.86	422.22	826		
425.52	827.67	426.14	828	429.24	829.72	429.75	830	429.89	830.02		
440.71	831.89	441.32	832	444.32	832	480.07	833.73	485.11	834		
492.49	835.38	495.7	836	499.07	836.62	506.5	838	512.87	839.45		
515.34	840	519.08	840.85	521.04	841.23	522.71	841.52	523.54	841.67		
525.58	842	527.64	842.31	530.45	842.83	534.69	843.56	536.71	844		
536.83	844	543.95	845.16	545.09	845.34	549.15	846	554.58	846.76		
563.93	848	564.84	848	566.68	848.39	572.35	850				

Manning's n Values num= 3

Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 356.58 .035 408.51 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 356.58 408.51 54.14 61.47 37.92 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

\*\*\*\*\*  
 \* E.G. Elev (ft) \* 831.98 \* Element \* Left OB \* Channel \* Right OB \*  
 \* Vel Head (ft) \* 0.47 \* Wt. n-val. \* 0.100 \* 0.035 \* 0.100 \*  
 \* W.S. Elev (ft) \* 831.51 \* Reach Len. (ft) \* 54.14 \* 61.47 \* 37.92 \*  
 \* Crit W.S. (ft) \* \* \* Flow Area (sq ft) \* 851.06 \* 461.38 \* 120.42 \*  
 \* E.G. Slope (ft/ft) \*0.001285 \* Area (sq ft) \* 851.06 \* 461.38 \* 120.42 \*  
 \* Q Total (cfs) \* 4015.30 \* Flow (cfs) \* 903.20 \* 2954.38 \* 157.72 \*  
 \* Top Width (ft) \* 384.11 \* Top Width (ft) \* 302.17 \* 51.93 \* 30.00 \*  
 \* Vel Total (ft/s) \* 2.80 \* Avg. vel. (ft/s) \* 1.06 \* 6.40 \* 1.31 \*  
 \* Max Chl Dpth (ft) \* 9.48 \* Hydr. Depth (ft) \* 2.82 \* 8.88 \* 4.01 \*  
 \* Conv. Total (cfs) \*112005.1 \* Conv. (cfs) \* 25194.4 \* 82411.1 \* 4399.7 \*  
 \* Length Wtd. (ft) \* 59.23 \* Wetted Per. (ft) \* 302.65 \* 53.46 \* 31.23 \*  
 \* Min Ch El (ft) \* 822.03 \* Shear (lb/sq ft) \* 0.23 \* 0.69 \* 0.31 \*  
 \* Alpha \* 3.88 \* Stream Power (lb/ft s) \* 572.35 \* 0.00 \* 0.00 \*  
 \* Frctn Loss (ft) \* 0.06 \* Cum Volume (acre-ft) \* 11.18 \* 5.86 \* 0.80 \*  
 \* C & E Loss (ft) \* 0.05 \* Cum SA (acres) \* 2.86 \* 0.70 \* 0.33 \*  
 \*\*\*\*\*

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1421.670

INPUT

Description:

Station Elevation Data		num= 114							
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	2.79	849.15	6.37	848	7.77	847.56	9.4	847.08
12.05	846.29	13.14	846	17.43	845.03	21.19	844.05	21.4	844
21.6	843.92	27.18	842	28.6	841.36	31.86	840	34.65	838.93
36.95	838	39.48	837.09	43.26	836.17	43.69	836.05	43.78	836.04
43.84	836.03	44.08	836	45.26	836	47.98	835.5	50.67	835.2
52.4	835.01	53.64	834.87	56.33	834.58	56.76	834.53	58.93	834.29
59.09	834.26	60.91	834	61.53	833.91	61.77	833.88	65.76	833.25
67.21	833.05	69.67	832.68	74.1	832	75.37	831.72	78.33	831.04
79.3	830.81	83.15	830	84.82	829.93	85.04	829.92	85.58	829.89
89.94	829.68	94.22	829.47	99.72	829.24	110.94	828.47	113.82	828.32
115.24	828.25	117.83	828	174.08	828	174.52	828.04	194.87	830
195.39	830.04	197.72	830.24	210.01	830.31	216.6	830.41	218.07	830.25
219.57	830.05	219.97	830	222.23	829.79	230.6	829.12	241.79	828.19
244.75	828	267.96	828	272.56	827.85	273.71	827.84	275.94	827.7
278.22	827.59	301.45	826	323.5	826	356.72	826	358.07	824.91

Saddle2.rep

359.23	824	359.84	823.54	362.77	821.27	387.26	822.16	393.71	822.38
411.92	823.65	414.58	824	416.84	824	418.53	825.41	418.9	825.72
419.26	826	419.65	826.31	421.76	828	424.27	830	435.33	830.62
437.01	830.73	456.8	832	472.29	832.9	493.97	834	495.74	834.51
500.32	836	502.54	836.66	507.57	838	509.02	838.37	515.42	840
517.32	840.46	523.35	842	525.17	842.45	527.3	843.03	531.03	844
538.61	844.9	543.35	845.45	545.39	845.69	547.61	846	547.81	846
553.14	846.84	558.54	847.64	560.73	848	567.55	850		

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	356.72	.035	424.27	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	356.72	424.27		284.66	127.14	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.87	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.32	* Wt. n-val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.56	* Reach Len. (ft)	* 284.66	* 127.14	* 14.01
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 978.83	* 575.77	* 20.58
* E.G. Slope (ft/ft)	* 0.000926	* Area (sq ft)	* 978.83	* 575.77	* 20.58
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 1016.45	* 2990.82	* 8.03
* Top width (ft)	* 373.80	* Top width (ft)	* 280.64	* 67.55	* 25.61
* Vel Total (ft/s)	* 2.55	* Avg. vel. (ft/s)	* 1.04	* 5.19	* 0.39
* Max Chl Dpth (ft)	* 10.29	* Hydr. Depth (ft)	* 3.49	* 8.52	* 0.80
* Conv. Total (cfs)	* 131983.2	* Conv. (cfs)	* 33410.6	* 98308.6	* 264.0
* Length Wtd. (ft)	* 164.00	* Wetted Per. (ft)	* 281.15	* 71.39	* 25.66
* Min Ch El (ft)	* 821.27	* Shear (lb/sq ft)	* 0.20	* 0.47	* 0.05
* Alpha	* 3.14	* Stream Power (lb/ft s)	* 567.55	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.12	* Cum Volume (acre-ft)	* 10.04	* 5.13	* 0.74
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 2.50	* 0.62	* 0.30

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork  
 RS: 1293.596

INPUT

Description:

Station Elevation Data num= 131

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	4.12	848	8.06	846.06	8.17	846	8.81	845.68
12.19	844	12.67	843.76	16.32	842	21.32	840.26	22.02	840
22.88	839.69	23.71	839.41	27.76	838	30.51	837.06	33.76	836
35.14	835.59	43.54	835.21	44.85	835.17	45.09	835.16	45.37	835.14
46.01	835.06	52.66	834.02	52.75	834	52.76	834	52.81	833.98

Saddle2.rep

57.47	832	61.78	831.6	64.46	831.35	70.98	830.78	77.87	830.09
78.18	830.06	78.72	830	83.23	829.79	84.2	829.74	90.44	829.43
96.17	829.17	104.55	828.86	106.6	828.82	107.4	828.77	113.81	829.28
116.59	829.47	116.83	829.46	116.9	829.46	127.6	828.54	136.41	828.39
140.21	828.11	141.37	828.01	141.44	828	146.09	826.7	148.09	826.12
148.31	826.05	148.61	826	150.46	826	151.22	826.07	153.3	826.23
153.77	826.17	156.73	826.29	164.02	826	170.8	826	174.64	825.61
175.18	825.62	175.49	825.64	183.13	825.23	183.52	825.24	184.54	825.29
187.88	825.12	189.56	825.18	209.18	825.12	214.39	825	221.13	824.84
227.6	824.69	228.7	824.66	236.9	824.44	243.38	824.3	257.03	824
259.48	822.47	260.32	821.95	260.94	821.57	261.45	821.27	308.31	821.27
308.52	821.4	308.8	821.51	310.32	821.96	310.46	822	314.14	823
319.94	824	319.95	824	323.41	824.63	327.21	825.87	327.4	825.93
327.57	826	328.17	826.28	331.9	828	333.47	828.78	334.86	829.52
335.72	830	337.6	830	376.51	830	434.08	831.68	435.98	831.69
439.81	831.83	440.38	831.83	444.86	831.97	445.9	832	450.97	832.69
452.42	832.95	456.13	833.55	457.6	833.77	459.01	834	463.1	834.77
468.93	836	473.04	836.97	475.41	837.5	477.76	838	482.57	838.97
485.12	839.48	487.6	840	490.72	840.62	493.43	841.09	495.45	841.46
498.55	842	501.14	842.35	510.55	844	510.81	844.04	520.74	845.8
521.82	845.99	521.85	846	522.07	846.04	533.57	848	536.16	848.49
544.51	850								

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	257.03	.035	335.72	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	257.03	335.72		379.96	235.75	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.73	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.24	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.49	* Reach Len. (ft)	* 379.96	* 235.75	* 67.58
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 887.08	* 698.33	* 98.87
* E.G. Slope (ft/ft)	*0.000611	* Area (sq ft)	* 887.08	* 698.33	* 98.87
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 895.91	* 3081.25	* 38.14
* Top Width (ft)	* 364.64	* Top width (ft)	* 194.08	* 78.69	* 91.87
* Vel Total (ft/s)	* 2.38	* Avg. vel. (ft/s)	* 1.01	* 4.41	* 0.39
* Max Chl Dpth (ft)	* 10.22	* Hydr. Depth (ft)	* 4.57	* 8.87	* 1.08
* Conv. Total (cfs)	*162409.9	* Conv. (cfs)	* 36237.5	*124629.8	* 1542.6
* Length Wtd. (ft)	* 231.75	* Wetted Per. (ft)	* 194.61	* 81.02	* 91.89
* Min Ch El (ft)	* 821.27	* Shear (lb/sq ft)	* 0.17	* 0.33	* 0.04
* Alpha	* 2.67	* Stream Power (lb/ft s)	* 544.51	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	* 3.95	* 3.27	* 0.72
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 0.95	* 0.41	* 0.28

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1000.000

INPUT

Description:

Station Elevation		Data		num= 116		Sta Elev		Sta Elev		Sta Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	.26	849.64	1.5	848	2.99	846	3.07	845.88		
4.81	843.56	5.98	842	6.08	841.88	7.5	840	7.81	839.63		
9.02	838	9.72	837.47	11.66	836	13.76	834.45	14.37	834		
16.27	832.6	17.09	832	17.85	831.92	30.72	830.59	44.39	830.01		
44.63	830	45.04	829.98	46.91	829.91	49.1	829.82	56.19	828.94		
64.04	828	65.22	827.34	67.37	826	68.79	825.02	70.4	824		
72.12	823.16	74.22	822	74.83	821.71	75.57	821.27	103.45	821.27		
104.71	821.26	104.99	821.33	105.34	821.44	106.87	822	111.85	823.77		
112.67	824	117.18	825.27	120.39	826	125.39	826.29	127.25	826.41		
131	826.54	132.8	826.64	134.71	826.73	135.12	826.75	136.89	826.83		
139.24	826.93	141.51	827.02	146.36	827.18	148.33	827.25	149.98	827.29		
151.35	827.32	153.84	827.41	154.85	827.43	156.24	827.48	157.49	827.51		
158.19	827.53	158.7	827.55	160.43	827.56	160.84	827.58	161.3	827.6		
161.9	827.63	163.96	827.58	164.7	827.62	166.92	827.51	167.83	827.56		
168.62	827.6	169.33	827.64	173.57	827.47	209.25	827.32	211.63	827.36		
213.59	827.39	215.1	827.41	220.28	827.46	247.59	828	260.33	828		
264.01	828.05	265.31	828.07	266.01	828.08	267.24	828.1	349.67	828.76		
354.21	828.9	359.57	829.06	360.66	829.06	365.65	829.23	369.72	829.39		
372.38	829.49	376.5	829.66	382.67	829.92	383.11	829.93	384.54	830		
398.78	831.6	401.74	832	404.21	832.82	407.8	834	411.97	835.59		
413.07	836	414.97	836.81	417.7	838	419.82	838.96	422.17	840		
426.51	841.74	427.16	842	428.24	842.38	432.79	844	437.73	845.68		
438.63	846	439.07	846.15	440.44	846.61	443.79	847.72	444.64	848		
450.39	850										

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
0	.013	49.1	.035
		120.39	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	49.1	120.39		1	1		.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.50	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.40	* Wt. n-Val.	* 0.013	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.10	* Reach Len. (ft)	*	*	*
* Crit W.S. (ft)	* 828.88	* Flow Area (sq ft)	* 17.78	* 509.01	* 827.09

Saddle2.rep

* E.G. Slope (ft/ft)	*0.001447	* Area (sq ft)	* 17.78	* 509.01	* 827.09
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 64.43	* 2974.55	* 976.32
* Top width (ft)	* 368.54	* Top width (ft)	* 23.31	* 71.29	* 273.94
* Vel Total (ft/s)	* 2.97	* Avg. vel. (ft/s)	* 3.62	* 5.84	* 1.18
* Max Chl Dpth (ft)	* 9.84	* Hydr. Depth (ft)	* 0.76	* 7.14	* 3.02
* Conv. Total (cfs)	*105549.1	* Conv. (cfs)	* 1693.7	* 78191.2	* 25664.2
* Length Wtd. (ft)	*	* Wetted Per. (ft)	* 23.36	* 73.96	* 274.08
* Min Ch El (ft)	* 821.26	* Shear (lb/sq ft)	* 0.07	* 0.62	* 0.27
* Alpha	* 2.94	* Stream Power (lb/ft s)	* 450.39	* 0.00	* 0.00
* Frctn Loss (ft)	*	* Cum volume (acre-ft)	*	*	*
* C & E Loss (ft)	*	* Cum SA (acres)	*	*	*

\*\*\*\*\*

SUMMARY OF MANNING'S N VALUES

River: Toms Fork

* Reach	* River Sta.	* n1	* n2	* n3
*Toms Fork	* 2865.327	* .1*	* .035*	* .1*
*Toms Fork	* 2579.832	* .1*	* .035*	* .1*
*Toms Fork	* 2372.941	* .035*	* .035*	* .1*
*Toms Fork	* 2123.812	* .1*	* .035*	* .1*
*Toms Fork	* 2002.134	* .1*	* .035*	* .1*
*Toms Fork	* 1929.868	* .1*	* .035*	* .1*
*Toms Fork	* 1811.557	* .1*	* .035*	* .1*
*Toms Fork	* 1726.403	* .1*	* .035*	* .1*
*Toms Fork	* 1580.979	* .1*	* .035*	* .1*
*Toms Fork	* 1483.221	* .1*	* .035*	* .1*
*Toms Fork	* 1421.670	* .1*	* .035*	* .1*
*Toms Fork	* 1293.596	* .1*	* .035*	* .1*
*Toms Fork	* 1000.000	* .013*	* .035*	* .1*

\*\*\*\*\*

SUMMARY OF REACH LENGTHS

River: Toms Fork

* Reach	* River Sta.	* Left	* Channel	* Right
*Toms Fork	* 2865.327	* 212.2*	* 282.13*	* 186.24*
*Toms Fork	* 2579.832	* 271.1*	* 188.24*	* 66.66*
*Toms Fork	* 2372.941	* 494.68*	* 209.34*	* 278.69*
*Toms Fork	* 2123.812	* 4.85*	* 111.36*	* 132.72*
*Toms Fork	* 2002.134	* 5.33*	* 72.27*	* 84.5*
*Toms Fork	* 1929.868	* 5.86*	* 118.14*	* 110.15*
*Toms Fork	* 1811.557	* 17.98*	* 85.13*	* 75.99*
*Toms Fork	* 1726.403	* 25.62*	* 144.25*	* 127.32*

*Toms Fork	*	1580.979	*	123.76*	97.42*	118.65*
*Toms Fork	*	1483.221	*	54.14*	61.47*	37.92*
*Toms Fork	*	1421.670	*	284.66*	127.14*	14.01*
*Toms Fork	*	1293.596	*	379.96*	235.75*	67.58*
*Toms Fork	*	1000.000	*	1*	1*	1*

\*\*\*\*\*  
 \*\*\*\*\*

SUMMARY OF CONTRACTION AND EXPANSION COEFFICIENTS  
 River: Toms Fork

* Reach	* River Sta.	* Contr.	* Expan.
*Toms Fork	2865.327*	.1*	.3*
*Toms Fork	2579.832*	.1*	.3*
*Toms Fork	2372.941*	.1*	.3*
*Toms Fork	2123.812*	.1*	.3*
*Toms Fork	2002.134*	.1*	.3*
*Toms Fork	1929.868*	.1*	.3*
*Toms Fork	1811.557*	.1*	.3*
*Toms Fork	1726.403*	.1*	.3*
*Toms Fork	1580.979*	.1*	.3*
*Toms Fork	1483.221*	.1*	.3*
*Toms Fork	1421.670*	.1*	.3*
*Toms Fork	1293.596*	.1*	.3*
*Toms Fork	1000.000*	.1*	.3*

\*\*\*\*\*  
 \*\*\*\*\*

ERRORS WARNINGS AND NOTES

Errors Warnings and Notes for Plan : Existing

River: Toms Fork Reach: Toms Fork RS: 2579.832 Profile: PF 1  
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2372.941 Profile: PF 1  
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2123.812 Profile: PF 1  
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2002.134 Profile: PF 1  
 Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

Saddle2.rep

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 1929.868 Profile: PF 1

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water

surface that had the least amount of error between computed and assumed values.

Warning: Divided flow computed for this cross-section.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

River: Toms Fork Reach: Toms Fork RS: 1811.557 Profile: PF 1

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water

surface that had the least amount of error between computed and assumed values.

Warning: Divided flow computed for this cross-section.

River: Toms Fork Reach: Toms Fork RS: 1726.403 Profile: PF 1

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 1580.979 Profile: PF 1

Warning: Divided flow computed for this cross-section.

River: Toms Fork Reach: Toms Fork RS: 1293.596 Profile: PF 1

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.



**Supplement 3**

**HEC-RAS Analysis –Proposed Conditions Summary w/ Cross Sections**

HEC-RAS Version 4.1.0 Jan 2010  
U.S. Army Corps of Engineers  
Hydrologic Engineering Center  
609 Second Street  
Davis, California

```
X      X  XXXXXX   XXXX       XXXX       XX       XXXX
X      X  X       X   X       X   X       X  X       X
X      X  X       X       X       X   X       X  X       X
XXXXXXXX XXXX     X       XXX  XXXX     XXXXXX     XXXX
X      X  X       X       X   X       X   X       X       X
X      X  X       X   X       X   X       X   X       X
X      X  XXXXXX   XXXX       X   X       X   X       XXXXX
```

\*\*\*\*\*

PROJECT DATA

Project Title: Saddle2  
Project File : Saddle2.prj  
Run Date and Time: 7/16/2013 7:50:49 PM

Project in English units

\*\*\*\*\*

PLAN DATA

Plan Title: Culvert

Plan File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.p03

Geometry Title: Culvert

Geometry File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.g02

Flow Title : Existing-Revised

Flow File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.f02

Plan Summary Information:

Number of:	Cross Sections =	13	Multiple Openings =	0
	Culverts =	1	Inline Structures =	0
	Bridges =	0	Lateral Structures =	0

Computational Information

water surface calculation tolerance	=	0.001
Critical depth calculation tolerance	=	0.001
Maximum number of iterations	=	20
Maximum difference tolerance	=	0.3

Flow tolerance factor = 0.001

Computation Options

Critical depth computed only where necessary
Conveyance Calculation Method: At breaks in n values only
Friction Slope Method: Average Conveyance
Computational Flow Regime: Subcritical Flow

\*\*\*\*\*

FLOW DATA

Flow Title: Existing-Revised
Flow File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.f02

Flow Data (cfs)

\*\*\*\*\*
\* River Reach RS \* PF 1 \*
\* Toms Fork Toms Fork 2865.327\* 4015.3 \*

Boundary Conditions

\*\*\*\*\*
\* River Reach Profile \* Upstream Downstream \*
\* Toms Fork Toms Fork PF 1 \* Known WS = 833.5 Known WS = 831.1 \*

\*\*\*\*\*

GEOMETRY DATA

Geometry Title: Culvert
Geometry File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.g02

CROSS SECTION

RIVER: Toms Fork
REACH: Toms Fork RS: 2865.327

INPUT

Description:

Station Elevation Data num= 100
Table with 10 columns: Sta, Elev, Sta, Elev, Sta, Elev, Sta, Elev, Sta, Elev. Data rows include values like 0, 850, 2.89, 848, 3.73, 847.42, 5.78, 846, 8.24, 844.95.

Saddle2.rep

44.6	841.93	49.67	841.3	52.98	840.89	54.84	840.66	56.84	840.4
56.98	840.39	59.93	840	62.2	838.99	64.42	838	66.42	837.11
68.93	836	77.13	835.38	80.1	835.15	89.55	834.48	91.63	834.33
96.42	834	96.46	834	103.31	833.74	108.11	833.57	115.2	833.31
120.18	833.17	144.96	832.42	149.19	832.28	158.3	832	161.69	831.77
162.91	831.7	163.61	831.66	172.16	831.13	177.1	830.87	181.93	830.59
192.98	830.03	193.14	830.02	193.52	830	195.11	829.63	202.28	828
203.58	827.9	204.23	827.86	205.83	827.75	208.78	827.55	218.92	826.86
225.69	826.43	226.36	826.39	227.77	826.3	228.45	826.25	232.59	826
233.5	824.89	234.03	824.24	234.61	823.57	239.85	823.64	241.59	823.67
250.02	823.8	269.19	824.13	281.09	824.36	281.53	824.87	281.9	825.29
282.64	826	283.77	827.33	285.69	827.68	287.35	828	290.48	828
292.08	828.23	293.87	828.48	299.55	829.32	303.22	829.8	304.12	830
305.84	831.05	306.98	831.74	307.38	832	309.66	833.4	310.6	834
312.52	835.18	313.8	836	315.48	837.04	316.99	838	318.62	839.12
319.93	840	321.46	841.28	322.33	842	324.02	843.41	324.73	844
326.6	845.56	327.13	846	329.22	847.75	329.52	848	331.9	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	232.59	.035	287.35	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	232.59	287.35		212.2	282.13	186.24	.1
							.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 834.50	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.56	* wt. n-val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.94	* Reach Len. (ft)	* 212.20	* 282.13	* 186.24
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 419.77	* 527.29	* 98.85
* E.G. Slope (ft/ft)	* 0.001212	* Area (sq ft)	* 419.77	* 527.29	* 98.85
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 462.90	* 3422.51	* 129.89
* Top Width (ft)	* 212.40	* Top width (ft)	* 134.49	* 54.76	* 23.15
* Vel Total (ft/s)	* 3.84	* Avg. vel. (ft/s)	* 1.10	* 6.49	* 1.31
* Max Chl Dpth (ft)	* 10.37	* Hydr. Depth (ft)	* 3.12	* 9.63	* 4.27
* Conv. Total (cfs)	* 115338.3	* Conv. (cfs)	* 13296.7	* 98310.6	* 3731.0
* Length Wtd. (ft)	* 268.11	* Wetted Per. (ft)	* 134.87	* 57.29	* 24.42
* Min Ch El (ft)	* 823.57	* Shear (lb/sq ft)	* 0.24	* 0.70	* 0.31
* Alpha	* 2.45	* Stream Power (lb/ft s)	* 331.90	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.27	* Cum Volume (acre-ft)	* 17.76	* 21.18	* 6.63
* C & E Loss (ft)	* 0.05	* Cum SA (acres)	* 5.72	* 2.27	* 1.60

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 2579.832

INPUT

Description:

Station Elevation Data		num= 93		Sta		Elev		Sta		Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	2.44	848	2.66	847.82	4.89	846	5.28	845.68		
7.32	844	7.99	843.55	10.04	842	12.78	841.08	16.18	840		
20.07	838.81	22.77	838	31.3	838	32.34	838.23	36.84	839.24		
45.36	839.17	54.84	838.89	61	838.03	61.18	838	62.93	837.73		
65.72	837.27	73.51	836	74.45	835.56	77.9	834	80.43	832.85		
82.31	832	84.12	831.18	87.67	829.59	88.79	829.09	90.47	828.4		
91.43	828	93.28	827.16	95.87	826	99.12	824.4	99.91	824		
100.45	823.72	100.69	823.6	100.92	823.47	143.75	823.47	144.94	823.92		
145.14	824	151.82	825.23	155.09	825.97	155.22	826	157.83	826		
174.68	826.59	176.96	826.69	179.05	826.72	180.73	826.74	182.27	826.82		
183.75	826.84	185.06	826.91	186.58	826.95	188.92	827.07	190.49	827.12		
195.23	827.34	196.43	827.39	197.44	827.44	206.09	827.82	206.63	827.85		
210.34	828	214.91	828.57	218.82	829.06	221.21	829.36	222.27	829.51		
225.8	830	227.87	830.31	228.23	830.38	230.19	830.82	233.42	831.47		
235.56	832	238.7	832.97	242.37	834	244.36	834.61	248.21	835.78		
248.76	835.95	248.94	836	254.04	837.23	256.99	838	257.34	838		
262.74	838.68	270.79	839.6	273.44	840	283.77	841.65	285.91	842		
289.24	842.78	294.7	844	303.19	845.52	305.76	846	310.28	847.08		
313.75	847.86	314.38	848	323.1	850						

Manning's n Values		num= 3		Sta		n Val	
Sta	n Val	Sta	n Val	Sta	n Val	Sta	n Val
0	.1	95.87	.035	155.09	.1		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	95.87	155.09		271.1	188.24	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 834.19	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.40	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.78	* Reach Len. (ft)	* 271.10	* 188.24	* 66.66
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 68.49	* 589.33	* 488.19
* E.G. slope (ft/ft)	*0.000824	* Area (sq ft)	* 68.49	* 589.33	* 488.19
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 68.32	* 3290.13	* 656.85
* Top width (ft)	* 163.22	* Top width (ft)	* 17.49	* 59.22	* 86.51
* Vel Total (ft/s)	* 3.50	* Avg. vel. (ft/s)	* 1.00	* 5.58	* 1.35
* Max Chl Dpth (ft)	* 10.31	* Hydr. Depth (ft)	* 3.91	* 9.95	* 5.64
* Conv. Total (cfs)	*139869.5	* Conv. (cfs)	* 2380.0	*114608.8	* 22880.8
* Length wtd. (ft)	* 183.82	* Wetted Per. (ft)	* 19.15	* 60.11	* 87.15
* Min Ch El (ft)	* 823.47	* Shear (lb/sq ft)	* 0.18	* 0.50	* 0.29
* Alpha	* 2.11	* Stream Power (lb/ft s)	* 323.10	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	* 16.57	* 17.56	* 5.38
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 5.35	* 1.90	* 1.37

Saddle2.rep

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 2372.941

INPUT

Description:

Station Elevation Data		num= 105		Sta		Elev		Sta		Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	1.82	848	2.33	847.47	3.36	846.39	3.78	846		
6.59	844.33	7.14	844	10.17	842.28	10.68	842	13.68	840.29		
14.22	840	17.19	838.31	17.76	838	19.76	837.02	21.03	837.71		
30.82	836.97	45.33	836.96	53.11	837.04	58.14	836.39	62.87	836		
70.69	835.06	78.76	834	82.37	833.41	90.69	832	92.24	831.76		
95.46	831.2	102.19	830	104.15	829.57	105.93	829.26	108.63	828.71		
111.2	828.33	113.43	828	114.56	827.83	114.6	827.82	114.66	827.81		
114.94	827.78	118.37	827.27	120.84	826.94	122.59	826.68	127.81	826		
128.07	825.95	128.15	825.95	128.23	825.93	131.37	825.41	132.07	825.31		
133.39	825.14	134.95	824.85	136.9	824.63	140.69	824	140.95	824		
141.56	823.88	142.39	823.69	142.76	823.59	143.18	823.47	161.64	823.47		
162.23	823.66	162.96	823.86	163.49	824	170.49	824.97	178.34	826		
184.38	826.66	190.63	827.37	196.22	828	204.78	828.89	209.26	829.26		
213.01	829.61	214.44	829.73	215.21	829.78	215.72	829.81	218.51	830		
221.09	830.31	222.16	830.45	226.82	831.04	233.45	832	259.72	833.51		
267.46	833.9	270.43	834	277.5	834	293.51	834.86	300.19	835.16		
303.03	835.27	310.96	835.62	312.48	835.69	319.76	836	323.88	836.36		
332.03	837.03	340.66	837.87	342.02	838	347.21	839.1	350.16	839.67		
350.48	839.73	351.82	840	353.9	840.42	357.17	841.11	360.16	841.74		
361.41	842	366.93	843.14	371.51	844	376.07	845.15	379.47	846		
382.67	846.77	388.2	848	388.9	848.16	389.32	848.25	397.14	850		

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
0	.035	136.9	.035
		170.49	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	136.9	170.49		494.68	209.34	278.69	.1
							.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 833.96	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.64	* Wt. n-Val.	* 0.035	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.32	* Reach Len. (ft)	* 494.68	* 209.34	* 278.69
* Crit w.s. (ft)	*	* Flow Area (sq ft)	* 245.16	* 319.14	* 319.31
* E.G. slope (ft/ft)	* 0.001608	* Area (sq ft)	* 245.16	* 319.14	* 319.31
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 1134.88	* 2425.21	* 455.21
* Top width (ft)	* 173.43	* Top width (ft)	* 53.98	* 33.59	* 85.86
* Vel Total (ft/s)	* 4.54	* Avg. vel. (ft/s)	* 4.63	* 7.60	* 1.43
* Max chl Dpth (ft)	* 9.85	* Hydr. Depth (ft)	* 4.54	* 9.50	* 3.72
* Conv. Total (cfs)	* 100120.2	* Conv. (cfs)	* 28297.8	* 60471.9	* 11350.5

Saddle2.rep

```
* Length Wtd. (ft)      * 268.28 * Wetted Per. (ft)      * 54.69 * 33.85 * 86.30 *
* Min Ch El (ft)      * 823.47 * Shear (lb/sq ft)     * 0.45 * 0.95 * 0.37 *
* Alpha                * 1.99  * Stream Power (lb/ft s) * 397.14 * 0.00 * 0.00 *
* Frctn Loss (ft)     * 0.24  * Cum Volume (acre-ft)  * 15.59 * 15.60 * 4.76 *
* C & E Loss (ft)     * 0.12  * Cum SA (acres)        * 5.13  * 1.70 * 1.24 *
*****
```

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 2123.812

INPUT

Description:

Station Elevation Data num= 145

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	7.61	848.12	8.1	848	11.48	846.85	14.02	846
17.32	844.89	20.19	844	29.09	842.54	32.44	842	39.97	840.57
41	840.36	41.44	840.27	41.87	840.18	42.76	840	44.29	839.85
44.87	839.81	45.61	839.77	58.05	838.76	60.93	838.66	73.97	838
80.16	838	86.28	837.78	88.03	837.76	89.01	837.75	89.33	837.75
96.23	837.46	96.83	837.47	114.62	837.25	123.08	837.03	153.21	836.5
165.6	836.24	167.39	836.2	176.66	836	183.88	836	185.94	835.94
186.45	835.92	193.78	835.74	197.53	835.66	200.81	835.61	203.09	835.51
207.46	835.41	211.32	835.23	215.79	835.06	217.31	834.99	218.58	834.93
219.59	834.88	221.23	834.79	225.89	834.56	228.39	834.42	237.61	834
240.15	833.94	250.89	833.92	251.23	833.98	252.74	834.04	256.18	834.13
266.1	834.44	276.79	834.81	279.36	834.6	282	834.51	292.41	834.43
302.29	834.14	305	834	306.65	834	318.72	833.83	322.62	833.82
326.83	833.77	349.34	833.52	366.28	833.31	381.19	833.17	409.51	832.76
442.18	832	458.66	832	459.09	831.91	460.58	831.67	467.09	830.52
470.93	830	472.47	829.86	473.63	829.73	474.35	829.63	476.54	829.59
478.33	829.44	480.51	829.24	482.35	829.05	484.53	829.08	493.14	828.72
510.22	828	540.14	828	541.2	827.11	542.5	826	543.18	825.38
544.61	824	544.96	823.68	545.31	822.47	562.34	822.47	590.93	822.47
591.34	823.26	591.75	823.47	592.68	823.87	592.98	824	596.16	824.59
597.7	824.75	600.18	825.16	601.92	825.29	603.14	825.47	603.8	825.56
606.61	825.79	609.14	825.89	609.21	825.89	611.75	826	618.47	826
623.51	826.14	623.89	826.15	627.54	826.26	629.08	826.31	634.67	826.43
637.3	826.52	638.18	826.54	665.48	826.98	667.38	826.96	668.91	827.09
670.46	827.22	674.09	827.49	676.03	827.52	680.97	828	682.63	828.93
684.49	830	686.81	831.3	688.03	832	689.62	832.9	691.61	834
693.43	834.9	695.67	836	699.67	837.95	699.76	838	699.9	838.07
703.8	840	708.04	841.9	708.27	842	708.74	842.21	712.7	844
716.95	845.96	717.03	846	717.11	846.04	721.13	848	725.2	850

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 540.14 .035 611.75 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 540.14 611.75 4.85 111.36 132.72 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

\*\*\*\*\*  
 \* E.G. Elev (ft) \* 833.60 \* Element \* Left OB \* Channel \* Right OB \*  
 \* Vel Head (ft) \* 0.25 \* Wt. n-Val. \* 0.100 \* 0.035 \* 0.100 \*  
 \* W.S. Elev (ft) \* 833.35 \* Reach Len. (ft) \* 4.85 \* 111.36 \* 132.72 \*  
 \* Crit W.S. (ft) \* \* \* Flow Area (sq ft) \* 432.87 \* 708.11 \* 486.34 \*  
 \* E.G. slope (ft/ft) \*0.000558 \* Area (sq ft) \* 432.87 \* 708.11 \* 486.34 \*  
 \* Q Total (cfs) \* 4015.30 \* Flow (cfs) \* 275.19 \* 3172.43 \* 567.68 \*  
 \* Top width (ft) \* 327.53 \* Top width (ft) \* 177.24 \* 71.61 \* 78.69 \*  
 \* Vel Total (ft/s) \* 2.47 \* Avg. vel. (ft/s) \* 0.64 \* 4.48 \* 1.17 \*  
 \* Max chl Dpth (ft) \* 10.88 \* Hydr. Depth (ft) \* 2.44 \* 9.89 \* 6.18 \*  
 \* Conv. Total (cfs) \*170048.2 \* Conv. (cfs) \* 11654.4 \* 134352.7 \* 24041.2 \*  
 \* Length wtd. (ft) \* 100.66 \* Wetted Per. (ft) \* 177.48 \* 74.95 \* 80.15 \*  
 \* Min Ch El (ft) \* 822.47 \* Shear (lb/sq ft) \* 0.08 \* 0.33 \* 0.21 \*  
 \* Alpha \* 2.64 \* Stream Power (lb/ft s) \* 725.20 \* 0.00 \* 0.00 \*  
 \* Frctn Loss (ft) \* 0.08 \* Cum Volume (acre-ft) \* 11.74 \* 13.13 \* 2.18 \*  
 \* C & E Loss (ft) \* 0.03 \* Cum SA (acres) \* 3.82 \* 1.45 \* 0.71 \*  
 \*\*\*\*\*

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 2002.134

INPUT

Description:

Station Elevation Data num= 120  
 Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
 \*\*\*\*\*  
 0 850 5.75 848.69 9.25 848 12.54 847.07 14.98 846.36  
 16.39 846 21.54 844.57 23.9 844 28.14 843.37 29.49 843.11  
 31.27 842.82 35.31 842 36.84 841.71 44.09 840.36 45.66 840.07  
 46.05 840 58.46 838.43 59.73 838.27 60.32 838.19 61.51 838  
 68.14 838 84.71 837.13 87.17 837.04 90.91 836.93 93.76 836.87  
 96.92 836.74 102.52 836.63 109.38 836.49 117.27 836.33 120.05 836.28  
 121.42 836.22 123.9 836.21 135.46 836 152.3 836 152.93 835.97  
 153.56 835.95 175.95 834.99 193.37 834.28 196.51 834.15 200.1 834  
 205.39 833.72 210.34 833.1 210.74 833.15 211.69 833.31 213.96 833.36  
 216.02 833.45 235.66 834 252.32 834 256.05 833.9 257.04 833.88



saddle2.rep

276.33	833.31	279.34	833.28	281.75	833.27	295.27	832.92	301.58	832.91
307.93	832.77	318.74	832.74	323.19	832.66	337.48	832.62	342.49	832.54
382.49	832.24	402.49	832	443.94	832	448.99	831.31	452.91	830.94
462.54	830	463.53	829.84	463.96	829.78	467.24	829.24	468.14	829.14
470.59	828.79	471.7	828.67	472.1	828.64	472.57	828.59	474.78	828.35
475.89	828.26	476.06	828.26	477.8	828	488.57	828	491.73	827.76
492.21	827.75	494.02	827.72	494.54	827.71	527.7	826.75	553.46	826
561.05	826	561.73	825.49	563.27	824	563.54	823.79	564.49	822.87
577.19	822.74	603.13	822.47	605.42	823.91	605.57	824	609.95	825.19
612.91	826	613.85	826.72	615.51	828	616.81	828.98	618.12	830
619.93	831.36	620.77	832	623.33	833.91	623.44	834	623.55	834.08
625.99	836	626.03	836.04	628.31	838	629.29	838.81	630.68	840
632.39	841.41	633.09	842	635.36	843.87	635.52	844	636.52	844.78
637.1	845.24	638.07	846	640.63	847.87	640.8	848	643.54	850

Manning's n	Values	num=	3
Sta	n Val	Sta	n Val
0	.1	561.05	.035
		612.91	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	561.05	612.91		5.33	72.27		.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 833.49	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.56	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 832.93	* Reach Len. (ft)	* 5.33	* 72.27	* 84.50
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 679.33	* 507.54	* 31.44
* E.G. Slope (ft/ft)	*0.001199	* Area (sq ft)	* 679.33	* 507.54	* 31.44
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 652.05	* 3331.54	* 31.71
* Top width (ft)	* 327.29	* Top width (ft)	* 266.32	* 51.86	* 9.11
* Vel Total (ft/s)	* 3.30	* Avg. vel. (ft/s)	* 0.96	* 6.56	* 1.01
* Max Chl Dpth (ft)	* 10.46	* Hydr. Depth (ft)	* 2.55	* 9.79	* 3.45
* Conv. Total (cfs)	*115965.4	* Conv. (cfs)	* 18831.7	* 96217.8	* 915.9
* Length Wtd. (ft)	* 64.31	* Wetted Per. (ft)	* 266.60	* 53.79	* 11.45
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.19	* 0.71	* 0.21
* Alpha	* 3.31	* Stream Power (lb/ft s)	* 643.54	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.10	* Cum volume (acre-ft)	* 11.68	* 11.58	* 1.39
* C & E Loss (ft)	* 0.05	* Cum SA (acres)	* 3.79	* 1.29	* 0.58

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1929.868

INPUT

Description:

Station	Elevation	Data	num=	127					
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev

Saddle2.rep

```
*****
0      850    9.69  848.14  10.44    848    16.57  846.52    19    846
22.06  845.27  23.4  844.99  28.18    844    28.7   843.91   29.27  843.8
34.05  842.91  38.56    842    39.24   841.89  39.57  841.83   44.23  841.11
46.52  840.64  48.15  840.39  49.88    840    53.06  839.56   57.34  839.03
62.7   838    63.49    838    95.81  836.27  101.33  836.06  101.57  836.05
103.51  836    104.46    836    106.48  835.94  113.45  835.8   113.98  835.79
120.44  835.67  140.38  835.62  141.17  835.63  142.8   835.61  144.74  835.58
147.99  835.47  148.7   835.47  152.05  835.32  153.09  835.29  166.02  834.72
167.81  834.65  171.79  834.47  182.48    834   186.18  832.37  186.98    832
189.63    832  190.59  832.17  191.57  832.36  193.59  832.72  211.11  833.08
214.56  833.17  215.19  833.21  215.57  833.24  217.58  833.36  229.11    834
235.48    834  243.03  833.47  247.63  833.34  262.04  832.65  276.26  832.35
277.28  832.32  293.07    832  355.46    832  360.25  831.81  388.23  831.91
390.46  831.9   394.56    832  411.75    832  413.92  831.91  418.69  831.72
420.02  831.67  421.45  831.61  434.07  831.52  435.68  831.52  435.95  831.61
436.19  831.7   437.05    832  451.01    832  457.66  831.46  460.43  831.24
464.27  830.93  466.72  830.73  472.68    830  477.88    828.1  478.17    828
487.76  826.55  489.16  826.33    495.7    826  497.25    826  519.34    826
520.31  825.28  522.18    824  522.87  823.57  523.4   823.17  523.76  822.87
527.6   822.84  528.89  822.83  532.08  822.8   552.31  822.57  560.43  822.47
561.98  823.63  562.39    824  563.46  824.74  565.18    826  566.72  827.13
568.04    828  569.7   829.21  570.9    830  572.63  831.25  573.74    832
575.53  833.28  576.58    834  577.39  834.76  578.84    836  579.87  837.17
580.64    838  581.81  839.35  582.42    840  583.77  841.56  584.18    842
585.76  843.84  585.91    844  586.04  844.16  586.72  844.95  587.6    846
589.67    848  591.96    850
```

```
Manning's n Values      num=      3
Sta  n Val      Sta  n Val      Sta  n Val
*****
0      .1  519.34      .035  565.18      .1
```

```
Bank Sta: Left  Right  Lengths: Left Channel  Right  Coeff Contr.  Expan.
          519.34  565.18          5.86  118.14  110.15          .1          .3
Ineffective Flow      num=      1
Sta L  Sta R  Elev Permanent
0      235.48  834      F
```

CROSS SECTION OUTPUT Profile #PF 1

```
*****
* E.G. Elev (ft)      * 833.34 * Element      * Left OB * Channel * Right OB *
* Vel Head (ft)      * 1.05 * Wt. n-Val.   * 0.100 * 0.035 * 0.100 *
* W.S. Elev (ft)     * 832.28 * Reach Len. (ft) * 5.86 * 118.14 * 110.15 *
* Crit W.S. (ft)     * 829.15 * Flow Area (sq ft) * 348.92 * 424.90 * 28.02 *
* E.G. Slope (ft/ft) * 0.002253 * Area (sq ft) * 349.99 * 424.90 * 28.02 *
* Q Total (cfs)      * 4015.30 * Flow (cfs) * 314.97 * 3663.34 * 36.98 *
* Top Width (ft)     * 299.91 * Top width (ft) * 245.12 * 45.84 * 8.96 *
* Vel Total (ft/s)   * 5.01 * Avg. vel. (ft/s) * 0.90 * 8.62 * 1.32 *
* Max Chl Dpth (ft) * 9.81 * Hydr. Depth (ft) * 1.45 * 9.27 * 3.13 *
* Conv. Total (cfs)  * 84593.0 * Conv. (cfs) * 6635.7 * 77178.1 * 779.2 *
* Length Wtd. (ft)   * 109.20 * Wetted Per. (ft) * 240.98 * 48.01 * 10.94 *
```

```

* Min Ch El (ft)      * 822.47 * Shear (lb/sq ft) * 0.20 * 1.24 * 0.36 *
* Alpha              * 2.71 * Stream Power (lb/ft s) * 591.96 * 0.00 * 0.00 *
* Frctn Loss (ft)    * 0.24 * Cum Volume (acre-ft) * 11.62 * 10.80 * 1.33 *
* C & E Loss (ft)    * 0.02 * Cum SA (acres) * 3.76 * 1.21 * 0.56 *
*****
    
```

Warning: Divided flow computed for this cross-section.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork            RS: 1811.557

INPUT

Description:

Station Elevation Data		num= 127		Sta		Elev		Sta		Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	8.09	848.68	9.6	848.44	12.25	848	15.63	847.32		
17.53	847.03	22.85	846.14	23.34	846.05	23.62	846	29.14	845.01		
29.7	844.93	31.77	844.59	35.22	844	38.73	843.44	40.77	843.25		
44.36	842.76	49.7	842.06	50.03	842	54.63	840.79	58.16	840		
60.2	839.66	63.13	839.24	66.64	838.88	68.31	838.67	72.99	838.13		
73.95	838	87.5	836.44	90.85	836	91.66	836	100.94	835.61		
101.33	835.59	110.34	835.25	110.4	835.24	121.22	834.87	124.68	834.79		
125.19	834.78	128.31	834.73	131.18	834.66	139.14	834.59	139.43	834.59		
145.89	834.47	154.04	834.29	161.88	834	163.25	834	165.31	833.16		
168	832	173.5	832	173.52	832	175.04	832.3	193.36	832.94		
194.25	832.97	194.4	832.96	194.97	833.03	195.62	833.08	208.04	834		
229.9	834	238.7	833.13	240.06	833.08	246.53	832	265.48	832		
303.93	831.45	312.8	831.4	332.62	831	353.67	831.77	354.78	831.72		
359.46	831.02	369.02	830.99	369.43	831	369.91	830.99	370.02	830.99		
370.53	830.98	370.91	830.97	389.65	830.53	394.54	830.38	401.08	830.18		
406.7	830	407.31	829.79	412.33	828	413.45	827.6	414.68	827.16		
417.14	826.3	417.99	826	443.82	826	444.09	825.85	445.72	825.04		
447.77	824	447.95	823.91	449.82	822.87	459.79	822.8	489.1	822.47		
489.21	822.59	489.36	822.75	490.51	824	490.88	824.38	492.37	826		
493.93	827.55	494.37	828	497.57	830.56	499.37	832	499.82	832.35		
501.88	834	503.33	835.14	504.41	836	505.89	837.68	506.17	838		
506.24	838.08	507.77	840	508.33	840.71	509.35	842	510.56	843.55		
510.91	844	511.55	844.84	512.54	846	513.19	846.66	514.51	848		
516.01	849.18	517.12	850	518.94	851.43	519.47	851.82	519.7	852		
521.72	853.59	522.26	854	524.41	855.7	524.8	856	527.06	857.79		
527.34	858	530.07	860								

Manning's n Values		num= 3		Sta		n Val	
Sta	n Val	Sta	n Val	Sta	n Val	Sta	n Val
0	.1	443.82	.035	492.37	.1		

Saddle2.rep

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 443.82 492.37 17.98 85.13 75.99 .1 .3  
 Ineffective Flow num= 1  
 Sta L Sta R Elev Permanent  
 0 229.9 834 F

CROSS SECTION OUTPUT Profile #PF 1

```
*****
* E.G. Elev (ft) * 833.08 * Element * Left OB * Channel * Right OB *
* Vel Head (ft) * 0.99 * Wt. n-Val. * 0.100 * 0.035 * 0.100 *
* W.S. Elev (ft) * 832.09 * Reach Len. (ft) * 17.98 * 85.13 * 75.99 *
* Crit W.S. (ft) * 828.93 * Flow Area (sq ft) * 330.43 * 440.93 * 20.66 *
* E.G. Slope (ft/ft) * 0.002159 * Area (sq ft) * 330.97 * 440.93 * 20.66 *
* Q Total (cfs) * 4015.30 * Flow (cfs) * 320.32 * 3670.83 * 24.14 *
* Top Width (ft) * 259.71 * Top Width (ft) * 204.04 * 48.55 * 7.12 *
* Vel Total (ft/s) * 5.07 * Avg. vel. (ft/s) * 0.97 * 8.33 * 1.17 *
* Max Chl Dpth (ft) * 9.62 * Hydr. Depth (ft) * 1.67 * 9.08 * 2.90 *
* Conv. Total (cfs) * 86410.0 * Conv. (cfs) * 6893.4 * 78997.0 * 519.6 *
* Length wtd. (ft) * 77.71 * Wetted Per. (ft) * 198.63 * 50.86 * 9.38 *
* Min Ch El (ft) * 822.47 * Shear (lb/sq ft) * 0.22 * 1.17 * 0.30 *
* Alpha * 2.47 * Stream Power (lb/ft s) * 530.07 * 0.00 * 0.00 *
* Frctn Loss (ft) * 0.17 * Cum Volume (acre-ft) * 11.57 * 9.63 * 1.27 *
* C & E Loss (ft) * 0.00 * Cum SA (acres) * 3.73 * 1.08 * 0.54 *
*****
```

Warning: Divided flow computed for this cross-section.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 1726.403

INPUT

Description:

```
Station Elevation Data num= 111
Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev
*****
0 850 7.69 848.75 12.67 848 13.53 847.86 13.88 847.81
14.58 847.69 23.99 846 24.2 845.96 24.7 845.87 35.04 844
35.58 844 35.72 843.97 36.71 843.76 44.45 842 50.81 840.91
56.16 840 62.16 839.16 70.39 838 76.77 836.99 82.9 836
107.43 834.59 111.92 834.32 113.55 834.23 114.44 834.18 115.04 834.14
118.29 834 133.54 833 145.97 832 153.68 832 153.78 832.03
154.17 832.11 170.85 832.35 172.32 832.36 172.33 832.36 172.33 832.35
172.36 832.35 172.46 832.35 172.61 832.34 172.88 832.33 173.84 832.26
177.54 832 261.15 832 263.09 831.66 263.15 831.66 264.41 831.43
264.73 831.44 265.31 831.48 266.23 831.31 267.04 831.34 274.24 831.18
277.67 831.06 279.87 830.91 303.11 830.11 303.13 830.11 303.2 830.11
```

Saddle2.rep

313.87	830.99	332.27	830.68	338.82	830.44	346.78	830.13	350.22	830
354.85	828.9	358.99	828	361.29	827.15	364.99	826	368.69	826
374.3	826	386.59	824.73	394.79	824.26	396.56	824.16	399.37	824
400.62	823.5	401.24	823.25	402.13	822.87	415.76	822.73	440.37	822.47
441.28	823.54	441.62	824	442.72	825.29	443.28	826	446.77	827.59
447.66	828	451.15	831.19	452.07	832	453.87	833.62	454.27	834
454.56	834.26	456.73	836	458.44	837.72	458.72	838	459.92	839.21
460.72	840	461.32	840.61	462.7	842	463.86	843.24	464.51	844
465.71	845.39	466.11	845.85	466.23	846	466.54	846.24	468.77	848
470.01	848.97	471.31	850	472.48	850.91	473.86	852	474.93	852.84
476.4	854	477.37	854.77	478.94	856	481.17	857.79	481.43	858
485.12	860								

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	399.37	.035	441.62	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	399.37	441.62		25.62	144.25	127.32	.1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 832.90	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 1.02	* Wt. n-val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.88	* Reach Len. (ft)	* 25.62	* 144.25	* 127.32
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 389.41	* 386.16	* 41.05
* E.G. Slope (ft/ft)	* 0.002315	* Area (sq ft)	* 389.41	* 386.16	* 41.05
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 555.18	* 3397.53	* 62.59
* Top Width (ft)	* 190.08	* Top width (ft)	* 137.52	* 42.25	* 10.31
* Vel Total (ft/s)	* 4.92	* Avg. vel. (ft/s)	* 1.43	* 8.80	* 1.52
* Max Chl Dpth (ft)	* 9.41	* Hydr. Depth (ft)	* 2.83	* 9.14	* 3.98
* Conv. Total (cfs)	* 83449.8	* Conv. (cfs)	* 11538.2	* 70610.8	* 1300.8
* Length wtd. (ft)	* 131.54	* Wetted Per. (ft)	* 138.29	* 43.20	* 13.18
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.41	* 1.29	* 0.45
* Alpha	* 2.72	* Stream Power (lb/ft s)	* 485.12	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.22	* Cum Volume (acre-ft)	* 11.42	* 8.82	* 1.22
* C & E Loss (ft)	* 0.14	* Cum SA (acres)	* 3.66	* 0.99	* 0.52

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1580.979

INPUT

Description:

Station	Elevation	Data	num=	105	Sta	Elev	Sta	Elev	Sta	Elev
0	850	9.68	848	15.17	846.8	15.87	846.64	18.77	846	

Saddle2.rep

20.81	845.56	28	844	35.76	842.18	36.54	842	36.96	841.92
47.38	840	47.87	839.9	56.87	838	68.15	836.06	68.41	836.01
77.1	834.66	80.22	834.43	85.29	834	85.35	834	89.24	833.81
92.24	833.63	92.64	833.63	93.17	833.63	94.58	833.62	97.89	833.46
100.76	833.32	133.45	832	138.56	832	141.4	831.74	147.18	831.31
158.75	831.48	165.31	831.53	185.18	831.5	191.55	831.44	193.11	831.6
206.25	831.02	217.47	830.66	227.63	830.24	231.61	830.09	236.83	830
237.47	829.75	238.59	829.37	245.76	829.63	249.16	829.77	253.95	830
253.96	830	253.97	830	260.61	830	272.1	829.31	290.5	828
293.32	828	298.88	827.16	303.61	826.89	315.57	826	316.11	826
317.58	826	317.83	825.95	322.94	825.12	323.18	825.12	328.6	824.28
328.79	824.25	330.08	824	334.79	823.2	336.76	822.74	337.42	822.86
337.84	822.87	365.19	822.64	382.75	822.47	382.79	822.67	383	822.67
386.52	823.76	387.12	824	389.83	824.32	390.64	824.42	395.83	825.08
400.52	825.66	403.1	826	409.08	826.75	412.02	827.12	419.58	827.98
419.67	827.99	419.74	827.99	419.75	827.99	419.78	828	427.07	828
428.22	828.41	434.02	830	434.67	830.39	436.52	832	439.1	833.98
441.66	836	442.29	836.49	444.2	838	446.24	839.6	446.78	840
447.35	840.4	449.74	842	451.59	843.1	453.32	844	456.03	845.43
457.1	846	457.93	846.44	460.96	848	463.4	849.33	464.87	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	330.08	.035	387.12	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	330.08	387.12		123.76	97.42	118.65	.1 .3

Ineffective Flow num= 2

Sta L	Sta R	Elev	Permanent
182.24	294.39	833	F
450.58	456.57	833	F

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 832.54	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.56	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.98	* Reach Len. (ft)	* 123.76	* 97.42	* 118.65
* Crit W.S. (ft)	* 828.25	* Flow Area (sq ft)	* 229.86	* 523.17	* 246.63
* E.G. Slope (ft/ft)	* 0.001236	* Area (sq ft)	* 446.38	* 523.17	* 246.63
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 243.76	* 3401.25	* 370.29
* Top Width (ft)	* 297.76	* Top width (ft)	* 191.34	* 57.04	* 49.38
* Vel Total (ft/s)	* 4.02	* Avg. vel. (ft/s)	* 1.06	* 6.50	* 1.50
* Max Chl Dpth (ft)	* 9.51	* Hydr. Depth (ft)	* 2.90	* 9.17	* 4.99
* Conv. Total (cfs)	* 114213.5	* Conv. (cfs)	* 6933.7	* 96747.0	* 10532.9
* Length wtd. (ft)	* 97.42	* Wetted Per. (ft)	* 79.47	* 57.55	* 50.62
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.22	* 0.70	* 0.38
* Alpha	* 2.24	* Stream Power (lb/ft s)	* 464.87	* 0.00	* 0.00
* Frctn Loss (ft)	*	* Cum volume (acre-ft)	* 11.18	* 7.32	* 0.80
* C & E Loss (ft)	*	* Cum SA (acres)	* 3.56	* 0.83	* 0.43

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, water surface was used.

CULVERT

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1528.223

INPUT

Description:  
 Distance from Upstream XS = 40.2  
 Deck/Roadway Width = 25  
 Weir Coefficient = 2.6  
 Upstream Deck/Roadway Coordinates

num= 5

Sta	Hi	Cord	Lo	Cord	Sta	Hi	Cord	Lo	Cord	Sta	Hi	Cord	Lo	Cord
167.15	831.47	822	316.08	838.58	822	403.716	838.58	822						
467.81	840	822	485.69	842	822									

Upstream Bridge Cross Section Data

Station Elevation Data num= 105

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	9.68	848	15.17	846.8	15.87	846.64	18.77	846
20.81	845.56	28	844	35.76	842.18	36.54	842	36.96	841.92
47.38	840	47.87	839.9	56.87	838	68.15	836.06	68.41	836.01
77.1	834.66	80.22	834.43	85.29	834	85.35	834	89.24	833.81
92.24	833.63	92.64	833.63	93.17	833.63	94.58	833.62	97.89	833.46
100.76	833.32	133.45	832	138.56	832	141.4	831.74	147.18	831.31
158.75	831.48	165.31	831.53	185.18	831.5	191.55	831.44	193.11	831.6
206.25	831.02	217.47	830.66	227.63	830.24	231.61	830.09	236.83	830
237.47	829.75	238.59	829.37	245.76	829.63	249.16	829.77	253.95	830
253.96	830	253.97	830	260.61	830	272.1	829.31	290.5	828
293.32	828	298.88	827.16	303.61	826.89	315.57	826	316.11	826
317.58	826	317.83	825.95	322.94	825.12	323.18	825.12	328.6	824.28
328.79	824.25	330.08	824	334.79	823.2	336.76	822.74	337.42	822.86
337.84	822.87	365.19	822.64	382.75	822.47	382.79	822.67	383	822.67
386.52	823.76	387.12	824	389.83	824.32	390.64	824.42	395.83	825.08
400.52	825.66	403.1	826	409.08	826.75	412.02	827.12	419.58	827.98
419.67	827.99	419.74	827.99	419.75	827.99	419.78	828	427.07	828
428.22	828.41	434.02	830	434.67	830.39	436.52	832	439.1	833.98
441.66	836	442.29	836.49	444.2	838	446.24	839.6	446.78	840
447.35	840.4	449.74	842	451.59	843.1	453.32	844	456.03	845.43
457.1	846	457.93	846.44	460.96	848	463.4	849.33	464.87	850

Manning's n Values

num= 3

Sta	n val	Sta	n val	Sta	n val
0	.1	330.08	.035	387.12	.1

Bank Sta: Left Right Coeff Contr. Expan.  
 330.08 387.12 .1 .3  
 Ineffective Flow num= 2  
 Sta L Sta R Elev Permanent  
 182.24 294.39 833 F  
 450.58 456.57 833 F

Downstream Deck/Roadway Coordinates  
 num= 7

Sta	Hi	Cord	Lo	Cord	Sta	Hi	Cord	Lo	Cord	Sta	Hi	Cord	Lo	Cord
205.21	830.68	822	340.24	838.58	822	417.62	838.58	822	535.53	845.45	822	535.53	845.45	822
483.32	840	822	502.13	842	822	535.53	845.45	822	535.53	845.45	822	535.53	845.45	822
563.93	848	822												

Downstream Bridge Cross Section Data

Station Elevation Data num= 119

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	5.81	848	7.38	847.46	9.29	846.8	11.59	846
12.45	845.72	17.64	844	22	842.63	23.96	842	28.51	840.53
30.08	840	35.58	838.12	35.95	838	37.05	837.65	42.19	836
46.82	834.38	47.91	834	52.05	832.41	53.12	832	53.33	831.92
58.38	830	59.39	830	69.2	829.64	77.21	829.39	84.78	829.19
91.53	828.99	94.05	828.92	103.42	828.67	104.03	828.65	110.46	828.46
112.7	828.4	114.09	828.37	119.86	828.27	120.77	828.25	122.62	828.22
123.19	828.21	132.4	828.09	132.67	828.09	133.01	828.08	134.54	828.07
135.22	828.07	135.64	828.07	139.19	828.09	139.28	828.09	139.61	828.09
139.88	828.09	140.15	828.09	143.01	828.18	152.35	828.3	153.73	828.36
156.58	828.49	168.1	828.8	176.97	829.32	188.61	830	189.36	830.1
191.09	830.42	197.36	830.41	210.1	830.63	218.76	830.09	220.05	830
220.87	830	270.1	828.71	272.93	828.65	299.31	828	302.7	827.77
303.52	827.77	306.38	827.68	320.02	827.07	325.65	826.82	326.24	826.81
328.46	826.79	353.75	826	356.58	826	357.24	825.45	359.31	824
360.1	823.52	362.29	822.03	382.46	822.33	401.54	822.42	405.94	823.87
406.29	824	408.51	824.33	415.99	825.23	420.95	825.86	422.22	826
425.52	827.67	426.14	828	429.24	829.72	429.75	830	429.89	830.02
440.71	831.89	441.32	832	444.32	832	480.07	833.73	485.11	834
492.49	835.38	495.7	836	499.07	836.62	506.5	838	512.87	839.45
515.34	840	519.08	840.85	521.04	841.23	522.71	841.52	523.54	841.67
525.58	842	527.64	842.31	530.45	842.83	534.69	843.56	536.71	844
536.83	844	543.95	845.16	545.09	845.34	549.15	846	554.58	846.76
563.93	848	564.84	848	566.68	848.39	572.35	850		

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 0 .1 356.58 .035 408.51 .1

Bank Sta: Left Right Coeff Contr. Expan.  
 356.58 408.51 .1 .3  
 Ineffective Flow num= 2



Saddle2.rep

Sta L	Sta R	Elev	Permanent
221.06	261.25	832	F
445.63	572.35	832	F

Upstream Embankment side slope = 0 horiz. to 1.0 vertical  
 Downstream Embankment side slope = 0 horiz. to 1.0 vertical  
 Maximum allowable submergence for weir flow = .98  
 Elevation at which weir flow begins =  
 Energy head used in spillway design =  
 Spillway height used in design =  
 weir crest shape = Broad Crested

Number of Culverts = 1

Culvert Name Shape Rise Span  
 Culvert #1 Arch 11.33 35.83  
 FHWA Chart # 41- Arch; Corrugated metal  
 FHWA Scale # 1 - 90 Degree headwall

Solution Criteria = Highest U.S. EG  

Culvert Upstrm Dist	Length	Top n	Bottom n	Depth Blocked	Entrance Loss Coef	Exit Loss Coef
32.68	40	.022	.035	0	.5	.3

Number of Barrels = 2  
 Upstream Elevation = 822.66  
 Centerline Stations  
 Sta. Sta.  
 339.42 377.91  
 Downstream Elevation = 822.38  
 Centerline Stations  
 Sta. Sta.  
 364.26 402.7

CULVERT OUTPUT Profile #PF 1 Culv Group: Culvert #1

```

*****
* Q Culv Group (cfs) * 3901.78 * Culv Full Len (ft) *
* # Barrels * 2 * Culv Vel US (ft/s) * 7.00 *
* Q Barrel (cfs) * 1950.89 * Culv Vel DS (ft/s) * 6.89 *
* E.G. US. (ft) * 832.55 * Culv Inv El Up (ft) * 822.66 *
* W.S. US. (ft) * 831.98 * Culv Inv El Dn (ft) * 822.38 *
* E.G. DS (ft) * 831.99 * Culv Frctn Ls (ft) * 0.10 *
* W.S. DS (ft) * 831.49 * Culv Exit Loss (ft) * 0.07 *
* Delta EG (ft) * 0.55 * Culv Entr Loss (ft) * 0.38 *
* Delta WS (ft) * 0.49 * Q Weir (cfs) * 113.52 *
* E.G. IC (ft) * 829.99 * Weir Sta Lft (ft) * 119.98 *
* E.G. OC (ft) * 832.55 * Weir Sta Rgt (ft) * 182.24 *
* Culvert Control * Outlet * Weir Submerg * 0.03 *
* Culv WS Inlet (ft) * 831.40 * Weir Max Depth (ft) * 1.23 *
* Culv WS Outlet (ft) * 831.33 * Weir Avg Depth (ft) * 0.75 *
* Culv Nml Depth (ft) * 5.75 * Weir Flow Area (sq ft) * 46.96 *
* Culv Crt Depth (ft) * 4.51 * Min El Weir Flow (ft) * 831.32 *
*****
    
```

Warning: During the culvert inlet control computations, the program could not balance the culvert/weir flow. The

reported inlet  
energy grade answer may not be valid.

CROSS SECTION

RIVER: Toms Fork  
REACH: Toms Fork RS: 1483.221

INPUT

Description:

Station Elevation Data num= 119

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	5.81	848	7.38	847.46	9.29	846.8	11.59	846
12.45	845.72	17.64	844	22	842.63	23.96	842	28.51	840.53
30.08	840	35.58	838.12	35.95	838	37.05	837.65	42.19	836
46.82	834.38	47.91	834	52.05	832.41	53.12	832	53.33	831.92
58.38	830	59.39	830	69.2	829.64	77.21	829.39	84.78	829.19
91.53	828.99	94.05	828.92	103.42	828.67	104.03	828.65	110.46	828.46
112.7	828.4	114.09	828.37	119.86	828.27	120.77	828.25	122.62	828.22
123.19	828.21	132.4	828.09	132.67	828.09	133.01	828.08	134.54	828.07
135.22	828.07	135.64	828.07	139.19	828.09	139.28	828.09	139.61	828.09
139.88	828.09	140.15	828.09	143.01	828.18	152.35	828.3	153.73	828.36
156.58	828.49	168.1	828.8	176.97	829.32	188.61	830	189.36	830.1
191.09	830.42	197.36	830.41	210.1	830.63	218.76	830.09	220.05	830
220.87	830	270.1	828.71	272.93	828.65	299.31	828	302.7	827.77
303.52	827.77	306.38	827.68	320.02	827.07	325.65	826.82	326.24	826.81
328.46	826.79	353.75	826	356.58	826	357.24	825.45	359.31	824
360.1	823.52	362.29	822.03	382.46	822.33	401.54	822.42	405.94	823.87
406.29	824	408.51	824.33	415.99	825.23	420.95	825.86	422.22	826
425.52	827.67	426.14	828	429.24	829.72	429.75	830	429.89	830.02
440.71	831.89	441.32	832	444.32	832	480.07	833.73	485.11	834
492.49	835.38	495.7	836	499.07	836.62	506.5	838	512.87	839.45
515.34	840	519.08	840.85	521.04	841.23	522.71	841.52	523.54	841.67
525.58	842	527.64	842.31	530.45	842.83	534.69	843.56	536.71	844
536.83	844	543.95	845.16	545.09	845.34	549.15	846	554.58	846.76
563.93	848	564.84	848	566.68	848.39	572.35	850		

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	356.58	.035	408.51	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
356.58 408.51 54.14 61.47 37.92 .1 .3

Ineffective Flow num= 2

Sta L	Sta R	Elev	Permanent
221.06	261.25	832	F
445.63	572.35	832	F

CROSS SECTION OUTPUT Profile #PF 1

Saddle2.rep

```

*****
* E.G. Elev (ft)          * 831.99 * Element                * Left OB * Channel * Right OB *
* Vel Head (ft)          * 0.50  * Wt. n-Val.            * 0.100  * 0.035  * 0.100  *
* W.S. Elev (ft)         * 831.49 * Reach Len. (ft)       * 54.14  * 61.47  * 37.92  *
* Crit W.S. (ft)         * 828.49 * Flow Area (sq ft)     * 764.27 * 460.44 * 119.88 *
* E.G. Slope (ft/ft)     * 0.001340 * Area (sq ft)         * 845.60 * 460.44 * 119.88 *
* Q Total (cfs)          * 4015.30 * Flow (cfs)           * 848.00 * 3007.06 * 160.24 *
* Top Width (ft)         * 383.95 * Top Width (ft)       * 302.12 * 51.93  * 29.90  *
* Vel Total (ft/s)       * 2.99  * Avg. Vel. (ft/s)     * 1.11  * 6.53  * 1.34  *
* Max Chl Dpth (ft)     * 9.46  * Hydr. Depth (ft)     * 2.92  * 8.87  * 4.01  *
* Conv. Total (cfs)      * 109670.2 * Conv. (cfs)          * 23161.6 * 82132.0 * 4376.7 *
* Length Wtd. (ft)      * 59.27 * Wetted Per. (ft)     * 262.39 * 53.46  * 31.13  *
* Min Ch El (ft)        * 822.03 * Shear (lb/sq ft)     * 0.24  * 0.72  * 0.32  *
* Alpha                  * 3.62  * Stream Power (lb/ft s) * 572.35 * 0.00  * 0.00  *
* Frctn Loss (ft)       * 0.07  * Cum Volume (acre-ft) * 11.18  * 5.86  * 0.80  *
* C & E Loss (ft)       * 0.06  * Cum SA (acres)       * 2.86  * 0.70  * 0.33  *
*****

```

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, water surface was used.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork                      RS: 1421.670

INPUT

Description:

Station Elevation Data		num= 114		Elev		Sta		Elev		Sta		Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	2.79	849.15	6.37	848	7.77	847.56	9.4	847.08				
12.05	846.29	13.14	846	17.43	845.03	21.19	844.05	21.4	844				
21.6	843.92	27.18	842	28.6	841.36	31.86	840	34.65	838.93				
36.95	838	39.48	837.09	43.26	836.17	43.69	836.05	43.78	836.04				
43.84	836.03	44.08	836	45.26	836	47.98	835.5	50.67	835.2				
52.4	835.01	53.64	834.87	56.33	834.58	56.76	834.53	58.93	834.29				
59.09	834.26	60.91	834	61.53	833.91	61.77	833.88	65.76	833.25				
67.21	833.05	69.67	832.68	74.1	832	75.37	831.72	78.33	831.04				
79.3	830.81	83.15	830	84.82	829.93	85.04	829.92	85.58	829.89				
89.94	829.68	94.22	829.47	99.72	829.24	110.94	828.47	113.82	828.32				
115.24	828.25	117.83	828	174.08	828	174.52	828.04	194.87	830				
195.39	830.04	197.72	830.24	210.01	830.31	216.6	830.41	218.07	830.25				
219.57	830.05	219.97	830	222.23	829.79	230.6	829.12	241.79	828.19				
244.75	828	267.96	828	272.56	827.85	273.71	827.84	275.94	827.7				
278.22	827.59	301.45	826	323.5	826	356.72	826	358.07	824.91				
359.23	824	359.84	823.54	362.77	821.27	387.26	822.16	393.71	822.38				
411.92	823.65	414.58	824	416.84	824	418.53	825.41	418.9	825.72				
419.26	826	419.65	826.31	421.76	828	424.27	830	435.33	830.62				
437.01	830.73	456.8	832	472.29	832.9	493.97	834	495.74	834.51				
500.32	836	502.54	836.66	507.57	838	509.02	838.37	515.42	840				

Saddle2.rep

517.32	840.46	523.35	842	525.17	842.45	527.3	843.03	531.03	844
538.61	844.9	543.35	845.45	545.39	845.69	547.61	846	547.81	846
553.14	846.84	558.54	847.64	560.73	848	567.55	850		

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 356.72 .035 424.27 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 356.72 424.27 284.66 127.14 14.01 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.87	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.32	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.56	* Reach Len. (ft)	* 284.66	* 127.14	* 14.01
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 978.83	* 575.77	* 20.58
* E.G. Slope (ft/ft)	* 0.000926	* Area (sq ft)	* 978.83	* 575.77	* 20.58
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 1016.45	* 2990.82	* 8.03
* Top width (ft)	* 373.80	* Top width (ft)	* 280.64	* 67.55	* 25.61
* Vel Total (ft/s)	* 2.55	* Avg. vel. (ft/s)	* 1.04	* 5.19	* 0.39
* Max Chl Dpth (ft)	* 10.29	* Hydr. Depth (ft)	* 3.49	* 8.52	* 0.80
* Conv. Total (cfs)	* 131983.2	* Conv. (cfs)	* 33410.6	* 98308.6	* 264.0
* Length wtd. (ft)	* 164.00	* Wetted Per. (ft)	* 281.15	* 71.39	* 25.66
* Min Ch El (ft)	* 821.27	* Shear (lb/sq ft)	* 0.20	* 0.47	* 0.05
* Alpha	* 3.14	* Stream Power (lb/ft s)	* 567.55	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.12	* Cum Volume (acre-ft)	* 10.04	* 5.13	* 0.74
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 2.50	* 0.62	* 0.30

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1293.596

INPUT

Description:

Station	Elevation	Data	num=	131
Sta	Elev	Sta	Elev	Sta Elev Sta Elev
*****	*****	*****	*****	*****
0	850	4.12	848	8.06 846.06 8.17 846 8.81 845.68
12.19	844	12.67	843.76	16.32 842 21.32 840.26 22.02 840
22.88	839.69	23.71	839.41	27.76 838 30.51 837.06 33.76 836
35.14	835.59	43.54	835.21	44.85 835.17 45.09 835.16 45.37 835.14
46.01	835.06	52.66	834.02	52.75 834 52.76 834 52.81 833.98
57.47	832	61.78	831.6	64.46 831.35 70.98 830.78 77.87 830.09
78.18	830.06	78.72	830	83.23 829.79 84.2 829.74 90.44 829.43
96.17	829.17	104.55	828.86	106.6 828.82 107.4 828.77 113.81 829.28
116.59	829.47	116.83	829.46	116.9 829.46 127.6 828.54 136.41 828.39
140.21	828.11	141.37	828.01	141.44 828 146.09 826.7 148.09 826.12

saddle2.rep

148.31	826.05	148.61	826	150.46	826	151.22	826.07	153.3	826.23
153.77	826.17	156.73	826.29	164.02	826	170.8	826	174.64	825.61
175.18	825.62	175.49	825.64	183.13	825.23	183.52	825.24	184.54	825.29
187.88	825.12	189.56	825.18	209.18	825.12	214.39	825	221.13	824.84
227.6	824.69	228.7	824.66	236.9	824.44	243.38	824.3	257.03	824
259.48	822.47	260.32	821.95	260.94	821.57	261.45	821.27	308.31	821.27
308.52	821.4	308.8	821.51	310.32	821.96	310.46	822	314.14	823
319.94	824	319.95	824	323.41	824.63	327.21	825.87	327.4	825.93
327.57	826	328.17	826.28	331.9	828	333.47	828.78	334.86	829.52
335.72	830	337.6	830	376.51	830	434.08	831.68	435.98	831.69
439.81	831.83	440.38	831.83	444.86	831.97	445.9	832	450.97	832.69
452.42	832.95	456.13	833.55	457.6	833.77	459.01	834	463.1	834.77
468.93	836	473.04	836.97	475.41	837.5	477.76	838	482.57	838.97
485.12	839.48	487.6	840	490.72	840.62	493.43	841.09	495.45	841.46
498.55	842	501.14	842.35	510.55	844	510.81	844.04	520.74	845.8
521.82	845.99	521.85	846	522.07	846.04	533.57	848	536.16	848.49
544.51	850								

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	257.03	.035	335.72	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	257.03	335.72		379.96	235.75	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.73	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.24	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.49	* Reach Len. (ft)	* 379.96	* 235.75	* 67.58
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 887.08	* 698.33	* 98.87
* E.G. Slope (ft/ft)	*0.000611	* Area (sq ft)	* 887.08	* 698.33	* 98.87
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 895.91	* 3081.25	* 38.14
* Top Width (ft)	* 364.64	* Top width (ft)	* 194.08	* 78.69	* 91.87
* Vel Total (ft/s)	* 2.38	* Avg. vel. (ft/s)	* 1.01	* 4.41	* 0.39
* Max Chl Dpth (ft)	* 10.22	* Hydr. Depth (ft)	* 4.57	* 8.87	* 1.08
* Conv. Total (cfs)	*162409.9	* Conv. (cfs)	* 36237.5	*124629.8	* 1542.6
* Length Wtd. (ft)	* 231.75	* Wetted Per. (ft)	* 194.61	* 81.02	* 91.89
* Min Ch El (ft)	* 821.27	* Shear (lb/sq ft)	* 0.17	* 0.33	* 0.04
* Alpha	* 2.67	* Stream Power (lb/ft s)	* 544.51	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	* 3.95	* 3.27	* 0.72
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 0.95	* 0.41	* 0.28

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

Saddle2.rep

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 1000.000

INPUT

Description:

Station Elevation Data num= 116

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	.26	849.64	1.5	848	2.99	846	3.07	845.88
4.81	843.56	5.98	842	6.08	841.88	7.5	840	7.81	839.63
9.02	838	9.72	837.47	11.66	836	13.76	834.45	14.37	834
16.27	832.6	17.09	832	17.85	831.92	30.72	830.59	44.39	830.01
44.63	830	45.04	829.98	46.91	829.91	49.1	829.82	56.19	828.94
64.04	828	65.22	827.34	67.37	826	68.79	825.02	70.4	824
72.12	823.16	74.22	822	74.83	821.71	75.57	821.27	103.45	821.27
104.71	821.26	104.99	821.33	105.34	821.44	106.87	822	111.85	823.77
112.67	824	117.18	825.27	120.39	826	125.39	826.29	127.25	826.41
131	826.54	132.8	826.64	134.71	826.73	135.12	826.75	136.89	826.83
139.24	826.93	141.51	827.02	146.36	827.18	148.33	827.25	149.98	827.29
151.35	827.32	153.84	827.41	154.85	827.43	156.24	827.48	157.49	827.51
158.19	827.53	158.7	827.55	160.43	827.56	160.84	827.58	161.3	827.6
161.9	827.63	163.96	827.58	164.7	827.62	166.92	827.51	167.83	827.56
168.62	827.6	169.33	827.64	173.57	827.47	209.25	827.32	211.63	827.36
213.59	827.39	215.1	827.41	220.28	827.46	247.59	828	260.33	828
264.01	828.05	265.31	828.07	266.01	828.08	267.24	828.1	349.67	828.76
354.21	828.9	359.57	829.06	360.66	829.06	365.65	829.23	369.72	829.39
372.38	829.49	376.5	829.66	382.67	829.92	383.11	829.93	384.54	830
398.78	831.6	401.74	832	404.21	832.82	407.8	834	411.97	835.59
413.07	836	414.97	836.81	417.7	838	419.82	838.96	422.17	840
426.51	841.74	427.16	842	428.24	842.38	432.79	844	437.73	845.68
438.63	846	439.07	846.15	440.44	846.61	443.79	847.72	444.64	848
450.39	850								

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.013	49.1	.035	120.39	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.

49.1	120.39	1	1	1	.1	.3
------	--------	---	---	---	----	----

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.50	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.40	* Wt. n-Val.	* 0.013	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.10	* Reach Len. (ft)	*	*	*
* Crit W.S. (ft)	* 828.88	* Flow Area (sq ft)	* 17.78	* 509.01	* 827.09
* E.G. Slope (ft/ft)	* 0.001447	* Area (sq ft)	* 17.78	* 509.01	* 827.09
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 64.43	* 2974.55	* 976.32
* Top width (ft)	* 368.54	* Top width (ft)	* 23.31	* 71.29	* 273.94
* Vel Total (ft/s)	* 2.97	* Avg. vel. (ft/s)	* 3.62	* 5.84	* 1.18
* Max chl Dpth (ft)	* 9.84	* Hydr. Depth (ft)	* 0.76	* 7.14	* 3.02

* Conv. Total (cfs)	*105549.1	* Conv. (cfs)	* 1693.7	* 78191.2	* 25664.2
* Length wtd. (ft)	*	* Wetted Per. (ft)	* 23.36	* 73.96	* 274.08
* Min Ch El (ft)	* 821.26	* Shear (lb/sq ft)	* 0.07	* 0.62	* 0.27
* Alpha	* 2.94	* Stream Power (lb/ft s)	* 450.39	* 0.00	* 0.00
* Frctn Loss (ft)	*	* Cum Volume (acre-ft)	*	*	*
* C & E Loss (ft)	*	* Cum SA (acres)	*	*	*

\*\*\*\*\*

SUMMARY OF MANNING'S N VALUES

River:Toms Fork

* Reach	* River Sta.	* n1	* n2	* n3
*Toms Fork	* 2865.327	* .1*	* .035*	* .1*
*Toms Fork	* 2579.832	* .1*	* .035*	* .1*
*Toms Fork	* 2372.941	* .035*	* .035*	* .1*
*Toms Fork	* 2123.812	* .1*	* .035*	* .1*
*Toms Fork	* 2002.134	* .1*	* .035*	* .1*
*Toms Fork	* 1929.868	* .1*	* .035*	* .1*
*Toms Fork	* 1811.557	* .1*	* .035*	* .1*
*Toms Fork	* 1726.403	* .1*	* .035*	* .1*
*Toms Fork	* 1580.979	* .1*	* .035*	* .1*
*Toms Fork	* 1528.223	* Culvert	*	*
*Toms Fork	* 1483.221	* .1*	* .035*	* .1*
*Toms Fork	* 1421.670	* .1*	* .035*	* .1*
*Toms Fork	* 1293.596	* .1*	* .035*	* .1*
*Toms Fork	* 1000.000	* .013*	* .035*	* .1*

\*\*\*\*\*

SUMMARY OF REACH LENGTHS

River: Toms Fork

* Reach	* River Sta.	* Left	* Channel	* Right
*Toms Fork	* 2865.327	* 212.2*	* 282.13*	* 186.24*
*Toms Fork	* 2579.832	* 271.1*	* 188.24*	* 66.66*
*Toms Fork	* 2372.941	* 494.68*	* 209.34*	* 278.69*
*Toms Fork	* 2123.812	* 4.85*	* 111.36*	* 132.72*
*Toms Fork	* 2002.134	* 5.33*	* 72.27*	* 84.5*
*Toms Fork	* 1929.868	* 5.86*	* 118.14*	* 110.15*
*Toms Fork	* 1811.557	* 17.98*	* 85.13*	* 75.99*
*Toms Fork	* 1726.403	* 25.62*	* 144.25*	* 127.32*
*Toms Fork	* 1580.979	* 123.76*	* 97.42*	* 118.65*
*Toms Fork	* 1528.223	* Culvert	*	*
*Toms Fork	* 1483.221	* 54.14*	* 61.47*	* 37.92*
*Toms Fork	* 1421.670	* 284.66*	* 127.14*	* 14.01*

*Toms Fork	*	1293.596	*	379.96*	235.75*	67.58*
*Toms Fork	*	1000.000	*	1*	1*	1*

\*\*\*\*\*

\*\*\*\*\*

SUMMARY OF CONTRACTION AND EXPANSION COEFFICIENTS  
River: Toms Fork

\*\*\*\*\*

* Reach	* River Sta.	* Contr.	* Expan.
*Toms Fork	* 2865.327*	.1*	.3*
*Toms Fork	* 2579.832*	.1*	.3*
*Toms Fork	* 2372.941*	.1*	.3*
*Toms Fork	* 2123.812*	.1*	.3*
*Toms Fork	* 2002.134*	.1*	.3*
*Toms Fork	* 1929.868*	.1*	.3*
*Toms Fork	* 1811.557*	.1*	.3*
*Toms Fork	* 1726.403*	.1*	.3*
*Toms Fork	* 1580.979*	.1*	.3*
*Toms Fork	* 1528.223*culvert	*	*
*Toms Fork	* 1483.221*	.1*	.3*
*Toms Fork	* 1421.670*	.1*	.3*
*Toms Fork	* 1293.596*	.1*	.3*
*Toms Fork	* 1000.000*	.1*	.3*

\*\*\*\*\*

\*\*\*\*\*

ERRORS WARNINGS AND NOTES  
Errors Warnings and Notes for Plan : Existing

River: Toms Fork Reach: Toms Fork RS: 2579.832 Profile: PF 1  
Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2372.941 Profile: PF 1  
Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2123.812 Profile: PF 1  
Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2002.134 Profile: PF 1  
Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 1929.868 Profile: PF 1



Saddle2.rep

Warning:The energy equation could not be balanced within the specified number of iterations. The program selected the water

surface that had the least amount of error between computed and assumed values.

Warning:Divided flow computed for this cross-section.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

River: Toms Fork Reach: Toms Fork RS: 1811.557 Profile: PF 1

Warning:The energy equation could not be balanced within the specified number of iterations. The program selected the water

surface that had the least amount of error between computed and assumed values.

Warning:Divided flow computed for this cross-section.

River: Toms Fork Reach: Toms Fork RS: 1726.403 Profile: PF 1

Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 1580.979 Profile: PF 1


Warning:Divided flow computed for this cross-section.

River: Toms Fork Reach: Toms Fork RS: 1293.596 Profile: PF 1


Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 2865.327




Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 2579.832




Saddle2 Plan: 1) Culvert 2) Existing

Geom: Culvert Flow: Existing-Revised


River = Toms Fork Reach = Toms Fork RS = 2372.941




Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 2123.812




Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 2002.134



Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1929.868




Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1811.557




Legend	
WS PF 1 - Culvert	—▲—
WS PF 1 - Existing	—■—
Ground	—▲—
Ineff	▲
Bank Sta	●




Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1726.403




Saddle2 Plan: 1) Culvert 2) Existing  
 Geom: Culvert Flow: Existing-Revised  
 River = Toms Fork Reach = Toms Fork RS = 1580.979




Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1528.223 Culv



Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1528.223 Culv




Saddle2 Plan: 1) Culvert 2) Existing  
 Geom: Culvert Flow: Existing-Revised  
 River = Toms Fork Reach = Toms Fork RS = 1483.221






Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1421.670

Legend	
WS PF 1 - Culvert	▲
WS PF 1 - Existing	■
Ground	■
Bank Sta	●




Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1293.596



Legend	
WS PF 1 - Culvert	(dashed line)
WS PF 1 - Existing	(solid line)
Ground	(thick black line)
Bank Sta	(red dot)

Saddle2 Plan: 1) Culvert 2) Existing  
Geom: Culvert Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1000.000





**FLOODPLAIN ANALYSIS OF  
TOMS FORK  
NEW MILTON COMPRESSOR STATION  
ACCESS ROAD WITH BRIDGE**



VICINITY MAP

1" = 2,000'



151 Windy Hill Lane  
Winchester, VA 22602  
Telephone: (888) 662-4185  
[www.navituseng.com](http://www.navituseng.com)

Engineering ◀ Survey ◀ Environmental ◀ GIS

Prepared For:



981 East Washington Avenue  
Ellenboro, WV 26346  
(304) 869-3405

Contacts:

Bill Prehm, Project Manager  
(303) 807-4436  
Anthony Smith, Field Engineer  
(304) 673-6196  
Mike Heaster, Land Agent  
(304) 871-0085



Designed By:  
Navitus Engineering Inc.

Project Manager:  
Dan Murphy, CFM  
[dmurphy@navituseng.com](mailto:dmurphy@navituseng.com)

Tax Parcel:  
Map 8 Parcel 37

Location:  
New Milton District, Doddridge County  
West Virginia

Date: July 16, 2013

FN# ANT096

## 1. Objective

The objective of this floodplain analysis was to establish boundaries for the existing and proposed conditions of the 100 year base flood elevations (BFE). The proposed condition includes the installation of a 60' span steel bridge and an access road to provide access to a compressor station site where the entrance off of State Route 18 is within the FEMA Flood Zone "AE".

## 2. Existing Conditions

### 2.1. *Property Description*

This site is located in Doddridge County, West Virginia along Toms Fork and State Route 18 south of West Union in the New Milton District. The proposed access road entrance is located on the east side of State Route 18.

### 2.2. *Floodplain Delineation*

The approximate limit of the 100-year floodplain (a flood event that has a 1% chance of being equaled or exceeded in any given year) is shown on FEMA Flood Insurance Rate Map (FIRM) for Doddridge County on panels 54017C0230C effective October 4, 2011. This floodplain is located in flood zone designation "AE" and base flood elevations have been established. Detailed study information was found in the Flood Insurance Study for Doddridge County, dated October 4, 2011.

### 2.3. *Floodplain Ordinance*

This site is administered under the Doddridge County Floodplain Ordinance, enacted May 31st, 2013.

Per Section 4.3 of the ordinance, when a site is located in FEMA Flood Zone designation "AE" without Floodway Area, the Floodplain Administrator shall require the applicant to demonstrate that the cumulative effect of the proposed development, when combined with all other existing and anticipated development, will not increase the elevation of the 100-year flood more than one (1) foot at any point.

Per Section 4.5.A of the ordinance, any developer shall notify in writing, by certified mail, Doddridge County's Floodplain Administrator, the State Coordinating Office, and adjacent communities and any adjacent property owners of all such intended activities prior to the alteration of the stream. Copies of all required notifications must be submitted to the Federal Insurance Administration. In addition prior to issuing the local permit the Floodplain Administrator shall require copies of all necessary permits from those government agencies from which Federal or State Law requires approval.

Per Section 4.5.B a stream crossing analysis for the proposed permanent crossing of Toms Fork has been provided under separate cover and includes a cover letter signed by the

responsible professional, a detailed report, hydraulic and hydrologic computations and a sitemap detailing the planned construction.

Per Section 4.5.C of this ordinance the stream crossing has been designed with "best practice" techniques in mind. A 60' span steel bridge were selected to pass the base flow and 10 year storm events. The bridge will span the stream to allow for aquatic passage and preservation of the existing stream channel. The bridge was designed to be a permanent stream crossing. All fill utilized will be 2-4" clean rock aggregate with a 4-6" large angular durable rock base to minimize erosion during storm events. Concrete abutments and wing walls will be utilized to minimize scour around the culvert. Sandbag cofferdams and a dewatering-bag-system will be utilized during construction to minimize erosion and allow for construction in the stream channel.

Per Section 4.5.D of this ordinance the bridge will be properly anchored as required.

Per Section 4.5.E of this ordinance the Developer shall provide Doddridge County with all required legal agreements detailing inspections and maintenance.

Per Section 5.1 of this ordinance Permits are required for the construction of the permanent stream crossing. The format of the permit will coincide with the requirements set forth in Section 5.2 of the ordinance.

Per Section 6.1E of this ordinance the fill associated with this plan has been designed to not adversely affect adjacent properties. The access road and bridge were located to minimize floodway constriction and the height above the existing grade was minimized to allow as much flow as possible to be unimpeded. Impacts to the 100 year base flood elevation are demonstrated later in this report, however, increases to the 100 year base flood elevations were limited to approximately 1,052' upstream of the proposed culvert and returned to 0.0' of impact approximately 1,1052' upstream of the proposed culvert. Impacts downstream of the proposed culvert were limited approximately 45' downstream and returned to 0.0' of impact immediately. Fill as stated above shall consist of 2-4" clean rock aggregate with a 4-6" large angular durable rock base. No less than 2:1 slopes will be utilized in the construction of the proposed crossing.

Per Section 6.1F the structure has been placed with the longitudinal axis parallel to the direction of flood flow and to maintain the same flood-flow lines of the adjoining structures.

Per Section 6.1.I of this ordinance, no material or equipment storage shall be allowed within the vicinity of the entrance. The storage of all material and equipment shall be onsite and away from the entrance.

Per Section 6.1.K of this ordinance, a flow line is proposed adjacent to State Route 18 along the entrance to allow adequate drainage across the proposed entrance.

All other specific requirements covered in Section 6.1 of this ordinance are not applicable to this design. (Sections 6.1.A, 6.1.B, 6.1.C, 6.1.D, 6.1.F, 6.1.G, 6.1.H, 6.1.J, and 6.1.L)

The developer shall conform with all administrative procedures as outline in Article 7 of this ordinance.

#### 2.4. *Toms Fork Characteristics*

Toms Fork is located in the New Milton District of Doddridge County and flows in a northern direction. The drainage area flowing to Toms Fork at the stream crossing is approximately 14.602 square miles of forested and agricultural land with an average basin slope of 36.04%.

### 3. Analysis Information

#### 3.1. *HEC-RAS*

A HEC-RAS hydraulic analysis was performed for the portion of the Toms Fork that has an impact on the BFE's across the property. HEC-RAS is designed to perform one-dimensional hydraulic calculations for a full network of natural and constructed channels. The steady flow system is designed for applications in floodplain management and flood insurance studies.

#### 3.2. *Analysis Limits*

The analysis information is based upon two foot interval aerial shot topography by Blue Mountain Aerial Mapping. The upstream analysis limit for Toms Fork is located approximately 1,337 feet upstream from the proposed stream crossing and represents the 28+65.327 section. The downstream analysis limit for Toms Fork is located approximately 1,564 feet downstream of the proposed stream crossing and represents the 10+00.000 section. These limits were selected so that the HEC-RAS model would accurately determine the base flood elevations on site and off site.

#### 3.3. *Flow Data*

The hydrologic analysis utilized USDA soil surveys for computation of drainage shed curve numbers, aerial topography and 3 meter West Virginia GIS Technical Center DEM to determine the drainage area(s) and time of concentration path(s). The peak 100-year discharge within the inundation area was determined through TR-55 SCS methodology. Time of concentration paths were calculated utilizing the SCS lag method. The hydrologic calculations for the drainage area were performed using HEC-HMS. See the table below for a summary of the flow conditions, and see Supplement 1 for the complete Drainage Computations.

<b>Stream</b>	<b>Drainage Area</b>	<b>Flow (cfs)</b>	<b>Note</b>
Upper Toms Fork	8,212.48 Ac.	3765.8	Upper Reach
Middle Toms Fork	1,132.16 Ac.	949.4	Middle Reach
Lower Toms Fork	604.16 Ac.	666.8	Lower Reach

### 3.4. Cross Section Data

The cross sections were employed at significant changes in site features. This includes major bends in the stream channel, areas of major contraction and expansion of the floodplain area, upstream and downstream of existing culverts, and at building obstructions (cross sections were compiled using Aerial Mapping by Blue Mountain Aerial Mapping).

### 3.5. Manning's n-value

The channel and overbank areas were assigned manning's n-values based on field review, site photographs, and close inspection of existing aerial photography. The chart below describes the manning's n values used in this study.

Manning's n value	Description	Portion Used
.035	Clean, straight, full, no rifts or deep pools, stones and weeds	Main Channel
.1	Heavy stand of timber, few down trees, little undergrowth, flow below branches	Floodplains (Normal)
.013	Asphalt	Floodplains
.035	High grass	Floodplains
.033	Rip Rap Dry Rubble	Floodplains
.06	Light Brush and trees, in summer	Floodplains
.08	Heavy stand of timber, few down trees, little undergrowth, flow below branches	Floodplains (Minimum)

## 4. Results

### 4.1. Existing Conditions

Since the site is in Zone "AE" floodplain area as shown on the FIRM, there has been a detailed study analysis with one foot interval base flood elevations established within the Doddridge County Flood Insurance Study (FIS) effective October 4, 2011. An existing conditions model was prepared based upon aerial topography and existing drainage computations. This information was processed in HEC-RAS to determine the existing conditions of the Base Flood Elevations and then compared with the FIS for accuracy.

### 4.2. Proposed Conditions

The proposed conditions model was based on the proposed topography for the site access road and proposed bridge in the stream. This information was added into the existing conditions cross sections, and then was processed in HEC-RAS to determine the proposed conditions of the Base Flood Elevations. A summary of elevation changes showing the

existing and proposed BFEs at the various cross sections has been provided below. As shown in the table, the proposed development will not increase the existing BFEs more than 0.3' throughout the project area and return to 0.0' at the upstream and downstream termini of the study area.

<b>NEW MILTON COMPRESSOR STATION ACCESS ROAD FLOODPLAIN STUDY SUMMARY OF COMPUTED ELEVATIONS</b>					
CROSS SECTION STATION	RIVER NAME	100 YEAR BASE FLOOD ELEVATION			
		DODDRIDGE COUNTY FIS MODEL*	EXISTING CONDITIONS MODEL	PROPOSED CONDITIONS MODEL	PROPOSED DIFFERENCE
2865.327	Toms Fork	833.5	833.9	833.9	0.0
2579.832	Toms Fork	833.0	833.7	833.7	0.0
2372.941	Toms Fork	832.8	833.2	833.3	+ 0.1
2123.812	Toms Fork	832.5	833.2	833.3	+ 0.1
2002.134	Toms Fork	832.3	832.8	832.9	+ 0.1
1929.868	Toms Fork	832.2	832.1	832.2	+ 0.1
1811.557	Toms Fork	832.1	831.7	832.0	+ 0.3
1726.403	Toms Fork	832.0	831.4	831.7	+ 0.3
1580.979	Toms Fork	831.8	831.6	831.8	+ 0.2
1528.223	Toms Fork	Bridge			
1483.221	Toms Fork	831.7	831.5	831.5	0.0
1421.670	Toms Fork	831.6	831.6	831.6	0.0
1293.596	Toms Fork	831.4	831.5	831.5	0.0
1000.000	Toms Fork	831.0	831.1	831.1	0.0

\* ELEVATIONS ARE INTERPOLATED FROM DODDRIDGE COUNTY FIS EFFECTIVE OCTOBER 4, 2011.

## 5. Conclusion

The results of this floodplain analysis indicate that there will be minimal changes in the 100 year base flood elevation and no impacts to upstream and downstream adjacent properties along Toms Fork. The largest increase in base flood elevation is 0.3' and is located on site directly upstream of the stream crossing.

**APPENDIX**

Exhibit A	FIRM Panel 54017C0230C
Exhibit B	Overall Plan
Exhibit C	Existing Conditions Plan
Exhibit D	Proposed Conditions Plan
<hr/>	
Supplement 1	Drainage Computations
Supplement 2	HEC-RAS Analysis –Existing Conditions Summary
Supplement 3	HEC-RAS Analysis –Proposed Conditions Summary w/ Cross Sections

**Exhibit A**

**FIRM Panel 54017C0230C**





MAP SCALE 1" = 1000'



**NFIP**

**NATIONAL FLOOD INSURANCE PROGRAM**

PANEL 0230C

**FIRM**  
 FLOOD INSURANCE RATE MAP  
 DODDRIDGE COUNTY,  
 WEST VIRGINIA  
 AND INCORPORATED AREAS

PANEL 230 OF 325  
 (SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
DODDRIDGE COUNTY	540024	0230	C

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

MAP NUMBER  
 54017C0230C  
 MAP REVISED  
 OCTOBER 4, 2011  
 Federal Emergency Management Agency





DODDRIDGE COUNTY UNINCORPORATED AREAS 540024


This is an official copy of a portion of the above referenced flood map. It was extracted using FIRM OnLine. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at [www.msc.fema.gov](http://www.msc.fema.gov)

**Exhibit B**  
**Overall Plan**



**LEGEND**

-  EX. DELINEATED STREAM
-  HEC-RAS STUDY CROSS SECTION
-  FEMA FLOOD ZONE "AE"  
PER FIRM #54017C0230C
-  EXISTING STRUCTURE



**NAVITUS**  
ENGINEERING INC.



151 Windy Hill Lane  
Winchester, Virginia 22602  
Telephone: (888) 662-4185  
www.navituseng.com

Engineering Survey Environmental GIS

CYRUS B. KUMP  
REGISTERED  
1978  
STATE OF  
WEST VIRGINIA  
PROFESSIONAL ENGINEER



07/16/2013

**ANTERO**  
RESOURCES

THIS DOCUMENT  
WAS PREPARED  
FOR:  
ANTERO RESOURCES  
CORPORATION




OVERALL PLAN

**NEW MILTON**  
COMPRESSOR STATION  
ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WV

SCALE: 1" = 200'

NEW MILTON  
JOB NO. ANT096


DATE: 07/16/2013





**Exhibit C**  
**Existing Conditions Plan**





**LEGEND**

- EX. DELINEATED STREAM
- HEC-RAS STUDY CROSS SECTION
- FEMA FLOODPLAIN ZONE "AE"
- EXISTING 100-YR FLOODPLAIN

GRID NORTH AND ELEVATIONS SHOWN  
HEREON WERE ESTABLISHED BY SURVEY  
GRADE GPS

**NAVITUS**  
ENGINEERING INC.

151 Windy Hill Lane  
Winchester, Virginia 22602  
Telephone: (540) 664-1185  
www.navituseng.com

Engineering Survey Environmental GIS

CYRUS B. KUMP  
REGISTERED  
19578  
STATE OF  
WEST VIRGINIA  
PROFESSIONAL ENGINEER

07/16/2013

**ANTERO**  
RESOURCES

THIS DOCUMENT  
WAS PREPARED  
FOR:  
ANTERO RESOURCES  
CORPORATION

EXISTING CONDITIONS PLAN

**NEW MILTON  
COMPRESSOR STATION  
ACCESS ROAD**

NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WV

SCALE: 1" = 50'

NEW MILTON  
JOB NO. ANT096

DATE: 07/16/2013











**Exhibit D**  
**Proposed Conditions Plan**



**LEGEND**

-  EX. DELINEATED STREAM
-  HEC-RAS STUDY CROSS SECTION
-  FEMA FLOODPLAIN ZONE "AE"
-  EXISTING 100-YR FLOODPLAIN
-  PROPOSED 100-YR WSE



GRID NORTH AND ELEVATIONS SHOWN  
HEREON WERE ESTABLISHED BY SURVEY  
GRADENCES

**NAVITUS**  
ENGINEERING INC.



151 Wainy Hill Lane  
Washington, Virginia 22602  
Telephone: (803) 662-4418  
www.navituseng.com

Engineering Survey Environmental GIS



07/16/2013

**ANTERO**  
RESOURCES  
THIS DOCUMENT  
WAS PREPARED  
FOR:  
ANTERO RESOURCES  
CORPORATION

PROPOSED CONDITIONS PLAN  
**NEW MILTON**  
**COMPRESSOR STATION**  
**ACCESS ROAD**  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WV

SCALE: 1" = 50'  
NEW MILTON  
JOB NO. ANT096  
DATE: 07/16/2013





**Supplement 1**  
**Drainage Computations**



USGS 7.5 OXFORD QUAD MAP



DRAINAGE MAP

USGS 7.5 NEW MILTON QUAD MAP



WEST VIRGINIA STATE PLANE  
 COORDINATE SYSTEM  
 NORTH ZONE, NAD83  
 ELEVATION BASED ON NAVD88  
 ESTABLISHED BY SURVEY GRADE GPS  
 & OPUS POST-PROCESSING

KEY	HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)
A	UPPER TOMS FORK	12,832
B	MIDDLE TOMS FORK	1,769
C	LOWER TOMS FORK	944
	TOTAL	15,545



SCALE: 1" = 4000'  
 NEW MILTON  
 JOB NO. ANT088  
 DATE: 07/16/2013

DRAINAGE MAP  
**NEW MILTON**  
 COMPRESSOR STATION  
 ACCESS ROAD  
 NEW MILTON DISTRICT  
 DODDRIDGE COUNTY, WV

**ANTERO RESOURCES**  
 THIS DOCUMENT WAS PREPARED FOR:  
 ANTERO RESOURCES CORPORATION

07/16/2013

**NAVITUS ENGINEERING INC.**  
 151 Windy Hill Lane  
 Winchester, Virginia 22602  
 Telephone: (888) 662-4155  
 www.navituseng.com

Engineering ◀ Survey ◀ Environmental ◀ GIS

Project: New Milton

Simulation Run: Existing

Start of Run: 11Jul2013, 00:00  
End of Run: 12Jul2013, 00:05  
Compute Time: 11Jul2013, 08:20

Basin Model: Existing  
Meteorologic Model: 100 YR  
Control Specifications: Control 1

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
Upper Toms Fork	12.832	3765.8	11Jul2013, 14:10	1397
Reach-1	12.832	3765	11Jul2013, 14:40	1380.7
Middle Toms Fork	1.77	949.1	11Jul2013, 12:55	199.5
Junction-1	14.602	4015.3	11Jul2013, 14:35	1580.2
Reach-2	14.602	4015.1	11Jul2013, 14:55	1567.8
Lower Toms Fork	0.944	666.8	11Jul2013, 12:35	107.3
Downstream	15.546	4101.3	11Jul2013, 14:55	1675.1

Saddle2.rep

HEC-RAS Version 4.1.0 Jan 2010  
U.S. Army Corps of Engineers  
Hydrologic Engineering Center  
609 Second Street  
Davis, California

```
X      X  XXXXXX   XXXX       XXXX       XX       XXXX
X      X  X       X   X       X   X       X   X   X
X      X  X       X           X   X       X   X   X
XXXXXXXX XXXX     X           XXX XXXX     XXXXXX   XXXX
X      X  X       X           X   X       X   X   X
X      X  X       X   X       X   X       X   X   X
X      X  XXXXXX   XXXX       X   X       X   X   XXXXX
```

\*\*\*\*\*

PROJECT DATA

Project Title: Saddle2  
Project File : Saddle2.prj  
Run Date and Time: 7/16/2013 7:49:15 PM

Project in English units

\*\*\*\*\*

PLAN DATA

Plan Title: Existing  
Plan File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.p01

Geometry Title: Existing  
Geometry File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.g01

Flow Title : Existing-Revised  
Flow File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.f02

Plan Summary Information:

Number of:	Cross Sections =	13	Multiple Openings =	0
	Culverts =	0	Inline Structures =	0
	Bridges =	0	Lateral Structures =	0

Computational Information

Water surface calculation tolerance =	0.001
Critical depth calculation tolerance =	0.001
Maximum number of iterations =	20
Maximum difference tolerance =	0.3

**Supplement 2**

**HEC-RAS Analysis –Existing Conditions Summary**

Flow tolerance factor = 0.001

Computation Options

Critical depth computed only where necessary
Conveyance Calculation Method: At breaks in n values only
Friction Slope Method: Average Conveyance
Computational Flow Regime: Subcritical Flow

\*\*\*\*\*

FLOW DATA

Flow Title: Existing-Revised
Flow File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.f02

Flow Data (cfs)

\*\*\*\*\*
\* River Reach RS \* PF 1 \*
\* Toms Fork Toms Fork 2865.327\* 4015.3 \*

Boundary Conditions

\*\*\*\*\*
\* River Reach Profile \* Upstream Downstream \*
\* Toms Fork Toms Fork PF 1 \* Known WS = 833.5 Known WS = 831.1 \*

\*\*\*\*\*

GEOMETRY DATA

Geometry Title: Existing
Geometry File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.g01

CROSS SECTION

RIVER: Toms Fork
REACH: Toms Fork RS: 2865.327

INPUT

Description:

Station Elevation Data num= 100
Table with 10 columns: Sta, Elev, Sta, Elev, Sta, Elev, Sta, Elev, Sta, Elev. Data rows include values like 0, 850, 2.89, 848, 3.73, 847.42, 5.78, 846, 8.24, 844.95.

Saddle2.rep

44.6	841.93	49.67	841.3	52.98	840.89	54.84	840.66	56.84	840.4
56.98	840.39	59.93	840	62.2	838.99	64.42	838	66.42	837.11
68.93	836	77.13	835.38	80.1	835.15	89.55	834.48	91.63	834.33
96.42	834	96.46	834	103.31	833.74	108.11	833.57	115.2	833.31
120.18	833.17	144.96	832.42	149.19	832.28	158.3	832	161.69	831.77
162.91	831.7	163.61	831.66	172.16	831.13	177.1	830.87	181.93	830.59
192.98	830.03	193.14	830.02	193.52	830	195.11	829.63	202.28	828
203.58	827.9	204.23	827.86	205.83	827.75	208.78	827.55	218.92	826.86
225.69	826.43	226.36	826.39	227.77	826.3	228.45	826.25	232.59	826
233.5	824.89	234.03	824.24	234.61	823.57	239.85	823.64	241.59	823.67
250.02	823.8	269.19	824.13	281.09	824.36	281.53	824.87	281.9	825.29
282.64	826	283.77	827.33	285.69	827.68	287.35	828	290.48	828
292.08	828.23	293.87	828.48	299.55	829.32	303.22	829.8	304.12	830
305.84	831.05	306.98	831.74	307.38	832	309.66	833.4	310.6	834
312.52	835.18	313.8	836	315.48	837.04	316.99	838	318.62	839.12
319.93	840	321.46	841.28	322.33	842	324.02	843.41	324.73	844
326.6	845.56	327.13	846	329.22	847.75	329.52	848	331.9	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	232.59	.035	287.35	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	232.59	287.35		212.2	282.13	186.24	.1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 834.43	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.57	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.86	* Reach Len. (ft)	* 212.20	* 282.13	* 186.24
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 409.12	* 522.91	* 97.01
* E.G. slope (ft/ft)	*0.001252	* Area (sq ft)	* 409.12	* 522.91	* 97.01
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 455.58	* 3431.24	* 128.48
* Top width (ft)	* 210.17	* Top width (ft)	* 132.39	* 54.76	* 23.03
* Vel Total (ft/s)	* 3.90	* Avg. vel. (ft/s)	* 1.11	* 6.56	* 1.32
* Max Chl Dpth (ft)	* 10.29	* Hydr. Depth (ft)	* 3.09	* 9.55	* 4.21
* Conv. Total (cfs)	*113459.8	* Conv. (cfs)	* 12873.3	* 96955.9	* 3630.5
* Length wtd. (ft)	* 268.25	* Wetted Per. (ft)	* 132.76	* 57.29	* 24.27
* Min ch El (ft)	* 823.57	* Shear (lb/sq ft)	* 0.24	* 0.71	* 0.31
* Alpha	* 2.43	* Stream Power (lb/ft s)	* 331.90	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.27	* Cum Volume (acre-ft)	* 19.22	* 20.54	* 6.95
* C & E Loss (ft)	* 0.05	* Cum SA (acres)	* 5.62	* 2.27	* 1.59

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 2579.832

INPUT

Saddle2.rep

Description:

Station Elevation Data		num= 93		Sta		Elev		Sta		Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	2.44	848	2.66	847.82	4.89	846	5.28	845.68		
7.32	844	7.99	843.55	10.04	842	12.78	841.08	16.18	840		
20.07	838.81	22.77	838	31.3	838	32.34	838.23	36.84	839.24		
45.36	839.17	54.84	838.89	61	838.03	61.18	838	62.93	837.73		
65.72	837.27	73.51	836	74.45	835.56	77.9	834	80.43	832.85		
82.31	832	84.12	831.18	87.67	829.59	88.79	829.09	90.47	828.4		
91.43	828	93.28	827.16	95.87	826	99.12	824.4	99.91	824		
100.45	823.72	100.69	823.6	100.92	823.47	143.75	823.47	144.94	823.92		
145.14	824	151.82	825.23	155.09	825.97	155.22	826	157.83	826		
174.68	826.59	176.96	826.69	179.05	826.72	180.73	826.74	182.27	826.82		
183.75	826.84	185.06	826.91	186.58	826.95	188.92	827.07	190.49	827.12		
195.23	827.34	196.43	827.39	197.44	827.44	206.09	827.82	206.63	827.85		
210.34	828	214.91	828.57	218.82	829.06	221.21	829.36	222.27	829.51		
225.8	830	227.87	830.31	228.23	830.38	230.19	830.82	233.42	831.47		
235.56	832	238.7	832.97	242.37	834	244.36	834.61	248.21	835.78		
248.76	835.95	248.94	836	254.04	837.23	256.99	838	257.34	838		
262.74	838.68	270.79	839.6	273.44	840	283.77	841.65	285.91	842		
289.24	842.78	294.7	844	303.19	845.52	305.76	846	310.28	847.08		
313.75	847.86	314.38	848	323.1	850						

Manning's n Values		num= 3		Sta		n Val	
Sta	n Val	Sta	n Val	Sta	n Val	Sta	n Val
0	.1	95.87	.035	155.09	.1		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	95.87	155.09		271.1	188.24	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 834.11	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.41	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.70	* Reach Len. (ft)	* 271.10	* 188.24	* 66.66
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 67.00	* 584.27	* 480.81
* E.G. slope (ft/ft)	* 0.000851	* Area (sq ft)	* 67.00	* 584.27	* 480.81
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 67.42	* 3295.57	* 652.31
* Top Width (ft)	* 162.73	* Top width (ft)	* 17.31	* 59.22	* 86.20
* Vel Total (ft/s)	* 3.55	* Avg. vel. (ft/s)	* 1.01	* 5.64	* 1.36
* Max Chl Dpth (ft)	* 10.23	* Hydr. Depth (ft)	* 3.87	* 9.87	* 5.58
* Conv. Total (cfs)	* 137645.8	* Conv. (cfs)	* 2311.1	* 112973.3	* 22361.4
* Length Wtd. (ft)	* 183.85	* Wetted Per. (ft)	* 18.94	* 60.11	* 86.83
* Min Ch El (ft)	* 823.47	* Shear (lb/sq ft)	* 0.19	* 0.52	* 0.29
* Alpha	* 2.10	* Stream Power (lb/ft s)	* 323.10	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	* 18.06	* 16.95	* 5.71
* C & E Loss (ft)	* 0.03	* Cum SA (acres)	* 5.26	* 1.90	* 1.35

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than



1.4. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 2372.941

INPUT

Description:

Station Elevation Data num= 105

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	1.82	848	2.33	847.47	3.36	846.39	3.78	846
6.59	844.33	7.14	844	10.17	842.28	10.68	842	13.68	840.29
14.22	840	17.19	838.31	17.76	838	19.76	837.02	21.03	837.71
30.82	836.97	45.33	836.96	53.11	837.04	58.14	836.39	62.87	836
70.69	835.06	78.76	834	82.37	833.41	90.69	832	92.24	831.76
95.46	831.2	102.19	830	104.15	829.57	105.93	829.26	108.63	828.71
111.2	828.33	113.43	828	114.56	827.83	114.6	827.82	114.66	827.81
114.94	827.78	118.37	827.27	120.84	826.94	122.59	826.68	127.81	826
128.07	825.95	128.15	825.95	128.23	825.93	131.37	825.41	132.07	825.31
133.39	825.14	134.95	824.85	136.9	824.63	140.69	824	140.95	824
141.56	823.88	142.39	823.69	142.76	823.59	143.18	823.47	161.64	823.47
162.23	823.66	162.96	823.86	163.49	824	170.49	824.97	178.34	826
184.38	826.66	190.63	827.37	196.22	828	204.78	828.89	209.26	829.26
213.01	829.61	214.44	829.73	215.21	829.78	215.72	829.81	218.51	830
221.09	830.31	222.16	830.45	226.82	831.04	233.45	832	259.72	833.51
267.46	833.9	270.43	834	277.5	834	293.51	834.86	300.19	835.16
303.03	835.27	310.96	835.62	312.48	835.69	319.76	836	323.88	836.36
332.03	837.03	340.66	837.87	342.02	838	347.21	839.1	350.16	839.67
350.48	839.73	351.82	840	353.9	840.42	357.17	841.11	360.16	841.74
361.41	842	366.93	843.14	371.51	844	376.07	845.15	379.47	846
382.67	846.77	388.2	848	388.9	848.16	389.32	848.25	397.14	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.035	136.9	.035	170.49	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 136.9 170.49 494.68 209.34 278.69 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 833.87	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.66	* Wt. n-Val.	* 0.035	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.21	* Reach Len. (ft)	* 494.68	* 209.34	* 278.69
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 239.21	* 315.42	* 309.90
* E.G. Slope (ft/ft)	* 0.001691	* Area (sq ft)	* 239.21	* 315.42	* 309.90
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 1126.07	* 2438.45	* 450.78

Saddle2.rep

```

* Top Width (ft)          * 170.84 * Top width (ft)          * 53.32 * 33.59 * 83.93 *
* Vel Total (ft/s)       * 4.64  * Avg. vel. (ft/s)      * 4.71 * 7.73 * 1.45 *
* Max Chl Dpth (ft)     * 9.74  * Hydr. Depth (ft)     * 4.49 * 9.39 * 3.69 *
* Conv. Total (cfs)      * 97647.1 * Conv. (cfs)          * 27384.5 * 59300.1 * 10962.5 *
* Length Wtd. (ft)      * 267.77 * Wetted Per. (ft)     * 54.02 * 33.85 * 84.37 *
* Min Ch El (ft)        * 823.47 * Shear (lb/sq ft)     * 0.47 * 0.98 * 0.39 *
* Alpha                  * 1.98  * Stream Power (lb/ft s) * 397.14 * 0.00 * 0.00 *
* Frctn Loss (ft)       * 0.25  * Cum Volume (acre-ft) * 17.10 * 15.01 * 5.11 *
* C & E Loss (ft)       * 0.12  * Cum SA (acres)       * 5.04 * 1.70 * 1.22 *
*****

```

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
 This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork                      RS: 2123.812

INPUT

Description:

Station Elevation Data		num= 145		Sta		Elev		Sta		Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	7.61	848.12	8.1	848	11.48	846.85	14.02	846		
17.32	844.89	20.19	844	29.09	842.54	32.44	842	39.97	840.57		
41	840.36	41.44	840.27	41.87	840.18	42.76	840	44.29	839.85		
44.87	839.81	45.61	839.77	58.05	838.76	60.93	838.66	73.97	838		
80.16	838	86.28	837.78	88.03	837.76	89.01	837.75	89.33	837.75		
96.23	837.46	96.83	837.47	114.62	837.25	123.08	837.03	153.21	836.5		
165.6	836.24	167.39	836.2	176.66	836	183.88	836	185.94	835.94		
186.45	835.92	193.78	835.74	197.53	835.66	200.81	835.61	203.09	835.51		
207.46	835.41	211.32	835.23	215.79	835.06	217.31	834.99	218.58	834.93		
219.59	834.88	221.23	834.79	225.89	834.56	228.39	834.42	237.61	834		
240.15	833.94	250.89	833.92	251.23	833.98	252.74	834.04	256.18	834.13		
266.1	834.44	276.79	834.81	279.36	834.6	282	834.51	292.41	834.43		
302.29	834.14	305	834	306.65	834	318.72	833.83	322.62	833.82		
326.83	833.77	349.34	833.52	366.28	833.31	381.19	833.17	409.51	832.76		
442.18	832	458.66	832	459.09	831.91	460.58	831.67	467.09	830.52		
470.93	830	472.47	829.86	473.63	829.73	474.35	829.63	476.54	829.59		
478.33	829.44	480.51	829.24	482.35	829.05	484.53	829.08	493.14	828.72		
510.22	828	540.14	828	541.2	827.11	542.5	826	543.18	825.38		
544.61	824	544.96	823.68	545.31	822.47	562.34	822.47	590.93	822.47		
591.34	823.26	591.75	823.47	592.68	823.87	592.98	824	596.16	824.59		
597.7	824.75	600.18	825.16	601.92	825.29	603.14	825.47	603.8	825.56		
606.61	825.79	609.14	825.89	609.21	825.89	611.75	826	618.47	826		
623.51	826.14	623.89	826.15	627.54	826.26	629.08	826.31	634.67	826.43		
637.3	826.52	638.18	826.54	665.48	826.98	667.38	826.96	668.91	827.09		
670.46	827.22	674.09	827.49	676.03	827.52	680.97	828	682.63	828.93		
684.49	830	686.81	831.3	688.03	832	689.62	832.9	691.61	834		

Saddle2.rep

693.43	834.9	695.67	836	699.67	837.95	699.76	838	699.9	838.07
703.8	840	708.04	841.9	708.27	842	708.74	842.21	712.7	844
716.95	845.96	717.03	846	717.11	846.04	721.13	848	725.2	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	540.14	.035	611.75	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	540.14	611.75		4.85 111.36	132.72	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 833.50	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.26	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.24	* Reach Len. (ft)	* 4.85	* 111.36	* 132.72
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 414.05	* 700.28	* 477.75
* E.G. Slope (ft/ft)	* 0.000581	* Area (sq ft)	* 414.05	* 700.28	* 477.75
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 271.80	* 3179.77	* 563.73
* Top width (ft)	* 316.78	* Top width (ft)	* 166.68	* 71.61	* 78.49
* Vel Total (ft/s)	* 2.52	* Avg. vel. (ft/s)	* 0.66	* 4.54	* 1.18
* Max Chl Dpth (ft)	* 10.77	* Hydr. Depth (ft)	* 2.48	* 9.78	* 6.09
* Conv. Total (cfs)	* 166543.1	* Conv. (cfs)	* 11273.4	* 131887.8	* 23381.9
* Length wtd. (ft)	* 100.93	* Wetted Per. (ft)	* 166.93	* 74.95	* 79.93
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.09	* 0.34	* 0.22
* Alpha	* 2.60	* Stream Power (lb/ft s)	* 725.20	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.08	* Cum Volume (acre-ft)	* 13.40	* 12.57	* 2.59
* C & E Loss (ft)	* 0.03	* Cum SA (acres)	* 3.79	* 1.45	* 0.70

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 2002.134

INPUT

Description:

Station Elevation Data		num= 120							
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	5.75	848.69	9.25	848	12.54	847.07	14.98	846.36
16.39	846	21.54	844.57	23.9	844	28.14	843.37	29.49	843.11
31.27	842.82	35.31	842	36.84	841.71	44.09	840.36	45.66	840.07
46.05	840	58.46	838.43	59.73	838.27	60.32	838.19	61.51	838
68.14	838	84.71	837.13	87.17	837.04	90.91	836.93	93.76	836.87
96.92	836.74	102.52	836.63	109.38	836.49	117.27	836.33	120.05	836.28

saddle2.rep

121.42	836.22	123.9	836.21	135.46	836	152.3	836	152.93	835.97
153.56	835.95	175.95	834.99	193.37	834.28	196.51	834.15	200.1	834
205.39	833.72	210.34	833.1	210.74	833.15	211.69	833.31	213.96	833.36
216.02	833.45	235.66	834	252.32	834	256.05	833.9	257.04	833.88
276.33	833.31	279.34	833.28	281.75	833.27	295.27	832.92	301.58	832.91
307.93	832.77	318.74	832.74	323.19	832.66	337.48	832.62	342.49	832.54
382.49	832.24	402.49	832	443.94	832	448.99	831.31	452.91	830.94
462.54	830	463.53	829.84	463.96	829.78	467.24	829.24	468.14	829.14
470.59	828.79	471.7	828.67	472.1	828.64	472.57	828.59	474.78	828.35
475.89	828.26	476.06	828.26	477.8	828	488.57	828	491.73	827.76
492.21	827.75	494.02	827.72	494.54	827.71	527.7	826.75	553.46	826
561.05	826	561.73	825.49	563.27	824	563.54	823.79	564.49	822.87
577.19	822.74	603.13	822.47	605.42	823.91	605.57	824	609.95	825.19
612.91	826	613.85	826.72	615.51	828	616.81	828.98	618.12	830
619.93	831.36	620.77	832	623.33	833.91	623.44	834	623.55	834.08
625.99	836	626.03	836.04	628.31	838	629.29	838.81	630.68	840
632.39	841.41	633.09	842	635.36	843.87	635.52	844	636.52	844.78
637.1	845.24	638.07	846	640.63	847.87	640.8	848	643.54	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	561.05	.035	612.91	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	561.05	612.91		5.33	72.27	84.5	.1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 833.38	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.58	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 832.80	* Reach Len. (ft)	* 5.33	* 72.27	* 84.50
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 644.97	* 500.64	* 30.24
* E.G. slope (ft/ft)	* 0.001269	* Area (sq ft)	* 644.97	* 500.64	* 30.24
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 634.08	* 3350.23	* 30.98
* Top Width (ft)	* 315.31	* Top Width (ft)	* 254.52	* 51.86	* 8.93
* Vel Total (ft/s)	* 3.41	* Avg. Vel. (ft/s)	* 0.98	* 6.69	* 1.02
* Max Chl Dpth (ft)	* 10.33	* Hydr. Depth (ft)	* 2.53	* 9.65	* 3.38
* Conv. Total (cfs)	* 112718.3	* Conv. (cfs)	* 17800.2	* 94048.5	* 869.7
* Length Wtd. (ft)	* 64.92	* wetted Per. (ft)	* 254.81	* 53.79	* 11.23
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.20	* 0.74	* 0.21
* Alpha	* 3.22	* Stream Power (lb/ft s)	* 643.54	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.11	* Cum Volume (acre-ft)	* 13.34	* 11.03	* 1.81
* C & E Loss (ft)	* 0.06	* Cum SA (acres)	* 3.77	* 1.29	* 0.57

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

Saddle2.rep

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 1929.868

INPUT

Description:

Station Elevation Data		num= 127		Sta Elev		Sta Elev		Sta Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	9.69	848.14	10.44	848	16.57	846.52	19	846
22.06	845.27	23.4	844.99	28.18	844	28.7	843.91	29.27	843.8
34.05	842.91	38.56	842	39.24	841.89	39.57	841.83	44.23	841.11
46.52	840.64	48.15	840.39	49.88	840	53.06	839.56	57.34	839.03
62.7	838	63.49	838	95.81	836.27	101.33	836.06	101.57	836.05
103.51	836	104.46	836	106.48	835.94	113.45	835.8	113.98	835.79
120.44	835.67	140.38	835.62	141.17	835.63	142.8	835.61	144.74	835.58
147.99	835.47	148.7	835.47	152.05	835.32	153.09	835.29	166.02	834.72
167.81	834.65	171.79	834.47	182.48	834	186.18	832.37	186.98	832
189.63	832	190.59	832.17	191.57	832.36	193.59	832.72	211.11	833.08
214.56	833.17	215.19	833.21	215.57	833.24	217.58	833.36	229.11	834
235.48	834	243.03	833.47	247.63	833.34	262.04	832.65	276.26	832.35
277.28	832.32	293.07	832	355.46	832	360.25	831.81	388.23	831.91
390.46	831.9	394.56	832	411.75	832	413.92	831.91	418.69	831.72
420.02	831.67	421.45	831.61	434.07	831.52	435.68	831.52	435.95	831.61
436.19	831.7	437.05	832	451.01	832	457.66	831.46	460.43	831.24
464.27	830.93	466.72	830.73	472.68	830	477.88	828.1	478.17	828
487.76	826.55	489.16	826.33	495.7	826	497.25	826	519.34	826
520.31	825.28	522.18	824	522.87	823.57	523.4	823.17	523.76	822.87
527.6	822.84	528.89	822.83	532.08	822.8	552.31	822.57	560.43	822.47
561.98	823.63	562.39	824	563.46	824.74	565.18	826	566.72	827.13
568.04	828	569.7	829.21	570.9	830	572.63	831.25	573.74	832
575.53	833.28	576.58	834	577.39	834.76	578.84	836	579.87	837.17
580.64	838	581.81	839.35	582.42	840	583.77	841.56	584.18	842
585.76	843.84	585.91	844	586.04	844.16	586.72	844.95	587.6	846
589.67	848	591.96	850						

Manning's n Values		num= 3		Sta n Val	
Sta	n Val	Sta	n Val	Sta	n Val
0	.1	519.34	.035	565.18	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 519.34 565.18 5.86 118.14 110.15 .1 .3

Ineffective Flow num= 1  
 Sta L Sta R Elev Permanent  
 0 235.48 834 F

CROSS SECTION OUTPUT Profile #PF 1

\* E.G. Elev (ft) \* 833.21 \* Element \* Left OB \* Channel \* Right OB \*

Saddle2.rep

```

* Vel Head (ft)          * 1.16 * Wt. n-Val.          * 0.100 * 0.035 * 0.100 *
* W.S. Elev (ft)        * 832.05 * Reach Len. (ft)    * 5.86 * 118.14 * 110.15 *
* Crit W.S. (ft)        * 829.15 * Flow Area (sq ft)  * 294.11 * 414.19 * 25.96 *
* E.G. slope (ft/ft)    * 0.002530 * Area (sq ft)       * 294.26 * 414.19 * 25.96 *
* Q Total (cfs)         * 4015.30 * Flow (cfs)         * 259.41 * 3720.50 * 35.39 *
* Top width (ft)        * 286.29 * Top width (ft)     * 231.82 * 45.84 * 8.63 *
* Vel Total (ft/s)      * 5.47 * Avg. vel. (ft/s)   * 0.88 * 8.98 * 1.36 *
* Max Chl Dpth (ft)    * 9.58 * Hydr. Depth (ft)   * 1.29 * 9.04 * 3.01 *
* Conv. Total (cfs)     * 79822.8 * Conv. (cfs)        * 5156.9 * 73962.3 * 703.6 *
* Length wtd. (ft)     * 106.42 * Wetted Per. (ft)   * 229.45 * 48.01 * 10.54 *
* Min Ch El (ft)       * 822.47 * Shear (lb/sq ft)   * 0.20 * 1.36 * 0.39 *
* Alpha                 * 2.50 * Stream Power (lb/ft s) * 591.96 * 0.00 * 0.00 *
* Frctn Loss (ft)      * 0.25 * Cum Volume (acre-ft) * 13.28 * 10.27 * 1.76 *
* C & E Loss (ft)      * 0.01 * Cum SA (acres)     * 3.74 * 1.21 * 0.55 *
*****

```

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water

surface that had the least amount of error between computed and assumed values.

Warning: Divided flow computed for this cross-section.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 1811.557

INPUT

Description:

Station Elevation Data		num= 127		Sta		Elev		Sta		Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	8.09	848.68	9.6	848.44	12.25	848	15.63	847.32		
17.53	847.03	22.85	846.14	23.34	846.05	23.62	846	29.14	845.01		
29.7	844.93	31.77	844.59	35.22	844	38.73	843.44	40.77	843.25		
44.36	842.76	49.7	842.06	50.03	842	54.63	840.79	58.16	840		
60.2	839.66	63.13	839.24	66.64	838.88	68.31	838.67	72.99	838.13		
73.95	838	87.5	836.44	90.85	836	91.66	836	100.94	835.61		
101.33	835.59	110.34	835.25	110.4	835.24	121.22	834.87	124.68	834.79		
125.19	834.78	128.31	834.73	131.18	834.66	139.14	834.59	139.43	834.59		
145.89	834.47	154.04	834.29	161.88	834	163.25	834	165.31	833.16		
168	832	173.5	832	173.52	832	175.04	832.3	193.36	832.94		
194.25	832.97	194.4	832.96	194.97	833.03	195.62	833.08	208.04	834		
229.9	834	238.7	833.13	240.06	833.08	246.53	832	265.48	832		
303.93	831.45	312.8	831.4	332.62	831	353.67	831.77	354.78	831.72		
359.46	831.02	369.02	830.99	369.43	831	369.91	830.99	370.02	830.99		
370.53	830.98	370.91	830.97	389.65	830.53	394.54	830.38	401.08	830.18		
406.7	830	407.31	829.79	412.33	828	413.45	827.6	414.68	827.16		
417.14	826.3	417.99	826	443.82	826	444.09	825.85	445.72	825.04		
447.77	824	447.95	823.91	449.82	822.87	459.79	822.8	489.1	822.47		

Saddle2.rep

489.21	822.59	489.36	822.75	490.51	824	490.88	824.38	492.37	826
493.93	827.55	494.37	828	497.57	830.56	499.37	832	499.82	832.35
501.88	834	503.33	835.14	504.41	836	505.89	837.68	506.17	838
506.24	838.08	507.77	840	508.33	840.71	509.35	842	510.56	843.55
510.91	844	511.55	844.84	512.54	846	513.19	846.66	514.51	848
516.01	849.18	517.12	850	518.94	851.43	519.47	851.82	519.7	852
521.72	853.59	522.26	854	524.41	855.7	524.8	856	527.06	857.79
527.34	858	530.07	860						

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 443.82 .035 492.37 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 443.82 492.37 17.98 85.13 75.99 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 832.78	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 1.04	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.74	* Reach Len. (ft)	* 17.98	* 85.13	* 75.99
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 268.92	* 424.04	* 18.26
* E.G. Slope (ft/ft)	*0.002415	* Area (sq ft)	* 268.92	* 424.04	* 18.26
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 356.05	* 3637.59	* 21.66
* Top width (ft)	* 214.39	* Top width (ft)	* 159.16	* 48.55	* 6.68
* Vel Total (ft/s)	* 5.65	* Avg. vel. (ft/s)	* 1.32	* 8.58	* 1.19
* Max Chl Dpth (ft)	* 9.27	* Hydr. Depth (ft)	* 1.69	* 8.73	* 2.73
* Conv. Total (cfs)	* 81703.8	* Conv. (cfs)	* 7245.0	* 74018.2	* 440.6
* Length Wtd. (ft)	* 78.20	* Wetted Per. (ft)	* 159.93	* 50.86	* 8.82
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.25	* 1.26	* 0.31
* Alpha	* 2.10	* Stream Power (lb/ft s)	* 530.07	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	* 13.24	* 9.14	* 1.70
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 3.71	* 1.08	* 0.53

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water

surface that had the least amount of error between computed and assumed values.

Warning: Divided flow computed for this cross-section.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1726.403

INPUT

Description:

Station Elevation Data num= 111  
 Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
 \*\*\*\*\*



Saddle2.rep

0	850	7.69	848.75	12.67	848	13.53	847.86	13.88	847.81
14.58	847.69	23.99	846	24.2	845.96	24.7	845.87	35.04	844
35.58	844	35.72	843.97	36.71	843.76	44.45	842	50.81	840.91
56.16	840	62.16	839.16	70.39	838	76.77	836.99	82.9	836
107.43	834.59	111.92	834.32	113.55	834.23	114.44	834.18	115.04	834.14
118.29	834	133.54	833	145.97	832	153.68	832	153.78	832.03
154.17	832.11	170.85	832.35	172.32	832.36	172.33	832.36	172.33	832.35
172.36	832.35	172.46	832.35	172.61	832.34	172.88	832.33	173.84	832.26
177.54	832	261.15	832	263.09	831.66	263.15	831.66	264.41	831.43
264.73	831.44	265.31	831.48	266.23	831.31	267.04	831.34	274.24	831.18
277.67	831.06	279.87	830.91	303.11	830.11	303.13	830.11	303.2	830.11
313.87	830.99	332.27	830.68	338.82	830.44	346.78	830.13	350.22	830
354.85	828.9	358.99	828	361.29	827.15	364.99	826	368.69	826
374.3	826	386.59	824.73	394.79	824.26	396.56	824.16	399.37	824
400.62	823.5	401.24	823.25	402.13	822.87	415.76	822.73	440.37	822.47
441.28	823.54	441.62	824	442.72	825.29	443.28	826	446.77	827.59
447.66	828	451.15	831.19	452.07	832	453.87	833.62	454.27	834
454.56	834.26	456.73	836	458.44	837.72	458.72	838	459.92	839.21
460.72	840	461.32	840.61	462.7	842	463.86	843.24	464.51	844
465.71	845.39	466.11	845.85	466.23	846	466.54	846.24	468.77	848
470.01	848.97	471.31	850	472.48	850.91	473.86	852	474.93	852.84
476.4	854	477.37	854.77	478.94	856	481.17	857.79	481.43	858
485.12	860								

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	399.37	.035	441.62	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	399.37	441.62		25.62	144.25	127.32	.1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 832.60	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 1.25	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.35	* Reach Len. (ft)	* 25.62	* 144.25	* 127.32
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 318.03	* 363.95	* 35.79
* E.G. Slope (ft/ft)	* 0.002988	* Area (sq ft)	* 318.03	* 363.95	* 35.79
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 459.43	* 3496.90	* 58.97
* Top width (ft)	* 185.33	* Top width (ft)	* 133.37	* 42.25	* 9.71
* Vel Total (ft/s)	* 5.59	* Avg. vel. (ft/s)	* 1.44	* 9.61	* 1.65
* Max Chl Dpth (ft)	* 8.88	* Hydr. Depth (ft)	* 2.38	* 8.61	* 3.68
* Conv. Total (cfs)	* 73457.0	* Conv. (cfs)	* 8404.9	* 63973.3	* 1078.8
* Length wtd. (ft)	* 130.95	* Wetted Per. (ft)	* 134.08	* 43.20	* 12.39
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.44	* 1.57	* 0.54
* Alpha	* 2.58	* Stream Power (lb/ft s)	* 485.12	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.25	* Cum Volume (acre-ft)	* 13.12	* 8.37	* 1.66
* C & E Loss (ft)	* 0.21	* Cum SA (acres)	* 3.65	* 0.99	* 0.52

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross

Saddle2.rep

sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
REACH: Toms Fork

RS: 1580.979

INPUT

Description:

Station Elevation Data		num= 105	
Sta	Elev	Sta	Elev
0	850	9.68	848
20.81	845.56	28	844
47.38	840	47.87	839.9
77.1	834.66	80.22	834.43
92.24	833.63	92.64	833.63
100.76	833.32	133.45	832
158.75	831.48	165.31	831.53
206.25	831.02	217.47	830.66
237.47	829.75	238.59	829.37
253.96	830	253.97	830
293.32	828	298.88	827.16
317.58	826	317.83	825.95
328.79	824.25	330.08	824
337.84	822.87	365.19	822.64
386.52	823.76	387.12	824
400.52	825.66	403.1	826
419.67	827.99	419.74	827.99
428.22	828.41	434.02	830
441.66	836	442.29	836.49
447.35	840.4	449.74	842
457.1	846	457.93	846.44

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
0	.1	330.08	.035

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	330.08	387.12		123.76	97.42	118.65	.1

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 832.14	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.56	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.59	* Reach Len. (ft)	* 123.76	* 97.42	* 118.65
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 371.62	* 500.61	* 227.20

* E.G. Slope (ft/ft)	*0.001341	* Area (sq ft)	* 371.62	* 500.61	* 227.20
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 383.83	* 3292.34	* 339.13
* Top Width (ft)	* 292.23	* Top width (ft)	* 186.26	* 57.04	* 48.93
* Vel Total (ft/s)	* 3.65	* Avg. Vel. (ft/s)	* 1.03	* 6.58	* 1.49
* Max Chl Dpth (ft)	* 9.12	* Hydr. Depth (ft)	* 2.00	* 8.78	* 4.64
* Conv. Total (cfs)	*109636.6	* Conv. (cfs)	* 10480.5	* 89896.3	* 9259.8
* Length Wtd. (ft)	* 102.95	* Wetted Per. (ft)	* 186.77	* 57.55	* 50.01
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.17	* 0.73	* 0.38
* Alpha	* 2.68	* Stream Power (lb/ft s)	* 464.87	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.14	* Cum Volume (acre-ft)	* 12.92	* 6.93	* 1.27
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 3.56	* 0.83	* 0.43

Warning: Divided flow computed for this cross-section.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1483.221

INPUT

Description:

Station	Elevation	Data	num=	119	Sta	Elev	Sta	Elev	Sta	Elev
0	850	5.81	848	7.38	847.46	9.29	846.8	11.59	846	
12.45	845.72	17.64	844	22	842.63	23.96	842	28.51	840.53	
30.08	840	35.58	838.12	35.95	838	37.05	837.65	42.19	836	
46.82	834.38	47.91	834	52.05	832.41	53.12	832	53.33	831.92	
58.38	830	59.39	830	69.2	829.64	77.21	829.39	84.78	829.19	
91.53	828.99	94.05	828.92	103.42	828.67	104.03	828.65	110.46	828.46	
112.7	828.4	114.09	828.37	119.86	828.27	120.77	828.25	122.62	828.22	
123.19	828.21	132.4	828.09	132.67	828.09	133.01	828.08	134.54	828.07	
135.22	828.07	135.64	828.07	139.19	828.09	139.28	828.09	139.61	828.09	
139.88	828.09	140.15	828.09	143.01	828.18	152.35	828.3	153.73	828.36	
156.58	828.49	168.1	828.8	176.97	829.32	188.61	830	189.36	830.1	
191.09	830.42	197.36	830.41	210.1	830.63	218.76	830.09	220.05	830	
220.87	830	270.1	828.71	272.93	828.65	299.31	828	302.7	827.77	
303.52	827.77	306.38	827.68	320.02	827.07	325.65	826.82	326.24	826.81	
328.46	826.79	353.75	826	356.58	826	357.24	825.45	359.31	824	
360.1	823.52	362.29	822.03	382.46	822.33	401.54	822.42	405.94	823.87	
406.29	824	408.51	824.33	415.99	825.23	420.95	825.86	422.22	826	
425.52	827.67	426.14	828	429.24	829.72	429.75	830	429.89	830.02	
440.71	831.89	441.32	832	444.32	832	480.07	833.73	485.11	834	
492.49	835.38	495.7	836	499.07	836.62	506.5	838	512.87	839.45	
515.34	840	519.08	840.85	521.04	841.23	522.71	841.52	523.54	841.67	
525.58	842	527.64	842.31	530.45	842.83	534.69	843.56	536.71	844	
536.83	844	543.95	845.16	545.09	845.34	549.15	846	554.58	846.76	
563.93	848	564.84	848	566.68	848.39	572.35	850			

Manning's n Values num= 3

Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 356.58 .035 408.51 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 356.58 408.51 54.14 61.47 37.92 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

\*\*\*\*\*  
 \* E.G. Elev (ft) \* 831.98 \* Element \* Left OB \* Channel \* Right OB \*  
 \* Vel Head (ft) \* 0.47 \* Wt. n-Val. \* 0.100 \* 0.035 \* 0.100 \*  
 \* W.S. Elev (ft) \* 831.51 \* Reach Len. (ft) \* 54.14 \* 61.47 \* 37.92 \*  
 \* Crit W.S. (ft) \* \* Flow Area (sq ft) \* 851.06 \* 461.38 \* 120.42 \*  
 \* E.G. Slope (ft/ft) \*0.001285 \* Area (sq ft) \* 851.06 \* 461.38 \* 120.42 \*  
 \* Q Total (cfs) \* 4015.30 \* Flow (cfs) \* 903.20 \* 2954.38 \* 157.72 \*  
 \* Top Width (ft) \* 384.11 \* Top width (ft) \* 302.17 \* 51.93 \* 30.00 \*  
 \* Vel Total (ft/s) \* 2.80 \* Avg. Vel. (ft/s) \* 1.06 \* 6.40 \* 1.31 \*  
 \* Max Chl Dpth (ft) \* 9.48 \* Hydr. Depth (ft) \* 2.82 \* 8.88 \* 4.01 \*  
 \* Conv. Total (cfs) \*112005.1 \* Conv. (cfs) \* 25194.4 \* 82411.1 \* 4399.7 \*  
 \* Length wtd. (ft) \* 59.23 \* Wetted Per. (ft) \* 302.65 \* 53.46 \* 31.23 \*  
 \* Min Ch El (ft) \* 822.03 \* Shear (lb/sq ft) \* 0.23 \* 0.69 \* 0.31 \*  
 \* Alpha \* 3.88 \* Stream Power (lb/ft s) \* 572.35 \* 0.00 \* 0.00 \*  
 \* Frctn Loss (ft) \* 0.06 \* Cum Volume (acre-ft) \* 11.18 \* 5.86 \* 0.80 \*  
 \* C & E Loss (ft) \* 0.05 \* Cum SA (acres) \* 2.86 \* 0.70 \* 0.33 \*  
 \*\*\*\*\*

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1421.670

INPUT

Description:

Station Elevation Data num= 114  
 Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
 \*\*\*\*\*  
 0 850 2.79 849.15 6.37 848 7.77 847.56 9.4 847.08  
 12.05 846.29 13.14 846 17.43 845.03 21.19 844.05 21.4 844  
 21.6 843.92 27.18 842 28.6 841.36 31.86 840 34.65 838.93  
 36.95 838 39.48 837.09 43.26 836.17 43.69 836.05 43.78 836.04  
 43.84 836.03 44.08 836 45.26 836 47.98 835.5 50.67 835.2  
 52.4 835.01 53.64 834.87 56.33 834.58 56.76 834.53 58.93 834.29  
 59.09 834.26 60.91 834 61.53 833.91 61.77 833.88 65.76 833.25  
 67.21 833.05 69.67 832.68 74.1 832 75.37 831.72 78.33 831.04  
 79.3 830.81 83.15 830 84.82 829.93 85.04 829.92 85.58 829.89  
 89.94 829.68 94.22 829.47 99.72 829.24 110.94 828.47 113.82 828.32  
 115.24 828.25 117.83 828 174.08 828 174.52 828.04 194.87 830  
 195.39 830.04 197.72 830.24 210.01 830.31 216.6 830.41 218.07 830.25  
 219.57 830.05 219.97 830 222.23 829.79 230.6 829.12 241.79 828.19  
 244.75 828 267.96 828 272.56 827.85 273.71 827.84 275.94 827.7  
 278.22 827.59 301.45 826 323.5 826 356.72 826 358.07 824.91

saddle2.rep

359.23	824	359.84	823.54	362.77	821.27	387.26	822.16	393.71	822.38
411.92	823.65	414.58	824	416.84	824	418.53	825.41	418.9	825.72
419.26	826	419.65	826.31	421.76	828	424.27	830	435.33	830.62
437.01	830.73	456.8	832	472.29	832.9	493.97	834	495.74	834.51
500.32	836	502.54	836.66	507.57	838	509.02	838.37	515.42	840
517.32	840.46	523.35	842	525.17	842.45	527.3	843.03	531.03	844
538.61	844.9	543.35	845.45	545.39	845.69	547.61	846	547.81	846
553.14	846.84	558.54	847.64	560.73	848	567.55	850		

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 356.72 .035 424.27 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 356.72 424.27 284.66 127.14 14.01 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.87	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.32	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.56	* Reach Len. (ft)	* 284.66	* 127.14	* 14.01
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 978.83	* 575.77	* 20.58
* E.G. Slope (ft/ft)	*0.000926	* Area (sq ft)	* 978.83	* 575.77	* 20.58
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 1016.45	* 2990.82	* 8.03
* Top width (ft)	* 373.80	* Top width (ft)	* 280.64	* 67.55	* 25.61
* Vel Total (ft/s)	* 2.55	* Avg. Vel. (ft/s)	* 1.04	* 5.19	* 0.39
* Max Chl Dpth (ft)	* 10.29	* Hydr. Depth (ft)	* 3.49	* 8.52	* 0.80
* Conv. Total (cfs)	*131983.2	* Conv. (cfs)	* 33410.6	* 98308.6	* 264.0
* Length Wtd. (ft)	* 164.00	* Wetted Per. (ft)	* 281.15	* 71.39	* 25.66
* Min Ch El (ft)	* 821.27	* Shear (lb/sq ft)	* 0.20	* 0.47	* 0.05
* Alpha	* 3.14	* Stream Power (lb/ft s)	* 567.55	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.12	* Cum Volume (acre-ft)	* 10.04	* 5.13	* 0.74
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 2.50	* 0.62	* 0.30

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1293.596

INPUT

Description:

Station Elevation Data num= 131									
Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev									
*****									
0 850 4.12 848 8.06 846.06 8.17 846 8.81 845.68									
12.19 844 12.67 843.76 16.32 842 21.32 840.26 22.02 840									
22.88 839.69 23.71 839.41 27.76 838 30.51 837.06 33.76 836									
35.14 835.59 43.54 835.21 44.85 835.17 45.09 835.16 45.37 835.14									
46.01 835.06 52.66 834.02 52.75 834 52.76 834 52.81 833.98									

Saddle2.rep

57.47	832	61.78	831.6	64.46	831.35	70.98	830.78	77.87	830.09
78.18	830.06	78.72	830	83.23	829.79	84.2	829.74	90.44	829.43
96.17	829.17	104.55	828.86	106.6	828.82	107.4	828.77	113.81	829.28
116.59	829.47	116.83	829.46	116.9	829.46	127.6	828.54	136.41	828.39
140.21	828.11	141.37	828.01	141.44	828	146.09	826.7	148.09	826.12
148.31	826.05	148.61	826	150.46	826	151.22	826.07	153.3	826.23
153.77	826.17	156.73	826.29	164.02	826	170.8	826	174.64	825.61
175.18	825.62	175.49	825.64	183.13	825.23	183.52	825.24	184.54	825.29
187.88	825.12	189.56	825.18	209.18	825.12	214.39	825	221.13	824.84
227.6	824.69	228.7	824.66	236.9	824.44	243.38	824.3	257.03	824
259.48	822.47	260.32	821.95	260.94	821.57	261.45	821.27	308.31	821.27
308.52	821.4	308.8	821.51	310.32	821.96	310.46	822	314.14	823
319.94	824	319.95	824	323.41	824.63	327.21	825.87	327.4	825.93
327.57	826	328.17	826.28	331.9	828	333.47	828.78	334.86	829.52
335.72	830	337.6	830	376.51	830	434.08	831.68	435.98	831.69
439.81	831.83	440.38	831.83	444.86	831.97	445.9	832	450.97	832.69
452.42	832.95	456.13	833.55	457.6	833.77	459.01	834	463.1	834.77
468.93	836	473.04	836.97	475.41	837.5	477.76	838	482.57	838.97
485.12	839.48	487.6	840	490.72	840.62	493.43	841.09	495.45	841.46
498.55	842	501.14	842.35	510.55	844	510.81	844.04	520.74	845.8
521.82	845.99	521.85	846	522.07	846.04	533.57	848	536.16	848.49
544.51	850								

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	257.03	.035	335.72	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	257.03	335.72		379.96	235.75	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.73	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.24	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.49	* Reach Len. (ft)	* 379.96	* 235.75	* 67.58
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 887.08	* 698.33	* 98.87
* E.G. Slope (ft/ft)	*0.000611	* Area (sq ft)	* 887.08	* 698.33	* 98.87
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 895.91	* 3081.25	* 38.14
* Top Width (ft)	* 364.64	* Top Width (ft)	* 194.08	* 78.69	* 91.87
* Vel Total (ft/s)	* 2.38	* Avg. vel. (ft/s)	* 1.01	* 4.41	* 0.39
* Max Chl Dpth (ft)	* 10.22	* Hydr. Depth (ft)	* 4.57	* 8.87	* 1.08
* Conv. Total (cfs)	*162409.9	* Conv. (cfs)	* 36237.5	*124629.8	* 1542.6
* Length wtd. (ft)	* 231.75	* Wetted Per. (ft)	* 194.61	* 81.02	* 91.89
* Min Ch El (ft)	* 821.27	* Shear (lb/sq ft)	* 0.17	* 0.33	* 0.04
* Alpha	* 2.67	* Stream Power (lb/ft s)	* 544.51	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	* 3.95	* 3.27	* 0.72
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 0.95	* 0.41	* 0.28

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1000.000

INPUT

Description:

Station Elevation Data		num= 116		Sta Elev		Sta Elev		Sta Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	.26	849.64	1.5	848	2.99	846	3.07	845.88
4.81	843.56	5.98	842	6.08	841.88	7.5	840	7.81	839.63
9.02	838	9.72	837.47	11.66	836	13.76	834.45	14.37	834
16.27	832.6	17.09	832	17.85	831.92	30.72	830.59	44.39	830.01
44.63	830	45.04	829.98	46.91	829.91	49.1	829.82	56.19	828.94
64.04	828	65.22	827.34	67.37	826	68.79	825.02	70.4	824
72.12	823.16	74.22	822	74.83	821.71	75.57	821.27	103.45	821.27
104.71	821.26	104.99	821.33	105.34	821.44	106.87	822	111.85	823.77
112.67	824	117.18	825.27	120.39	826	125.39	826.29	127.25	826.41
131	826.54	132.8	826.64	134.71	826.73	135.12	826.75	136.89	826.83
139.24	826.93	141.51	827.02	146.36	827.18	148.33	827.25	149.98	827.29
151.35	827.32	153.84	827.41	154.85	827.43	156.24	827.48	157.49	827.51
158.19	827.53	158.7	827.55	160.43	827.56	160.84	827.58	161.3	827.6
161.9	827.63	163.96	827.58	164.7	827.62	166.92	827.51	167.83	827.56
168.62	827.6	169.33	827.64	173.57	827.47	209.25	827.32	211.63	827.36
213.59	827.39	215.1	827.41	220.28	827.46	247.59	828	260.33	828
264.01	828.05	265.31	828.07	266.01	828.08	267.24	828.1	349.67	828.76
354.21	828.9	359.57	829.06	360.66	829.06	365.65	829.23	369.72	829.39
372.38	829.49	376.5	829.66	382.67	829.92	383.11	829.93	384.54	830
398.78	831.6	401.74	832	404.21	832.82	407.8	834	411.97	835.59
413.07	836	414.97	836.81	417.7	838	419.82	838.96	422.17	840
426.51	841.74	427.16	842	428.24	842.38	432.79	844	437.73	845.68
438.63	846	439.07	846.15	440.44	846.61	443.79	847.72	444.64	848
450.39	850								

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
0	.013	49.1	.035
		120.39	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 49.1 120.39 1 1 1 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.50	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.40	* Wt. n-Val.	* 0.013	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.10	* Reach Len. (ft)	*	*	*
* Crit W.S. (ft)	* 828.88	* Flow Area (sq ft)	* 17.78	* 509.01	* 827.09

Saddle2.rep

* E.G. Slope (ft/ft)	*0.001447	* Area (sq ft)	* 17.78	* 509.01	* 827.09
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 64.43	* 2974.55	* 976.32
* Top Width (ft)	* 368.54	* Top Width (ft)	* 23.31	* 71.29	* 273.94
* Vel Total (ft/s)	* 2.97	* Avg. vel. (ft/s)	* 3.62	* 5.84	* 1.18
* Max Chl Dpth (ft)	* 9.84	* Hydr. Depth (ft)	* 0.76	* 7.14	* 3.02
* Conv. Total (cfs)	*105549.1	* Conv. (cfs)	* 1693.7	* 78191.2	* 25664.2
* Length wtd. (ft)	*	* Wetted Per. (ft)	* 23.36	* 73.96	* 274.08
* Min Ch El (ft)	* 821.26	* Shear (lb/sq ft)	* 0.07	* 0.62	* 0.27
* Alpha	* 2.94	* Stream Power (lb/ft s)	* 450.39	* 0.00	* 0.00
* Frctn Loss (ft)	*	* Cum Volume (acre-ft)	*	*	*
* C & E Loss (ft)	*	* Cum SA (acres)	*	*	*

\*\*\*\*\*

SUMMARY OF MANNING'S N VALUES

River: Toms Fork

* Reach	* River Sta.	* n1	* n2	* n3
*Toms Fork	* 2865.327	* .1*	* .035*	* .1*
*Toms Fork	* 2579.832	* .1*	* .035*	* .1*
*Toms Fork	* 2372.941	* .035*	* .035*	* .1*
*Toms Fork	* 2123.812	* .1*	* .035*	* .1*
*Toms Fork	* 2002.134	* .1*	* .035*	* .1*
*Toms Fork	* 1929.868	* .1*	* .035*	* .1*
*Toms Fork	* 1811.557	* .1*	* .035*	* .1*
*Toms Fork	* 1726.403	* .1*	* .035*	* .1*
*Toms Fork	* 1580.979	* .1*	* .035*	* .1*
*Toms Fork	* 1483.221	* .1*	* .035*	* .1*
*Toms Fork	* 1421.670	* .1*	* .035*	* .1*
*Toms Fork	* 1293.596	* .1*	* .035*	* .1*
*Toms Fork	* 1000.000	* .013*	* .035*	* .1*

\*\*\*\*\*

SUMMARY OF REACH LENGTHS

River: Toms Fork

* Reach	* River Sta.	* Left	* Channel	* Right
*Toms Fork	* 2865.327	* 212.2*	* 282.13*	* 186.24*
*Toms Fork	* 2579.832	* 271.1*	* 188.24*	* 66.66*
*Toms Fork	* 2372.941	* 494.68*	* 209.34*	* 278.69*
*Toms Fork	* 2123.812	* 4.85*	* 111.36*	* 132.72*
*Toms Fork	* 2002.134	* 5.33*	* 72.27*	* 84.5*
*Toms Fork	* 1929.868	* 5.86*	* 118.14*	* 110.15*
*Toms Fork	* 1811.557	* 17.98*	* 85.13*	* 75.99*
*Toms Fork	* 1726.403	* 25.62*	* 144.25*	* 127.32*



*Toms Fork	*	1580.979	*	123.76*	97.42*	118.65*
*Toms Fork	*	1483.221	*	54.14*	61.47*	37.92*
*Toms Fork	*	1421.670	*	284.66*	127.14*	14.01*
*Toms Fork	*	1293.596	*	379.96*	235.75*	67.58*
*Toms Fork	*	1000.000	*	1*	1*	1*

\*\*\*\*\*  
 \*\*\*\*\*

SUMMARY OF CONTRACTION AND EXPANSION COEFFICIENTS  
 River: Toms Fork

* Reach	* River Sta.	* Contr.	* Expan.
*Toms Fork	* 2865.327*	.1*	.3*
*Toms Fork	* 2579.832*	.1*	.3*
*Toms Fork	* 2372.941*	.1*	.3*
*Toms Fork	* 2123.812*	.1*	.3*
*Toms Fork	* 2002.134*	.1*	.3*
*Toms Fork	* 1929.868*	.1*	.3*
*Toms Fork	* 1811.557*	.1*	.3*
*Toms Fork	* 1726.403*	.1*	.3*
*Toms Fork	* 1580.979*	.1*	.3*
*Toms Fork	* 1483.221*	.1*	.3*
*Toms Fork	* 1421.670*	.1*	.3*
*Toms Fork	* 1293.596*	.1*	.3*
*Toms Fork	* 1000.000*	.1*	.3*

\*\*\*\*\*

ERRORS WARNINGS AND NOTES  
 Errors Warnings and Notes for Plan : Existing

River: Toms Fork Reach: Toms Fork RS: 2579.832 Profile: PF 1  
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
 This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2372.941 Profile: PF 1  
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
 This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2123.812 Profile: PF 1  
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
 This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2002.134 Profile: PF 1  
 Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.  
 Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 1929.868 Profile: PF 1

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water

surface that had the least amount of error between computed and assumed values.

Warning: Divided flow computed for this cross-section.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

River: Toms Fork Reach: Toms Fork RS: 1811.557 Profile: PF 1

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water

surface that had the least amount of error between computed and assumed values.

Warning: Divided flow computed for this cross-section.

River: Toms Fork Reach: Toms Fork RS: 1726.403 Profile: PF 1

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 1580.979 Profile: PF 1

Warning: Divided flow computed for this cross-section.

River: Toms Fork Reach: Toms Fork RS: 1293.596 Profile: PF 1

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

**Supplement 3**

**HEC-RAS Analysis –Proposed Conditions Summary w/ Cross Sections**

HEC-RAS Version 4.1.0 Jan 2010  
U.S. Army Corps of Engineers  
Hydrologic Engineering Center  
609 Second Street  
Davis, California

```
X      X  XXXXXX   XXXX       XXXX       XX       XXXX
X      X  X       X   X       X   X       X   X       X
X      X  X       X       X       X   X       X   X       X
XXXXXXXX XXXX     X       XXX  XXXX     XXXXXX     XXXX
X      X  X       X       X       X   X       X   X       X
X      X  X       X   X       X   X       X   X       X
X      X  XXXXXX   XXXX       X   X       X   X       XXXXX
```

\*\*\*\*\*

PROJECT DATA

Project Title: Saddle2  
Project File : Saddle2.prj  
Run Date and Time: 7/16/2013 7:51:50 PM

Project in English units

\*\*\*\*\*

PLAN DATA

Plan Title: Bridge

Plan File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.p02

Geometry Title: Bridge

Geometry File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.g03

Flow Title : Existing-Revised

Flow File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.f02

Plan Summary Information:

Number of:	Cross Sections =	13	Multiple Openings =	0
	Culverts =	0	Inline Structures =	0
	Bridges =	1	Lateral Structures =	0

Computational Information

water surface calculation tolerance =	0.001
Critical depth calculation tolerance =	0.001
Maximum number of iterations =	20
Maximum difference tolerance =	0.3

Flow tolerance factor = 0.001

Computation Options

Critical depth computed only where necessary
Conveyance Calculation Method: At breaks in n values only
Friction Slope Method: Average Conveyance
Computational Flow Regime: Subcritical Flow

\*\*\*\*\*

FLOW DATA

Flow Title: Existing-Revised
Flow File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage Comp\Floodplain\Entrance-Crossing
Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.f02

Flow Data (cfs)

\*\*\*\*\*
\* River Reach RS \* PF 1 \*
\* Toms Fork Toms Fork 2865.327\* 4015.3 \*
\*\*\*\*\*

Boundary Conditions

\*\*\*\*\*
\* River Reach Profile \* Upstream Downstream \*
\*\*\*\*\*
\* Toms Fork Toms Fork PF 1 \* Known WS = 833.5 Known WS = 831.1 \*
\*\*\*\*\*

\*\*\*\*\*

GEOMETRY DATA

Geometry Title: Bridge
Geometry File : X:\Navitus Jobfiles\Antero Resources\ANT096-Saddle\Engineering\Drainage
Comp\Floodplain\Entrance-Crossing Study\Report\Computations\HEC-RAS\Revised Sections\Saddle2.g03

CROSS SECTION

RIVER: Toms Fork
REACH: Toms Fork RS: 2865.327

INPUT

Description:

Station Elevation Data num= 100
Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev
0 850 2.89 848 3.73 847.42 5.78 846 8.24 844.95
10.3 844 12.9 842.79 14.63 842 20.51 841.56 22.47 841.4
26.09 841.11 32.66 841.36 44.49 841.93 44.56 841.93 44.57 841.93

Saddle2.rep

44.6	841.93	49.67	841.3	52.98	840.89	54.84	840.66	56.84	840.4
56.98	840.39	59.93	840	62.2	838.99	64.42	838	66.42	837.11
68.93	836	77.13	835.38	80.1	835.15	89.55	834.48	91.63	834.33
96.42	834	96.46	834	103.31	833.74	108.11	833.57	115.2	833.31
120.18	833.17	144.96	832.42	149.19	832.28	158.3	832	161.69	831.77
162.91	831.7	163.61	831.66	172.16	831.13	177.1	830.87	181.93	830.59
192.98	830.03	193.14	830.02	193.52	830	195.11	829.63	202.28	828
203.58	827.9	204.23	827.86	205.83	827.75	208.78	827.55	218.92	826.86
225.69	826.43	226.36	826.39	227.77	826.3	228.45	826.25	232.59	826
233.5	824.89	234.03	824.24	234.61	823.57	239.85	823.64	241.59	823.67
250.02	823.8	269.19	824.13	281.09	824.36	281.53	824.87	281.9	825.29
282.64	826	283.77	827.33	285.69	827.68	287.35	828	290.48	828
292.08	828.23	293.87	828.48	299.55	829.32	303.22	829.8	304.12	830
305.84	831.05	306.98	831.74	307.38	832	309.66	833.4	310.6	834
312.52	835.18	313.8	836	315.48	837.04	316.99	838	318.62	839.12
319.93	840	321.46	841.28	322.33	842	324.02	843.41	324.73	844
326.6	845.56	327.13	846	329.22	847.75	329.52	848	331.9	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	232.59	.035	287.35	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	232.59	287.35		212.2	282.13	186.24	.1
							.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 834.46	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.57	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.90	* Reach Len. (ft)	* 212.20	* 282.13	* 186.24
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 414.33	* 525.06	* 97.91
* E.G. Slope (ft/ft)	*0.001232	* Area (sq ft)	* 414.33	* 525.06	* 97.91
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 459.17	* 3426.96	* 129.18
* Top width (ft)	* 211.27	* Top width (ft)	* 133.42	* 54.76	* 23.09
* Vel Total (ft/s)	* 3.87	* Avg. vel. (ft/s)	* 1.11	* 6.53	* 1.32
* Max Chl Dpth (ft)	* 10.33	* Hydr. Depth (ft)	* 3.11	* 9.59	* 4.24
* Conv. Total (cfs)	*114379.4	* Conv. (cfs)	* 13079.8	* 97619.9	* 3679.7
* Length wtd. (ft)	* 268.18	* Wetted Per. (ft)	* 133.80	* 57.29	* 24.34
* Min Ch El (ft)	* 823.57	* Shear (lb/sq ft)	* 0.24	* 0.71	* 0.31
* Alpha	* 2.44	* Stream Power (lb/ft s)	* 331.90	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.27	* Cum Volume (acre-ft)	* 18.41	* 20.67	* 6.74
* C & E Loss (ft)	* 0.05	* Cum SA (acres)	* 5.30	* 2.27	* 1.53

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 2579.832

INPUT

Saddle2.rep

Description:

Station Elevation Data		num= 93		Sta		Elev		Sta		Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	2.44	848	2.66	847.82	4.89	846	5.28	845.68		
7.32	844	7.99	843.55	10.04	842	12.78	841.08	16.18	840		
20.07	838.81	22.77	838	31.3	838	32.34	838.23	36.84	839.24		
45.36	839.17	54.84	838.89	61	838.03	61.18	838	62.93	837.73		
65.72	837.27	73.51	836	74.45	835.56	77.9	834	80.43	832.85		
82.31	832	84.12	831.18	87.67	829.59	88.79	829.09	90.47	828.4		
91.43	828	93.28	827.16	95.87	826	99.12	824.4	99.91	824		
100.45	823.72	100.69	823.6	100.92	823.47	143.75	823.47	144.94	823.92		
145.14	824	151.82	825.23	155.09	825.97	155.22	826	157.83	826		
174.68	826.59	176.96	826.69	179.05	826.72	180.73	826.74	182.27	826.82		
183.75	826.84	185.06	826.91	186.58	826.95	188.92	827.07	190.49	827.12		
195.23	827.34	196.43	827.39	197.44	827.44	206.09	827.82	206.63	827.85		
210.34	828	214.91	828.57	218.82	829.06	221.21	829.36	222.27	829.51		
225.8	830	227.87	830.31	228.23	830.38	230.19	830.82	233.42	831.47		
235.56	832	238.7	832.97	242.37	834	244.36	834.61	248.21	835.78		
248.76	835.95	248.94	836	254.04	837.23	256.99	838	257.34	838		
262.74	838.68	270.79	839.6	273.44	840	283.77	841.65	285.91	842		
289.24	842.78	294.7	844	303.19	845.52	305.76	846	310.28	847.08		
313.75	847.86	314.38	848	323.1	850						

Manning's n Values		num= 3		Sta		n Val	
Sta	n Val	Sta	n Val	Sta	n Val	Sta	n Val
0	.1	95.87	.035	155.09	.1		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	95.87	155.09		271.1	188.24	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 834.15	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.41	* Wt. n-val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.74	* Reach Len. (ft)	* 271.10	* 188.24	* 66.66
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 67.73	* 586.76	* 484.44
* E.G. Slope (ft/ft)	* 0.000838	* Area (sq ft)	* 67.73	* 586.76	* 484.44
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 67.86	* 3292.89	* 654.55
* Top width (ft)	* 162.97	* Top width (ft)	* 17.40	* 59.22	* 86.35
* Vel Total (ft/s)	* 3.53	* Avg. Vel. (ft/s)	* 1.00	* 5.61	* 1.35
* Max chl dpth (ft)	* 10.27	* Hydr. Depth (ft)	* 3.89	* 9.91	* 5.61
* Conv. Total (cfs)	* 138738.2	* Conv. (cfs)	* 2344.8	* 113777.0	* 22616.3
* Length Wtd. (ft)	* 183.84	* Wetted Per. (ft)	* 19.04	* 60.11	* 86.99
* Min Ch El (ft)	* 823.47	* Shear (lb/sq ft)	* 0.19	* 0.51	* 0.29
* Alpha	* 2.10	* Stream Power (lb/ft s)	* 323.10	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	* 17.24	* 17.07	* 5.49
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 4.93	* 1.90	* 1.29

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than

1.4. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 2372.941

INPUT

Description:

Station Elevation Data num= 105

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	1.82	848	2.33	847.47	3.36	846.39	3.78	846
6.59	844.33	7.14	844	10.17	842.28	10.68	842	13.68	840.29
14.22	840	17.19	838.31	17.76	838	19.76	837.02	21.03	837.71
30.82	836.97	45.33	836.96	53.11	837.04	58.14	836.39	62.87	836
70.69	835.06	78.76	834	82.37	833.41	90.69	832	92.24	831.76
95.46	831.2	102.19	830	104.15	829.57	105.93	829.26	108.63	828.71
111.2	828.33	113.43	828	114.56	827.83	114.6	827.82	114.66	827.81
114.94	827.78	118.37	827.27	120.84	826.94	122.59	826.68	127.81	826
128.07	825.95	128.15	825.95	128.23	825.93	131.37	825.41	132.07	825.31
133.39	825.14	134.95	824.85	136.9	824.63	140.69	824	140.95	824
141.56	823.88	142.39	823.69	142.76	823.59	143.18	823.47	161.64	823.47
162.23	823.66	162.96	823.86	163.49	824	170.49	824.97	178.34	826
184.38	826.66	190.63	827.37	196.22	828	204.78	828.89	209.26	829.26
213.01	829.61	214.44	829.73	215.21	829.78	215.72	829.81	218.51	830
221.09	830.31	222.16	830.45	226.82	831.04	233.45	832	259.72	833.51
267.46	833.9	270.43	834	277.5	834	293.51	834.86	300.19	835.16
303.03	835.27	310.96	835.62	312.48	835.69	319.76	836	323.88	836.36
332.03	837.03	340.66	837.87	342.02	838	347.21	839.1	350.16	839.67
350.48	839.73	351.82	840	353.9	840.42	357.17	841.11	360.16	841.74
361.41	842	366.93	843.14	371.51	844	376.07	845.15	379.47	846
382.67	846.77	388.2	848	388.9	848.16	389.32	848.25	397.14	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.035	136.9	.035	170.49	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 136.9 170.49 494.68 209.34 278.69 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 833.91	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.65	* Wt. n-Val.	* 0.035	* 0.035	* 0.100
* W.S. Elev (ft)	* 833.26	* Reach Len. (ft)	* 494.68	* 209.34	* 278.69
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 242.14	* 317.26	* 314.52
* E.G. Slope (ft/ft)	* 0.001650	* Area (sq ft)	* 242.14	* 317.26	* 314.52
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 1130.44	* 2431.91	* 452.95



Saddle2.rep

* Top Width (ft)	* 172.12	* Top Width (ft)	* 53.65	* 33.59	* 84.88
* Vel Total (ft/s)	* 4.59	* Avg. Vel. (ft/s)	* 4.67	* 7.67	* 1.44
* Max Chl Dpth (ft)	* 9.79	* Hydr. Depth (ft)	* 4.51	* 9.44	* 3.71
* Conv. Total (cfs)	* 98862.8	* Conv. (cfs)	* 27833.1	* 59877.4	* 11152.4
* Length Wtd. (ft)	* 268.00	* Wetted Per. (ft)	* 54.35	* 33.85	* 85.32
* Min Ch El (ft)	* 823.47	* Shear (lb/sq ft)	* 0.46	* 0.97	* 0.38
* Alpha	* 1.99	* Stream Power (lb/ft s)	* 397.14	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.24	* Cum Volume (acre-ft)	* 16.28	* 15.12	* 4.88
* C & E Loss (ft)	* 0.12	* Cum SA (acres)	* 4.71	* 1.70	* 1.16

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
 This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 2123.812

INPUT

Description:

Station Elevation Data		num= 145									
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	7.61	848.12	8.1	848	11.48	846.85	14.02	846		
17.32	844.89	20.19	844	29.09	842.54	32.44	842	39.97	840.57		
41	840.36	41.44	840.27	41.87	840.18	42.76	840	44.29	839.85		
44.87	839.81	45.61	839.77	58.05	838.76	60.93	838.66	73.97	838		
80.16	838	86.28	837.78	88.03	837.76	89.01	837.75	89.33	837.75		
96.23	837.46	96.83	837.47	114.62	837.25	123.08	837.03	153.21	836.5		
165.6	836.24	167.39	836.2	176.66	836	183.88	836	185.94	835.94		
186.45	835.92	193.78	835.74	197.53	835.66	200.81	835.61	203.09	835.51		
207.46	835.41	211.32	835.23	215.79	835.06	217.31	834.99	218.58	834.93		
219.59	834.88	221.23	834.79	225.89	834.56	228.39	834.42	237.61	834		
240.15	833.94	250.89	833.92	251.23	833.98	252.74	834.04	256.18	834.13		
266.1	834.44	276.79	834.81	279.36	834.6	282	834.51	292.41	834.43		
302.29	834.14	305	834	306.65	834	318.72	833.83	322.62	833.82		
326.83	833.77	349.34	833.52	366.28	833.31	381.19	833.17	409.51	832.76		
442.18	832	458.66	832	459.09	831.91	460.58	831.67	467.09	830.52		
470.93	830	472.47	829.86	473.63	829.73	474.35	829.63	476.54	829.59		
478.33	829.44	480.51	829.24	482.35	829.05	484.53	829.08	493.14	828.72		
510.22	828	540.14	828	541.2	827.11	542.5	826	543.18	825.38		
544.61	824	544.96	823.68	545.31	822.47	562.34	822.47	590.93	822.47		
591.34	823.26	591.75	823.47	592.68	823.87	592.98	824	596.16	824.59		
597.7	824.75	600.18	825.16	601.92	825.29	603.14	825.47	603.8	825.56		
606.61	825.79	609.14	825.89	609.21	825.89	611.75	826	618.47	826		
623.51	826.14	623.89	826.15	627.54	826.26	629.08	826.31	634.67	826.43		
637.3	826.52	638.18	826.54	665.48	826.98	667.38	826.96	668.91	827.09		
670.46	827.22	674.09	827.49	676.03	827.52	680.97	828	682.63	828.93		
684.49	830	686.81	831.3	688.03	832	689.62	832.9	691.61	834		

Saddle2.rep

693.43	834.9	695.67	836	699.67	837.95	699.76	838	699.9	838.07
703.8	840	708.04	841.9	708.27	842	708.74	842.21	712.7	844
716.95	845.96	717.03	846	717.11	846.04	721.13	848	725.2	850

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 540.14 .035 611.75 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 540.14 611.75 4.85 111.36 132.72 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

\*\*\*\*\*  
 \* E.G. Elev (ft) \* 833.55 \* Element \* Left OB \* Channel \* Right OB \*  
 \* Vel Head (ft) \* 0.25 \* Wt. n-Val. \* 0.100 \* 0.035 \* 0.100 \*  
 \* W.S. Elev (ft) \* 833.30 \* Reach Len. (ft) \* 4.85 \* 111.36 \* 132.72 \*  
 \* Crit W.S. (ft) \* \* \* Flow Area (sq ft) \* 423.18 \* 704.14 \* 481.98 \*  
 \* E.G. Slope (ft/ft) \* 0.000570 \* Area (sq ft) \* 423.18 \* 704.14 \* 481.98 \*  
 \* Q Total (cfs) \* 4015.30 \* Flow (cfs) \* 272.81 \* 3176.70 \* 565.79 \*  
 \* Top width (ft) \* 322.61 \* Top width (ft) \* 172.42 \* 71.61 \* 78.59 \*  
 \* Vel Total (ft/s) \* 2.50 \* Avg. vel. (ft/s) \* 0.64 \* 4.51 \* 1.17 \*  
 \* Max Chl Dpth (ft) \* 10.83 \* Hydr. Depth (ft) \* 2.45 \* 9.83 \* 6.13 \*  
 \* Conv. Total (cfs) \* 168236.2 \* Conv. (cfs) \* 11430.4 \* 133100.0 \* 23705.8 \*  
 \* Length wtd. (ft) \* 100.74 \* Wetted Per. (ft) \* 172.66 \* 74.95 \* 80.04 \*  
 \* Min Ch El (ft) \* 822.47 \* Shear (lb/sq ft) \* 0.09 \* 0.33 \* 0.21 \*  
 \* Alpha \* 2.62 \* Stream Power (lb/ft s) \* 725.20 \* 0.00 \* 0.00 \*  
 \* Frctn Loss (ft) \* 0.08 \* Cum volume (acre-ft) \* 12.50 \* 12.66 \* 2.34 \*  
 \* C & E Loss (ft) \* 0.03 \* Cum SA (acres) \* 3.43 \* 1.45 \* 0.64 \*  
 \*\*\*\*\*

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 2002.134

INPUT

Description:

Station Elevation Data num= 120

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	5.75	848.69	9.25	848	12.54	847.07	14.98	846.36
16.39	846	21.54	844.57	23.9	844	28.14	843.37	29.49	843.11
31.27	842.82	35.31	842	36.84	841.71	44.09	840.36	45.66	840.07
46.05	840	58.46	838.43	59.73	838.27	60.32	838.19	61.51	838
68.14	838	84.71	837.13	87.17	837.04	90.91	836.93	93.76	836.87
96.92	836.74	102.52	836.63	109.38	836.49	117.27	836.33	120.05	836.28

Saddle2.rep

121.42	836.22	123.9	836.21	135.46	836	152.3	836	152.93	835.97
153.56	835.95	175.95	834.99	193.37	834.28	196.51	834.15	200.1	834
205.39	833.72	210.34	833.1	210.74	833.15	211.69	833.31	213.96	833.36
216.02	833.45	235.66	834	252.32	834	256.05	833.9	257.04	833.88
276.33	833.31	279.34	833.28	281.75	833.27	295.27	832.92	301.58	832.91
307.93	832.77	318.74	832.74	323.19	832.66	337.48	832.62	342.49	832.54
382.49	832.24	402.49	832	443.94	832	448.99	831.31	452.91	830.94
462.54	830	463.53	829.84	463.96	829.78	467.24	829.24	468.14	829.14
470.59	828.79	471.7	828.67	472.1	828.64	472.57	828.59	474.78	828.35
475.89	828.26	476.06	828.26	477.8	828	488.57	828	491.73	827.76
492.21	827.75	494.02	827.72	494.54	827.71	527.7	826.75	553.46	826
561.05	826	561.73	825.49	563.27	824	563.54	823.79	564.49	822.87
577.19	822.74	603.13	822.47	605.42	823.91	605.57	824	609.95	825.19
612.91	826	613.85	826.72	615.51	828	616.81	828.98	618.12	830
619.93	831.36	620.77	832	623.33	833.91	623.44	834	623.55	834.08
625.99	836	626.03	836.04	628.31	838	629.29	838.81	630.68	840
632.39	841.41	633.09	842	635.36	843.87	635.52	844	636.52	844.78
637.1	845.24	638.07	846	640.63	847.87	640.8	848	643.54	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	561.05	.035	612.91	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	561.05	612.91		5.33	72.27	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 833.44	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.57	* Wt. n-val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 832.87	* Reach Len. (ft)	* 5.33	* 72.27	* 84.50
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 662.62	* 504.21	* 30.86
* E.G. Slope (ft/ft)	*0.001229	* Area (sq ft)	* 662.62	* 504.21	* 30.86
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 647.47	* 3336.50	* 31.32
* Top width (ft)	* 318.53	* Top width (ft)	* 257.65	* 51.86	* 9.03
* Vel Total (ft/s)	* 3.35	* Avg. vel. (ft/s)	* 0.98	* 6.62	* 1.02
* Max Chl Dpth (ft)	* 10.40	* Hydr. Depth (ft)	* 2.57	* 9.72	* 3.42
* Conv. Total (cfs)	*114531.9	* Conv. (cfs)	* 18468.4	* 95170.0	* 893.5
* Length Wtd. (ft)	* 64.58	* Wetted Per. (ft)	* 257.93	* 53.79	* 11.34
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.20	* 0.72	* 0.21
* Alpha	* 3.25	* Stream Power (lb/ft s)	* 643.54	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.11	* Cum Volume (acre-ft)	* 12.44	* 11.12	* 1.55
* C & E Loss (ft)	* 0.05	* Cum SA (acres)	* 3.40	* 1.29	* 0.50

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

CROSS SECTION

Saddle2.rep

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 1929.868

INPUT

Description:

Station Elevation Data num= 127

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	9.69	848.14	10.44	848	16.57	846.52	19	846
22.06	845.27	23.4	844.99	28.18	844	28.7	843.91	29.27	843.8
34.05	842.91	38.56	842	39.24	841.89	39.57	841.83	44.23	841.11
46.52	840.64	48.15	840.39	49.88	840	53.06	839.56	57.34	839.03
62.7	838	63.49	838	95.81	836.27	101.33	836.06	101.57	836.05
103.51	836	104.46	836	106.48	835.94	113.45	835.8	113.98	835.79
120.44	835.67	140.38	835.62	141.17	835.63	142.8	835.61	144.74	835.58
147.99	835.47	148.7	835.47	152.05	835.32	153.09	835.29	166.02	834.72
167.81	834.65	171.79	834.47	182.48	834	186.18	832.37	186.98	832
189.63	832	190.59	832.17	191.57	832.36	193.59	832.72	211.11	833.08
214.56	833.17	215.19	833.21	215.57	833.24	217.58	833.36	229.11	834
235.48	834	243.03	833.47	247.63	833.34	262.04	832.65	276.26	832.35
277.28	832.32	293.07	832	355.46	832	360.25	831.81	388.23	831.91
390.46	831.9	394.56	832	411.75	832	413.92	831.91	418.69	831.72
420.02	831.67	421.45	831.61	434.07	831.52	435.68	831.52	435.95	831.61
436.19	831.7	437.05	832	451.01	832	457.66	831.46	460.43	831.24
464.27	830.93	466.72	830.73	472.68	830	477.88	828.1	478.17	828
487.76	826.55	489.16	826.33	495.7	826	497.25	826	519.34	826
520.31	825.28	522.18	824	522.87	823.57	523.4	823.17	523.76	822.87
527.6	822.84	528.89	822.83	532.08	822.8	552.31	822.57	560.43	822.47
561.98	823.63	562.39	824	563.46	824.74	565.18	826	566.72	827.13
568.04	828	569.7	829.21	570.9	830	572.63	831.25	573.74	832
575.53	833.28	576.58	834	577.39	834.76	578.84	836	579.87	837.17
580.64	838	581.81	839.35	582.42	840	583.77	841.56	584.18	842
585.76	843.84	585.91	844	586.04	844.16	586.72	844.95	587.6	846
589.67	848	591.96	850						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	519.34	.035	565.18	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.

519.34	565.18	5.86	118.14	110.15	.1	.3
--------	--------	------	--------	--------	----	----

Ineffective Flow num= 1

Sta L	Sta R	Elev	Permanent
0	235.48	834	F

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 833.28	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 1.11	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 832.17	* Reach Len. (ft)	* 5.86	* 118.14	* 110.15
* Crit W.S. (ft)	* 829.15	* Flow Area (sq ft)	* 321.85	* 419.67	* 27.01

* E.G. Slope (ft/ft)	*0.002384	* Area (sq ft)	* 322.41	* 419.67	* 27.01
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 287.68	* 3691.40	* 36.21
* Top Width (ft)	* 293.29	* Top Width (ft)	* 238.66	* 45.84	* 8.80
* Vel Total (ft/s)	* 5.22	* Avg. Vel. (ft/s)	* 0.89	* 8.80	* 1.34
* Max Chl Dpth (ft)	* 9.70	* Hydr. Depth (ft)	* 1.37	* 9.16	* 3.07
* Conv. Total (cfs)	* 82236.1	* Conv. (cfs)	* 5892.0	* 75602.4	* 741.7
* Length Wtd. (ft)	* 109.66	* Wetted Per. (ft)	* 235.36	* 48.01	* 10.75
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.20	* 1.30	* 0.37
* Alpha	* 2.61	* Stream Power (lb/ft s)	* 591.96	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.25	* Cum Volume (acre-ft)	* 12.38	* 10.35	* 1.50
* C & E Loss (ft)	* 0.03	* Cum SA (acres)	* 3.37	* 1.21	* 0.49

Warning: Divided flow computed for this cross-section.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork

RS: 1811.557

INPUT

Description:

Station Elevation Data		num= 127		Sta Elev		Sta Elev		Sta Elev	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	8.09	848.68	9.6	848.44	12.25	848	15.63	847.32
17.53	847.03	22.85	846.14	23.34	846.05	23.62	846	29.14	845.01
29.7	844.93	31.77	844.59	35.22	844	38.73	843.44	40.77	843.25
44.36	842.76	49.7	842.06	50.03	842	54.63	840.79	58.16	840
60.2	839.66	63.13	839.24	66.64	838.88	68.31	838.67	72.99	838.13
73.95	838	87.5	836.44	90.85	836	91.66	836	100.94	835.61
101.33	835.59	110.34	835.25	110.4	835.24	121.22	834.87	124.68	834.79
125.19	834.78	128.31	834.73	131.18	834.66	139.14	834.59	139.43	834.59
145.89	834.47	154.04	834.29	161.88	834	163.25	834	165.31	833.16
168	832	173.5	832	173.52	832	175.04	832.3	193.36	832.94
194.25	832.97	194.4	832.96	194.97	833.03	195.62	833.08	208.04	834
229.9	834	238.7	833.13	240.06	833.08	246.53	832	265.48	832
303.93	831.45	312.8	831.4	332.62	831	353.67	831.77	354.78	831.72
359.46	831.02	369.02	830.99	369.43	831	369.91	830.99	370.02	830.99
370.53	830.98	370.91	830.97	389.65	830.53	394.54	830.38	401.08	830.18
406.7	830	407.31	829.79	412.33	828	413.45	827.6	414.68	827.16
417.14	826.3	417.99	826	443.82	826	444.09	825.85	445.72	825.04
447.77	824	447.95	823.91	449.82	822.87	459.79	822.8	489.1	822.47
489.21	822.59	489.36	822.75	490.51	824	490.88	824.38	492.37	826
493.93	827.55	494.37	828	497.57	830.56	499.37	832	499.82	832.35
501.88	834	503.33	835.14	504.41	836	505.89	837.68	506.17	838
506.24	838.08	507.77	840	508.33	840.71	509.35	842	510.56	843.55
510.91	844	511.55	844.84	512.54	846	513.19	846.66	514.51	848
516.01	849.18	517.12	850	518.94	851.43	519.47	851.82	519.7	852

521.72 853.59 522.26 854 524.41 855.7 524.8 856 527.06 857.79  
 527.34 858 530.07 860

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 443.82 .035 492.37 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 443.82 492.37 17.98 85.13 75.99 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

\*\*\*\*\*  
 \* E.G. Elev (ft) \* 832.99 \* Element \* Left OB \* Channel \* Right OB \*  
 \* Vel Head (ft) \* 1.02 \* Wt. n-Val. \* 0.100 \* 0.035 \* 0.100 \*  
 \* W.S. Elev (ft) \* 831.98 \* Reach Len. (ft) \* 17.98 \* 85.13 \* 75.99 \*  
 \* Crit W.S. (ft) \* \* Flow Area (sq ft) \* 308.55 \* 435.45 \* 19.86 \*  
 \* E.G. Slope (ft/ft) \* 0.002259 \* Area (sq ft) \* 308.55 \* 435.45 \* 19.86 \*  
 \* Q Total (cfs) \* 4015.30 \* Flow (cfs) \* 314.84 \* 3677.02 \* 23.44 \*  
 \* Top Width (ft) \* 232.40 \* Top width (ft) \* 176.88 \* 48.55 \* 6.97 \*  
 \* Vel Total (ft/s) \* 5.26 \* Avg. vel. (ft/s) \* 1.02 \* 8.44 \* 1.18 \*  
 \* Max Chl Dpth (ft) \* 9.51 \* Hydr. Depth (ft) \* 1.74 \* 8.97 \* 2.85 \*  
 \* Conv. Total (cfs) \* 84485.4 \* Conv. (cfs) \* 6624.6 \* 77367.7 \* 493.1 \*  
 \* Length Wtd. (ft) \* 78.01 \* Wetted Per. (ft) \* 177.65 \* 50.86 \* 9.20 \*  
 \* Min Ch El (ft) \* 822.47 \* Shear (lb/sq ft) \* 0.24 \* 1.21 \* 0.30 \*  
 \* Alpha \* 2.37 \* Stream Power (lb/ft s) \* 530.07 \* 0.00 \* 0.00 \*  
 \* Frctn Loss (ft) \* 0.19 \* Cum Volume (acre-ft) \* 12.34 \* 9.19 \* 1.44 \*  
 \* C & E Loss (ft) \* 0.01 \* Cum SA (acres) \* 3.34 \* 1.08 \* 0.47 \*  
 \*\*\*\*\*

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1726.403

INPUT  
 Description:

Station Elevation Data num= 111  
 Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
 \*\*\*\*\*  
 0 850 7.69 848.75 12.67 848 13.53 847.86 13.88 847.81  
 14.58 847.69 23.99 846 24.2 845.96 24.7 845.87 35.04 844  
 35.58 844 35.72 843.97 36.71 843.76 44.45 842 50.81 840.91  
 56.16 840 62.16 839.16 70.39 838 76.77 836.99 82.9 836  
 107.43 834.59 111.92 834.32 113.55 834.23 114.44 834.18 115.04 834.14  
 118.29 834 133.54 833 145.97 832 153.68 832 153.78 832.03  
 154.17 832.11 170.85 832.35 172.32 832.36 172.33 832.36 172.33 832.35  
 172.36 832.35 172.46 832.35 172.61 832.34 172.88 832.33 173.84 832.26  
 177.54 832 261.15 832 263.09 831.66 263.15 831.66 264.41 831.43  
 264.73 831.44 265.31 831.48 266.23 831.31 267.04 831.34 274.24 831.18  
 277.67 831.06 279.87 830.91 303.11 830.11 303.13 830.11 303.2 830.11

Saddle2.rep

313.87	830.99	332.27	830.68	338.82	830.44	346.78	830.13	350.22	830
354.85	828.9	358.99	828	361.29	827.15	364.99	826	368.69	826
374.3	826	386.59	824.73	394.79	824.26	396.56	824.16	399.37	824
400.62	823.5	401.24	823.25	402.13	822.87	415.76	822.73	440.37	822.47
441.28	823.54	441.62	824	442.72	825.29	443.28	826	446.77	827.59
447.66	828	451.15	831.19	452.07	832	453.87	833.62	454.27	834
454.56	834.26	456.73	836	458.44	837.72	458.72	838	459.92	839.21
460.72	840	461.32	840.61	462.7	842	463.86	843.24	464.51	844
465.71	845.39	466.11	845.85	466.23	846	466.54	846.24	468.77	848
470.01	848.97	471.31	850	472.48	850.91	473.86	852	474.93	852.84
476.4	854	477.37	854.77	478.94	856	481.17	857.79	481.43	858
485.12	860								

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 399.37 .035 441.62 .1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 399.37 441.62 25.62 144.25 127.32 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

\*\*\*\*\*  
 \* E.G. Elev (ft) \* 832.80 \* Element \* Left OB \* Channel \* Right OB \*  
 \* Vel Head (ft) \* 1.09 \* Wt. n-Val. \* 0.100 \* 0.035 \* 0.100 \*  
 \* W.S. Elev (ft) \* 831.71 \* Reach Len. (ft) \* 25.62 \* 144.25 \* 127.32 \*  
 \* Crit W.S. (ft) \* \* \* Flow Area (sq ft) \* 366.81 \* 379.19 \* 39.37 \*  
 \* E.G. Slope (ft/ft) \* 0.002505 \* Area (sq ft) \* 366.81 \* 379.19 \* 39.37 \*  
 \* Q Total (cfs) \* 4015.30 \* Flow (cfs) \* 525.18 \* 3428.63 \* 61.49 \*  
 \* Top Width (ft) \* 188.95 \* Top Width (ft) \* 136.58 \* 42.25 \* 10.12 \*  
 \* Vel Total (ft/s) \* 5.11 \* Avg. Vel. (ft/s) \* 1.43 \* 9.04 \* 1.56 \*  
 \* Max Chl Dpth (ft) \* 9.24 \* Hydr. Depth (ft) \* 2.69 \* 8.97 \* 3.89 \*  
 \* Conv. Total (cfs) \* 80222.1 \* Conv. (cfs) \* 10492.5 \* 68500.9 \* 1228.6 \*  
 \* Length Wtd. (ft) \* 131.80 \* Wetted Per. (ft) \* 137.34 \* 43.20 \* 12.93 \*  
 \* Min Ch El (ft) \* 822.47 \* Shear (lb/sq ft) \* 0.42 \* 1.37 \* 0.48 \*  
 \* Alpha \* 2.68 \* Stream Power (lb/ft s) \* 485.12 \* 0.00 \* 0.00 \*  
 \* Frctn Loss (ft) \* 0.23 \* Cum Volume (acre-ft) \* 12.20 \* 8.40 \* 1.39 \*  
 \* C & E Loss (ft) \* 0.15 \* Cum SA (acres) \* 3.28 \* 0.99 \* 0.45 \*  
 \*\*\*\*\*

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1580.979

INPUT

Description:  
 Station Elevation Data num= 105

Saddle2.rep

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	9.68	848	15.17	846.8	15.87	846.64	18.77	846
20.81	845.56	28	844	35.76	842.18	36.54	842	36.96	841.92
47.38	840	47.87	839.9	56.87	838	68.15	836.06	68.41	836.01
77.1	834.66	80.22	834.43	85.29	834	85.35	834	89.24	833.81
92.24	833.63	92.64	833.63	93.17	833.63	94.58	833.62	97.89	833.46
100.76	833.32	133.45	832	138.56	832	141.4	831.74	147.18	831.31
158.75	831.48	165.31	831.53	185.18	831.5	191.55	831.44	193.11	831.6
206.25	831.02	217.47	830.66	227.63	830.24	231.61	830.09	236.83	830
237.47	829.75	238.59	829.37	245.76	829.63	249.16	829.77	253.95	830
253.96	830	253.97	830	260.61	830	272.1	829.31	290.5	828
293.32	828	298.88	827.16	303.61	826.89	315.57	826	316.11	826
317.58	826	317.83	825.95	322.94	825.12	323.18	825.12	328.6	824.28
328.79	824.25	330.08	824	334.79	823.2	336.76	822.74	337.42	822.86
337.84	822.87	365.19	822.64	382.75	822.47	382.79	822.67	383	822.67
386.52	823.76	387.12	824	389.83	824.32	390.64	824.42	395.83	825.08
400.52	825.66	403.1	826	409.08	826.75	412.02	827.12	419.58	827.98
419.67	827.99	419.74	827.99	419.75	827.99	419.78	828	427.07	828
428.22	828.41	434.02	830	434.67	830.39	436.52	832	439.1	833.98
441.66	836	442.29	836.49	444.2	838	446.24	839.6	446.78	840
447.35	840.4	449.74	842	451.59	843.1	453.32	844	456.03	845.43
457.1	846	457.93	846.44	460.96	848	463.4	849.33	464.87	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	330.08	.035	387.12	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.

330.08	387.12	123.76	97.42	118.65	.1	.3
--------	--------	--------	-------	--------	----	----

Ineffective Flow num= 2

Sta L	Sta R	Elev	Permanent
182.24	289.41	833	F
459.1	456.57	833	F

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 832.42	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.58	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.84	* Reach Len. (ft)	* 43.71	* 43.71	* 43.71
* Crit W.S. (ft)	* 828.27	* Flow Area (sq ft)	* 237.83	* 515.02	* 239.59
* E.G. Slope (ft/ft)	* 0.001298	* Area (sq ft)	* 419.16	* 515.02	* 239.59
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 257.07	* 3395.60	* 362.63
* Top width (ft)	* 296.04	* Top width (ft)	* 189.78	* 57.04	* 49.22
* Vel Total (ft/s)	* 4.05	* Avg. vel. (ft/s)	* 1.08	* 6.59	* 1.51
* Max Chl Dpth (ft)	* 9.37	* Hydr. Depth (ft)	* 2.88	* 9.03	* 4.87
* Conv. Total (cfs)	* 111448.3	* Conv. (cfs)	* 7135.1	* 94248.1	* 10065.1
* Length Wtd. (ft)	* 43.71	* Wetted Per. (ft)	* 82.90	* 57.55	* 50.40
* Min Ch El (ft)	* 822.47	* Shear (lb/sq ft)	* 0.23	* 0.73	* 0.39
* Alpha	* 2.26	* Stream Power (lb/ft s)	* 464.87	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.08	* Cum Volume (acre-ft)	* 11.96	* 6.91	* 0.98



\* C & E Loss (ft) \* 0.05 \* Cum SA (acres) \* 3.18 \* 0.83 \* 0.37 \*  
 \*\*\*\*\*

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, water surface was used.

BRIDGE

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1528.223

INPUT

Description:

Distance from Upstream XS = 43.71

Deck/Roadway width = 18

Weir Coefficient = 2.6

Upstream Deck/Roadway Coordinates

num= 7

Sta	Hi	Cord	Lo	Cord	Sta	Hi	Cord	Lo	Cord	Sta	Hi	Cord	Lo	Cord
167.15	831.47		0		316.08	838.58				328.22	838.58		835.41	
386.19	838.58	835.41			403.716	838.58				467.81	840			
485.69	842		0											

Upstream Bridge Cross Section Data

Station Elevation Data

num= 105

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	9.68	848	15.17	846.8	15.87	846.64	18.77	846
20.81	845.56	28	844	35.76	842.18	36.54	842	36.96	841.92
47.38	840	47.87	839.9	56.87	838	68.15	836.06	68.41	836.01
77.1	834.66	80.22	834.43	85.29	834	85.35	834	89.24	833.81
92.24	833.63	92.64	833.63	93.17	833.63	94.58	833.62	97.89	833.46
100.76	833.32	133.45	832	138.56	832	141.4	831.74	147.18	831.31
158.75	831.48	165.31	831.53	185.18	831.5	191.55	831.44	193.11	831.6
206.25	831.02	217.47	830.66	227.63	830.24	231.61	830.09	236.83	830
237.47	829.75	238.59	829.37	245.76	829.63	249.16	829.77	253.95	830
253.96	830	253.97	830	260.61	830	272.1	829.31	290.5	828
293.32	828	298.88	827.16	303.61	826.89	315.57	826	316.11	826
317.58	826	317.83	825.95	322.94	825.12	323.18	825.12	328.6	824.28
328.79	824.25	330.08	824	334.79	823.2	336.76	822.74	337.42	822.86
337.84	822.87	365.19	822.64	382.75	822.47	382.79	822.67	383	822.67
386.52	823.76	387.12	824	389.83	824.32	390.64	824.42	395.83	825.08
400.52	825.66	403.1	826	409.08	826.75	412.02	827.12	419.58	827.98
419.67	827.99	419.74	827.99	419.75	827.99	419.78	828	427.07	828
428.22	828.41	434.02	830	434.67	830.39	436.52	832	439.1	833.98

Saddle2.rep

441.66	836	442.29	836.49	444.2	838	446.24	839.6	446.78	840
447.35	840.4	449.74	842	451.59	843.1	453.32	844	456.03	845.43
457.1	846	457.93	846.44	460.96	848	463.4	849.33	464.87	850

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	330.08	.035	387.12	.1

Bank Sta: Left Right Coeff Contr. Expan.

330.08	387.12	.1	.3
--------	--------	----	----

Ineffective Flow num= 2

Sta L	Sta R	Elev	Permanent
182.24	289.41	833	F
459.1	456.57	833	F

Downstream Deck/Roadway Coordinates

num= 9

Sta Hi	Cord	Lo Cord	Sta Hi	Cord	Lo Cord	Sta Hi	Cord	Lo Cord
205.21	830.68	0	340.24	838.58		353.33	838.58	835.41
411.19	838.58	835.41	417.62	838.58		483.32	840	
502.13	842		535.53	845.45		563.93	848	0

Downstream Bridge Cross Section Data

Station Elevation Data num= 119

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	5.81	848	7.38	847.46	9.29	846.8	11.59	846
12.45	845.72	17.64	844	22	842.63	23.96	842	28.51	840.53
30.08	840	35.58	838.12	35.95	838	37.05	837.65	42.19	836
46.82	834.38	47.91	834	52.05	832.41	53.12	832	53.33	831.92
58.38	830	59.39	830	69.2	829.64	77.21	829.39	84.78	829.19
91.53	828.99	94.05	828.92	103.42	828.67	104.03	828.65	110.46	828.46
112.7	828.4	114.09	828.37	119.86	828.27	120.77	828.25	122.62	828.22
123.19	828.21	132.4	828.09	132.67	828.09	133.01	828.08	134.54	828.07
135.22	828.07	135.64	828.07	139.19	828.09	139.28	828.09	139.61	828.09
139.88	828.09	140.15	828.09	143.01	828.18	152.35	828.3	153.73	828.36
156.58	828.49	168.1	828.8	176.97	829.32	188.61	830	189.36	830.1
191.09	830.42	197.36	830.41	210.1	830.63	218.76	830.09	220.05	830
220.87	830	270.1	828.71	272.93	828.65	299.31	828	302.7	827.77
303.52	827.77	306.38	827.68	320.02	827.07	325.65	826.82	326.24	826.81
328.46	826.79	353.75	826	356.58	826	357.24	825.45	359.31	824
360.1	823.52	362.29	822.03	382.46	822.33	401.54	822.42	405.94	823.87
406.29	824	408.51	824.33	415.99	825.23	420.95	825.86	422.22	826
425.52	827.67	426.14	828	429.24	829.72	429.75	830	429.89	830.02
440.71	831.89	441.32	832	444.32	832	480.07	833.73	485.11	834
492.49	835.38	495.7	836	499.07	836.62	506.5	838	512.87	839.45
515.34	840	519.08	840.85	521.04	841.23	522.71	841.52	523.54	841.67
525.58	842	527.64	842.31	530.45	842.83	534.69	843.56	536.71	844
536.83	844	543.95	845.16	545.09	845.34	549.15	846	554.58	846.76
563.93	848	564.84	848	566.68	848.39	572.35	850		

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 \*\*\*\*\*  
 0 .1 356.58 .035 408.51 .1

Bank Sta: Left Right Coeff Contr. Expan.  
 356.58 408.51 .1 .3  
 Ineffective Flow num= 2  
 Sta L Sta R Elev Permanent  
 221.06 238.64 832 F  
 456.13 572.35 832 F

Upstream Embankment side slope = 0 horiz. to 1.0 vertical  
 Downstream Embankment side slope = 0 horiz. to 1.0 vertical  
 Maximum allowable submergence for weir flow = .98  
 Elevation at which weir flow begins =  
 Energy head used in spillway design =  
 Spillway height used in design =  
 Weir crest shape = Broad Crested

Number of Bridge Coefficient Sets = 1

Low Flow Methods and Data

Energy  
 Selected Low Flow Methods = Highest Energy Answer

High Flow Method

Energy Only

Additional Bridge Parameters

Add Friction component to Momentum  
 Do not add weight component to Momentum  
 Class B flow critical depth computations use critical depth  
 inside the bridge at the upstream end  
 Criteria to check for pressure flow = Upstream energy grade line

BRIDGE OUTPUT Profile #PF 1

\*\*\*\*\*  
 \* E.G. US. (ft) \* 832.42 \* Element \*Inside BR US \*Inside BR DS \*  
 \* W.S. US. (ft) \* 831.84 \* E.G. Elev (ft) \* 832.28 \* 832.17 \*  
 \* Q Total (cfs) \* 4015.30 \* W.S. Elev (ft) \* 831.16 \* 831.27 \*  
 \* Q Bridge (cfs) \* 4015.30 \* Crit w.s. (ft) \* 828.20 \* 828.43 \*  
 \* Q Weir (cfs) \* \* Max chl Dpth (ft) \* 8.69 \* 9.24 \*  
 \* Weir Sta Lft (ft) \* \* Vel Total (ft/s) \* 8.31 \* 4.90 \*  
 \* Weir Sta Rgt (ft) \* \* Flow Area (sq ft) \* 483.15 \* 820.27 \*  
 \* Weir Submerg \* \* Froude # chl \* 0.51 \* 0.44 \*  
 \* Weir Max Depth (ft) \* \* Specif Force (cu ft) \* 3072.77 \* 3390.42 \*  
 \* Min El Weir Flow (ft) \* 831.32 \* Hydr Depth (ft) \* 8.32 \* 3.76 \*  
 \* Min El Prs (ft) \* 835.41 \* W.P. Total (ft) \* 72.91 \* 232.14 \*  
 \* Delta EG (ft) \* 0.43 \* Conv. Total (cfs) \* 75493.0 \* 87718.2 \*  
 \* Delta WS (ft) \* 0.34 \* Top Width (ft) \* 58.04 \* 218.16 \*

Saddle2.rep

```
* BR Open Area (sq ft) * 724.25 * Frctn Loss (ft) * 0.04 * 0.06 *
* BR Open Vel (ft/s) * 8.31 * C & E Loss (ft) * 0.07 * 0.13 *
* Coef of Q * * Shear Total (lb/sq ft) * 1.17 * 0.46 *
* Br Sel Method *Energy only * Power Total (lb/ft s) * 0.00 * 0.00 *
*****
```

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, water surface was used.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1483.221

INPUT

Description:

Station Elevation Data num= 119

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	5.81	848	7.38	847.46	9.29	846.8	11.59	846
12.45	845.72	17.64	844	22	842.63	23.96	842	28.51	840.53
30.08	840	35.58	838.12	35.95	838	37.05	837.65	42.19	836
46.82	834.38	47.91	834	52.05	832.41	53.12	832	53.33	831.92
58.38	830	59.39	830	69.2	829.64	77.21	829.39	84.78	829.19
91.53	828.99	94.05	828.92	103.42	828.67	104.03	828.65	110.46	828.46
112.7	828.4	114.09	828.37	119.86	828.27	120.77	828.25	122.62	828.22
123.19	828.21	132.4	828.09	132.67	828.09	133.01	828.08	134.54	828.07
135.22	828.07	135.64	828.07	139.19	828.09	139.28	828.09	139.61	828.09
139.88	828.09	140.15	828.09	143.01	828.18	152.35	828.3	153.73	828.36
156.58	828.49	168.1	828.8	176.97	829.32	188.61	830	189.36	830.1
191.09	830.42	197.36	830.41	210.1	830.63	218.76	830.09	220.05	830
220.87	830	270.1	828.71	272.93	828.65	299.31	828	302.7	827.77
303.52	827.77	306.38	827.68	320.02	827.07	325.65	826.82	326.24	826.81
328.46	826.79	353.75	826	356.58	826	357.24	825.45	359.31	824
360.1	823.52	362.29	822.03	382.46	822.33	401.54	822.42	405.94	823.87
406.29	824	408.51	824.33	415.99	825.23	420.95	825.86	422.22	826
425.52	827.67	426.14	828	429.24	829.72	429.75	830	429.89	830.02
440.71	831.89	441.32	832	444.32	832	480.07	833.73	485.11	834
492.49	835.38	495.7	836	499.07	836.62	506.5	838	512.87	839.45
515.34	840	519.08	840.85	521.04	841.23	522.71	841.52	523.54	841.67
525.58	842	527.64	842.31	530.45	842.83	534.69	843.56	536.71	844
536.83	844	543.95	845.16	545.09	845.34	549.15	846	554.58	846.76
563.93	848	564.84	848	566.68	848.39	572.35	850		

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	356.58	.035	408.51	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 356.58 408.51 54.14 61.47 37.92 .1 .3

Ineffective Flow num= 2  
 Sta L Sta R Elev Permanent  
 221.06 238.64 832 F  
 456.13 572.35 832 F

CROSS SECTION OUTPUT Profile #PF 1

```
*****
* E.G. Elev (ft) * 831.99 * Element * Left OB * Channel * Right OB *
* Vel Head (ft) * 0.48 * Wt. n-Val. * 0.100 * 0.035 * 0.100 *
* W.S. Elev (ft) * 831.51 * Reach Len. (ft) * 54.14 * 61.47 * 37.92 *
* Crit W.S. (ft) * 828.49 * Flow Area (sq ft) * 818.86 * 461.10 * 120.26 *
* E.G. Slope (ft/ft) * 0.001301 * Area (sq ft) * 849.46 * 461.10 * 120.26 *
* Q Total (cfs) * 4015.30 * Flow (cfs) * 886.99 * 2969.85 * 158.46 *
* Top width (ft) * 384.06 * Top width (ft) * 302.16 * 51.93 * 29.97 *
* Vel Total (ft/s) * 2.87 * Avg. vel. (ft/s) * 1.08 * 6.44 * 1.32 *
* Max Chl Dpth (ft) * 9.47 * Hydr. Depth (ft) * 2.88 * 8.88 * 4.01 *
* Conv. Total (cfs) * 111310.6 * Conv. (cfs) * 24588.7 * 82329.0 * 4392.9 *
* Length wtd. (ft) * 59.24 * Wetted Per. (ft) * 285.05 * 53.46 * 31.20 *
* Min Ch El (ft) * 822.03 * Shear (lb/sq ft) * 0.23 * 0.70 * 0.31 *
* Alpha * 3.77 * Stream Power (lb/ft s) * 572.35 * 0.00 * 0.00 *
* Frctn Loss (ft) * 0.06 * Cum Volume (acre-ft) * 11.18 * 5.86 * 0.80 *
* C & E Loss (ft) * 0.05 * Cum SA (acres) * 2.86 * 0.70 * 0.33 *
*****
```

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, water surface was used.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1421.670

INPUT

Description:

Station Elevation Data num= 114

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	2.79	849.15	6.37	848	7.77	847.56	9.4	847.08
12.05	846.29	13.14	846	17.43	845.03	21.19	844.05	21.4	844
21.6	843.92	27.18	842	28.6	841.36	31.86	840	34.65	838.93
36.95	838	39.48	837.09	43.26	836.17	43.69	836.05	43.78	836.04
43.84	836.03	44.08	836	45.26	836	47.98	835.5	50.67	835.2
52.4	835.01	53.64	834.87	56.33	834.58	56.76	834.53	58.93	834.29
59.09	834.26	60.91	834	61.53	833.91	61.77	833.88	65.76	833.25
67.21	833.05	69.67	832.68	74.1	832	75.37	831.72	78.33	831.04
79.3	830.81	83.15	830	84.82	829.93	85.04	829.92	85.58	829.89
89.94	829.68	94.22	829.47	99.72	829.24	110.94	828.47	113.82	828.32
115.24	828.25	117.83	828	174.08	828	174.52	828.04	194.87	830
195.39	830.04	197.72	830.24	210.01	830.31	216.6	830.41	218.07	830.25
219.57	830.05	219.97	830	222.23	829.79	230.6	829.12	241.79	828.19
244.75	828	267.96	828	272.56	827.85	273.71	827.84	275.94	827.7

Saddle2.rep

278.22	827.59	301.45	826	323.5	826	356.72	826	358.07	824.91
359.23	824	359.84	823.54	362.77	821.27	387.26	822.16	393.71	822.38
411.92	823.65	414.58	824	416.84	824	418.53	825.41	418.9	825.72
419.26	826	419.65	826.31	421.76	828	424.27	830	435.33	830.62
437.01	830.73	456.8	832	472.29	832.9	493.97	834	495.74	834.51
500.32	836	502.54	836.66	507.57	838	509.02	838.37	515.42	840
517.32	840.46	523.35	842	525.17	842.45	527.3	843.03	531.03	844
538.61	844.9	543.35	845.45	545.39	845.69	547.61	846	547.81	846
553.14	846.84	558.54	847.64	560.73	848	567.55	850		

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	356.72	.035	424.27	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	356.72	424.27		284.66	127.14	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.87	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.32	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.56	* Reach Len. (ft)	* 284.66	* 127.14	* 14.01
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 978.83	* 575.77	* 20.58
* E.G. Slope (ft/ft)	* 0.000926	* Area (sq ft)	* 978.83	* 575.77	* 20.58
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 1016.45	* 2990.82	* 8.03
* Top Width (ft)	* 373.80	* Top Width (ft)	* 280.64	* 67.55	* 25.61
* Vel Total (ft/s)	* 2.55	* Avg. Vel. (ft/s)	* 1.04	* 5.19	* 0.39
* Max Chl Dpth (ft)	* 10.29	* Hydr. Depth (ft)	* 3.49	* 8.52	* 0.80
* Conv. Total (cfs)	* 131983.2	* Conv. (cfs)	* 33410.6	* 98308.6	* 264.0
* Length wtd. (ft)	* 164.00	* Wetted Per. (ft)	* 281.15	* 71.39	* 25.66
* Min Ch El (ft)	* 821.27	* Shear (lb/sq ft)	* 0.20	* 0.47	* 0.05
* Alpha	* 3.14	* Stream Power (lb/ft s)	* 567.55	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.12	* Cum Volume (acre-ft)	* 10.04	* 5.13	* 0.74
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 2.50	* 0.62	* 0.30

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1293.596

INPUT

Description:

Station Elevation Data num= 131

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	4.12	848	8.06	846.06	8.17	846	8.81	845.68
12.19	844	12.67	843.76	16.32	842	21.32	840.26	22.02	840
22.88	839.69	23.71	839.41	27.76	838	30.51	837.06	33.76	836
35.14	835.59	43.54	835.21	44.85	835.17	45.09	835.16	45.37	835.14

Saddle2.rep

46.01	835.06	52.66	834.02	52.75	834	52.76	834	52.81	833.98
57.47	832	61.78	831.6	64.46	831.35	70.98	830.78	77.87	830.09
78.18	830.06	78.72	830	83.23	829.79	84.2	829.74	90.44	829.43
96.17	829.17	104.55	828.86	106.6	828.82	107.4	828.77	113.81	829.28
116.59	829.47	116.83	829.46	116.9	829.46	127.6	828.54	136.41	828.39
140.21	828.11	141.37	828.01	141.44	828	146.09	826.7	148.09	826.12
148.31	826.05	148.61	826	150.46	826	151.22	826.07	153.3	826.23
153.77	826.17	156.73	826.29	164.02	826	170.8	826	174.64	825.61
175.18	825.62	175.49	825.64	183.13	825.23	183.52	825.24	184.54	825.29
187.88	825.12	189.56	825.18	209.18	825.12	214.39	825	221.13	824.84
227.6	824.69	228.7	824.66	236.9	824.44	243.38	824.3	257.03	824
259.48	822.47	260.32	821.95	260.94	821.57	261.45	821.27	308.31	821.27
308.52	821.4	308.8	821.51	310.32	821.96	310.46	822	314.14	823
319.94	824	319.95	824	323.41	824.63	327.21	825.87	327.4	825.93
327.57	826	328.17	826.28	331.9	828	333.47	828.78	334.86	829.52
335.72	830	337.6	830	376.51	830	434.08	831.68	435.98	831.69
439.81	831.83	440.38	831.83	444.86	831.97	445.9	832	450.97	832.69
452.42	832.95	456.13	833.55	457.6	833.77	459.01	834	463.1	834.77
468.93	836	473.04	836.97	475.41	837.5	477.76	838	482.57	838.97
485.12	839.48	487.6	840	490.72	840.62	493.43	841.09	495.45	841.46
498.55	842	501.14	842.35	510.55	844	510.81	844.04	520.74	845.8
521.82	845.99	521.85	846	522.07	846.04	533.57	848	536.16	848.49
544.51	850								

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.1	257.03	.035	335.72	.1

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	257.03	335.72		379.96	235.75	.1	.3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.73	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 0.24	* Wt. n-Val.	* 0.100	* 0.035	* 0.100
* W.S. Elev (ft)	* 831.49	* Reach Len. (ft)	* 379.96	* 235.75	* 67.58
* Crit W.S. (ft)	*	* Flow Area (sq ft)	* 887.08	* 698.33	* 98.87
* E.G. Slope (ft/ft)	* 0.000611	* Area (sq ft)	* 887.08	* 698.33	* 98.87
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 895.91	* 3081.25	* 38.14
* Top Width (ft)	* 364.64	* Top width (ft)	* 194.08	* 78.69	* 91.87
* Vel Total (ft/s)	* 2.38	* Avg. vel. (ft/s)	* 1.01	* 4.41	* 0.39
* Max Chl Dpth (ft)	* 10.22	* Hydr. Depth (ft)	* 4.57	* 8.87	* 1.08
* Conv. Total (cfs)	* 162409.9	* Conv. (cfs)	* 36237.5	* 124629.8	* 1542.6
* Length Wtd. (ft)	* 231.75	* Wetted Per. (ft)	* 194.61	* 81.02	* 91.89
* Min ch El (ft)	* 821.27	* Shear (lb/sq ft)	* 0.17	* 0.33	* 0.04
* Alpha	* 2.67	* Stream Power (lb/ft s)	* 544.51	* 0.00	* 0.00
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	* 3.95	* 3.27	* 0.72
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	* 0.95	* 0.41	* 0.28

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than

1.4. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Toms Fork  
 REACH: Toms Fork RS: 1000.000

INPUT

Description:

Station Elevation Data num= 116

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	850	.26	849.64	1.5	848	2.99	846	3.07	845.88
4.81	843.56	5.98	842	6.08	841.88	7.5	840	7.81	839.63
9.02	838	9.72	837.47	11.66	836	13.76	834.45	14.37	834
16.27	832.6	17.09	832	17.85	831.92	30.72	830.59	44.39	830.01
44.63	830	45.04	829.98	46.91	829.91	49.1	829.82	56.19	828.94
64.04	828	65.22	827.34	67.37	826	68.79	825.02	70.4	824
72.12	823.16	74.22	822	74.83	821.71	75.57	821.27	103.45	821.27
104.71	821.26	104.99	821.33	105.34	821.44	106.87	822	111.85	823.77
112.67	824	117.18	825.27	120.39	826	125.39	826.29	127.25	826.41
131	826.54	132.8	826.64	134.71	826.73	135.12	826.75	136.89	826.83
139.24	826.93	141.51	827.02	146.36	827.18	148.33	827.25	149.98	827.29
151.35	827.32	153.84	827.41	154.85	827.43	156.24	827.48	157.49	827.51
158.19	827.53	158.7	827.55	160.43	827.56	160.84	827.58	161.3	827.6
161.9	827.63	163.96	827.58	164.7	827.62	166.92	827.51	167.83	827.56
168.62	827.6	169.33	827.64	173.57	827.47	209.25	827.32	211.63	827.36
213.59	827.39	215.1	827.41	220.28	827.46	247.59	828	260.33	828
264.01	828.05	265.31	828.07	266.01	828.08	267.24	828.1	349.67	828.76
354.21	828.9	359.57	829.06	360.66	829.06	365.65	829.23	369.72	829.39
372.38	829.49	376.5	829.66	382.67	829.92	383.11	829.93	384.54	830
398.78	831.6	401.74	832	404.21	832.82	407.8	834	411.97	835.59
413.07	836	414.97	836.81	417.7	838	419.82	838.96	422.17	840
426.51	841.74	427.16	842	428.24	842.38	432.79	844	437.73	845.68
438.63	846	439.07	846.15	440.44	846.61	443.79	847.72	444.64	848
450.39	850								

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.013	49.1	.035	120.39	.1

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 49.1 120.39 1 1 1 .1 .3

CROSS SECTION OUTPUT Profile #PF 1

* E.G. Elev (ft)	* 831.50	* Element	* Left OB	* Channel	* Right OB
* vel Head (ft)	* 0.40	* Wt. n-Val.	* 0.013	* 0.035	* 0.100
* w.S. Elev (ft)	* 831.10	* Reach Len. (ft)	*	*	*



* Crit w.s. (ft)	* 828.88	* Flow Area (sq ft)	* 17.78	* 509.01	* 827.09
* E.G. Slope (ft/ft)	* 0.001447	* Area (sq ft)	* 17.78	* 509.01	* 827.09
* Q Total (cfs)	* 4015.30	* Flow (cfs)	* 64.43	* 2974.55	* 976.32
* Top width (ft)	* 368.54	* Top width (ft)	* 23.31	* 71.29	* 273.94
* Vel Total (ft/s)	* 2.97	* Avg. vel. (ft/s)	* 3.62	* 5.84	* 1.18
* Max Chl Dpth (ft)	* 9.84	* Hydr. Depth (ft)	* 0.76	* 7.14	* 3.02
* Conv. Total (cfs)	* 105549.1	* Conv. (cfs)	* 1693.7	* 78191.2	* 25664.2
* Length wtd. (ft)	*	* Wetted Per. (ft)	* 23.36	* 73.96	* 274.08
* Min Ch El (ft)	* 821.26	* Shear (lb/sq ft)	* 0.07	* 0.62	* 0.27
* Alpha	* 2.94	* Stream Power (lb/ft s)	* 450.39	* 0.00	* 0.00
* Frctn Loss (ft)	*	* Cum Volume (acre-ft)	*	*	*
* C & E Loss (ft)	*	* Cum SA (acres)	*	*	*

\*\*\*\*\*

SUMMARY OF MANNING'S N VALUES

River: Toms Fork

* Reach	* River Sta.	* n1	* n2	* n3
*Toms Fork	* 2865.327	* .1*	* .035*	* .1*
*Toms Fork	* 2579.832	* .1*	* .035*	* .1*
*Toms Fork	* 2372.941	* .035*	* .035*	* .1*
*Toms Fork	* 2123.812	* .1*	* .035*	* .1*
*Toms Fork	* 2002.134	* .1*	* .035*	* .1*
*Toms Fork	* 1929.868	* .1*	* .035*	* .1*
*Toms Fork	* 1811.557	* .1*	* .035*	* .1*
*Toms Fork	* 1726.403	* .1*	* .035*	* .1*
*Toms Fork	* 1580.979	* .1*	* .035*	* .1*
*Toms Fork	* 1528.223	* Bridge	*	*
*Toms Fork	* 1483.221	* .1*	* .035*	* .1*
*Toms Fork	* 1421.670	* .1*	* .035*	* .1*
*Toms Fork	* 1293.596	* .1*	* .035*	* .1*
*Toms Fork	* 1000.000	* .013*	* .035*	* .1*

\*\*\*\*\*

SUMMARY OF REACH LENGTHS

River: Toms Fork

* Reach	* River Sta.	* Left	* Channel	* Right
*Toms Fork	* 2865.327	* 212.2*	* 282.13*	* 186.24*
*Toms Fork	* 2579.832	* 271.1*	* 188.24*	* 66.66*
*Toms Fork	* 2372.941	* 494.68*	* 209.34*	* 278.69*
*Toms Fork	* 2123.812	* 4.85*	* 111.36*	* 132.72*
*Toms Fork	* 2002.134	* 5.33*	* 72.27*	* 84.5*
*Toms Fork	* 1929.868	* 5.86*	* 118.14*	* 110.15*

*Toms Fork	*	1811.557	*	17.98*	85.13*	75.99*
*Toms Fork	*	1726.403	*	25.62*	144.25*	127.32*
*Toms Fork	*	1580.979	*	123.76*	97.42*	118.65*
*Toms Fork	*	1528.223	*	Bridge	*	*
*Toms Fork	*	1483.221	*	54.14*	61.47*	37.92*
*Toms Fork	*	1421.670	*	284.66*	127.14*	14.01*
*Toms Fork	*	1293.596	*	379.96*	235.75*	67.58*
*Toms Fork	*	1000.000	*	1*	1*	1*

\*\*\*\*\*

\*\*\*\*\*

SUMMARY OF CONTRACTION AND EXPANSION COEFFICIENTS

River: Toms Fork

\*\*\*\*\*

* Reach	* River Sta.	* Contr.	* Expan.
*Toms Fork	* 2865.327*	.1*	.3*
*Toms Fork	* 2579.832*	.1*	.3*
*Toms Fork	* 2372.941*	.1*	.3*
*Toms Fork	* 2123.812*	.1*	.3*
*Toms Fork	* 2002.134*	.1*	.3*
*Toms Fork	* 1929.868*	.1*	.3*
*Toms Fork	* 1811.557*	.1*	.3*
*Toms Fork	* 1726.403*	.1*	.3*
*Toms Fork	* 1580.979*	.1*	.3*
*Toms Fork	* 1528.223*Bridge	*	*
*Toms Fork	* 1483.221*	.1*	.3*
*Toms Fork	* 1421.670*	.1*	.3*
*Toms Fork	* 1293.596*	.1*	.3*
*Toms Fork	* 1000.000*	.1*	.3*

\*\*\*\*\*

\*\*\*\*\*

ERRORS WARNINGS AND NOTES

Errors Warnings and Notes for Plan : Bridge

River: Toms Fork Reach: Toms Fork RS: 2579.832 Profile: PF 1

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2372.941 Profile: PF 1

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2123.812 Profile: PF 1

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 2002.134 Profile: PF 1

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 1929.868 Profile: PF 1

Warning: Divided flow computed for this cross-section.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

River: Toms Fork Reach: Toms Fork RS: 1726.403 Profile: PF 1

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

River: Toms Fork Reach: Toms Fork RS: 1580.979 Profile: PF 1

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, water surface was used.

River: Toms Fork Reach: Toms Fork RS: 1528.223 Profile: PF 1 Upstream

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, water surface was used.

River: Toms Fork Reach: Toms Fork RS: 1483.221 Profile: PF 1


Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, water surface was used.

River: Toms Fork Reach: Toms Fork RS: 1293.596 Profile: PF 1

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.


This may indicate the need for additional cross sections.

Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 2865.327



Legend	
—	WS PF 1 - Bridge
- - -	WS PF 1 - Existing
—	Ground
●	Bank Sta

Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 2579.832




Legend	
WS PF 1 - Bridge	◆
WS PF 1 - Existing	■
Ground	■
Bank Sta	●


Saddle2 Plan: 1) Bridge 2) Existing

Geom: Bridge Flow: Existing-Revised

River = Toms Fork Reach = Toms Fork RS = 2372.941




Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 2123.812






Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 2002.134






Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1929.868




Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1811.557




Legend	
WS PF 1 - Bridge	—▲—
WS PF 1 - Existing	—■—
Ground	—■—
Bank Sta	●


Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1726.403



Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1580.979




Saddle2 Plan: 1) Bridge 2) Existing  
 Geom: Bridge Flow: Existing-Revised  
 River = Toms Fork Reach = Toms Fork RS = 1528.223 BR







Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1528.223 BR



Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1483.221



Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1421.670




**Legend**


- WS PF 1 - Bridge
- WS PF 1 - Existing
- Ground
- Bank Sta



Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1293.596



Saddle2 Plan: 1) Bridge 2) Existing  
Geom: Bridge Flow: Existing-Revised  
River = Toms Fork Reach = Toms Fork RS = 1000.000





Sent Cert Letters  
7/19/12

**CASTO-HARRIS**

Serving democracy through innovation

Denver COX  
2753 Smithton Rd  
Smithburg WV

~~1047110~~

26436

Robert C. Taylor

7289 WUB 18 S

New Milton, WV 26411

Louis R. Enlow

191 Saddletree Dr.

Kala Point

Port Townsend, WA 98368

**1-800-678-8683**

Fax (304) 927-2236

[www.casto-harris.com](http://www.casto-harris.com)

[chi@casto-harris.com](mailto:chi@casto-harris.com)

## New Milton Compressor Station

- Submitting HEC-RAS for both Arch Culvert and Bridge. Would like to get your approval on either option. We are currently waiting on manufacturer schedule/estimate to determine which crossing to pursue.
-

Permit # 13-038

STATE OF WEST VIRGINIA,  
COUNTY OF DODDRIDGE, TO WIT

I, Virginia Nicholson, Editor of THE  
HERALD RECORD, a weekly newspaper  
published regularly, in Doddridge County,  
West Virginia, Do Hereby Certify Upon  
Oath That the Accompanying Legal Notice  
Entitled:

*Floodplain Permit Application*

.....  
.....  
was published in said paper for *2*.....

successive weeks beginning with the issue  
of *July 23*..... 2013 and  
ending with the issue of

*July 30*..... 2013 and  
that said notice contains *168*.....

WORD SPACE at *115*..... cents a word  
amounts to the sum of \$ *19.32*.....

FOR FIRST PUBLICATION, SECOND  
PUBLICATION IS 75% OF THE FIRST  
PUBLICATION

\$ *14.49*.....  
and each publication thereafter

\$ *33.81*..... TOTAL

EDITOR

*W. O. Nicholson*


SWORN TO AND SUBSCRIBED

BEFORE ME THIS THE *1*..... DAY  
OF *August*..... 2013

NOTARY PUBLIC


*Laura J. Adams*

LEGAL ADVERTISEMENT  
Doddridge County  
Floodplain/Permit Application  
Please take notice that on the 19<sup>th</sup> day of July, 2013,  
ANTERORESOURCES APPALACHIAN CORP. re-filed  
an application for a Floodplain Permit to develop land  
located at or about Kathryn H. Marshall, Clinton D. &  
Kevin Means, Mary Ann Phillips, Ruth E. Phillips,  
William C. Phillips, and Laverne A.H. Williams, Surface  
Owners, 147.86 acres, New Milton District, Tax Map 8,  
Parcel 57. The Application is on file with the Clerk of the  
County Court and may be inspected or copied during  
regular business hours. Any interested persons who desire  
to comment shall present the same in writing by August 8,  
2013.  
Delivered to the  
Clerk of the County Court  
118 E. Court Street, West Union, WV 26456  
Beth A. Rogers, Doddridge County Clerk  
Dan Avelines, Doddridge County Flood Plain Manager  
723-2118





# FIRM EXHIBIT



## LANDOWNER TABULATION

<b>A</b>	TM 8-39 COMSTOCK IRREVOCABLE TRUST & SILVESTRE IRREVOCABLE TRUST DB 261 PG 037 & DB 261 PG 034 68 ACRES 191 SADDLETREE DR. KALA POINT, PORT TOWNSEND, WA 98368	<b>F</b>	TM 8-17 DALE W. II & MELISSA KEPLINGER DB 236 PG 546 59.96 ACRES RR 1 BOX 191A ELLENBORO, WV 26346
<b>B</b>	TM 8-37 KATHRYN H. MARSHALL (MS 017 PG 722) CLINTON D. & KEVIN M. MEANS (DB 287 PG 272) MARVIN L. PHILLIPS (WB 033 PG 405) RUTH E. PHILLIPS (WB 038 PG 170) WILLIAM C. PHILLIPS (WB 033 PG 405) LAVERNE H. WILLIAMS (MS 017 PG 722) 147.86 ACRES RT 2 BOX 478 WEST UNION, WV 26456	<b>G</b>	TM 8-18 DALE W. II & MELISSA KEPLINGER DB 236 PG 546 14 ACRES RR 1 BOX 191A ELLENBORO, WV 26346
<b>C</b>	TM 8-37.2 LOUIS R. ENLOW DB 248 PG 066 0.58 ACRE 191 SADDLETREE DR. KALA POINT, PORT TOWNSEND, WA 98368	<b>H</b>	TM 8-19 CHARLES L. PEARCY II & ELIZABETH ANN SMITH WB 021 PG 187, 23 ACRES 516 KINNEY ST BRIDGEPORT, WV 26330
<b>D</b>	TM 8-15 ROBERT E. & EUNICE N. TAYLOR DB 260 PG 055 27.7 ACRES RT 1 BOX 90 NEW MILTON, WV 26411	<b>I</b>	TM 8-40 ROGER A. II & STACY L. McCLAIN DB 288 PG 303 118.66 ACRES RT 2 BOX 330 NEW MILTON, WV 26411
<b>E</b>	TM 8-16 ROBERT C. TAYLOR DB 245 PG 366 18 ACRES 7289 WV RT 18 S NEW MILTON, WV 26411	<b>J</b>	TM 8-41 NORMAN G. DEVOL AP 038 PG 340 86.549 ACRES 820 RACE STREET PARKERSBURG, WV 26101
		<b>K</b>	TM 8-41.5 JAMES CHARLES DB 272 PG 246 5.225 ACRES PO BOX 81 NEW MILTON, WV 26411

### FLOODPLAIN NOTE

THE PROPOSED SITE IS LOCATED WITHIN FEMA FLOOD ZONE "X" PER FEMA FLOOD MAPS #54017C0230C & #54017C0235C. THE PROPOSED SITE ENTRANCE IS LOCATED IN FEMA FLOOD ZONE "AE" PER FEMA FLOOD MAP #54017C0230C.

**NFIP**  
PANEL 0230C

**FIRM**  
FLOOD INSURANCE RATE MAP  
DODDRIDGE COUNTY,  
WEST VIRGINIA  
AND INCORPORATED AREAS

PANEL 230 OF 325  
(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
DODDRIDGE COUNTY	54024	0230	C

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

**MAP NUMBER**  
54017C0230C  
**MAP REVISED**  
OCTOBER 4, 2011

Federal Emergency Management Agency

**NFIP**  
PANEL 0235C

**FIRM**  
FLOOD INSURANCE RATE MAP  
DODDRIDGE COUNTY,  
WEST VIRGINIA  
AND INCORPORATED AREAS

PANEL 235 OF 325  
(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
DODDRIDGE COUNTY	54024	0235	C

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

**MAP NUMBER**  
54017C0235C  
**MAP REVISED**  
OCTOBER 4, 2011

Federal Emergency Management Agency

Engineering  
Survey  
Environmental  
GIS

**NAVITUS**  
ENGINEERING INC.

151 Windy Hill Lane  
Winchester, Virginia 22602  
Telephone: (888) 662-4185  
www.navituseng.com

REVISION

DATE

**ANTERO**  
RESOURCES  
THIS DOCUMENT  
WAS PREPARED  
FOR:  
ANTERO RESOURCES  
CORPORATION

FIRM EXHIBIT  
**NEW MILTON**  
 COMPRESSOR STATION ACCESS ROAD  
 NEW MILTON DISTRICT  
 DODDRIDGE COUNTY, WEST VIRGINIA



DATE: 07/16/2013

SCALE: 1" = 200'

SHEET 20 OF 20



**LOCATION COORDINATES**

ACCESS ROAD ENTRANCE  
 LATITUDE: 39.225844 LONGITUDE: -80.898042 (NAD 83)  
 N 4341882.65 E 528083.78 (UTM NAD83, ZONE 17 METERS)

**GENERAL DESCRIPTION**

THE ACCESS ROAD(S) ARE BEING CONSTRUCTED TO AID IN THE DEVELOPMENT OF A NATURAL GAS COMPRESSOR STATION. THE COMPRESSOR STATION PAD SITE IS BY OTHERS.

**FLOODPLAIN NOTE**

THE PROPOSED SITE IS LOCATED WITHIN FEMA FLOOD ZONE "X" PER FEMA FLOOD MAPS #54017C0230C & #54017C0235C. THE PROPOSED SITE ENTRANCE IS LOCATED IN FEMA FLOOD ZONE "AE" PER FEMA FLOOD MAP #54017C0230C.

**MISS UTILITY STATEMENT**

ANTERO RESOURCES CORPORATION WILL NOTIFY MISS UTILITY OF WEST VIRGINIA FOR THE LOCATING OF UTILITIES PRIOR TO THIS PROJECT DESIGN; TICKET #1319350188. IN ADDITION, MISS UTILITY WILL BE CONTACTED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION FOR THIS PROJECT.

**ENTRANCE PERMIT**

ANTERO RESOURCES CORPORATION WILL OBTAIN AN ENCROACHMENT PERMIT (FORM MM-109) FROM THE WEST VIRGINIA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.

**GEOTECHNICAL NOTE**

NO SOIL STUDIES OR SUBSURFACE INVESTIGATIONS WERE PERFORMED AND ANALYZED FOR THE DESIGN OF THIS SITE. A SUBSURFACE INVESTIGATION SHALL BE PERFORMED PRIOR TO CONSTRUCTION ACTIVITIES.

**ENVIRONMENTAL NOTES**

WETLAND DELINEATIONS WERE PERFORMED JULY, 2013 BY KLEINFELDER TO REVIEW THE SITE FOR WATERS AND WETLANDS THAT ARE MOST LIKELY WITHIN THE REGULATORY PURVIEW OF THE U.S. ARMY CORPS OF ENGINEERS (USACE) AND/OR THE WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (WVDEP). THE JULY 15, 2013 JURISDICTIONAL FEATURES MAP WAS PREPARED BY KLEINFELDER AND SUMMARIZES THE RESULTS OF THE FIELD DELINEATION. THE MAP DOES NOT, IN ANY WAY, REPRESENT A JURISDICTIONAL DETERMINATION OF THE LANDWARD LIMITS OF WATERS AND WETLANDS WHICH MAY BE REGULATED BY THE USACE OR THE WVDEP. IT IS STRONGLY RECOMMENDED THAT THE AFOREMENTIONED AGENCIES BE CONSULTED IN AN EFFORT TO GAIN WRITTEN CONFIRMATION OF THE DELINEATION SHOWN ON THIS EXHIBIT PRIOR TO ENGAGING CONSTRUCTION ON THE PROPERTY DESCRIBED HEREIN. THE DEVELOPER SHALL OBTAIN THE APPROPRIATE PERMITS FROM THE FEDERAL AND/OR STATE REGULATORY AGENCIES PRIOR TO ANY PROPOSED IMPACTS TO WATERS OF THE U.S., INCLUDING WETLAND FILLS AND STREAM CROSSINGS.

NEW MILTON COMPRESSOR STATION PERENNIAL STREAM IMPACT (LINEAR FEET)				
Stream and Impact Cause	Culvert (LF)	Inlets/Outlets Structures (LF)	Const. Disturb to LOD (LF)	Total Impact (LF)
Stream 1 (Access Rd "A")	40	0	58.5	98.5
<b>Total</b>				<b>98.5</b>

**PROJECT CONTACTS**

**OPERATOR:**  
 ANTERO RESOURCES APPALACHIAN CORPORATION  
 981 EAST WASHINGTON AVENUE  
 ELLENBORO, WV 26346  
 PHONE: (304) 869-3405  
 FAX: (304) 869-3408

ELI WAGONER - ENVIRONMENTAL ENGINEER  
 OFFICE: (304) 622-3842, EXT. 311 CELL: (304) 476-9770

ANTHONY SMITH - FIELD ENGINEER  
 OFFICE: (304) 869-3405 CELL: (304) 673-6196

BILL PREHM - PROJECT MANAGER  
 CELL: (303) 807-4436

MICK HEASTER - LAND AGENT  
 CELL: (304) 871-0085

**ENGINEER/SURVEYOR:**  
 NAVITUS ENGINEERING, INC.  
 CYRUS S. KUMP, PE - PROJECT MANAGER/ENGINEER  
 OFFICE: (888) 682-4185 CELL: (540) 888-8747

**ENVIRONMENTAL:**  
 KLEINFELDER  
 RUSSELL PERKINS - PROJECT MANAGER  
 OFFICE: (410) 850-0404 CELL: (443) 857-4545



**RESTRICTIONS NOTES:**

1. THERE IS A PERENNIAL STREAM IMPACT THAT WILL NEED TO BE PERMITTED BY THE APPROPRIATE AGENCIES.


# NEW MILTON COMPRESSOR STATION ACCESS ROAD SITE DESIGN & CONSTRUCTION PLAN, EROSION & SEDIMENT CONTROL PLANS

NEW MILTON DISTRICT, DODDRIDGE COUNTY, WEST VIRGINIA  
 TOMS FORK & MEATHOUSE FORK WATERSHEDS

USGS 7.5 NEW MILTON QUAD MAP





WEST VIRGINIA COUNTY MAP



(NOT TO SCALE)

WVDOH COUNTY ROAD MAP



MISS Utility of West Virginia  
 1-800-245-4848  
 West Virginia State Law  
 (Section XIV: Chapter 24-C)  
 Requires that you call two  
 business days before you dig in  
 the state of West Virginia.  
**IT'S THE LAW!!**

WEST VIRGINIA STATE PLANE COORDINATE SYSTEM  
 NORTH ZONE, NAD83  
 ELEVATION BASED ON NAVD88  
 ESTABLISHED BY SURVEY GRADE GPS & OPUS  
 POST-PROCESSING

**SHEET INDEX**

- 01 - COVER SHEET
- 02 - CONSTRUCTION AND E&S CONTROL NOTES
- 03 - MATERIAL QUANTITIES
- 04 - EXISTING CONDITIONS
- 05 - OVERALL PLAN SHEET INDEX & VOLUMES
- 06-08 - ACCESS ROAD PLAN
- 09-10 - ACCESS ROAD PROFILES
- 11-13 - ACCESS ROAD SECTIONS
- 14 - STREAM CROSSING "A" DETAILS
- 15 - STREAM CROSSING "A" ALTERNATE DETAILS
- 16-19 - CONSTRUCTION DETAILS
- 20 - FIRM EXHIBIT

NEW MILTON COMPRESSOR STATION ACCESS ROAD LIMITS OF DISTURBANCE AREA (AC)	
<b>Total Site</b>	
Access Road "A" (4419')	13.41
Excess/Topsoil Material Stockpiles	3.62
<b>Total Affected Area</b>	<b>17.03</b>
Total Wooded Acres Disturbed	
	12.18
Impacts to Kathryn H. Marshall, Clinton D. & Kevin M. Means, Marvin L. Phillips, Ruth E. Phillips, William C. Phillips, Laverne H. Williams TM 8-37	
Access Road "A" (1081')	3.46
<b>Total Affected Area</b>	<b>3.46</b>
Total Wooded Acres Disturbed	
	2.45
Impacts to Comstock Irrevocable Trust & Silvestre Irrevocable Trust TM 8-39	
Access Road "A" (1023')	3.76
Excess/Topsoil Material Stockpiles	1.30
<b>Total Affected Area</b>	<b>5.06</b>
Total Wooded Acres Disturbed	
	4.28
Impacts to Roger A. II & Stacey L. McClain TM 8-40	
Access Road "A" (2315')	6.19
Excess/Topsoil Material Stockpiles	2.32
<b>Total Affected Area</b>	<b>8.51</b>
Total Wooded Acres Disturbed	
	5.45

Engineering Survey Environmental GIS

**NAVITUS ENGINEERING INC.**

151 Windy Hill Lane  
 Winchester, Virginia 22602  
 Telephone: (888) 682-4185  
 www.navituseng.com

DATE	REVISION

ANTERO RESOURCES CORPORATION  
 THIS DOCUMENT WAS PREPARED FOR:  
 ANTERO RESOURCES CORPORATION

COVER SHEET

**NEW MILTON  
 COMPRESSOR STATION ACCESS ROAD**

NEW MILTON DISTRICT  
 DODDRIDGE COUNTY, WEST VIRGINIA

DATE: 07/16/2013  
 SCALE: AS SHOWN  
 SHEET 1 OF 20



# CONSTRUCTION AND E&S CONTROL NOTES

## CONSTRUCTION NOTES:

1. THE CONTRACTOR IS TO VERIFY FIELD CONDITIONS PRIOR TO AND DURING CONSTRUCTION AND WILL NOTIFY NAVITUS ENGINEERING AT (888) 662-4165 IMMEDIATELY OF ANY DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THE APPROVED PLAN. ANY WORK PERFORMED BY THE CONTRACTOR AFTER THE FINDING OF SUCH DISCREPANCIES SHALL BE DONE AT THE CONTRACTOR'S RISK.
2. METHODS AND MATERIALS USED IN THE CONSTRUCTION OF THE IMPROVEMENTS HEREIN SHALL CONFORM TO THE CURRENT COUNTY CONSTRUCTION STANDARDS AND SPECIFICATIONS AND/OR CURRENT WV DEP EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE MANUAL STANDARDS AND SPECIFICATIONS. SHOULD A CONFLICT BETWEEN THE DESIGN, SPECIFICATIONS, AND PLANS OCCUR, THE MOST STRINGENT REQUIREMENT WILL APPLY. THE APPROVAL OF THESE PLANS IN NO WAY RELIEVES THE DEVELOPER OR HIS AGENT OF THE RESPONSIBILITIES CONTAINED IN THE WV DEP EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE MANUAL.
3. AN APPROVED SET OF PLANS AND ALL APPLICABLE PERMITS MUST BE AVAILABLE AT THE CONSTRUCTION SITE. ALSO, A REPRESENTATIVE OF THE DEVELOPER MUST BE AVAILABLE AT ALL TIMES.
4. THE CONTRACTOR SHALL PROVIDE ADEQUATE MEANS OF CLEANING MUD FROM TRUCKS AND/OR OTHER EQUIPMENT PRIOR TO ENTERING PUBLIC STREETS, AND IT IS THE CONTRACTOR'S RESPONSIBILITY TO CLEAN STREETS, ALLAY DUST, AND TO TAKE WHATEVER MEASURES ARE NECESSARY TO INSURE THAT THE STREETS ARE MAINTAINED IN A CLEAN, MUD AND DUST FREE CONDITION AT ALL TIMES.
5. THE LOCATION OF EXISTING UTILITIES SHOWN IN THESE PLANS ARE FROM FIELD LOCATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE EXACT HORIZONTAL AND VERTICAL LOCATION OF ALL EXISTING UTILITIES AS NEEDED PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL INFORM THE ENGINEER OF ANY CONFLICTS ARISING FROM HIS EXISTING UTILITY VERIFICATION AND THE PROPOSED CONSTRUCTION.
6. THE CONTRACTOR SHALL PROVIDE NOTIFICATION TO THE APPROPRIATE UTILITY COMPANY PRIOR TO CONSTRUCTION OF WATER AND/OR GAS PIPE LINES. INFORMATION SHOULD ALSO BE OBTAINED FROM THE APPROPRIATE AUTHORITY CONCERNING PERMITS, CUT SHEETS, AND CONNECTIONS TO EXISTING LINES.
7. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE REPAIR OF ANY DAMAGES TO THE EXISTING STREETS AND UTILITIES WHICH OCCURS AS A RESULT OF HIS CONSTRUCTION PROJECT WITHIN OR CONTIGUOUS TO THE EXISTING RIGHT-OF-WAY.
8. WHEN GRADING IS PROPOSED WITHIN EASEMENTS OF UTILITIES, LETTERS OF PERMISSION FROM ALL INVOLVED COMPANIES MUST BE OBTAINED PRIOR TO GRADING AND/OR SITE DEVELOPMENT.
9. THE DEVELOPER WILL BE RESPONSIBLE FOR THE RELOCATION OF ANY UTILITIES WHICH IS REQUIRED AS A RESULT OF HIS PROJECT. THE RELOCATION SHOULD BE DONE PRIOR TO CONSTRUCTION.
10. THESE PLANS IDENTIFY THE LOCATION OF ALL KNOWN GRAVESITES. GRAVESITES SHOWN ON THIS PLAN WILL BE PROTECTED IN ACCORDANCE WITH STATE LAW. IN THE EVENT GRAVESITES ARE DISCOVERED DURING CONSTRUCTION, THE OWNER AND ENGINEER MUST BE NOTIFIED IMMEDIATELY.
11. THE CONTRACTOR(S) SHALL NOTIFY OPERATORS WHO MAINTAIN UNDERGROUND UTILITY LINES IN THE AREA OF PROPOSED EXCAVATING OR BLASTING AT LEAST TWO (2) WORKING DAYS, BUT NOT MORE THAN TEN (10) WORKING DAYS, PRIOR TO COMMENCEMENT OF EXCAVATION OR DEMOLITION.
12. CONTRACTOR TO CONTACT OPERATOR AND ENGINEER IF GROUNDWATER IS ENCOUNTERED DURING CONSTRUCTION.
13. THE CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE EROSION AND SEDIMENT CONTROL INSPECTOR 2 DAYS PRIOR TO THE START OF CONSTRUCTION.
14. THE CONTRACTOR IS RESPONSIBLE FOR ALL FILL MATERIAL TESTING REQUIRED DURING THE CONSTRUCTION OF THIS PROJECT. ALL MATERIAL TESTS SHALL BE CONDUCTED BY A CERTIFIED MATERIALS TESTING LABORATORY AND A CERTIFICATION OF THE MATERIALS TESTED SHALL BE PROVIDED BY A LICENSED PROFESSIONAL ENGINEER REPRESENTING THE LABORATORY. ALL TEST RESULTS SHALL BE SUBMITTED TO THE ENGINEER CERTIFYING THE CONSTRUCTED FACILITY. FAILURE TO CONDUCT THE DENSITY TEST SHALL BE CAUSE FOR NON-ACCEPTANCE OF THE CONSTRUCTED FACILITY.
15. SATISFACTORY MATERIALS FOR USE AS FILL FOR PAD AREAS INCLUDE MATERIALS CLASSIFIED IN ASTM D-2487 AS GW, GP, GM, GC, SW, SP, SM, SC, ML, AND CL GROUPS. MOISTURE CONTENT WILL BE CONTROLLED IN ACCORDANCE WITH THE STANDARD PROCTOR TEST (ASTM-D698) RESULTS. GENERALLY, UNSATISFACTORY MATERIALS INCLUDE MATERIALS CLASSIFIED IN ASTM D-2487 AS PT, CH, MH, OL, OH, AND ANY SOIL TOO WET TO FACILITATE COMPACTION. CH AND MH SOILS MAY BE USED SUBJECT TO APPROVAL OF THE ENGINEER. SOILS SHALL HAVE A MINIMUM DRY DENSITY OF 92LB/CF PER ASTM D-698 AND SHALL HAVE A PLASTICITY INDEX LESS THAN 17.
16. CONTRACTOR SHALL SUBMIT A GENERIC GROUNDWATER PROTECTION PLAN (GPP) TO THE WV DEP GROUNDWATER PROGRAM. THE GROUNDWATER PROTECTION PLAN SHALL BE ADHERED TO DURING CONSTRUCTION.
17. THE CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTING THE SITE IN ACCORDANCE WITH THE DESIGN PLANS AND CONSTRUCTION DOCUMENTS AND THE SCOPE OF WORK SHALL CONFORM WITH THE GRADES, BERMS, DEPTHS, DIMENSIONS, ETC. SHOWN HEREON.

## SITE CLEANUP & RECYCLE PROGRAM

1. GARBAGE, FUELS OR ANY SUBSTANCE HARMFUL TO HUMAN, AQUATIC OR FISH LIFE, WILL BE PREVENTED FROM ENTERING SPRINGS, STREAMS, PONDS, LAKES, WETLANDS OR ANY WATER COURSE OR WATER BODY.
2. OILS, FUELS, LUBRICANTS AND COOLANTS WILL BE PLACED IN SUITABLE CONTAINERS AND DISPOSED PROPERLY.
3. ALL TRASH AND GARBAGE WILL BE COLLECTED AND DISPOSED PROPERLY.
4. ALL SEDIMENT REMOVED FROM SEDIMENT CAPTURING DEVICES SHALL BE PLACED ON THE TOPSOIL STOCKPILE, THEN SEEDING AND MULCHED, AS NECESSARY. ALTERNATIVELY, THE REMOVED SEDIMENT CAN BE TRANSPORTED TO A SITE WITH AN APPROVED PERMIT.
5. ALL POLLUTION AND EMERGENCY SPILLS SHALL BE IMMEDIATELY REPORTED TO THE WV DEP OFFICE OF OIL AND GAS. (EMERGENCY #1-800-642-3074)

## EROSION AND SEDIMENT CONTROL NARRATIVE

**PROJECT DESCRIPTION:** THE PURPOSE OF THIS PROJECT IS TO CONSTRUCT AN ACCESS ROAD(S) TO AID IN THE DEVELOPMENT OF A NATURAL GAS COMPRESSOR STATION. THE ACCESS ROAD ENTRANCE TO THE PROPOSED SITE IS LOCATED ON THE EAST SIDE OF WV RT. 18, 1.2 MILES SOUTH OF THE INTERSECTION OF WV RT. 18 & CO RT. 25 IN NEW MILTON DISTRICT, DODDRIDGE COUNTY, WEST VIRGINIA. THE TOTAL APPROXIMATE LAND DISTURBANCE ASSOCIATED WITH THIS PROJECT IS 17.03 ACRES.

**EXISTING SITE CONDITIONS:** THE EXISTING SITE IS APPROXIMATELY 71.5% WOODED. THE TOPOGRAPHY RANGES FROM MODERATE TO STEEP TERRAIN (2X TO 60X SLOPES). PRESENT ON SITE ARE EXISTING GAS PIPELINES AND EXISTING GAS WELLS. ALSO PRESENT ARE ACCESS ROADS, STRUCTURES, OVERHEAD UTILITIES, TWO PEM WETLANDS, ONE PERENNIAL STREAM, ONE INTERMITTENT STREAM, FIVE EPHEMERAL STREAMS, AND ONE POND. THE SITE IS LOCATED ON A RIDGE AND DRAINS TO TOMS FORK & MEATHOUSE FORK. NO EROSION WAS NOTICED ON SITE.

**ADJACENT PROPERTY:** THE SITE IS BORDERED BY FORESTED LANDS ON ALL SIDES.

**CRITICAL AREAS:** THE AREA(S) SHOWN ALONG THE FIELD DELINEATED STREAMS, WETLANDS, AND PONDS, AS SHOWN ON THE PLANS, ARE DESIGNATED AS CRITICAL AREA(S). IF PRESENT, ALL 3:1 SLOPES AND STEEPER, DITCHES, AND OTHER CONTROLS SHALL BE CONSIDERED CRITICAL EROSION AREAS. THESE AREAS SHALL BE MONITORED AND MAINTAINED DAILY AND AFTER EACH RAINFALL OF 0.5 INCHES OR GREATER. COMPOST FILTER SOCKS ARE TO BE USED TO PROTECT THESE FIELD DELINEATED AREA(S) FROM SEDIMENT LEAVING THE SITE. ADDITIONALLY, ORANGE SAFETY FENCE IS RECOMMENDED TO BE INSTALLED ABOVE/AROUND THESE AREA(S), TO SERVE AS A PHYSICAL BARRIER, ENSURING THE AREA(S) ARE NOT DISTURBED. THE LOCAL GOVERNING AUTHORITY WILL HAVE THE AUTHORITY TO RECOMMEND THE PLACEMENT OF ADDITIONAL EROSION CONTROL MEASURES IN THESE AREAS IF IT BECOMES EVIDENT DURING CONSTRUCTION THAT THE ONES IN PLACE ARE NOT FUNCTIONING SUFFICIENTLY.

**SOILS:** NO SOIL STUDIES OR SUBSURFACE INVESTIGATIONS WERE PERFORMED AND ANALYZED FOR THE DESIGN OF THIS SITE. A SUBSURFACE INVESTIGATION SHALL BE PERFORMED PRIOR TO CONSTRUCTION ACTIVITIES.

**OFF SITE AREAS:** THERE ARE NO BORROW AREA(S) OR EXPORT STOCKPILE AREA(S) OUTSIDE OF THE PROPOSED LIMITS OF DISTURBANCE FOR THIS PROJECT.

**EROSION AND SEDIMENT CONTROL MEASURES:** UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE CURRENT WEST VIRGINIA EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE MANUAL.

### STRUCTURAL PRACTICES:

1. INSTALL ORANGE SAFETY FENCE TO ENSURE NO DISTURBANCE TO THE DELINEATED AREA(S).
2. INSTALL TEMPORARY CONSTRUCTION ENTRANCE.
3. INSTALL COMPOST FILTER SOCKS AS SHOWN ON THE PLANS TO REMOVE SEDIMENT FROM RUNOFF. SELECTIVELY REMOVE TREES REQUIRED TO INSTALL COMPOST FILTER SOCK IN WOODED AREAS. CLEARING AND GRUBBING SHALL BE KEPT AT A MINIMUM TO INSTALL E&S CONTROLS.
4. EROSION CONTROL BLANKETS (JUTE MATTING) SHALL BE PLACED ON ALL CRITICAL SLOPES (3:1 OR GREATER) AND AS NEEDED TO STABILIZE DISTURBED AREAS.
5. FILL SLOPE SURFACE SHALL BE LEFT IN A ROUGHENED CONDITION TO REDUCE EROSION. CONTRACTOR SHALL REDIRECT RUNOFF AWAY FROM THE FILL SLOPE BY INSTALLING EARTHEN DIVERSION BERMS AND DIVERTING THE RUNOFF TO SEDIMENT TRAPPING DEVICES.
6. INSTALL V-DITCHES, DITCH RELIEF CULVERTS, AND OUTLET PROTECTION (RAP-RAP APRONS) AS SHOWN ON THE PLANS.

**DEVICES LISTED ABOVE ARE CONSIDERED MINIMUM EROSION AND SEDIMENT CONTROLS. ADDITIONAL CONTROL MEASURES MAY BE NECESSARY DUE TO CONTRACTOR PHASING OR OTHER UNFORESEEN CONDITIONS. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE CONTRACTOR SHALL IMPLEMENT APPROPRIATE BMP'S TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION. ALL MEASURES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE CURRENT WEST VIRGINIA EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE MANUAL.**

**PERMANENT STABILIZATION:** ALL AREAS LEFT UNCOVERED BY EITHER BUILDINGS OR PAVEMENT SHALL BE STABILIZED WITH PERMANENT SEEDING IMMEDIATELY FOLLOWING FINISH GRADING AND WITHIN SEVEN (7) DAYS. AT NO TIME SHALL LAND LAY DORMANT LONGER THAN TWENTY-ONE (21) DAYS.

**MAINTENANCE PROGRAM:** DURING CONSTRUCTION ACTIVITIES, ALL CONTROL MEASURES SHALL BE INSPECTED DAILY BY THE SITE SUPERINTENDENT OR HIS REPRESENTATIVE AND WITHIN TWENTY-FOUR (24) HOURS AFTER ANY SIGNIFICANT RAIN EVENT, WHICH SHALL BE DEFINED AS RAINFALL OF TWO (2) INCHES OR MORE IN A SIX (6) HOUR PERIOD. ONCE CONSTRUCTION ACTIVITIES HAVE CONCLUDED, THE SITE SHALL BE INSPECTED EVERY TWO (2) WEEKS FOR THE LIFE OF THE FACILITY AND WITHIN TWENTY-FOUR (24) HOURS OF A SIGNIFICANT RAIN EVENT AS DEFINED ABOVE. ANY DAMAGED STRUCTURAL MEASURES ARE TO BE REPAIRED, BY THE END OF THE DAY, OR AT THE EARLIEST TIME IN WHICH IT IS SAFE TO DO SO. SEEDED AREAS SHALL BE CHECKED REGULARLY TO ENSURE THAT A GOOD STAND OF GRASS IS MAINTAINED. ALL AREAS SHALL BE FERTILIZED AND RESEEDED AS NEEDED UNTIL GRASS IS ESTABLISHED.

**TRAPPED SEDIMENT IS TO BE REMOVED AS REQUIRED TO MAINTAIN 50% TRAP AND/OR SOCK EFFICIENCY AND DISPOSED OF BY SPREADING ON THE STOCKPILE.**

**INLET OF DITCH RELIEF CULVERTS SHALL BE CHECKED REGULARLY FOR SEDIMENT BUILD-UP. IF THE GRAVEL OUTLET IS CLOGGED BY SEDIMENT, IT SHALL BE REMOVED AND CLEANED OR REPLACED IMMEDIATELY.**

**SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THIS PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED OR SWEEPED INTO ANY ROADSIDE DITCH, CULVERT OR SURFACE WATER.**

**ANY DISTURBED AREAS ALONG THE ACCESS ROAD SHALL BE STABILIZED PRIOR TO THE END OF EACH DAY WITH EITHER ROCK STABILIZATION OR SEEDING AND MULCHING METHODS.**

**NOTE: THE WV DEP RETAINS THE RIGHT TO ADD AND/OR MODIFY THESE EROSION AND SEDIMENT CONTROL MEASURES DURING THE CONSTRUCTION PROCESS, WITHIN REASON, TO ENSURE ADEQUATE PROTECTION TO THE PUBLIC AND THE ENVIRONMENT.**

### SEEDING (SOIL STABILIZATION):

1. CONTRACTOR SHALL APPLY SEED AND STABILIZATION IN ACCORDANCE WITH THE WV DEP EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP) MANUAL, BASED UPON SITE SPECIFIC SOIL CHARACTERISTICS.
2. WHEREVER SEEDING IS TO BE APPLIED TO STEEP SLOPES ( $\geq$  3H:1V), SEED MIXTURES SHOULD BE SELECTED THAT ARE APPROPRIATE FOR STEEP SLOPES.

### DUST CONTROL:

1. TEMPORARY SEEDING SHALL BE APPLIED TO ALL DISTURBED AREAS SUBJECT TO LITTLE OR NO CONSTRUCTION TRAFFIC.
2. ALL HAUL ROADS AND OTHER HEAVY TRAFFIC ROUTES SHALL BE SPRINKLED WITH WATER UNTIL THE SURFACE IS WET AND REPEATED AS NEEDED TO CONTROL DUST.

## CONSTRUCTION SEQUENCE

THE DEVELOPMENT OF THIS SITE SHALL BE CONSISTENT WITH THE FOLLOWING GENERAL SEQUENCE OF CONSTRUCTION. THE CONTRACTOR SHALL IMPLEMENT, MAINTAIN, AND OPERATE ALL PROPOSED EROSION AND SEDIMENT CONTROL MEASURES TO EFFECTIVELY MITIGATE THE HAZARD OF ACCELERATED EROSION AND SEDIMENTATION TO ACCEPTABLE LEVELS. MINOR DEVIATIONS FROM THIS SEQUENCE SHALL BE EXECUTED BY THE PROJECT'S SUPERINTENDENT AS NEEDED TO ELIMINATE ANY POTENTIAL EROSION CONDITION THAT MAY ARISE FOR THE DURATION OF THE PROJECT. THE WV DEP OFFICE OF OIL AND GAS SHALL BE NOTIFIED OF ANY AND ALL SUCH DEVIATIONS FROM THE APPROVED PLANS.

1. A PRE-CONSTRUCTION CONFERENCE WITH THE CONTRACTOR AND THE APPROPRIATE EROSION AND SEDIMENT CONTROL INSPECTOR 48 HOURS PRIOR TO BEGINNING WORK TO REVIEW THE CONSTRUCTION DRAWINGS AND PROVIDE ANY REQUESTED GUIDANCE.
2. STAKE THE LIMITS OF CONSTRUCTION AND MARK ALL IDENTIFIED WETLANDS, STREAMS, AND OTHER AREAS OF CONCERN FOR CONSTRUCTION ACTIVITIES. INSTALL SIGNS TO DESIGNATE THE AREAS AND ORANGE SAFETY FENCE TO IDENTIFY IMPORTANT PROJECT ATTRIBUTES SUCH AS APPROVED ACCESS ROADS, NO REFUELING ZONES, WETLANDS/STREAM BOUNDS, ETC.
3. CONSTRUCT THE ROCK CONSTRUCTION ENTRANCE. ALL VEHICLES ENTERING AND EXITING THE SITE SHALL DO SO VIA THE ROCK CONSTRUCTION ENTRANCE.
4. CONSTRUCT ALL BMP'S AS SOON AS CLEARING AND GRUBBING OPERATIONS ALLOW. DIVERSIONS AND SEDIMENT TRAP(S)/BASIN(S) SHALL BE SEEDED AND MULCHED IMMEDIATELY.
5. IF APPLICABLE, CONVEY UPSLOPE DRAINAGE AROUND THE ACCESS ROAD AREA BY CONSTRUCTING ALL DIVERSION BERM(S) AND/OR COMPOST FILTER SOCK DIVERSION(S) AS SHOWN ON THE PLANS.
6. CLEAR AND GRUB THE SITE. ALL WOODY MATERIAL, BRUSH, TREES, STUMPS, LARGE ROOTS, BOULDERS, AND DEBRIS SHALL BE CLEARED FROM THE SITE AREA AND KEPT TO THE MINIMUM NECESSARY FOR PROPER CONSTRUCTION, INCLUDING THE INSTALLATION OF NECESSARY SEDIMENT CONTROLS. TREES SIX INCHES IN DIAMETER AND LARGER SHALL BE CUT AND LOGS STACKED. SMALLER TREES, BRUSH, & STUMPS SHALL BE CUT AND/OR GRUBBED AND WINDROWED IN APPROPRIATE AREAS FOR USE AS BRUSH PILE SEDIMENT BARRIERS (AS SHOWN ON THE PLANS). WILDLIFE HABITATS, BURNED (AS PER WV FOREST FIRE LAWS), REMOVED FROM SITE, OR DISPOSED OF BY OTHER METHODS APPROVED BY WV DEP.
7. IF APPLICABLE, INSTALL ALL WETLAND OR STREAM CROSSINGS AS SHOWN ON THE PLANS.
8. STRIP THE TOPSOIL FROM THE ACCESS ROAD. ALL STRIPPED TOPSOIL SHALL BE STOCKPILED IN AREAS SHOWN IN THE PLANS AND IMMEDIATELY STABILIZED. ADDITIONAL BMP MEASURES SHALL BE CONSTRUCTED AROUND TOPSOIL STOCKPILES, IF NECESSARY.
9. CONSTRUCT THE ACCESS ROAD. ALL FILL AREAS SHALL BE "KEYED IN" AND COMPACTED IN HORIZONTAL LIFTS WITH A MAXIMUM LOOSE LIFT THICKNESS OF 12" AND MAXIMUM PARTICLE SIZE OF LESS THAN 6". ALL FILL SHALL BE COMPACTED BY A VIBRATING SHEEPSFOOT ROLLER TO 95% PER THE STANDARD PROCTOR TEST (ASTM-D698). MOISTURE CONTENT WILL BE CONTROLLED IN ACCORDANCE WITH THE STANDARD PROCTOR TEST (ASTM-D698) RESULTS. DITCH RELIEF CULVERTS SHALL BE INSTALLED AT A GRADE OF 1-8X TO MINIMIZE OUTLET VELOCITIES TO THE EXTENT POSSIBLE. INSTALL OUTLET PROTECTION ONCE DITCH RELIEF CULVERTS ARE INSTALLED, AS SHOWN ON PLANS. STABILIZE THE ROAD WITH GEOTEXTILE FABRIC & STONE SIDE SLOPES AS SPECIFIED WITH PERMANENT SEEDING. EXCESS MATERIAL SHALL BE STOCKPILED (IF NECESSARY) IN AREAS SHOWN IN THE PLANS AND IMMEDIATELY STABILIZED. ALL DITCH LINES SHALL BE CLEANED PRIOR TO INSTALLATION OF LINED PROTECTION.
10. ALL BMP'S MUST REMAIN IN PLACE AND FUNCTIONAL UNTIL ALL AREAS WITHIN THE LIMIT OF DISTURBANCE ARE COMPLETE AND PERMANENTLY STABILIZED. MAINTENANCE MUST INCLUDE INSPECTION OF ALL EROSION AND SEDIMENT CONTROLS AFTER EACH RUNOFF EVENT IN EXCESS OF 0.5" AND ON A BIWEEKLY BASIS.
11. THE CONSTRUCTION SITE SHOULD BE STABILIZED AS SOON AS POSSIBLE AFTER COMPLETION. ESTABLISHMENT OF FINAL COVER MUST BE INITIATED NO LATER THAN 7 DAYS AFTER REACHING FINAL GRADE. A NOTICE OF TERMINATION MUST BE FILED WITH THE WV DEP WHEN THE SITE REACHES FINAL STABILIZATION. FINAL STABILIZATION MEANS THAT ALL SOIL-DISTURBING ACTIVITIES ARE COMPLETED, AND THAT EITHER A PERMANENT VEGETATIVE COVER WITH A DENSITY OF 70% OR GREATER HAS BEEN ESTABLISHED OR THAT THE SURFACE HAS BEEN STABILIZED BY HARD COVER SUCH AS PAVEMENT OR BUILDINGS. IT SHOULD BE NOTED THAT THE 70% REQUIREMENT REFERS TO THE TOTAL AREA VEGETATED AND NOT JUST A PERCENT OF THE SITE.
12. ALL PERMANENT SEDIMENT CONTROL MEASURES CAN BE REMOVED AFTER THE SITE IS PERMANENTLY STABILIZED AND APPROVAL IS RECEIVED FROM THE WV DEP.
13. ANY AREAS DISTURBED BY REMOVAL OF CONTROLS SHALL BE REPAIRED, STABILIZED, AND PERMANENTLY SEEDED.

Engineering  
Survey  
Environmental  
GIS

NAVITUS  
ENGINEERING INC.



131 Windy Hill Lane  
Martinsburg, WV 26151  
Telephone: (888) 662-4165  
www.navituseng.com

REVISION

DATE



CONSTRUCTION AND E&S CONTROL NOTES

NEW MILTON

COMPRESSOR STATION ACCESS ROAD

NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA



07/16/2013

DATE: 07/16/2013

SCALE: N/A

SHEET 2 OF 20



# MATERIAL QUANTITIES

MATERIAL QUANTITIES				
ACCESS ROAD SITE: NEW MILTON COMPRESSOR STATION				
Item	Description	Quantity	Unit	Item Total
1.0	Mobilization (Limited to 10% of Total Base Bid)	1.0	LS	\$
2.0	Erosion & Sediment Control			
2.1	Clearing and Grubbing			
2.1.1	Wooded	12.18	AC	\$
2.1.2	Open Field	4.85	AC	\$
2.2	Super Silt Fence	186.2	LF	\$
2.3	12" Compost Filter Sock	3,496.7	LF	\$
2.4	18" Compost Filter Sock	911.3	LF	\$
2.5	24" Compost Filter Sock	128.0	LF	\$
2.6	32" Compost Filter Sock	430.4	LF	\$
2.7	12" Compost Sock Diversion	764.7	LF	\$
2.8	Jute Matting - Slope Matting	402,783.2	SF	\$
2.9	Ditch Lining - Synthetic Matting (TRM)	16,500.8	SF	\$
3.0	Unclassified Earthwork			
3.1	Access Road "A"			
3.1.1	Topsoil Removal to Stockpile (Assume 6" Depth)	6,930.2	CY	\$
3.1.2	Excavation (Cut to Compact Fill)	16,802.8	CY	\$
3.1.3	Excavation (Export to Stockpile)	17,880.8	CY	\$
3.2	Excavation/Undiggable Material (Hammering)		CY	\$
3.3	Excavation/Undiggable Material (Blasting)		CY	\$
4.0	Stone and Aggregate Surfacing			
4.1	Construction Entrance			
4.1.1	6"-4" Crusher Run (10" Depth)	280.7	TONS	\$
4.1.2	Geotextile Fabric (US 200 or Equal)	6,087.8	SF	\$
4.2	Access Road "A"			
4.2.1	6"-4" Crusher Run (8" Depth)	4,508.3	TONS	\$
4.2.2	3/4"-1 1/2" Crusher Run (2" Depth)	1,128.8	TONS	\$
4.2.3	Geotextile Fabric (US 200 or Equal)	121,117.2	SF	\$
4.2.4	Clean Rock Fill (2"-4" Coarse Aggregate)	2,982.0	TONS	\$
4.3	4" Rip Rap (Outlets/Level Spreaders) 18" Depth	374.2	TONS	\$
4.4	4" Rip Rap (Rock-Lined Ditches) 6" Depth	361.7	TONS	\$
4.5	Rock Fill Check Dams (#4 Stone)	22.5	TONS	\$
5.0	Ditch Relief and Drainage Culverts			
5.1	15" CPP (total)	687.5	LF	\$
5.2	35' 10" x 11' 4" Contech Bridgecor #25A5 Arch Culvert (total)	80.0	LF	\$
6.0	Miscellaneous			
6.1	Seeding and Mulching			
6.1.1	Temporary Seeding (Vegetation & Mulch)	0.0	AC	\$
6.1.2	Permanent Seeding (Vegetation & Mulch / Fertilizer/ Lime)	14.2	AC	\$
6.1.3	Lime, Fertilizer, Seeding, and Hydro-Mulch w/tack (HYC2 or Equal)		AC	\$
6.2	3'x3'x6' Gabion Basket	100.0	EA	\$

**NOTE:**

1. THE SQUARE FOOTAGE FOR THE GEOTEXTILE FABRIC DOES NOT ACCOUNT FOR MATERIAL OVERLAP AND WASTE.

Engineering  
Survey  
Environmental  
GIS

**NAVITUS**  
ENGINEERING INC.

151 Windy Hill Lane  
Wilmington, NC 28402  
Telephone: (858) 662-1185  
www.navituseng.com



REVISION

DATE

**ANTERO**  
RESOURCES  
THIS DRAWING  
WAS PREPARED  
FOR:  
ANTERO RESOURCES  
CORPORATION

MATERIAL QUANTITIES  
**NEW MILTON**  
COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA




DATE: 07/16/2013  
SCALE: N/A  
SHEET 3 OF 20



**GENERAL NOTES:**

1. THE TOPOGRAPHIC INFORMATION SHOWN HEREON IS BASED ON MARCH 30, 2013 AERIAL PHOTOGRAPHY COMPILED JULY, 2013 BY BLUE MOUNTAIN AERIAL MAPPING, BURTON, WEST VIRGINIA.
2. THE PROPERTY LINES SHOWN HEREON DO NOT REPRESENT A BOUNDARY SURVEY ON ANY OF THE PARCELS SHOWN. PROPERTY CORNERS AND LINES PERTINENT TO THE ACCESS ROAD LOCATION ARE BASED ON A FIELD SURVEY. THE REMAINDER OF THE PROPERTY LINES ARE BASED ON COUNTY REAL ESTATE TAX MAPS, GIS INFORMATION AND DEEDS OF RECORD.
3. UTILITIES AND THEIR LOCATIONS AS SHOWN HEREON ARE BASED ON: A) OBSERVABLE EVIDENCE OF THOSE VISIBLE, ABOVE-GROUND FACILITIES, FEATURES, AND MARKERS WHICH WERE FOUND ON THE SUBJECT PROPERTY AT THE TIME OF SURVEY PERFORMED BY NAVITUS ENGINEERING AND B) FIELD MARKINGS PLACED BY UTILITY COMPANIES IN RESPONSE TO THE WV 811 TICKET SUBMITTED BY NAVITUS ENGINEERING. NAVITUS ENGINEERING CANNOT GUARANTEE THE ACCURACY OF THE UTILITY MARKINGS PERFORMED BY OTHERS OR THAT ALL UTILITIES EXISTING WITHIN THE LIMITS OF THIS PLAN ARE SHOWN. ANY UTILITIES ENCOUNTERED SUBSEQUENT TO PLAN APPROVAL OR DURING CONSTRUCTION THAT ARE NOT SHOWN ON THE PLAN SHOULD BE REPORTED TO NAVITUS ENGINEERING AND ANTERO RESOURCES APPALACHIAN CORPORATION.

**EXISTING CONDITIONS**



LEGEND	
EX. INDEX CONTOUR	--- 700 ---
EX. INTERMEDIATE CONTOUR	---
EX. PROPERTY LINE	---
EX. ROAD EDGE OF GRAVEL/DIRT	---
EX. ROAD EDGE OF PAVEMENT	---
EX. ROAD CENTERLINE	---
EX. DITCHLINE	---
EX. CULVERT	---
EX. FENCELINE	---
EX. OVERHEAD UTILITY	---
EX. POWER POLE/GUY WIRE	---
EX. GASLINE	---
EX. TRELINER	---
EX. DELINEATED STREAM	---
EX. DELINEATED WETLAND	---
EX. BUILDING	---
DELINEATION STUDY AREA	---

Engineering  
Survey  
Environmental  
GIS

**NAVITUS ENGINEERING INC.**



151 W. Windy Hill Lane, 22602  
Telephone: (888) 463-4185  
www.navituseng.com

REVISION

DATE

**ANTERO RESOURCES**  
THIS PROJECT WAS PREPARED FOR:  
**ANTERO RESOURCES CORPORATION**

EXISTING CONDITIONS

**NEW MILTON**

COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA



DATE: 07/16/2013

SCALE: 1" = 150'

SHEET 4 OF 20





# OVERALL PLAN SHEET INDEX & VOLUMES

<b>Access Road "A"</b>	
Topsoil Removal:	6,930.2 C.Y.
Total Cut:	34,683.6 C.Y. (Cut/Swell=1)
Total Fill:	16,802.8 C.Y. (Fill Shrink=1)
Cut slope percent grade:	50.00 % slope ratio: 2:1
Fill slope percent grade:	50.00 % slope ratio: 2:1
Gravel (10" Depth):	3,758.0 C.Y.

NEW MILTON COMPRESSOR STATION ACCESS ROAD						
Description	Cut (CY)	Fill (CY)	Spoil (CY)	Borrow (CY)	Max. Slope (%)	Length of Slope (FT)
Access Road "A"	34,683.6	16,802.8	17,880.8	0.0	18.0	1,490.0
Stripped Topsoil (6")	6,930.2	0.0	6,930.2	0.0	n/a	n/a
Material Stockpiles	0.0	28,070.0	0.0	28,070.0	n/a	n/a
<b>Totals</b>	<b>41,613.8</b>	<b>44,872.8</b>	<b>24,811.0</b>	<b>28,070.0</b>	<b>n/a</b>	<b>n/a</b>
Total Spoil (CY) =			-3,259.0			

THE EARTHWORK QUANTITIES PROVIDED ARE AN ESTIMATE FOR CONSIDERATION. THE QUANTITIES SHOWN ARE CALCULATED USING A 1:1 CUT/SWELL & FILL SHRINK FACTOR. THE QUANTITIES SHOWN MAY BE GREATER OR LESSER THAN ACTUALLY EXCAVATED. THE ENGINEER IS NOT RESPONSIBLE FOR VARIANCES FROM THE ESTIMATED QUANTITIES AND DOES NOT CERTIFY TO THEIR ACCURACY.

MATERIAL STOCKPILES		
Name	Excess	Topsoil
A	3,930.0	0.0
B	16,820.0	0.0
C	0.0	7,320.0
<b>TOTAL</b>	<b>20,750.0</b>	<b>7,320.0</b>



Engineering  
Survey  
Environmental  
GIS

**NAVITUS**  
ENGINEERING INC.

151 Windy Hill Lane  
Wichita, KS 67260  
Telephone: (888) 662-4185  
www.navituseng.com

REVISION

DATE

**ANTERO**  
RESOURCES  
THIS PROJECT  
WAS PREPARED  
FOR:  
ANTERO RESOURCES  
CORPORATION

OVERALL PLAN SHEET INDEX & VOLUMES

**NEW MILTON**  
COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA




DATE: 07/16/2013

SCALE: 1" = 150'

SHEET 5 OF 20



# ACCESS ROAD PLAN



147.39.225844  
10N-80.698042  
(NAD 83)


TM 8-37  
KATHRYN H. MARSHALL (MS 017 PG 722)  
CLINTON D. & KEVIN M. MEANS (DB 287 PG 272)  
MARVIN L. PHILLIPS (WB 033 PG 405)  
RUTH E. PHILLIPS (WB 038 PG 170)  
WILLIAM C. PHILLIPS (WB 033 PG 405)  
LAVENNE H. WILLIAMS (MS 017 PG 722)  
147.86 ACRES

TM 8-37  
CONSTOCK/IRREVOCABLE  
TRUST & SILVESTER  
IRREVOCABLE TRUST  
DB 281 PG 37  
DB 281 PG 34  
28 ACRES

**NOTES:**  
1. ALL PROPOSED DITCH RELIEF AND DRAINAGE CULVERTS SHALL HAVE ADEQUATE OUTLET PROTECTION (4" RIP-RAP) AS SHOWN ON THESE PLANS.  
2. ALL FILL AREAS SHALL BE "KEYED IN" AND COMPACTED IN 12" (MAXIMUM) LOOSE LIFT THICKNESS WITH A VIBRATING SHEEPSFOOT ROLLER TO 95% COMPACTION PER STANDARD PROCTOR. MOISTURE CONTENT WILL BE CONTROLLED IN ACCORDANCE WITH THE STANDARD PROCTOR TEST (ASTM-D698) RESULTS.

### LEGEND

EX. INDEX CONTOUR	---	700	PROP. INDEX CONTOUR	---	700
EX. INTERMEDIATE CONTOUR	---		PROP. INTERMEDIATE CONTOUR	---	
EX. PROPERTY LINE	---		PROP. INDEX CONTOUR (ROAD)	---	700
EX. ROAD EDGE OF GRAVEL/DIRT	---		PROP. INTERMEDIATE CTR (ROAD)	---	
EX. ROAD EDGE OF PAVEMENT	---		PROP. LIMITS OF DISTURBANCE	---	
EX. ROAD CENTERLINE	---		PROP. WELL HEAD	---	
EX. DITCHLINE	---		PROP. PERIMETER SAFETY FENCE	---	
EX. CULVERT	---		PROP. ACCESS GATE WITH EMERGENCY LIFELINE	---	
EX. FENCELINE	---		PROP. ROAD EDGE OF GRAVEL	---	
EX. OVERHEAD UTILITY	---		PROP. ROAD CENTERLINE	---	
EX. POWER POLE/GUY WIRE	---		PROP. V-DITCH W/ CHECK DAMS	---	
EX. GASLINE	---		PROP. CULVERT W/ RIP-RAP	---	
EX. TREELINE	---		PROP. COMPOST FILTER SOCK	---	
EX. DELINEATED STREAM	---		PROP. SUPER SILT FENCE	---	
EX. DELINEATED WETLAND	---		MATCHLINE	---	
EX. BUILDING	---		BRUSH PILE SEDIMENT BARRIER	---	
100' WETLAND/STREAM BUFFER	---		DELINEATION STUDY AREA	---	



**NAVITUS ENGINEERING INC.**  
Engineering Survey Environmental GIS  
151 Wickham Hill Lane  
Winchester, Virginia 22602  
Telephone: (888) 662-4185  
www.navituseng.com

REVISION	DATE


**ANTERO RESOURCES**  
THIS DOCUMENT WAS PREPARED FOR:  
ANTERO RESOURCES CORPORATION

**ACCESS ROAD PLAN**  
**NEW MILTON**  
**COMPRESSOR STATION ACCESS ROAD**  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA

07/16/2013  
DATE: 07/16/2013  
SCALE: 1" = 50'  
SHEET 6 OF 20



# ACCESS ROAD PLAN



**NOTES:**  
 1. ALL PROPOSED DITCH RELIEF AND DRAINAGE CULVERTS SHALL HAVE ADEQUATE OUTLET PROTECTION (4" RIP-RAP) AS SHOWN ON THESE PLANS.  
 2. ALL FILL AREAS SHALL BE "KEYED IN" AND COMPACTED IN 12" (MAXIMUM) LOOSE LIFT THICKNESS WITH A VIBRATING SHEEPSFOOT ROLLER TO 95% COMPACTION PER STANDARD PROCTOR. MOISTURE CONTENT WILL BE CONTROLLED IN ACCORDANCE WITH THE STANDARD PROCTOR TEST (ASTM-D698) RESULTS.

LEGEND	
EX. INDEX CONTOUR	--- 700 ---
EX. INTERMEDIATE CONTOUR	--- 700 ---
EX. PROPERTY LINE	---
EX. ROAD EDGE OF GRAVEL/DIRT	---
EX. ROAD EDGE OF PAVEMENT	---
EX. ROAD CENTERLINE	---
EX. DITCHLINE	---
EX. CULVERT	---
EX. FENCELINE	---
EX. OVERHEAD UTILITY	---
EX. POWER POLE/GUY WIRE	---
EX. GASLINE	---
EX. TREELINE	---
EX. DELINEATED STREAM	---
EX. DELINEATED WETLAND	---
EX. BUILDING	---
100' WETLAND/STREAM BUFFER	---
DELINEATION STUDY AREA	---
PROP. INDEX CONTOUR	--- 700 ---
PROP. INTERMEDIATE CONTOUR	---
PROP. INDEX CONTOUR (ROAD)	--- 700 ---
PROP. INTERMEDIATE CTR (ROAD)	---
PROP. LIMITS OF DISTURBANCE	---
PROP. WELL HEAD	---
PROP. PERIMETER SAFETY FENCE	---
PROP. ACCESS GATE WITH EMERGENCY LIFELINE	---
PROP. ROAD EDGE OF GRAVEL	---
PROP. ROAD CENTERLINE	---
PROP. V-DITCH W/ CHECK DAMS	---
PROP. CULVERT W/ RIP-RAP	---
PROP. COMPOST FILTER SOCK	---
PROP. SUPER SILT FENCE	---
MATCHLINE	---
BRUSH PILE SEDIMENT BARRIER	---

**NAVITUS ENGINEERING INC.**  
 Engineering Survey Environmental GIS  
 151 Windy Hill Lane, 22402  
 Winchester, Virginia  
 Telephone: (888) 965-4185  
 www.navituseng.com

DATE	REVISION

**ANTERO RESOURCES**  
 THIS DOCUMENT WAS PREPARED FOR:  
 ANTERO RESOURCES CORPORATION

**ACCESS ROAD PLAN**  
**NEW MILTON**  
**COMPRESSOR STATION ACCESS ROAD**  
 NEW MILTON DISTRICT  
 DODDRIDGE COUNTY, WEST VIRGINIA

07/16/2013  
 DATE: 07/16/2013  
 SCALE: 1" = 50'  
 SHEET 7 OF 20




**LEGEND**

EX. INDEX CONTOUR	--- 700 ---	PROP. INDEX CONTOUR	--- 700 ---
EX. INTERMEDIATE CONTOUR	--- 700 ---	PROP. INTERMEDIATE CONTOUR	--- 700 ---
EX. PROPERTY LINE	---	PROP. INDEX CONTOUR (ROAD)	--- 700 ---
EX. ROAD EDGE OF GRAVEL/DIRT	---	PROP. INTERMEDIATE CTR (ROAD)	---
EX. ROAD EDGE OF PAVEMENT	---	PROP. LIMITS OF DISTURBANCE	---
EX. ROAD CENTERLINE	---	PROP. WELL HEAD	⊕
EX. DITCHLINE	---	PROP. PERIMETER SAFETY FENCE	⊗
EX. CULVERT	---	PROP. ACCESS GATE WITH EMERGENCY LIFELINE	⊕
EX. FENCELINE	---	PROP. ROAD EDGE OF GRAVEL	---
EX. OVERHEAD UTILITY	---	PROP. ROAD CENTERLINE	---
EX. POWER POLE/GUY WIRE	---	PROP. V-DITCH W/ CHECK DAMS	---
EX. GASLINE	---	PROP. CULVERT W/ RIP-RAP	---
EX. TREELINE	---	PROP. COMPOST FILTER SOCK	---
EX. DELINEATED STREAM	---	PROP. SUPER SILT FENCE	SSP - SSP
EX. DELINEATED WETLAND	---	MATCHLINE	---
EX. BUILDING	---	BRUSH PILE SEDIMENT BARRIER	---
100' WETLAND/STREAM BUFFER DELINEATION STUDY AREA	---		

**NOTES:**

1. ALL PROPOSED DITCH RELIEF AND DRAINAGE CULVERTS SHALL HAVE ADEQUATE OUTLET PROTECTION (4" RIP-RAP) AS SHOWN ON THESE PLANS.
2. ALL FILL AREAS SHALL BE "KEYED IN" AND COMPACTED IN 12" (MAXIMUM) LOOSE LIFT THICKNESS WITH A VIBRATING SHEEPSFOOT ROLLER TO 95% COMPACTION PER STANDARD PROCTOR. MOISTURE CONTENT WILL BE CONTROLLED IN ACCORDANCE WITH THE STANDARD PROCTOR TEST (ASTM-D698) RESULTS.



**ACCESS ROAD PLAN**

**NAVITUS ENGINEERING INC.**  
 Engineering Survey Environmental GIS  
 151 Windy Hill Lane, 22602  
 Telephone: (888) 462-4185  
 www.navituseng.com

DATE	REVISION

**ANTERO RESOURCES**  
 THIS DOCUMENT WAS PREPARED FOR:  
 ANTERO RESOURCES CORPORATION

**ACCESS ROAD PLAN**  
**NEW MILTON**  
**COMPRESSOR STATION ACCESS ROAD**  
 NEW MILTON DISTRICT  
 DODDRIDGE COUNTY, WEST VIRGINIA




DATE: 07/16/2013  
 SCALE: 1" = 50'  
 SHEET 8 OF 20







# ACCESS ROAD PROFILES



ACCESS ROAD "A" PROFILE

SCALE: HORIZ. 1" = 50' VERT. 1" = 50'

### LEGEND

- X-SECTION GRID INDEX
- X-SECTION GRID INTERMEDIATE
- X-SECTION PROPOSED GRADE
- X-SECTION EXISTING GRADE
- X-SECTION WATER SURFACE
- MATCHLINE

REVISION

DATE



ANTERO RESOURCES  
THIS DOCUMENT  
WAS PREPARED  
FOR:  
ANTERO RESOURCES  
CORPORATION

ACCESS ROAD PROFILES  
**NEW MILTON**  
COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA



DATE: 07/16/2013  
SCALE: AS SHOWN  
SHEET 10 OF 20

**NAVITUS**  
ENGINEERING INC.

Engineering  
Survey  
Environmental  
GIS

151 Windy Hill Lane, 2nd Floor  
Martinsburg, WV 25753  
Telephone: (800) 663-4182  
www.navituseng.com

# ACCESS ROAD SECTIONS

LEGEND	
X-SECTION GRID INDEX	---
X-SECTION GRID INTERMEDIATE	---
X-SECTION PROPOSED GRADE	---
X-SECTION EXISTING GRADE	---
X-SECTION WATER SURFACE	---
MATCHLINE	---





NOTE:  
1. ALL CUT & FILL SLOPES ALONG THE ACCESS ROAD SHALL BE 2:1 UNLESS STATED OTHERWISE.

Engineering Survey Environmental GIS



## ACCESS ROAD "A" CROSS-SECTIONS

SCALE: HORIZ. 1" = 50' VERT. 1" = 10'



REVISION	DATE

ANTERO RESOURCES CORPORATION  
THIS REPORT WAS PREPARED FOR:  
ANTERO RESOURCES CORPORATION

ACCESS ROAD SECTIONS  
**NEW MILTON**  
COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA



DATE: 07/16/2013  
SCALE: AS SHOWN  
SHEET 11 OF 20

# ACCESS ROAD SECTIONS

## ACCESS ROAD "A" CROSS-SECTIONS

SCALE: HORIZ. 1" = 50' VERT. 1" = 10'


















LEGEND	
X-SECTION GRID INDEX	-----
X-SECTION GRID INTERMEDIATE	-----
X-SECTION PROPOSED GRADE	-----
X-SECTION EXISTING GRADE	-----
X-SECTION WATER SURFACE	-----
MATCHLINE	-----

NOTE:  
1. ALL CUT & FILL SLOPES ALONG THE ACCESS ROAD SHALL BE 2:1 UNLESS STATED OTHERWISE.

Engineering Survey Environmental GIS

**NAVITUS ENGINEERING INC.**

151 Windy Hill Lane  
Winchester, Virginia 22602  
Telephone: (888) 662-4182  
www.naveng.com



REVISION	DATE

ANTERO RESOURCES CORPORATION  
THIS DOCUMENT WAS PREPARED FOR:  
ANTERO RESOURCES CORPORATION

ACCESS ROAD SECTIONS  
**NEW MILTON**  
COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA





















# ACCESS ROAD SECTIONS

## ACCESS ROAD "A" CROSS-SECTIONS

SCALE: HORIZ. 1" = 50' VERT. 1" = 10'

LEGEND	
X-SECTION GRID INDEX	---
X-SECTION GRID INTERMEDIATE	---
X-SECTION PROPOSED GRADE	---
X-SECTION EXISTING GRADE	---
X-SECTION WATER SURFACE	---
MATCHLINE	---

NOTE:  
1. ALL CUT & FILL SLOPES ALONG THE ACCESS ROAD SHALL BE 2:1 UNLESS STATED OTHERWISE.



Engineering Survey Environmental GIS

**NAVITUS ENGINEERING INC.**

151 Windy Hill Lane  
U.S. Highway 17  
Telephone: (888) 462-4185  
www.navituseng.com

REVISION	DATE


**ANTERO RESOURCES**  
THIS REPORT WAS PREPARED FOR:  
ANTERO RESOURCES CORPORATION

ACCESS ROAD SECTIONS

**NEW MILTON**

COMPRESSOR STATION ACCESS ROAD

NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA



DATE: 07/16/2013  
SCALE: AS SHOWN  
SHEET 13 OF 20




**GENERAL STREAM CROSSING NOTES:**

- 2" TO 4" COARSE AGGREGATE OR LARGER SHALL BE USED TO FORM THE FIRST 6" OF FILL FOR THE CROSSING, THE REMAINDER OF MATERIAL SHALL BE ONLY LARGE ANGULAR DURABLE ROCK. "DO NOT USE ERODIBLE MATERIAL FOR CONSTRUCTION OF THE CROSSING."
- IF MULTIPLE CULVERTS ARE USED, THEY SHALL BE SEPARATED BY AT LEAST 18 INCHES OF COMPACTED AGGREGATE FILL.
- CLEARING AND EXCAVATION OF THE STREAMBED AND BANKS SHALL BE KEPT TO A MINIMUM.
- APPROPRIATE PERIMETER CONTROLS SUCH AS COMPOST FILTER SOCK, SUPER SILT FENCE AND/OR SEDIMENT TRAPS SHALL BE EMPLOYED ALONG THE BANKS AND PARALLEL TO THE STREAMBED.
- GABION WALLS ON THE UPSTREAM AND DOWNSTREAM SIDE OF THE CULVERT INSTALLATION SHALL BE INSTALLED TO REDUCE STRUCTURAL DAMAGE DURING HIGH VELOCITY WATER OVERFLOW PERIODS.
- STREAMBED MATERIAL IS NOT TO BE USED AS FILL.
- GREEN CONCRETE SHALL NOT BE PLACED IN CONTACT WITH FLOWING WATER.
- WHEN THE CROSSING HAS SERVED ITS PURPOSE, ALL STRUCTURES INCLUDING CULVERTS, BEDDING, AND FILTER CLOTH SHALL BE REMOVED. REMOVAL OF THE STRUCTURE AND CLEAN UP OF THE AREA SHOULD BE ACCOMPLISHED WITHOUT CONSTRUCTION EQUIPMENT WORKING IN THE WATERWAY CHANNEL. UPON REMOVAL OF THE STRUCTURE, THE STREAM BANK SHALL IMMEDIATELY BE STABILIZED.
- DURING ROUTINE MAINTENANCE DO NOT GRADE MUD AND DEBRIS OVER THE SIDES OF THE CROSSING INTO THE STREAM.
- THE CROSSING MUST BE INSPECTED AFTER EVERY RAIN EVENT OF 0.5 INCHES OR MORE AND ONCE A WEEK TO ENSURE THAT THE CULVERTS, STREAMBED, AND STREAM BANKS ARE MAINTAINED AND NOT DAMAGED. NEVER ALLOW THE CULVERTS TO BECOME CLOGGED WITH DEBRIS AND REMOVE ANY OBSTRUCTIONS IMMEDIATELY.
- FLUSHING IS NOT AN APPROVED METHOD TO BE UTILIZED FOR CULVERT CLEANOUT.


**PUMP AND DEWATERING NOTES:**

- CONSTRUCTION SHOULD BE PERFORMED DURING LOW FLOW PERIODS.
- PUMP(S) AND DEWATERING BAG SHOULD BE SUFFICIENTLY LARGE TO CONTAIN THE ENTIRE STREAM AREA BEING DAMMED.
- THE COFFERDAM CONSTRUCTED MUST BE IMPERVIOUS TO WATER.
- THE INLET OF THE PUMP(S) IS TO BE SUSPENDED ABOVE THE STREAMBED IN ORDER TO PREVENT SUCKING MUD AND SEDIMENT.

**STREAM CROSSING "A" DETAILS**




**STREAM CROSSING "A" SECTIONS**



**CROSS SECTION "A-A"**

SCALE: HORIZ. 1" = 50' VERT. 1" = 10'



**CROSS SECTION "B-B"**

SCALE: HORIZ. 1" = 50' VERT. 1" = 10'




- NOTE:**
- SEE STREAM CROSSING REPORT AND FLOODPLAIN ANALYSIS OF TOMS FORK BY NAVITUS ENGINEERING FOR CULVERT AND DRAINAGE COMPUTATIONS.
  - ANTERO RESOURCES SHALL OBTAIN A STREAM ACTIVITY PERMIT THROUGH THE PUBLIC LAND CORPORATION OFFICE OF LAND AND STREAMS FOR STREAM CROSSING "A".

**LEGEND**

X-SECTION GRID INDEX	---
X-SECTION GRID INTERMEDIATE	---
X-SECTION PROPOSED GRADE	---
X-SECTION EXISTING GRADE	---
X-SECTION WATER SURFACE	---
MATCHLINE	---

**LEGEND**

EX. INDEX CONTOUR	---	PROP. INDEX CONTOUR	---
EX. INTERMEDIATE CONTOUR	---	PROP. INTERMEDIATE CONTOUR	---
EX. PROPERTY LINE	---	PROP. INDEX CONTOUR (ROAD)	---
EX. ROAD EDGE OF GRAVEL/DIRT	---	PROP. INTERMEDIATE CTR (ROAD)	---
EX. ROAD EDGE OF PAVEMENT	---	PROP. LIMITS OF DISTURBANCE	---
EX. ROAD CENTERLINE	---	PROP. WELL HEAD	---
EX. DITCHLINE	---	PROP. PERIMETER SAFETY FENCE	---
EX. CULVERT	---	PROP. ACCESS GATE WITH EMERGENCY LIFELINE	---
EX. FENCELINE	---	PROP. ROAD EDGE OF GRAVEL	---
EX. OVERHEAD UTILITY	---	PROP. ROAD CENTERLINE	---
EX. POWER POLE/GUY WIRE	---	PROP. V-DITCH W/ CHECK DAMS	---
EX. GASLINE	---	PROP. CULVERT W/ RIP-RAP	---
EX. TREELINE	---	PROP. COMPOST FILTER SOCK	---
EX. DELINEATED STREAM	---	PROP. SUPER SILT FENCE	---
EX. DELINEATED WETLAND	---	MATCHLINE	---
EX. BUILDING	---		
100' WETLAND/STREAM BUFFER	---		
DELINEATION STUDY AREA	---		



Engineering Survey Environmental GIS

**NAVITUS ENGINEERING INC.**

151 Wandy Hill Lane  
Tomball, TX 77375  
Tel: (281) 462-4185  
www.navitus-engineering.com

DATE	REVISION

ANTERO RESOURCES  
THIS DOCUMENT  
WAS PREPARED  
FOR:  
ANTERO RESOURCES CORPORATION

**STREAM CROSSING "A" DETAILS**

**NEW MILTON**  
COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA

REGISTERED PROFESSIONAL ENGINEER  
STATE OF WEST VIRGINIA  
07/16/2013

DATE: 07/16/2013  
SCALE: AS SHOWN  
SHEET 14 OF 20




















Table 4.1  
Compost Sock Fabric Minimum Specifications

Material Type	3 mil HDPE Photo-degradable	5 mil HDPE Photo-degradable	6 mil HDPE Bio-degradable	Multi-Filament Polypropylene (MPP)	Heavy Duty Multi-Filament Polypropylene (HDMPP)
Material Characteristics	Photo-degradable	Photo-degradable	Bio-degradable	Photo-degradable	Photo-degradable
Sock Diameters	12", 18"	12", 16", 24", 32"	12", 16", 24", 32"	12", 16", 24", 32"	12", 16", 24", 32"
Mesh Opening	3/8"	3/8"	3/8"	3/8"	1/8"
Tenile Strength	20 psi	20 psi	20 psi	44 psi	202 psi
Ultraviolet Stability % Original Strength (ASTM G-155)	23% at 1000 hr.	23% at 1000 hr.		100% at 1000 hr.	100% at 1000 hr.
Minimum Functional Longevity	6 months	9 months	6 months	1 year	2 years

Two-ply systems

Inner Containment Netting	HDPE biaxial net
	Continuously wound
	Welded Joints
	3/4" x 3/4" Max. aperture size
Outer Filtration Mesh	Composite Polypropylene Fabric (woven layer & non-woven fleece mechanically fused via needle punch)
	3/16" Max. aperture size

Sock fabrics composed of burlap may be used on projects lasting 6 months or less.



Engineering Survey Environmental GIS

**NAVITUS ENGINEERING INC.**  
151 Wicks Hill Lane  
Winchester, Virginia 22602  
Telephone: (888) 662-4185  
www.navituseng.com

REVISION	DATE

ANTERO RESOURCES CORPORATION  
THIS DOCUMENT WAS PREPARED FOR:  
ANTERO RESOURCES CORPORATION

CONSTRUCTION DETAILS  
**NEW MILTON**  
COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA

PROFESSIONAL ENGINEER  
WEST VIRGINIA  
07/16/2013

DATE: 07/16/2013  
SCALE: N/A  
SHEET 17 OF 20

**REVEGETATION**

Taken from the  
West Virginia Erosion and Sediment Control Field Manual  
West Virginia Division of Environmental Protection Office of Oil and Gas  
Charleston, W.Va.  
Section IV

**Temporary Seeding**

**a. General Conditions Where Practice Applies**

Where exposed soil surfaces are not to be fine-graded or worked for periods longer than 21 days. Temporary vegetative cover with sediment controls must be established where runoff will go directly into a stream. Immediately upon construction of the site (site includes road and location), vegetation must be established on road bank and location slopes. A permanent vegetative cover shall be applied to areas that will be left un-worked for a period of more than six months.

**b. Seed Mixtures and Planting Dates**

Refer to Tables 2 through 4 for recommended dates to establish vegetative cover and the approved lists of temporary and permanent plant species, and planting rates. Table 3 gives recommended types of temporary vegetation, rates of application, and optimum seeding dates. In situations where another cover is desired, contact the local soil conservation district for seeding recommendations.

**c. Seed Application**

Apply seed by broadcasting, drilling, or by hydroseed according to the rates indicates in Table IV-3. Perform all planting operations at right angles to the slope. Necessary site preparation and roughening of the soil surface should be done just prior to seeding. Seedbed preparation may not be required on newly disturbed areas.

**Permanent Seeding**

**a. General**

Permanent vegetative cover will be established where no further soil disturbance is anticipated or needed. Soil fertility and pH level should be tested and adjusted according to seed species planted. Planting of permanent vegetative covers must be performed on all disturbed areas after completion of the drilling process. Any site that contains significant amounts of topsoil shall have the topsoil removed and stockpiled when feasible. Topsoil should not be added to slopes steeper than 2:1 unless a good bonding to the sub-layer can be achieved. After proper grading and seedbed preparation, the vegetation will reestablish ground cover for the control of surface water runoff erosion.

All required seedbed preparation and loosening of soil by disking or dozer tracking should be performed just prior to seeding. If seedbed preparation is not feasible, 50% more seed shall be added to the recommended rates shown in Tables IV-3 and IV-4. When hydroseeding, seedbed preparation may not be necessary if adequate site preparation was performed. Incorporate the appropriate amount of lime and/or fertilizer in the slurry mix when hydroseeding.

When hydroseeding, first mix the lime, fertilizer, and hydro-mulch in the recommended amount of water. Mix the seed and inoculants together within one hour prior to planting, and add to the slurry just before seeding. Apply the slurry uniformly over the prepared site. Assure that agitation is continuous throughout the seeding operation and the mix is applied within one hour of initial mixing.

**b. Lime and Fertilizer**

1. Lime shall be applied to all permanent seedings. The pH of the soil is to be determined and lime applied accordingly. Once the pH is known, select the amount of lime to be applied from Table IV-5.

2. Fertilizer shall be applied in all permanent seedings. Apply the equivalent for 500 lbs. minimum 10-20-20 fertilizer per acre or use the amount of fertilizer and lime recommended by a certified soil test.

3. Application: For best results and maximum benefits, the lime and fertilizer are to be applied at the time of seedbed preparation.

**c. Permanent Seed Mixtures**

Planners should take into consideration the species makeup of the existing pasture and the landowner's future pasture management plans when recommending seed mixtures. Selection: From Tables IV 4a and b, Permanent Seeding Mixtures Suitable for Establishment in West Virginia.

**Notes:**

- All legumes must be planted with the proper inoculants prior to seeding.
- Lathco Flatpea is potentially poisonous to some livestock.
- Only endophyte free varieties of Tall Fescue should be used. Tall Fescue and Crownvetch are also very invasive species, non-native to WV.
- For unprepared seedbeds or seeding outside the optimum timeframes, add 50% more seed to the specified rate. Mixtures in Table 4b are more wildlife and farm friendly; those listed in bold are suitable for use in shaded woodland settings. Mixtures in italic are suitable for use in filter strips.

**d. Seeding for Wildlife Habitat**

Consider the use of the native plants or locally adapted plants when selecting cover types and species for wildlife habitat. Wildlife friendly species or mixes that have multiple values should be considered. See wildlife friendly species/mixtures in Table IV-4b. Consider selecting no or low maintenance long-lived plants adaptable to sites which may be difficult to maintain with equipment.

**Mulching**

**a. General Organic Mulches**

The application of straw, hay or other suitable materials to the soil surface to prevent erosion. Straw made from wheat or oats is the preferred mulch, the use of hay is permissible, but not encouraged due to the risk of spreading invasive species. Mulch must be applied to all temporary and permanent seeding on all disturbed areas. Depending on site conditions, in critical areas such as waterways or steep slopes, additional or substitute soil protective measures may be used if deemed necessary. Examples include jute mesh and soil stabilization blankets or erosion control matting.

Areas that have been temporarily or permanently seeded should be mulched immediately following seeding. Mulches conserve desirable soil properties, reduce soil moisture loss, prevent crusting and sealing of the soil surface and provide a suitable microclimate for seed germination.

Areas that cannot be seeded because of the season should be mulched to provide some protection to the soil surface. An organic mulch, straw or hay should be used and the area then seeded as soon as weather or seasonal conditions permit. Do not use fiber mulch (cellulose-hydroseed) alone for this practice; at normal application rates it will not give the soil protection of other types of mulch. Wood cellulose fiber mulch is used in hydroseeding operations and applied as part of the slurry. It creates the best seed-soil contact when applied over the top of (as a separate operation) newly seeded areas. Fiber mulch does not alone provide sufficient protection on highly erodible soils, or during less than favorable growing conditions. Fiber mulch should not be used alone during the dry summer months or when used for late fall mulch cover. Use straw mulch during these periods and fiber mulch may be used to tack (anchor) the straw mulch. Fiber mulch is well suited for steep slopes, critical areas and areas susceptible to wind.

**b. Chemical Mulches, Soil Binders and Tackifiers**

A wide range of synthetic spray on materials are marketed to stabilize and protect the soil surface. These are mixed with water and sprayed over the mulch and to the soil. They may be used alone in some cases as temporary stabilizers, or in conjunction with fiber mulch, straw or hay. When used alone most chemical mulches do not have the capability to insulate the soil or retain soil moisture that organic mulches have.

**c. Specifications**

From Table IV-6 select the type of mulch and rate of application that will best suit the conditions at the site.

**d. Anchoring**

Depending on the field situation, mulch may not stay in place because of wind action or rapid water runoff. In such cases, mulch is to be anchored mechanically or with mulch netting.

**1. Mechanical Anchoring**

Apply mulch and pull mulch anchoring tool over the mulch. When a disk is used set the disk straight and pull across slope. Mulch material should be tugged into the soil about three inches.

**2. Mulch netting**

Follow manufacturer's recommendation when positioning and stapling the mulch netting in the soil.

**Table IV-1  
Recommended Seeding Dates**

Planting Dates	Suitability
March 1 - April 15 and August 1 - October 1	Best Seeding Periods
April 15 - August 1	HIGH RISK - moisture stress likely
October 1 - December 1	HIGH RISK - freeze damage to young seedlings
December 1 - March 1	Good seeding period - Dormant seeding

**Table 2  
Acceptable Fertilization Recommendation**

Species	N (lbs/ac)	P2O5 (lbs/ac)	Example Rec. (per acre)
Cool Season Grass	40	80	400 lbs. 10-20-20
CS Grass & Legume	30	60	300 lbs. 10-20-20
Temporary Cover	40	40	200 lbs. 19-19-19

**Table 3  
Temporary Cover**

Species	Seeding Rate (lbs/acre)	Optimum Seeding Dates	Drainage	pH Range
Annual Ryegrass	40	3/1 - 6/15 or 8/15 - 9/15	Well - Poorly	5.5 - 7.5
Field Bromegrass	40	3/1 - 6/15 or 8/15 - 9/15	Well - Mod. Well	6.0 - 7.0
Spring Oats	96	3/1 - 6/15	Well - Poorly	5.5 - 7.0
Sundangrass	40	5/15 - 8/15	Well - Poorly	5.5 - 7.5
Winter Rye	168	8/15 - 10/15	Well - Poorly	5.5 - 7.5
Winter Wheat	180	6/15 - 11/15	Well - Mod. Well	5.5 - 7.0
Japanese Millet	30	6/15 - 8/15	Well	4.5 - 7.0
Redtop	5	3/1 - 6/15	Well	4.0 - 7.5
Annual Ryegrass	26	3/1 - 6/15	Well - Poorly	5.5 - 7.5
Spring Oats	64	3/1 - 6/15	Well - Poorly	5.5 - 7.5

NOTE: These rates should be increased by 50% if planted April 15 - August 1 and October 1 - March 1.

**Table 4a  
Permanent Seeding Mixture**

Species/Mixture	Seeding Rate (lbs/acre)	Soil Drainage preference	pH Range
Crownvetch / Tall Fescue	10 - 15	Well - Mod. Well	5.0 - 7.5
Crownvetch / Perennial Ryegrass	10 - 15	Well - Mod. Well	5.0 - 7.5
Flatpea or Perennial Pea / Tall Fescue	20	Well - Mod. Well	4.0 - 8.0
Ladino Clover / Serecia Lespedeza / Tall Fescue	30	Well - Mod. Well	4.5 - 7.5
Ladino Clover / Redtop	3	Well - Mod. Well	5.0 - 7.5
Crownvetch / Tall Fescue / Redtop	10	Well - Mod. Well	5.0 - 7.5
Tall Fescue / Birdsfoot Trefoil / Redtop	40	Well - Mod. Well	5.0 - 7.5
Serecia Lespedeza / Tall Fescue / Redtop	25	Well - Mod. Well	4.5 - 7.5
Redtop / Tall Fescue / Creeping Red	30	Well - Mod. Well	5.0 - 7.5
Tall Fescue / Perennial Ryegrass / Tall Fescue / Lathco Flatpea	50	Well - Poorly	4.5 - 7.5
	10	Well - Poorly	5.8 - 8.0
	15	Well - Poorly	5.8 - 8.0
	20	Well - Poorly	5.8 - 8.0

\*Lathco Flatpea is potentially poisonous to some livestock. All legumes should be planted with proper inoculants prior to seeding. For unprepared seedbeds or seeding outside the optimum timeframe, add 50% more seed to the specified rate.

Mixtures listed in bold are suitable for use in shaded woodland settings; those in italics are suitable for use in filter strips.

**Table 4b  
Wildlife and Farm-Friendly Seed Mixtures**

Species/Mixture	Seeding Rate (lbs/acre)	Soil Drainage preference	pH Range
KY Bluegrass / Redtop	20	Well - Mod. Well	5.5 - 7.5
Ladino Clover or Birdsfoot-Trefoil	2 / 10	Well - Mod. Well	5.5 - 7.5
Timothy / Alfalfa	5	Well - Mod. Well	6.5 - 8.0
Timothy / Birdsfoot-Trefoil	5	Well - Poorly	5.5 - 7.5
Orchardgrass / Ladino Clover / Redtop	10	Well - Mod. Well	5.5 - 7.5
Orchardgrass / Ladino Clover	2	Well - Mod. Well	5.5 - 7.5
Orchardgrass / Perennial Ryegrass	20	Well - Mod. Well	5.5 - 7.5
Creeping Red Fescue / Perennial Ryegrass	30	Well - Mod. Well	5.5 - 7.5
Orchardgrass or KY Bluegrass	20	Well - Mod. Well	6.0 - 7.5
Birdsfoot-Trefoil / Redtop / Orchardgrass	10	Well - Mod. Well	5.5 - 7.5
Lathco Flatpea / Perennial Ryegrass	30	Well - Mod. Well	5.5 - 7.5
Lathco Flatpea / Orchardgrass	20	Well - Mod. Well	5.5 - 7.5

\*Lathco Flatpea is potentially poisonous to some livestock. All legumes should be planted with proper inoculants prior to seeding. For unprepared seedbeds or seeding outside the optimum timeframe, add 50% more seed to the specified rate.

Mixtures listed in bold are suitable for use in shaded woodland settings; those in italics are suitable for use in filter strips.

**Table IV-5  
Lime and Fertilizer Application Table**

pH of Soil	Lime in Tons per Acre	Fertilizer, Lbs. per Acre (10-20-20 or Equivalent)
Above 6.0	2	500
5.0 to 6.0	3	500
Below 5.0	4	500

The pH can be determined with a portable pH testing kit or by sending the soil samples to a soil testing laboratory. When 4 tons of lime per acre are applied it must be incorporated into the soil by disking, backblading or tracking up and down the slope.

**Table IV-6  
Mulch Materials Rates and Uses**

Material	Minimum Rates per acre	Coverage	Remarks
Hay or Straw	2 to 3 Tons	Cover 75% to 90% of Surface	Subject to wind blowing or washing unless tied down
Wood Fiber	100 to 150 bales	Cover all Disturbed Areas	For hydroseeding
Pulp Fiber	1000 to 1500 lbs	Cover all Disturbed Areas	For hydroseeding
Wood - Cellulose			
Recirculated Paper			

Engineering Survey Environmental GIS

**NAVITUS ENGINEERING INC.**  
151 Windy Hill Lane  
Winchester, Virginia 22602  
Telephone: (888) 662-1155  
www.navituseng.com

REVISION

DATE

ANTERO RESOURCES CORPORATION  
THIS DOCUMENT WAS PREPARED FOR ANTERO RESOURCES CORPORATION

CONSTRUCTION DETAILS  
**NEW MILTON**  
COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA

REGISTERED PROFESSIONAL ENGINEER  
STATE OF WEST VIRGINIA  
07/16/2013

DATE: 07/16/2013  
SCALE: N/A  
SHEET 18 OF 20







# FIRM EXHIBIT



## LANDOWNER TABULATION

<b>A</b>	TM 8-39 COMSTOCK IRREVOCABLE TRUST & SILVESTRE IRREVOCABLE TRUST DB 261 PG 037 & DB 261 PG 034 68 ACRES 191 SADDLETREE DR. KALA POINT, PORT TOWNSEND, WA 98368	<b>F</b>	TM 8-17 DALE W. II & MELISSA KEPLINGER DB 236 PG 546 59.96 ACRES RR 1 BOX 191A ELLENBORO, WV 26346
<b>B</b>	TM 8-37 KATHRYN H. MARSHALL (MS 017 PG 722) CLINTON D. & KEVIN M. MEANS (DB 287 PG 272) MARVIN L. PHILLIPS (WB 033 PG 405) RUTH E. PHILLIPS (WB 038 PG 170) WILLIAM C. PHILLIPS (WB 033 PG 405) LAVERNE H. WILLIAMS (MS 017 PG 722) 147.86 ACRES RT 2 BOX 478 WEST UNION, WV 26456	<b>G</b>	TM 8-18 DALE W. II & MELISSA KEPLINGER DB 236 PG 546 14 ACRES RR 1 BOX 191A ELLENBORO, WV 26346
<b>C</b>	TM 8-37.2 LOUIS R. ENLOW DB 248 PG 066 0.58 ACRE 191 SADDLETREE DR. KALA POINT, PORT TOWNSEND, WA 98368	<b>H</b>	TM 8-19 CHARLES L. PEARCY II & ELIZABETH ANN SMITH WB 021 PG 187, 23 ACRES 516 KINNEY ST BRIDGEPORT, WV 26330
<b>D</b>	TM 8-15 ROBERT E. & EUNICE N. TAYLOR DB 260 PG 055 27.7 ACRES RT 1 BOX 90 NEW MILTON, WV 26411	<b>I</b>	TM 8-40 ROGER A., II & STACY L. McCLAIN DB 288 PG 303 118.66 ACRES RT 2 BOX 330 NEW MILTON, WV 26411
<b>E</b>	TM 8-16 ROBERT C. TAYLOR DB 245 PG 366 18 ACRES 7289 WV RT 18 S NEW MILTON, WV 26411	<b>J</b>	TM 8-41 NORMAN G. DEVOL AP 038 PG 340 86.549 ACRES 820 RACE STREET PARKERSBURG, WV 26101
		<b>K</b>	TM 8-41.5 JAMES CHARLES DB 272 PG 246 5.225 ACRES PO BOX 81 NEW MILTON, WV 26411

**FLOODPLAIN NOTE**  
THE PROPOSED SITE IS LOCATED WITHIN FEMA FLOOD ZONE "X" PER FEMA FLOOD MAPS #54017C0230C & #54017C0235C. THE PROPOSED SITE ENTRANCE IS LOCATED IN FEMA FLOOD ZONE "AE" PER FEMA FLOOD MAP #54017C0230C.

**NFIP** PANEL 0230C

**FIRM**  
FLOOD INSURANCE RATE MAP  
DODDRIDGE COUNTY,  
WEST VIRGINIA  
AND INCORPORATED AREAS

PANEL 230 OF 325  
(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

COMMUNITY	NUMBER	PANEL	SUFFIX
DODDRIDGE COUNTY	54024	0230	C

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

**MAP NUMBER**  
54017C0230C  
**MAP REVISED**  
OCTOBER 4, 2011

Federal Emergency Management Agency

**NFIP** PANEL 0235C

**FIRM**  
FLOOD INSURANCE RATE MAP  
DODDRIDGE COUNTY,  
WEST VIRGINIA  
AND INCORPORATED AREAS

PANEL 235 OF 325  
(SEE MAP INDEX FOR FIRM PANEL LAYOUT)


COMMUNITY	NUMBER	PANEL	SUFFIX
DODDRIDGE COUNTY	54024	0235	C

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

**MAP NUMBER**  
54017C0235C  
**MAP REVISED**  
OCTOBER 4, 2011

Federal Emergency Management Agency

Engineering  
Survey  
Environmental  
GIS



DATE	REVISION



FIRM EXHIBIT  
**NEW MILTON**  
COMPRESSOR STATION ACCESS ROAD  
NEW MILTON DISTRICT  
DODDRIDGE COUNTY, WEST VIRGINIA



DATE: 07/16/2013  
SCALE: 1" = 200'  
SHEET 20 OF 20