

Commercial/Industrial Floodplain Development Permit

Doddridge County, WV Floodplain Management

This permit has been issued to Dominion Transmission Inc., and is for the approved commercial and/or industrial development project associated with this permit that impacts the FEMA-designated floodplain and/or floodway of Doddridge County, WV, pursuant to the rules and regulations established by all applicable Federal, State and local laws and ordinances, including the Doddridge County Floodplain Ordinance. This permit must be posted at the site of work as to be clearly visible, and must remain posted during entirety of development.

Permit: #14-189

| Date Approved: 07/02/2014 | Expires: N/A |
|---|---------------------------|
| Issued to: Antero Resources | POC: Shaye Marshall |
| Company Address: | 303-357-6412 |
| Project Address: | |
| Firm: N/A | |
| Purpose of development: Pipeline. <u>Project do</u> | es not impact floodplain. |
| Issued by: Edwin L. "Bo" Wriston, Doddridge | County FPM (or designee) |
| | Date:07/01/2014 |



Antero Resources 1625 17th Street Denver, Colorado 80202 Office 303.357.7310 Fax 303.357.7315

March 28, 2014

Doddridge County Commission Doddridge County Floodplain Manager 118 East Court Street, Room 102 West Union, WV 26456

To whom it may concern:

Per the Doddridge County Ordinance, Antero Resources Corporation (Antero) would like to submit a floodplain determination for the Pearl Jean to Canton Pipeline which is **NOT** located in the floodplain. The proposed project consists of a buried 12-inch steel natural gas pipeline from the existing Canton Pipeline to the proposed Pearl Jean Well Pad. Per the FIRM Map 54017C0145C and the WV Flood Tool Map no part of the pipeline & access road for construction will cross a designated FEMA floodplain. Please find enclosed the following:

- Doddridge County Floodplain Permit Application
- FIRM Map
- WV Flood Tool Map
- Pearl Jean to Canton Pipeline Construction Plans

If you have any questions please feel free to contact me at (303) 357-6412.

Sincerely,

Shaye Marshall

Permit Representative
Antero Resources Corporation

Enclosures

BETH A. ROGERS
COUNTY CLERK
DODDRIDGE COUNTY, WY



Civil & Environmental Consultants, Inc.

Celebrating 25 Years

March 27, 2014

Ralph Sandora Doddridge County Clerk's Office 118 E. Court Street, Room 102 West Union, WV 26456

Mr. Sandora:

Subject:

Antero resources Corporation

Proposed Pearl Jean to Canton Pipeline Project Floodplain Development Permit Application

Doddridge County, West Virginia

CEC Project 132-985

Civil & Environmental Consultants, Inc. (CEC) is pleased to submit this letter in support of the floodplain development permit application for the above referenced project on behalf of Antero Resources Corporation. The proposed Project consists of the installation of a buried 12-inch steel natural gas pipeline. The purpose of the Project is to transport natural gas from the existing Canton Pipeline to the proposed Pearl Jean Well Pad. The project is located east of Smithburg in Doddridge County, West Virginia. The eastern section of the project begins at 39.285490°, -80.673715° North American Datum (NAD) 83, and its western end lies at 39.286097°, -80.681023° NAD83.

The proposed project is located on Flood Insurance Rate Map (FIRM) map number 54017C0145C, panel 145 of 325 with a map revised date of October 4, 2011. The proposed pipeline and associated access roads will not be located in a FEMA designated 100 year floodplain. The proposed pipelines will be installed utilizing open cut construction methods. The pipeline trenches will be excavated and backfilled to match the original ground contour.

CEC appreciates your time and effort in reviewing this floodplain development permit application. Please feel free to contact me at 304-933-3119 or via e-mail at <u>jlittler@cecinc.com</u> if you have questions or need additional information.

Respectfully submitted,

CIVIL & ENVIRONMENTAL CONSULTANTS, INC.

Jason Littler, P.S.

Project Manager

Greg Linder, P.E.

Project Manager

cc:

Shayelyn Marshall, Antero Resources Corporation Shauna Demattee, Antero Resources Corporation Patricia Kazimier, Antero Resources Corporation

#14-189

DODDRIDGE COUNTY FLOODPLAIN DEVELOPMENT PERMIT APPLICATION

| SECTION | 1: GENERAL PROVISIONS (APPLICANT TO READ AND SIGN) |
|----------|--|
| | AR SIGNATURE AND |
| 1. | No work may start until a permit is issued. |
| | The permit may be revoked if any false statements are made herein. |
| · 3. | If revoked, all work must cease until permit is re-issued. |
| 4. | Development shall not be used or occupied until a Certificate of Complete is sissued. |
| 5. | The permit will expire if no work is commenced within six months of issuance. |
| | Applicant is hereby informed that other permits may be required to fulfill local, state, and federal requirements. |
| 7. | Applicant hereby gives consent to the Floodplain Administrator/Manager or his/her representative to make inspections to verify compliance. |
| 8. | I, THE APPLICANT CERTIFY THAT ALL STATEMENTS HEREIN AND IN |
| | ATTACHMENTS TO THIS APPLICATION ARE, TO THE BEST OF MY |
| | KNOWLEDGE, TRUE AND ACCURATE. |
| | |
| | APPLICANT'S SIGNATURE |
| | DATE |
| SECTION | 2: PROPOSE DEVELOPMENT (TO BE COMPLETED BY APPLICANT). |
| IF. | THE APPLICANT IS NOT A NATURAL PERSON, THE NAME, ADDRESS, AND |
| TELEPHO | NE NUMBER OF A NATURAL PERSON WHO SHALL BE APPOINTED BY |
| THE APPI | LICANT TO RECEIVE NOTICE PURSUANT TO ANY PROVISION OF THE |
| | DODDRIDGE COUNTY FLOODPLAIN ORDINANCE. |
| | |
| APPLICAI | nt's name: <u>Landy Eldoerdanz</u> |
| ADDRESS | : 1625 17th Street, Denver, 🐠 80202 |

TELEPHONE NUMBER: Contact Shaye Marshall: 303-357-6412

| BUILDER'S NAME: Antero Resources Corporation |
|--|
| ADDRESS: 1625 17th Street, Denver, CO 80202 |
| TELEPHONE NUMBER: (303) 357-7310 |
| |
| ENGINEER'S NAME: Civil & Environmental Consultants, Inc |
| ADDRESS:99 Cambridge Place, Bridgeport, WV 26330 |
| TELEHONE NUMBER: 304-933-3119 |
| PROJECT LOCATION: |
| NAME OF SURFACE OWNER/OWNERS (IF NOT THE APPLICANT) Please See Exhibit A |
| ADDRESS OF SURFACE OWNER/OWNERS (IF NOT THE APPLICANT) Please See Exhibit A |
| DISTRICT: Grant |
| DATE/FROM WHOM PROPERTY |
| PURCHASED: N/A |
| LAND BOOK DESCRIPTION: |
| DEED BOOK REFERENCE: Please See Exhibit A TAX MAP REFERENCE: Please See Exhibit A |
| EXISTING BUILDINGS/USES OF PROPERTY: N/A |
| NAME OF AT LEAST ONE ADULT RESIDING IN EACH RESIDENCE LOCATED UPON THE SUBJECT PROPERTY N/A |
| ADDRESS OF AT LEAST ONE ADULT RESIDING IN EACH RESIDENCE LOCATED UPON THE SUBJECT PROPERTY_N/A |
| |

To avoid delay in processing the application, please provide enough information to easily identify the project location.

DESCRIPTION OF WORK (CHECK ALL APPLICABLE BOXES) A. STRUCTURAL DEVELOPMENT

ACTIVITY

STRUCTURAL TYPE

| X | New Structu | re | | | [] | Reside | ential (| (1 – 4 Family) | |
|----|---------------|---------|----------------|----------|----------|----------|----------|---------------------|------|
| [] | Addition | | | | Ö | | | (more than 4 Fam | ilvl |
| [] | Alteration | | | | Ö | | | ntial (floodproofin | |
| [] | Relocation | | | | 0 | | | Jse (res. & com.) | 6) |
| [] | Demolition | | | | 0 | Replac | | • | |
| [] | Manufactur | ed/Mo | bil Home | | u | | | •• | |
| В. | OTHER DEV | EOPLI | MENT ACTIV | /ITIES: | | | | | |
| [] | Fill | [] | Mining | () | Drilling | <u> </u> | X | Pipelining | |
| [] | Grading | | | | _ | • | | p | |
| [] | Excavation (| except | for STRUCTUR | RAL DEVE | LOPMENT | r check | ed ab | ove) | |
| [] | | | ation (includi | | | | | | |
| [] | | | ents (includir | | | | | ,, | |
| | Road, Street, | or Brid | dge Construct | ion | · | | | • | |
| [] | Subdivision (| includi | ng new expan | sion) | • | | | | ` |
| [] | Individual Wa | ater or | Sewer Systen | n | | | | | |
| [] | Other (please | | | | | | | | |
| | | | | | | | · | | |

C. STANDARD SITE PLAN OR SKETCH

- 1. SUBMIT ALL STANDARD SITE PLANS, IF ANY HAVE BEEN PREPARED.
- 2. IF STANDARD SITE PLANS HAVE NOT BEEN PREPARED:

 SKETCH ON A SEPARATE 8 ½ X 11 INCH SHEET OF PAPER THE SHAPE AND LOCATION OF THE LOT. SHOW THE LOCATION OF THE INTENDED CONSTRUCTION OR LAND USE INDICATING BUILDING SETBACKS, SIZE & HEIGHT. IDENTIFY EXISTING BUILDINGS, STRUCTURES OR LAND USES ON THE PROPERTY.
- 3. SIGN AND DATE THE SKETCH.

ACTUAL TOTAL CONSTRUCTION COSTS OF THE COMPLETE DEVELOPMENT IRRESPECTIVE OF WHETHER ALL OR ANY PART OF THE SUBJECT PROPOSED CONSTRUCTION PROJECT IS WITHIN THE FLOODPLAIN \$ N/A - Location is not within the floodplain

D. ADJACENT AND/OR AFFECTED LANDOWNERS:

1. NAME AND ADDRESS OF ALL OWNERS OF SURFACE TRACTS ADJACENT TO THE AREA OF THE SURFACE TRACT (UP & DOWN STREAM) UPON WHICH THE PROPOSED ACTIVITY WILL OCCUR AND ALL OTHER SURFACE OWNERS UP & DOWN STREAM) WHO OWN PROPERTY THAT MAY BE AFFECTED BY FLOODING AS IS DEMONSTRATED BY A FLOODPLAIN STUDY OR SURVEY (IF ONE HAS BEEN COMPLETED).

| ADDRESS:_immediate and common boundary up or down stream due to the location not being in floodplain | ADDRESS: |
|--|--|
| NAME: | NAME: |
| ADDRESS: | ADDRESS: |
| APPLICATION IS FILED AND THE NAME A | RTY AT THE TIME THE FLOODPLAIN PERMIT AND ADDRESS OF AT LEAST ONE ADULT ERTY THAT MAY BE AFFECTED BY FLOODING AS |
| NAME: | NAME: |
| ADDRESS: | ADDRESS: |
| | |

E. CONFIRMATION FORM

THE APPLICANT ACKNOWLEDGES, AGREES, AND CONFIRMS THAT HE/IT WILL PAY WITHIN 30 DAYS OF RECEIPT OF INVOICE BY THE COUNTY FOR ALL EXPENSES RELATIVE TO THE PERMIT APPLICATION PROCESS GREATER THAN THE REQUIRED DEPOSIT FOR EXPENSES INCLUDING:

- (A) PERSONAL SERVICE OF PROCESS BY THE DODDRIDGE COUNTY SHERIFF AT THE RATES PERMITTED BY LAW FOR SUCH SERVICE.
- (B) SERVICE BY CERTIFIED MAIL RETURN RECEIPT REQUESTED.
- (C) PUBLICATION.

EXHIBIT A

| Surface Owners | Deed Book/Pg # | Tax Map/Parcel | Ac. | Address |
|-----------------------|------------------------|-------------------------------|-------|----------------------------------|
| Dean R. and Martha A. | | Parcel ID: 3-16-21 (District | | 1203 East Run, West Union, WV |
| Pennington | Deed Book 275 Page 51 | 3/ Map 16 / Parcel 21) | 62.63 | 26456 |
| | | Parcel ID: 3-19-7 (District 3 | Ï | |
| Gloria J. Jett | Deed Book 237 Page 504 | / Map 19 / Parcel 7) | 70.43 | RR4 Box 697A, Fairmont WV, 26554 |

- (D) COURT REPORTING SERVICES AT ANY HEARINGS REQUESTED BY THE APPLICANT.
- (E) CONSULTANTS AND/OR HEARING EXPERTS UTILIZED BY DODDRIDGE COUNTY FLOODPLAIN ADMINISTRATOR/MANAGER OR FLOODPLAIN APPEALS BOARD FOR REVIEW OF MATERIALS AND/OR TESTIMONY REGARDING THE EFFICACY OF GRANTING OR DENYING THE APPLICANT'S FLOODPLAIN PERMIT.

| NAME (PRIN | T): <u>Landy</u> | Kluberdanz | , |
|------------------------------|---|---|--|
| SIGNATURE: | | | DATE:3/28/14 |
| After comple Administrato | ting SECTION 2, APPLICATE Tr/Manager or his/her re | ANT should submit form to epresentative for review. | Floodplain |
| SECTION 3: Administra | FLOODPLAIN DETER | RMINATION (to be con /her representative) | npleted by Floodplain |
| THE PROPO | SED DEVELOPMENT | Γ: | |
| THE PROPOS | ED DEVELOPMENT IS LO | CATED ON: | |
| FIRM Panel:_ | | | |
| Dated: | | | |
| Is <u>NO</u> | [located in a Specific FloopLA | ood Hazard Area (Notify ap | plicant that the application IS REQUIRED). |
| [] Is loca | ted in Special Flood Haz | zard Area. | |
| | |) | |
| | 100-Year flood elevation | on is: | NGVD (MSL) |
| [] Unava | | | |
| [] The pr | oposed development is Panel No | located in a floodway. | Dated |
| | | | |

See section 4 for additional instructions.

[]

SIGNED alphande

DATE 4-4-14

SECTION 4: ADDITIONAL INFORMATION REQUIRED (To be completed by Floodplain Administrator/Manager or his/her representative)

The applicant must submit the documents checked below before the application can be processed.

| | A plan showing the location of all existing structures, water bodies, adjacent roads, lot dimensions and proposed development. |
|-----|--|
| [I] | Development plans, drawn to scale, and specifications, including where applicable: details for anchoring structures, storage tanks, proposed elevation of lowest floor, (including basement or crawl space), types of water resistant materials used below the first floor, details of flood proffing of utilities located below the first floor and details of enclosures below the first floor. Also |
| () | Subdivision or other development plans (If the subdivision or development exceeds 50 lots or 5 acres, whichever is the lesser, the applicant must provide 100-year flood elevations if they are not otherwise available). |
| [] | Plans showing the extent of watercourse relocation and/or landform alterations. |
| [] | Top of new fill elevationFt. NGVD (MSL). For floodproofing structures applicant must attach certification from registered engineer or architect. |
| [] | Certification from a registered engineer that the proposed activity in a regulatory floodway will not result in any increase in the height of the 100-year flood. A copy of all data and calculations supporting this finding must also be submitted. |
| [] | Manufactured homes located in a floodplain area must have a West Virginia Contractor's License and a Manufactured Home Installation License as required by the Federal Emergency Management Agency (FEMA). |

| RINGS: PPRI | AST DETERMINATION | <u>.</u> | |
|---------------------------|--|--|-----------------------|
| Administra | MIT DETERMINATION (To be ator/Manager or his/her re | <u>ecompleted by Floodpla</u> presentative) | <u>in</u> |
| provisions of County on M | mined that the proposed activity f the Floodplain Ordinance adop lay 21, 2013. The permit is issue f this permit. | ed by the County Commissio | n of Dodo |
| SIGNED | | DATE | . : |
| with the pro | lain Administrator/Manager fou visions of the Doddridge County the applicant may complete an a | Floodplain Ordinance and/or | conforma denied ti |
| APPEALS: | Appealed to the County Comm | nission of Doddridge County? | [] Yes {} |
| | nearing Date. | | |

<u>SECTION 6: AS-BUILT ELEVATIONS (To be submitted by APPLICANT before Certificate of Compliance is issued).</u>

The following information must be provided for project structures. This section must be completed by a registered professional engineer or a licensed land surveyor (or attach a certification to this application).


COMPLETE 1 OR 2 BELOW:

| 1 | Actual (As-Built) Elevation of the top of the lowest floor (including basement or crawl space isFT. NGVD (MSL) |
|--------------|---|
| 2 | Actual (As Built) elevation of floodproofing isFT. NGVD (MSL) |
| Note: | : Any work performed prior to submittal of the above information is at risk of the cant. |
| SECT | ION 7: COMPLIANCE ACTION (To be completed by the Floodplain |
| <u>Adm</u> | inistrator/Manager or his/her representative). |
| as app | loodplain Administrator/Manager or his/her representative will complete this section plicable based on inspection of the project to ensure compliance with the Doddridge by Floodplain Ordinance. |
| IN: | SPECTIONS: |
| | DATE:BY: |
| co | DMMENTS |
| | |
| | |
| | |
| | |
| SECTI | ON 8: CERTIFICATE OF COMPLIANCE (To be completed by Floodplain |
| <u>Admiı</u> | nistrator/Manager or his/her representative). |
| Certific | cate of Compliance issued: DATE: BY: |

CERTIFICATE OF COMPLIANCE FOR DEVELOPMENT IN SPECIAL FLOOD HAZARD AREA (OWNER MUST RETAIN)

| PERMI PERMI | T NUMBER: |
|---|--|
| PURPOSE – | |
| CONSTRUCTION LOCATION: | |
| | |
| OWNER'S ADDRESS: | |
| | |
| | · |
| | |
| | |
| THE FOLLOWING MUST BE COM ADMINISTRATOR/MANAGER OR | PLETED BY THE FLOODPLAIN HIS/HER AGENT. |
| COMPLIANCE IS HEREBY C | ERTIFIED WITH THE REQUIREMENT OF THE |
| FLOODPLAIN ORDINANCE ADOP DODDRIDGE COUNTY ON MAY 2 | TED BY THE COUNTY COMMISSION OF |
| SIGNED | DATE |

WV Flood Map



Map Created on 1/31/2014



Location of the mouse click



Flood Hazard Zone (1% annual chance floodplain)

User Notes:

Pearl Jean To Canton Pipeline

Disclaimer:

The online map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. To obtain more detailed information in areas where Base Flood Elevations have been determined, users are encouraged to consult the latest Flood Profile data contained in the official flood insurance study. These studies are available online at www.msc.fema.gov.

WV Flood Tool is supported by FEMA, WV NFIP Office, and WV GIS Technical Center (http://www.MapWV.gov/flood)

Flood Hazard Area: Selected site is NOT WITHIN any identified flood hazard area. Unmapped flood

hazard areas may be and the


Elevation: About 946 feet

Location (long, lat): 80.675895 W, 39.285214 N **Location (UTM 17N):** (527952, 4348478) **FEMA Issued Flood Map:** 54017C0145C

Contacts: Doddridge County

CRS Information: No CRS information available

Parcel Number:



DODDRIDGE COUNTY ROAD MAP

SCALE IN FEET

0 1/2 MILES 1 MILES 1 INCH = 1/2 MILE

PROJECT OWNER/APPLICANT **ANTERO RESOURCES**

CORPORATION **1625 17TH STREET DENVER, CO 80202**

PH: (303) 357-6827 CONTACT: JEREMY GRAMLING **CIVIL ENGINEER**

CIVIL & ENVIRONMENTAL CONSULTANTS, INC.

99 CAMBRIDGE PLACE BRIDGEPORT, WV. 26330 PH: (304) 933-3119

FAX: (304) 933-3327 CONTACTS: GREG LINDER, P.E.



MISS UTILITY OF WEST VIRGINIA 1-800-245-4848 IT'S THE LAW

MISS UTILITY OF WEST VIRGINIA ONE CALL WAS PERFORMED IN JANUARY, 2014

THE FOLLOWING UTILITY COMPANIES MAY BE PRESENT IN THE PROJECT AREA:

- FRONTIER COMMUNICATIONS (FORMERLY VERIZON)
 ANTERO RESOURCES APPALACHIAN CORP
 DOMINION HOPE
 MARKWEST LIBERTY MIDSTREAM & RESOURCES LLC
 FIRSTENERGY COPP
 DOMINION TRANSMISSION CORPORATION
- SUMMIT MIDSTREAM



REFERENCES:

- EXISTING CONTOURS ARE DERIVED FROM THE WEST VIRGINIA GIS DIGITAL ELEVATION MODELS (USGS 3-METER) DATED 2003 (ftp://ftp.wrgis.wvu.edu/pub/Clearinghouse/Elevation/3MeterDEM_SAMB_2003_utm83/); ACCESSED 8-08-02-031 AND FROM BLUE MOUNTAIN AERIAL MAPPING 2-FOOT CONTOUR INTERVALS, DATED 03-22-2012 (www.bluemountainaerialmapping.com);.
- AERIAL PHOTOGRAPHY IS A SCREEN CAPTURE FROM GOOGLE EARTH PRO EXTRACTED ON 01-21-2014, IMAGERY DATE 2013.
- THIS IS NOT A BOUNDARY SURVEY. BOUNDARY LINES AS SHOWN HEREON ARE BASED ON TAX PARCEL INFORMATION DERIVED FROM G.I.S.
- BY GRAPHIC PLOTTING ONLY, THIS PIPELINE IS NOT LOCATED IN A FLOODPLAIN ACCORDING TO THE FLOOD INSURANCE RATE MAP FOR DODDRIDGE COUNTY, MAP #54017C014SC, WITH A MAP EFFECTIVE DATE OF OCTOBER 04, 2011.
- USGS 7.5 MIN. TOPOGRAPHIC QUADRANGLE SMITHBURG, WV, DATED 1981; PHOTOREVISED 1976.
- WETLAND AND STREAM DELINEATION WAS BASED ON SURVEYS CONDUCTED BY CEC ON JANUARY 14, 2014. WETLAND AND STREAM DATA WAS COLLECTED BY MAPPING GRADE G.P.S..




Civil & Environmental Consultants, Inc.


99 Cambridge Place - Bridgeport, WV 26330 Ph: 304.933.3119 Fax: 304.933.3327 www.cecinc.com

LINE TABULATION HORIZONTAL SLOPE DIAMETER LENGTH LENGTH GAS PEARL JEAN TO CANTON HORIZONTAL SHEET 2 2,660' 2,785' 12" 2,660* 2,785 12*

PEARL JEAN TO CANTON GASLINE **GRANT DISTRICT DODDRIDGE COUNTY WEST VIRGINIA**

LAT./LONG: N 39° 17' 01.43" W80° 40' 39.15" (APPROXIMATE CENTER OF PROJECT)









LOCATION MAP

SMITHBURG USGS 7.5' QUAD SCALE IN FEET 2000 1 INCH = 2000 FEET



PLAN REPRODUCTION WARNING

THE PLANS HAVE BEEN CREATED ON ANSI D (22" X 34") SHEETS. FOR REDUCTIONS, REFER TO GRAPHIC SCALE.

THE PLANS HAVE BEEN CREATED FOR FULL COLOR PLOTTING.
ANY SET OF THE PLANS THAT IS NOT PLOTTED IN FULL COLOR
SHALL NOT BE CONSIDERED ADEQUATE FOR CONSTRUCTION
PURPOSES.

WARNING: INFORMATION MAY BE LOST IN COPYING AND/OF GRAY SCALE PLOTTING

| RECEIVING W | ATERS |
|-----------------------|---------------|
| AQUATIC RESOURCE NAME | WATERSHED |
| UNT-1 | BUCKEYE CREEK |
| UNT-2 | BUCKEYE CREEK |

| SHEET INDEX | | |
|--------------|---|--|
| SHEET 1 OF 7 | COVER SHEET | |
| SHEET 2 OF 7 | ALIGNMENT SHEETS STATION 0+00 TO 26+59,79 | |
| SHEET 3 OF 7 | STREAM CROSSING DETAILS | |
| SHEET 4 OF 7 | STREAM AND WETLAND LOCATION MAP | |
| SHEET 5 OF 7 | EROSION & SEDIMENTATION CONTROL NOTES | |
| SHEET 6 TO 7 | FROSION & SEDIMENTATION CONTROL DETAILS | |

LIMITS OF CONSTRUCTION AND LIMITS OF DISTURBANCE - 5.60 AC COVER SHEET


| SUMMARY OF MATERIALS | | | "NOTE TO CONTRACTOR" THE CONTRACTOR SHALL REFER TO ALL PLANS WITHIN |
|----------------------|------------------------------------|-----------|---|
| | DESCRIPTION | QUANTITY | THIS CONSTRUCTION SET. IT IS NOT THE ENGINEER'S |
| | 12,750" O.D. X 52 X 0,375 W.T. FBE | 2,785 LF | INTENT THAT ANY SINGLE PLAN SHEET IN THIS SET OF DOCUMENTS FULLY DEPICT ALL WORK ASSOCIATED |
| Ī | 12" FILTER SOCK | 667 LF | WITH THE PROJECT. |
| | 18" FILTER SOCK | 1,500 LF | |
| | 24" FILTER SOCK | 269LF | THE CONTRACTOR SHALL FIELD VERIFY ALL UTILITIES. THE CONTRACTOR IS REQUIRED TO CONTACT WEST |
| _ | 32" FILTER SOCK | 415 LF | VIRGINIA ONE CALL SYSTEM PRIOR TO PERFORMING |
| | WATERBARS | 27 EA | ANY EXCAVATION. |
| | TRENCH PLUGS | 12 EA | CIVIL & ENVIRONMENTAL CONSULTANTS, INC. DOES |
| _ | EROSION CONTROL BLANKET | 20,725 SY | NOT GUARANTEE THAT THIS SURVEY OR MAP DEPICTS |
| | STABILIZED CONSTRUCTION ENTRANCE | 1 EA | COMPLETE OR CONCLUSIVE SUBSURFACE |
| | | | |

| SEAL | REVISION RECORD | | | |
|----------------|-----------------|---------------|-------------------------|--|
| | NO. | DATE | DESCRIPTION | |
| والمناوا | 1 | 3 / 25 / 2014 | ISSUED FOR CONSTRUCTION | |
| CONTO | | | | |
| COSTE C. | | | | |
| i Stand, Saute | | | | |
| S . | | | | |
| | - | | | |
| | | | | |
| THE THE | <u> </u> | | | |

Antero

PEARL JEAN TO CANTON GASLINE

3/25/2014 PROJECT NO: 132-965 SHEET 1 OF 7




- ETEMENCES:

 EXISTING CONTOURS ARE DERIVED FROM THE WEST VIRGINIA GIS DIGITAL ELEVATION MODELS (USGS 3-METER) DATED 2003

 (ttp://ttp.wrgis.wvu.edu/pub/clearing/bosse/Elevation/3Meter/DEM_SAMB_2003_utm83/);
 AND FROM BILDE MOUNTAIN AERICAL MAPPING 2-FOOT CONTOUR INTERVALS, DATED 03-22-2012 (www.bluemountainaerialmapping.com);.
- AERIAL PHOTOGRAPHY IS A SCREEN CAPTURE FROM GOOGLE EARTH PRO EXTRACTED ON 01-21-2014, IMAGERY DATE 2013.
- THIS IS NOT A BOUNDARY SURVEY, BOUNDARY LINES AS SHOWN HEREON ARE BASED ON TAX PARCEL INFORMATION DERIVED FROM G.I.S.
- BY GRAPHIC PLOTTING ONLY, THIS PIPELINE IS NOT LOCATED IN A FLOODPLAIN ACCORDING TO THE FLOOD INSURANCE RATE MAP FOR DODDRIDGE COUNTY, MAP #54017C014SC, WITH A MAP EFFECTIVE DATE OF OCTOBER 04, 2011.
- USGS 7.5 MIN, TOPOGRAPHIC QUADRANGLE SMITHBURG, WV, DATED 1961; PHOTOREVISED 1976.
- WETLAND AND STREAM DELINEATION WAS BASED ON SURVEYS CONDUCTED BY CEC ON JANUARY 14, 2014. WETLAND AND STREAM DATA WAS COLLECTED BY MAPPING GRADE G.P.S..

KEY NOTES

- 1 FURNISH AND INSTALL EROSION SEDIMENT CONTROL BLANKET PER DETAIL 1 AND 2 ON SHEET 6 (TYPICAL)
- ② FURNISH AND INSTALL TRENCH PLUG PER DETAIL 3 ON SHEET 6 (TYPICAL).
- (3) FURNISH AND INSTALL WATERBAR PER DETAIL 7 ON SHEET 7 (TYPICAL).
- 4 FURNISH AND INSTALL FILTER SOCK PER DETAIL 4 ON
- SHEET 6 (TYPICAL).
- (5) FURNISH AND INSTALL STABILIZED CONSTRUCTION ENTRANCE PER DETAIL 6 ON SHEET 6.



DETAIL A - UNT-1 (INT) AND UNT-2 (INT) STREAM CROSSING

UNT-1 AND UNT-2

- INSTALL WATERBARS AT APPROACH TO STREAM CROSSING AS SHOWN. INSTALL COMPOST FILTER SOCK AT OUTLET OF WATERBARS.
- REFER TO DETAIL 9 OR 10 ON SHEET 7 FOR PLAN VIEW OF FLUME PIPE DIVERSION OR PUMP AROUND.
- 3. INSTALL FLUME PIPE ON EXISTING STREAMBED IMMEDIATELY PRIOR TO UTILITY LINE INSTALLATION, FLUME PIPE SHALL ONLY REMAIN IN PLACE DURING THE UTILITY LINE INSTALLATION TIME PERIOD. THE UTILITY LINE INSTALLATION TIME PERIOD IS 24-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH OR LESS AND 44-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH OR LESS AND 44-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH OR LESS AND 45-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH UNLESS AND 45-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH UNLESS AND 45-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH UNLESS AND 45-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH UNLESS AND 45-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH UNLESS AND 45-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH UNLESS AND 45-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH UNLESS AND 45-HOURS FOR A STREAM WITH A 10-100' BOTTOM WIDTH A 10-100' BOTTOM WITH A 10-100' BOTT
- INSTALL WATERBARS AT APPROACH TO STREAM CROSSING AND FILTER SOCK ALONG STREAM BANKS. INSTALL COMPOST FILTER SOCK AT OUTLET OF WATERBARS.
- . INSTALL A ROCK PAD APPROACH 10' PRIOR TO THE TIMBER MATS (REFER TO DETAIL 7 ON SHEET 7).
- APPROACHES TO CROSSINGS ARE NOT TO EXCEED A DEPTH OF 6-INCHES ABOVE ORIGINAL GRADE.
- MOBILE BRIDGE IS TO EXTEND FROM TOP OF BANK TO TOP OF BANK OF THE STREAM. CONTRACTOR SHALL NOT PLACE FILL UNDER THE MOBILE BRIDGE. FLUME PIPE SHALL NOT SUPPORT MOBILE BRIDGE.
- CONTRACTOR MAY SUPPLEMENT FLUME PIPE SHOWN WITH ADDITIONAL FLUME PIPES OR PUMPS TO ACCOMMODATE STREAM FLOW DURING CONSTRUCTION.
- 9. DEWATERING ZONE IS TO BE PUMPED OUT USING A PUMP AND FILTER BAG.
- GEOTEXTILE SHALL BE ATTACHED TO THE UNDERSIDE OF THE TIMBER MAT BRIDGE.

NORTH " THIS PLAN HAS BEEN CREATED ON AN ANSI D (22"X34") SHEET, FOR REDUCTIONS, REFER TO GRAPHIC SCALE."

REVISION RECORD SEAL
 NO.
 DATE
 DESCRIPTION

 1
 3/25/2014
 ISSUED FOR CONSTRUCTION

Antero

PEARL JEAN TO CANTON GASLINE

STREAM AND WETLAND CROSSING DETAILS

12" GASLINE GRANT DISTRICT, DODDRIDGE COUNTY, WV


3/25/2014 PROJECT NO: 132-965

Civil & Environmental Consultants, Inc. 99 Cambridge Place - Bridgeport, WV 26330 Ph: 304.933.3119 · Fax: 304.933.3327

www.cecinc.com

TEL.

SHEET 3 OF 7



Civil & Environmental Consultants, Inc.
99 Cambridge Place - Bridgeport, WV 26330
Ph: 304.933.3119 - Fax: 304.933.3327
www.cecinc.com

| ST | REAM AND WETLAND IMPACTS | 5 |
|----------------|--------------------------|---------|
| STREAM/WETLAND | CLASSIFICATION | STATION |
| UNT-1 | INTERMITTENT | 19+37 |
| UNT-2 | INTERMITTENT | 19+79 |



| SEAL | | RE | VISION RECORD |
|-------------|-----|-----------------------|-------------------------------------|
| | NO. | DATE 3 / 25 / 2014 | DESCRIPTION ISSUED FOR CONSTRUCTION |
| S SOUSTEN 2 | | | |
| 10 Table | - | | |
| 124.72 | | | |
| The Park | | | |

Antero

PEARL JEAN TO CANTON GASLINE

12" GASLINE GRANT DISTRICT, DODDRIDGE COUNTY, WV 3/25/2014 PROJECT NO: 132-985

SHEET 4 OF 7

2. ALL CONTRACTORS/SUBCONTRACTORS PERFORMING WORK ON THIS PROJECT SHALL 2. ALL CONTRACTORS/SUBCONTRACTORS PERFORMING WORK ON THIS PROJECT SHALL
FAMILLARIZE THEMSELVES WITH THE SITE AND SHALL BE SOLELY RESPONSIBLE FOR ANY DAMAGE
TO EXISTING FACILITIES RESULTING DIRECTLY OR INDIRECTLY FROM THEIR OPERATIONS. SAID
EXISTING IMPROVEMENTS SHALL INCLUDE BUT NOT BE LIMITED TO BERMS, DITCHES, FENCES AND
PLANTS. ANY REMOVAL OR DAMAGE TO EXISTING IMPROVEMENTS SHALL BE REPLACED OR
REPAIRED BY THE CONTRACTORS AT THEIR EXPENSE AND SHALL BE APPROVED BY THE

3. ALL CONSTRUCTION SHALL MEET OR EXCEED ALL REQUIREMENTS OF THE "PERMITTING ENTITY" AND WYDOT WYDNR & WYDEP

4. ALL TESTING SHALL BE DONE BY AN APPROVED LABORATORY AT THE EXPENSE OF THE

5. PRIOR TO CONSTRUCTION, ALL CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH THE CONTRACT DOCUMENTS AND SPECIFICATIONS, THE PLANS INCLUDING ALL NOTES. THE CONDITIONS OF ALL PERMITS AND ANY OTHER APPLICABLE STANDARDS OR SPECIFICATIONS RELEVANT TO THE PROPER COMPLETION OF THE WORK SPECIFIED. FAILURE ON THE PART OF THE CONTRACTOR TO FAMILLARIZE HIMSELF WITH ALL STANDARDS OR SPECIFICATIONS PERTAINING TO THIS WORK SHALL IN NO WAY RELIEVE THE CONTRACTOR OF RESPONSIBILITY FOR PERFORMING THE WORK IN ACCORDANCE WITH ALL SUCH APPLICABLE STANDARDS AND SPECIFICATIONS

6, CONTRACTORS SHALL HAVE IN THEIR POSSESSION, PRIOR TO CONSTRUCTION, ALL NECESSARY PERMITS, LICENSES, BONDS, INSURANCE, ETC. CONTRACTORS SHALL EACH HAVE AT LEAST ONE SET OF APPROVED ENGINEERING PLANS AND SPECIFICATIONS, SWPPP, AND GPP ON-SITE AT ALL

7. CONTRACTORS MUST CONFINE THEIR ACTIVITIES TO THE WORK AREA. NO ENCROACHMENT ONTO DEVELOPED AREAS WILL BE ALLOWED. ANY DAMAGE RESULTING THEREFROM SHALL BE THE

8. IT WILL BE THE RESPONSIBILITY OF EACH CONTRACTOR TO PROTECT ALL EXISTING PUBLIC AND PRIVATE UTILITIES THROUGHOUT THE CONSTRUCTION OF THIS PROJECT. CONTRACTORS SHALL CALL WEST VIRGINIA UTILITIES PROTECTION SERVICE AT 1-800-245-4848 OR 811 AND CONTACT THE APPROPRIATE UTILITY COMPANIES OR LINE LOCATIONS AT LEAST 2 WORKING DAYS (48 HOURS) PRIOR TO CONSTRUCTION AND SHALL ASSUME FULL LIABILITY TO THOSE COMPANIES FOR ANY DAMAGES CAUSED TO THEIR FACILITIES.

9. TRENCHES WHICH LIE OUTSIDE EXISTING OR FUTURE PAVEMENTS SHALL BE BACK-FILLED ABOVE THE TOP OF THE EMBEDMENT AND COMPACTED TO 95% PROCTOR DENSITY

10. TOP OF NATURAL GAS PIPELINE SHALL BE A MINIMUM OF 3'-0" BELOW THE FINISHED GROUND ELEVATION EXCEPT IN AGRICULTURAL FIELDS IN WHICH THE DEPTH SHALL BE 4'-0".

11. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH STANDARD ANTERO RESOURCES CORPORATION TRENCH SAFETY GUIDELINES AND SHALL BE IN ACCORDANCE WITH THE U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY AND

12. THIS IS NOT A BOUNDARY SURVEY. BOUNDARY LINES AS SHOWN HEREON ARE BASED ON TAX PARCEL INFORMATION DERIVED FROM THE WEST VIRGINIA DEPARTMENT OF REVENUE, DATED 2008.

13, CONTRACTOR IS RESPONSIBLE FOR NOTIFICATION TO THE PROJECT DESIGN ENGINEER FOR ANY DEVIATION FOUND RELATIVE TO PROJECT.

14. EXISTING EASEMENTS AND/OR RIGHT-OF-WAYS WERE NOT ADDRESSED DURING THIS SURVEY,

15. FENCE LINES ENCOUNTERED DURING CONSTRUCTION SHOULD BE RELOCATED AND REPLACED PER THE GUIDANCE OF THE LANDOWNER AND THE ANTERO RESOURCES CORPORATION REPRESENTATIVE. CONTRACTOR SHALL SURVEY THE LOCATION OF ALL EXISTING FENCES PRIOR TO REMOVAL AND RECONSTRUCT AFTER CONSTRUCTION IS COMPLETE.

16. CONTRACTOR IS TO VERIFY HEIGHT OF OVERHEAD POWER LINE PRIOR TO CONSTRUCTION.

17. CONTRACTOR IS TO INSTALL TEMPORARY DIVERSION DITCHES WITH STABILIZED OUTLETS IN ACCORDANCE WITH THE PLANS AND THE OWNER'S CONSTRUCTION SPECIALIST OR THE CHIEF INSPECTOR IN ACCORDANCE WITH WY DEP EROSION AND SEDIMENT CONTROL BMP MANUAL.

PRODUCT TRANSPORTED: NATURAL GAS

EROSION CONTROL NOTES:

1. ADEQUATE MEASURES SHALL BE TAKEN TO PREVENT EROSION. IN THE EVENT THAT EROSION OCCURS AS A RESULT OF CONSTRUCTION, THE CONTRACTOR SHALL RESTORE THE ERODED AREA TO ITS ORIGINAL CONDITION PRIOR TO MULCHING.

2. ALL CONSTRUCTION, EROSION CONTROL MEASURES, AND STORM WATER DISCHARGES FROM THE SITE. ALTIME CONSTRUCTION, EROSION CONTROL MEASURES, AND STORM WATER DISCHARGES FROM THE SITE SHALL ADHERE TO THE CONDITIONS OF THE WEST VIRGINIA OIL AND GAS CONSTRUCTION STORMWATER GENERAL PERMIT.

WATER QUALITY
THE CONTRACTOR WILL BE RESPONSIBLE FOR WATER QUALITY THROUGHOUT THE OPERATION OF CONSTRUCTION. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE FOLLOWING:

IMPLEMENTING THE EROSION CONTROL PLAN.

DIRECTING THE CONSTRUCTION OPERATING AND DISMANTLING OF TEMPORARY FROSION CONTROL FEATURES

IMPLEMENTING REMEDIAL ACTION REQUIRED TO REPAIR FAILING EROSION AND SEDIMENTATION CONTROL FEATURES.

IMPLEMENTING STORM AND WINTER SHUTDOWN PROCEDURES AS REQUIRED. THE CONTRACTOR WILL SHAPE EARTHWORK PRIOR TO THE SUSPENSION OF GRADING OPERATIONS EACH DAY IN A MANNER THAT WILL PERMIT STORM RUNOFF WITH A MINIMUM AMOUNT OF EROSION.

EROSION CONTROL FEATURES INSTALLED BY THE CONTRACTOR WILL BE

OPERATED AND MAINTAINED IN AN ACCEPTABLE CONDITION.
WHEN ANY EROSION OR SEDIMENT CONTROL FEATURE HAS REACHED HALF
OF IT'S CAPACITY, THE DEVICE IS TO BE CLEANED OUT AND RESTORED

CONTACTOR IS ADVISED TO CLOSELY EXAMINE THE WATERBAR DETAILS TO ENSURE THAT A SUPER SILT FENCE BARRIER IS PLACED AROUND THE OUTLET OF EACH WATERBAR

Civil & Environmental Consultants, Inc.

99 Cambridge Place - Bridgeport, WV 26330 Ph: 304.933.3119 · Fax: 304.933.3327 www.cecinc.com

CONSTRUCTION NOTES:

1. DATUM BASED ON WEST VIRGINIA STATE PLANE COORDINATES SYSTEM, NAD 83 NORTH ZONE,

2 PRIOR TO CONSTRUCTION AND CALL WEST VIRGINIA 1071 ITIES PROTECTION SERVICE AT 1-800-245-4848 OR 811 AND ALL OTHER UTILITY COMPANIES AT LEAST 2 WORKING DAYS (48 HOURS) PRIOR TO

3 ALL EXCAVATION AND EARTH MOVING ACTIVITIES INCLUDING BUT NOT LIMITED TO OPEN 3. ALL EXCAVATION AND EART IN MOVING A CITYTHES INCLUDING BUT NOT LIMITED TO OPEN EXCAVATIONS, OVERBURDEN AND BACKFILL REQUIREMENTS, FINAL CUT AND FILL SLOPES AND BENCHING REQUIREMENTS WILL BE IN SUBSTANTIAL CONFORMANCE CONSTRUCTION STANDARDS. EXCAVATION - EXCAVATION WILL NOT BE CLASSIFIED AND WILL INCLUDE ALL MATERIALS ENCOUNTERED, REGARDLESS OF NATURE.

GENERAL CONSTRUCTION SEQUENCE
Prior to beginning land disturbing activities, clearly mark all clearing limits, sensitive areas and their buffers, and trees that are to be preserved within the construction area. These shall be clearly marked, both in the field and on the plans, to prevent damage and offsite impacts.

- 2. Install stone construction entrances at all locations where temporary access roads will be accessing a paved
- 3. Install temporary E&S controls (silt fence. ROW diversions, etc.) Prior to any excavation work to ensure, to the maximum extent practicable, that no significant erosion or sedimentation of
- ROW diversions and/or other erosion and sediment control devices will be installed as needed. If clearing and grubbing is required, see below regarding the management and disposal of debris
- 5. After access to and along the proposed utility line has been provided, together with the E&S controls, the general clearing and grubbing of the trees and brush along the ROW for pipe trenching may commence to the width specified in the E&SC Plans. Trees shall be windrowed on low side of right-of-way. All pollutants, including waste materials and demolition debris, that occur on-site during construction shall be handled and disposed of in a manner that does not cause contamination of surface waters. Woody debris may be chopped and spread on-site. If burning is chosen method for disposal of woody debris, check local ordinance and tentilations for requirements and others have necessariant. nutations for requirements and obtain any necessary permits
- 6. Minor grading within the ROW will be conducted where necessary to provide an even surface for safe and at operation of construction equipment. Grading will be the minimum amount necessary and BMPs will be installed promptly. Tree stumps, and large rocks and boulders will also be removed for safety at this time.
- 7. Excavate pineline trench. Pipeline trench shall be excavated to a width of approximately 5' and a minimum cover of 3' shall be provided above pipeline at all locations except for wetlands and streams. A minimum cover of 5' shall be provided along pipeline at wetland and stream crossings.
- The proposed construction ROW will be used as a work area for trench excavation, equipment movement, and the storage of soil stockpiles, as needed. Equipment soil stockpiles, and other materials area to remain
- Segregation of topsoil and subsoil will be performed where trench excavation takes place in an agricultural, wetland, or residential area.
- Temporary E&S controls for stream crossings shall be installed at locations shown on the E&SC Plans and associated detail sheets located in Appendix E.
- Stream and river pipeline crossing construction methods will be installed at locations shown on the E&SC Plan sheets and as specified on the detail sheets. Waterbodies will be crossed with temporary bridges, such as er mats or approved equal crossings, prior to crossing the conveyance, if flowing water is present at the of the construction of that waterbody, Streambank stabilization will be performed immediately following
- 12. Wetland crossing widths for utility crossings will be kept to a minimum and will be stabilized by placing timber mats, riprap, or pre-fabricated swamp mats, as shown on the detail sheets. No wetland impacts or disturbances are associated with the 12-lanch Pearl Jean to Canton Pipeline Project. All materials used to stabilize access roads in wetland areas will be removed from the wetland upon completion of the pipeline
- 13. Pipeline sections will be transported to the work area and strung along the working side of the ROW parallel to repenies sections will be transported to the wint state and study along acting the wonting sace of the recover parametric the trench line. The pipeline will be bent to conform to the trench contour, aligned, welded, sealed and placed on temporary supports elongside the trench. Welds will be visually and radio-graphically inspected and repaired as necessary. The pipe section will be lowered into the trench and placed on padding material laid on the trench bottom to protect the pipe coating. Any wetness encountered during construction work will be dewatered by using pumps, hoses, and dewatering bags, and will be discharged to a well-vegetated upland
- 14. Install trench breakers (plugs) at locations as shown on the E&SC Plan sheets and as specified on the detail
- backfill material will be slightly crowned in upland areas to allow for settlement that may occur. Crowning the soil sightly over the pipeline will help prevent future stormwater-related problems from settling of the backfilled area. No crowning of the soils will take place in wetlands, streams, or floodplains, disturbed areas will be restored to their original topographic contours.
- 16. Exposed and unworked soils shall be stabilized by application of effective BMPs that protect the soil from erosive forces of raindrops, flowing water and wind. All disturbed areas that are at final grade must be seeded and mutched within seven days and areas that will not be worked again for 21 days or more must be seeded and mutched within seven days. For disturbed areas with slopes of 3:1 or greater, the area will be vertically tracked and erosion control fabric shall be installed after seed, mulch, and soil supplements have been applied. The temporary/permanent seeding and mulch tables, on the detail sheets, consist of the type of seed and application rate that shall be applied, including the nurse crop that shall be used during certain time of the year to promote stabilization of the soil until the perennial seedlings establish.
- 17. In the unlikely event that there are excess excavated materials remaining after the trench has been backfilled, the material will be disposed of within the existing ROW in an upland area. Material will be spread in a thin layer and tied into existing contours to create positive drainage for stormwater runoff
- any storm event greater than 0.5-inch per 24-hour period until there is a uniform, perennial 70 percent vegetative coverage established. Temporary BMPs will be removed upon achieving vegetative stabilization ement refers to the total area vegetated and not a percent of the
- 19. No sediment tracking on the roadway is allowed. In the event that sediment is inadvertently tracked onto the no sediment according of the troatedy's advector in the event units sediment is according to the control of conditions of the condition of the

CONSTRUCTION NOTES:

GENERAL CONSTRUCTION SEQUENCE CONTINUED

- Construction access restoration shall be equal or better than the pre-construction condition and grades that
 were altered during construction activities shall be restored to original grades and match existing drainage
- Applicable practices include, but are not limited to, temporary and permanent seeding, sodding, mulching, erosion control (abrics and matting, soil application of polyacrytamide (PAM), the early application of gravel base on areas to be paved, and dust control.
- 22. Selected soil stabilization measures shall be appropriate for the time of year, site conditions, and estimated
- 23. Soil stockpiles must be stabilized and protected with sediment trapping measures
- 24. Linear construction activities such as ROW and easement clearing, roadway development, pipelines, and trenching for utilities, shall be conducted to meet the soil stabilization timeframe requirements, Contractors shall install the bedding materials, roadbeds, structures, pipelines, or utilities and re-stabilize the disturbed
- 25. Excavated material shall be placed on the uphill side of trenches, consistent with safety and space

EROSION & SEDIMENT CONTROL NARRATIVE

EROSION CONTROL PROGRAM FROSION CONTROL SHALL BE MAXIMIZED THROUGH RAPID STABILIZATION OF THE DISTURBED AREAS AND BY DIVERTING ERUSUN CONTROL SHALL BE MAXIMIZED I FINOUGH RAYED STABILIZATION OF THE LEST INDIGED AREAS OF TOWER IN CLEAN WATER AND EROSKE FLOWS AROUND OR THROUGH DISTURBED AREAS IN A NON-EROSIVE MANNER. WHERE FINAL GRADING HAS BEEN ESTABLISHED, FERTILIZER (OUTSIDE OF STREAMWEILAND CROSSING AREAS) PERMANENT AND TEMPORARY SEEDING, AND MULCHING SHALL BE APPLIED IMMEDIATELY. BARE SOIL AREAS MUST BE FERTILIZED (OUTSIDE STREAMWEILAND CROSSING AREAS) SEEDED, AND MULCHED AFTER 14 DAYS WHEN TEMPORARY OR FINAL GRADE IS ESTABLISHED IF NO WORK IS PLANNED IN THAT AREA DURING THE FOLLOWING 7 DAYS (I.E. 21 CONSECUTIVE DAYS), REVEGETATION ACTIVITIES SHALL BE PERFORMED IN AN AGGRESSIVE MANNER THROUGHOUT THE

SEDIMENT CONTROL PROGRAM.
SEDIMENT CONTROL SHALL BE ACCOMPLISHED THROUGH RAPID STABILIZATION AND BY THE INSTALLATION OF STRUCTURAL DEVICES, AS SHOWN ON THE CONSTRUCTION PLANS.

VEGETATIVE PRACTICES

1. SURFACE ROUGHENING - AREAS TO BE SEEDED SHALL BE LIGHTLY ROUGHENED AND LOOSE TO A DEPTH OF 2" TO 4" PRIOR TO SEEDING AREAS WHICH HAVE BEEN GRADED AND WILL NOT BE STABILIZED IMMEDIATELY, MAY BE ROUGHENED TO REDUCE VELOCITY UNTIL SEEDING TAKES PLACE.

2 TOP SOILING (STOCKPILE) - TOPSOIL WILL BE STRIPPED FROM AREAS TO BE GRADED AND STOCKPILED FOR LATER USE. STOCKPILE LOCATION SHALL BE LOCATED WITHIN CONSTRUCTION RW, AND TO BE STABILIZED WITH TEMPORARY VEGETATION. AREAS OF STOCKPILE, ONCE REMOVED, SHALL BE GRADED RESTORED & PERMANENTLY.

TEMPORARY STABILIZATION - SELECTION OF THE SEED MIXTURE WILL DEPEND ON THE TIME OF THE YEAR IT IS APPLIED AND SHALL BE DONE WITH TEMPORARY SEEDING MEASURES SPECIFIED BELOW. MULCHING SHALL BE APPLIED AT A RATE OF TWO TONS OF STRAW O R WEED FREE HAY PER ARR. EXCEPT IN STREAMMETLAND CROSSING AREAS, FERTILIZER SHALL BE APPLIED AT A RATE OF 1,000 LBS/ACRE AND LIME SHALL RE APPLIED AT 1 0 TON/ACRE

PERMANENT STABILIZATION
ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE STABILIZED WITH PERMANENT SEEDING IMMEDIATELY FOLLOWING FINISHED GRADING, SEEDING SHALL BE DONE WITH PERMANENT SEEDING MEASURES AS SPECIFIED BELOW IN ALL SEEDING OPERATIONS SEED WILL BE APPLIED PRIOR TO MULCHING, MULCHING SPECIFIED BELOW. IN ALL SEEDING OPERATIONS, SEED WILL BE APPLIED FRICE TO MOLCHING. SHALL BE APPLIED AT A RATE OF TWO TONS OF STRAW OR WEED FREE HAY PER ACRE, OUTSIDE OF STREAMMETLAND CROSSING AREAS, FERTILIZER SHALL BE APPLIED AT A RATE OF 1000 LBS/ACRE AND LIME SHALL BE APPLIED AT 1.0 TON/ACRE.

**NOTE: SEED MIXES SHALL NOT BE MODIFIED WITHOUT APPROVAL OF ENGINEER

SEED MIXTURE: OUTSIDE STREAMWETLAND CROSSING

| PERMANENT SEEDING | | | |
|-----------------------|-----------------------------------|------------------------------|--|
| SPECIES | PLANTING DATES | APPLICATION RATE LBS/ACRE | |
| SWITCHGRASS | 3/1-6/5 8/15-9/15 | 15 | |
| PERENNIAL RYEGRASS | 3/1-6/5 8/15-9/15 | 20 | |
| REDTOP | 3/1-6/15 | 5 | |
| BIRDSFOOT TREFOIL | 3/1-6/5 8/15 -0 /15 | 15 | |
| JAPANESE MILLET | 06/16-08/14 | 15 | |
| WINTER RYE | 09/16-08/28 | 85 | |

HINE: ACRICULTURAL CROUND HIESTONE AT 1 TON PER ACRE FERTILIZER: 10-20-10 AT A RATE OF 1,000 POUNDS PER ACRE. MULCH: GRASS HAY OR CEREAL STRAW AT 2 TONS PER ACRE, ANCHOR STRAW AND HAY WITH ASPHALT EMULSION, CHEMICAL ANCHORING SOLUTION, NETTING OR A MULCH-ANCHORING TOOL. A LIQUID MULCH BINDER

| KIND OF SEED | PLANTING DATES | APPLICATION RATE LBS/ACRE | |
|--|-----------------------|------------------------------|--|
| ANNUAL RYEGRASS | 2/16-5/15 8/1-11/1 | 40 | |
| FIELD BROMEGRASS | 3/1-6/15 8/1-9/5 | 40 | |
| SPRING OATS | 3/1-6/15 | 100 | |
| WINTER RYE | 8/15-2/28 | 170 | |
| VINTER WHEAT | 8/15-2/28 | 180 | |
| JAPANESE MILLET | 5/15-8/15 | 30 | |
| REDTOP | 3/1-6/15 | 10 | |
| ANNUAL RYEGRASS AND SPRING OATS | 3/1-6/15 | 30 70 | |
| GERMAN/FOXT AIL MILLET | 5/1-8/1 | 40 | |
| HAIRY VETCH | 8/15-4/1 | 60 | |

TEMPORARY SEEDING

MINIMUM CONSTRUCTION STANDARDS NARRATIVE

- 1. FERTILIZING, SEEDING, AND MULCH SHALL BE APPLIED TO ALL DISTURBED AREAS WHERE FERTILIZING, SELDING, AND MOLEN SPALE DE APPLIED TO ALL ISSTUDIED AND SEASON WHEN CONSTRUCTION IS NOT TO BE CONDUCTED FOR A PERIOD OF 7 DAYS OR MORE AND TO ALL AREAS WHERE FINAL GRADE HAS BEEN REACHED. WHERE CONSTRUCTION ACTIVITY WILL RESUME ON A PORTION OF THE SITE WITHIN 21 DAYS FROM WHEN ACTIVITIES CEASED, THE STARIL IZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE BY THE 7TH DAY AFTER CONSTRUCTION ACTIVITIES HAVE TEMPORARILY CEASED, REVEGETATION ACTIVITIES SHALL BE PERFORMED IN AN AGGRESSIVE MANNER THROUGHOUT THE CONSTRUCTION PROCESS.
- 2 DURING CONSTRUCTION OF THE PROJECT, SOIL STOCKPILES SHALL BE STABILIZED WITH PROPRIATE REST MANAGEMENT PRACTICES.
- PERMANENT VEGETATION SHALL NOT BE CONSIDERED ESTABLISHED UNTIL A GROUND COVER IS ACHIEVED THAT IS UNIFORM, MATURE ENOUGH TO SURVIVE, AND WILL INHIBIT EROSION, 70% VEGETATIVE COVER SHALL BE CONSIDERED STABILIZED.
- WHERE CONSTRUCTION VEHICLE ACCESS ROUTES INTERSECT PAVED OR PUBLIC ROADS, PROVISIONS SHALL BE MADE TO MINIMIZE THE TRANSPORT OF SEDIMENT BY VEHICULAR TRACKING ONTO THE PAVED SURFACE WHERE SEDIMENT IS TRANSPORTED ONTO A PAVED OR PUBLIC ROAD SURFACE THE ROAD SURFACE SHALL BE CLEANED THOROUGHLY AT THE END OF EACH DAY. SEDIMENT SHALL BE REMOVED FROM THE ROADS BY SHOVELING OR SWEEPING AND TRANSPORTED TO A SEDIMENT CONTROL.
- 5. ALL TEMPORARY SEDIMENT CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL VEGETATION IS WELL ESTABLISHED ON ALL AREAS TO WHICH THE STRUCTURE IS BEING UTILIZED. NO EROSION CONTROL MEASURE CAN BE CHANGED OR REMOVED WITHOUT THE PERMISSION OF THE WEST VIRIGINAL DEPARTMENT OF ENVIRONMENTAL PROTECTION.
- PROPERTIES AND WATERWAYS DOWNSTREAM FROM DEVELOPMENT SITES SHALL BE PROTECTED FROM SEDIMENT DEPOSITION, EROSION AND DAMAGE DUE TO INCREASES IN VOLUME, VELOCITY AND PEAK FLOW RATE OF STORMWATER RUNOFF.
- ALL MEASURES USED TO PROTECT PROPERTIES AND WATERWAYS SHALL BE EMPLOYED IN A MANNER WHICH MINIMIZES IMPACTS ON THE PHYSICAL CHEMICAL, AND BIOLOGICAL NTEGRITY OF RIVERS, STREAMS, AND OTHER WATERS OF THE STATE
- STABILIZATION MEASURES SHALL BE APPLIED IMMEDIATELY TO EARTHEN STRUCTURES SUCH AS BERMS AND DIVERSIONS IMMEDIATELY AFTER INSTALLATION.
- AREAS WHERE THE SEED HAS FAILED TO GERMINATE ADECUATELY (UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 70%) WITHIN 30 DAYS AFTER SEEDING AND MULCHING MUST BE RESEEDED IMMEDIATELY, OR AS SOON AS WEATHER CONDITIONS
- CLEAN WATER DIVERSIONS MUST BE STABILIZED PRIOR TO BECOMING FUNCTIONAL

MAINTENANCE PROGRAM

ALL PERSONNEL INVOLVED IN THE INSTALLATION OF THE TEMPORARY SEDIMENT CONTROL ALL PERSONNEL INVOLVED IN THE INSTALLATION OF THE TEMPORARY SEDIMENT CONTINUE.

STRUCTURES SHALL BE PROPERLY INSTRUCTED ON THE CORRECT INSTALLMENT PROCEDURES
OF EACH MEASURE. ON-THE-JOB TRAINING SHALL BE CONDUCTED TO ENSURE THOSE
PERSONNEL PERFORMING CONSTRUCTION ACTIVITIES ON THE PROJECT SITE ARE AWARE OF
THE COMPONENTS, METHODS, AND EXPECTED PERFORMANCE OF THE EROSION & SEDIMENT

AT A MINIMUM, ALL EROSION CONTROL MEASURES SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF RAIN PER 24 HOUR PERIOD,

ALL STRUCTURES ARE TO BE REPAIRED OR REPLACED IMMEDIATELY UPON THE FINDING OF ANY DEFICIENCY, REFER TO NOTES ON EROSION CONTROL MEASURE DETAILS FOR ADDITIONAL

CONSTRUCTION ENTRANCES: INSPECTION SHALL BE MADE DAILY FOR ENTRANCE INTEGRITY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY. THE EXISTING ROAD/DRIVEWAY SHALL BE MAINTAINED AND REMAIN ACCESSIBLE TO USERS.

RIGHT OF WAY INTERCEPTOR DIVERSION: INSPECTION SHALL BE MADE ONCE EVERY WEEK AND AFTER EVERY RAINFALL EVENT OF 0.5 INCH OR MORE WHETHER A STORM EVENT HAS OCCURRED OR NOT AND REPAIRS SHALL BE MADE AS NECESSARY. IN AREAS WHERE CONSTRUCTION IS ACTIVELY OCCURRING. INSPECTIONS SHALL BE PERFORMED DAILY AND ANY SHALL BE REPAIRED BY THE END OF THE DAY

SILT FENCE/SILT SOCK: INSPECTION SHALL BE MADE DAILY FOR FENCE INTEGRITY; REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY, FENCES SHOULD BE INSPECTED AFTER RAINFALL OF 0.5 INCH OR GREATER, SEDIMENT IS TO BE REMOVED WHEN DEPOSITS REACH ONE-HALF THE FENCE


PERMANENT SEEDING: SEEDED AREAS SHALL BE CHECKED REGULARLY TO ENSURE A GOOD STAND OF GRASS IS BEING MAINTAINED. AREAS THAT FAIL TO ESTABLISH VEGETATIVE COVER. ADEQUATE TO PREVENT RILL EROSION SHALL BE RE-SEEDED AS SOON AS THEY ARE IDENTIFIED.

MULCHING: ALL MULCHED AREAS SHALL BE INSPECTED PERIODICALLY, PARTICULARLY AFTER RAINSTORMS, TO CHECK FOR EROSION. REPAIR AS NEEDED.


DEVICES SHOWN ARE TO BE CONSIDERED AS MINIMUM EROSION AND SEDIMENTATION DEVICES SHOWN ARE TO BE CONSIDERED ANY BE INCESSARY DUE TO CONTRACTORS PHASING OR OTHER UNANTICIPATED CONDITIONS, IT IS THE CONTRACTORS RESPONSIBILITY TO PROVIDE ADDITIONAL DEVICES AS NECESSARY IN ORDER TO CONTROL EROSION AND SEDIMENTATION. EROSION AND SEDIMENTATION MEASURES SHALL BE INSTALLED AND MAINTAINED IN ERIOSOTA WILL SELIMIENT IN ION MERSOURES SYPILE DE MOST LILLED AND MAINT AMPLET IN ACCORDANCE WITH THE POLICIES AND REQUIREMENTS OF THE WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION BEST MANAGEMENT PRACTICES MANUAL CONTROLS MAY BE REMOVED AFTER THE AREAS ABOVE THEM HAVE BEEN STABILIZED AND WITH THE APPROVAL OF THE WEST OF

SPECIAL CARE NOTES
IT IS THE INTENT OF THIS PLAN TO PRECLUDE SEDIMENT POLLUTION FROM LEAVING THE
DELINEATED CONSTRUCTION ZONES, THE CONTRACTOR AND THE DEVELOPER SHALL TAKE
SPECIAL CARE TO PREVENT CONSTRUCTION DEBRIS AND MUD FROM BEING TRACKED ONTO SURROUNDING PUBLIC AND PRIVATE ROADS, CONSTRUCTION TRAFFIC SHALL ONLY ENTER AND EXIT THE CONSTRUCTION SITE VIA DESIGNATED LOCATIONS. THE CONTRACTOR AND DEVELOPER SHALL TAKE SPECIAL CARE TO PROTECT THE EXIST SHOWN ON THE PLANS.
WATERWAYS OUTSIDE OF THE DESIGNATED LIMITS OF WORK SHOWN ON THE PLANS. FROSION AND SEDIMENT CONTROL NOTES

| l | | | EROSIONAN | EROSION AND SEDIMENT CONTROL NOTES | | |
|---|----------|---------------|-------------------------|------------------------------------|--|--|
| SEAL | | RE | VISION RECORD | | | |
| | NO. | DATE | DESCRIPTION | | Antero | |
| Commission Commission | 1 | 3 / 25 / 2014 | ISSUED FOR CONSTRUCTION | | Resources | |
| COBA 2 | | | | | | |
| 100000000000000000000000000000000000000 | ⊢ | | | PEARL J | EAN TO CANTON | |
| | <u> </u> | | | | GASLINE | |
| EQ 3 SINGED A 105 | ┢ | | | | | |
| 100 | | | | GRANT DIS | 12" GASLINE TRICT, DODDRIDGE COUNTY, WV | |
| | | | | DATE: 3/25/201 | PROJECT NO: 132-985 | |
| 1 24 Til | | | | SCALE: | | |
| E. J. | | i | | DRAWN BY: RLC | SHEET 5 OF 7 | |
| | | | | CHECKED BY: JH | | |




EROSION CONTROL BLANKET STAPLE PATTERN NOT TO SCALE



EROSION CONTROL MEASURES FOR PIPELINE TRENCHES

III II II Civil & Environmental Consultants, Inc. 99 Cambridge Place - Bridgeport, WV 26330 Ph: 304.933.3119 Fax: 304.933.3327


www.cecinc.com




FROSION CONTROL BLANKET (NORTH AMERICAN GREEN \$150) (OR APPROVED EQUAL) NOTES:

- PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF UME, FERTILIZER, AND SEED.
- BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN 6° DEEP X 6° WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
- ROLL THE BLANKETS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE.
- THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2° OVERLAP.
- WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 12" OVERLAP, STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART.
- EROSION CONTROL BLANKETS SHALL BE INSTALLED ON ALL 3:1 OR STEEPER SLOPES.
- REFER TO DETAIL 7, THIS SHEET FOR STAPLE PATTERN

EROSION CONTROL BLANKET NOT TO SCALE





TRENCH PLUG SHALL BE INSTALLED:
 ON SLOPES ALONG THE TRENCH LINE WHERE THE NATURAL DRAINAGE PATTERN, PROFILE, AND TYPE OF BACKFILL MATERIAL MAY RESULT IN LOSS OF BACKFILL MATERIAL OR ALTERATION OF NATURAL PATTERN;
 AT THE BASE OF SLOPES ADJACENT TO WATERBODIES AND WETLANDS
 WHERE NEEDED TO AVIOLD DRAINING A WETLAND
 ON UPLAND SLOPES, AT THE SAME SPACING AS SLOPE BREAKERS AND UP SLOPE OF SLOPE BREAKERS
 IN CULTIVATED LAND AND RESIDENTIAL AREAS WHERE PERMANENT SLOPE BREAKERS ARE NOT TYPICALLY INSTALLED, AT THE SAME SPACING AS IF PERMANENT SLOPE BREAKERS WHERE REQUIRED.

SIDE VIEW


- AS AN ALTERNATIVE TO THE MATERIALS SPECIFIED IN THE TABLE BELOW, OPEN WEAVE HEMP OR JUTE SACKS MAY BE FILLED WITH A MINIMUM OF 5516s. MIXTURE OF 1 PART CEMENT TO 6 PARTS SAND OR SUBSOIL SO THAT NATURAL GROUND WATER WILL PERMIT MIXTURE TO EXUDE AND BOND SACKS TOGETHER.
- 4. ALL MATERIALS SHALL BE SUPPLIED BY CONTRACTOR.
- 5. GEOTECHNICAL POLYURETHANE FOAM TRENCH PLUGS MAY BE USED IN LIEU OF SACKS FILLED WITH CEMENT / SOIL MIXTURE
- 6. TRENCH PLUG SPACING SHOWN BELOW IS THE MAXIMUM ALLOWABLE PER PADEP REGULATIONS. ALL TRENCH PLUG LOCATIONS SHOWN ARE APPROXIMATE. FINAL LOCATIONS WILL BE FIELD IDENTIFIED BY A QUALIFIED INDIMIDUAL TO ACCOMMODATE PIPELINE FITTINGS, SIDE BENDS, OVER BENDS AND SAG BENDS TO ASSURE THAT ALL TRENCH PLUG INDUCED STRESSES ARE MINIMIZED.


| | MAXIMUM S | PACING AND MATERIALS FOR TRENCH PLUGS |
|------------------|------------------|--|
| TRENCH SLOPE (%) | SPACING L (FEET) | TRENCH PLUG MATERIAL |
| 0 - 5 | 1,000 | *CLAY, BENTONITE, OR CONCRETE FILLED SACKS, OR AS SPECIFIED IN NOTES 2 AND 5 |
| 5 - 15 | 500 | *CLAY, BENTONITE, OR CONCRETE FILLED SACKS, OR AS SPECIFIED IN NOTES 2 AND 5 |
| 15 - 25 | 300 | *CLAY, BENTONITE, OR CONCRETE FILLED SACKS, OR AS SPECIFIED IN NOTES 2 AND 5 |
| 25 - 35 | 200 | *CLAY, BENTONITE, OR CONCRETE FILLED SACKS, OR AS SPECIFIED IN NOTES 2 AND 5 |
| 35 - 100 | 100 | *CLAY, BENTONITE, OR CONCRETE FILLED SACKS, OR AS SPECIFIED IN NOTES 2 AND 5 |
| OVER 100 | 50 | CEMENT FILLED BAGS, (WETTED), MORTARED STONE, OR GEOTECHNICAL POLYURETHANE FOR |

DETAIL 3

*TOPSOIL MAY NOT BE USED TO FILL SACKS.

**IMPERVIOUS TRENCH PLUGS ARE REQUIRED AT ALL STREAM, RIVER, WETLAND, OR OTHER WATERBODY CROSSINGS.






NOTE:
1. COMPOST FILTER SOCK TO BE FILTREXX SILTSOXX OR APPROVED EQUIVALENT.

- 12", 18", AND 24" COMPOST FILTER SOCK TO BE USED. SEE PLAN SHEET FOR SIZES AND LOCATIONS.
- 3. ACCUMULATED SEDIMENT SHALL BE REMOVED AND DISPOSED OF WHEN IT REACHES 1/4. THE ABOVE GROUND HEIGHT OF THE COMPOST FILTER SOCK.
- COMPOST FILTER SOCK SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED COMPOST FILTER SOCK SHALL BE REPARED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION

DETAIL 4 COMPOST FILTER SOCK NOT TO SCALE



- 4" to 6" STONE SHALL EXTEND THE FULL WIDTH OF THE ACCESS ROAD.
- 4" to 6" STONE SHALL MEET THE GRADATION REQUIREMENTS FOR CLASS 7 AGGREGATE IN TABLE 704.6.2A OF THE WYDOH STANDARD SPECIFICATIONS FOR ROADS AND BRIDGES.
- A MOUNDED BERM MUST BE USED AT ALL STONE CONSTRUCTION ENTRANCES.
- TURNOUTS ONTO PAVED ROADS FROM STONE CONSTRUCTION ENTRANCES SHALL BE A MINIMUM OF 10.0 FEET AS MEASURED ALONG THE PAVED ROAD, RECARDLESS OF THE ANGLE AT WHICH THE STONE CONSTRUCTION ENTRANCE ENCOUNTERS THE PAVED ROAD.

REVISION RECORD SEAL
 NO.
 DATE
 DESCRIPTION

 1
 3 / 25 / 2014
 ISSUED FOR CONSTRUCTION
 EAntero **PEARL JEAN TO CANTON** 352 **GASLINE** T STUDECE. 12" GASLINE GRANT DISTRICT, DODDRIDGE COUNTY, WV SHEET 6 OF 7

DETAIL 6 STABILIZED CONSTRUCTION ENTRANCE NOT TO SCALE

CROSS SECTION AT ROAD DITCH, TYP.

