

Commercial/Industrial Floodplain Development Permit

Doddridge County, WV Floodplain Management

This permit has been issued to **CESO**, **Inc. CONSOL**, & **Cone Gathering**, **LLC**, and is for the approved commercial and/or industrial development project associated with this permit that impacts the FEMA-designated floodplain and/or floodway of Doddridge County, WV, pursuant to the rules and regulations established by all applicable Federal, State and local laws and ordinances, including the Doddridge County Floodplain Ordinance. This permit must be posted at the site of work as to be clearly visible, and must remain posted during entirety of development.

Permit: #14-254 ~ CONSOL OX11 - OX13 Pipeline

Date Approved: 08/08/2014 Expires: N/A

Issued to: CESO, CONSOL, Cone Gathering, LLC

POC: Natalie Hooton 412-221-2236

Company Address: 800 Bursca Drive STE 804

Bridgeville, PA 15017-1451

Project Address: Southwest District

Lat/Long: 39.168227N/80.748344W to 39168227N/80.760058W

Purpose of development: Pipeline constructionn. Project does not impact floodplain.

Issued by: Edwin L, "Bo" Wriston, Doddridge County FPM (or designee)

Date: 08/08/2014



Commercial/Industrial Floodplain Development Permit

Doddridge County, WV Floodplain Management

This permit has been issued to **CESO**, **Inc. CONSOL**, & **Cone Gathering**, **LLC**, and is for the approved commercial and/or industrial development project associated with this permit that impacts the FEMA-designated floodplain and/or floodway of Doddridge County, WV, pursuant to the rules and regulations established by all applicable Federal, State and local laws and ordinances, including the Doddridge County Floodplain Ordinance. This permit must be posted at the site of work as to be clearly visible, and must remain posted during entirety of development.

Permit: #14-254 ~ CONSOL OX11 - OX13 Pipeline

Date Approved: 08/08/2014 Expires: N/A

Issued to: CESO, CONSOL, Cone Gathering, LLC

POC: Natalie Hooton 412-221-2236

Company Address: 800 Bursca Drive STE 804

Bridgeville, PA 15017-1451

Project Address: Southwest District

Lat/Long: 39.168227N/80.748344W to 39168227N/80.760058W

Purpose of development: Pipeline constructionn. Project does not impact floodplain.

Issued by: Edwin L. "Bo" Wriston, Doddridge County FPM (or designee)

Date: 08/08/2014

Legal Advertisement:

Doddridge County

Floodplain Permit Application

Please take notice that on the 4^{th} day of August, 2014

CONSOL, CESO, & Cone Gathering, LLC

filed an application for a Floodplain Permit to develop land located at or about:

Southwest District 39.168227N / 80.748344W to 39.168227N / 80.760058W

Permit #14-254 CONSOL OX-11 to OX-13 Pipeline

(Note: This project is not within the floodplain)

The Application is on file with the Clerk of the County Court and may be inspected or copied during regular business hours. As this project is outside the FEMA identified floodplain of Doddridge County, Doddridge County Floodplain Management has no regulatory authority.

Any interested persons who desire to

comment shall present the same in writing by September 8, 2014, delivered to:

Clerk of the County Court

118 E. Court Street, West Union, WV 26456

Beth A Rogers, Doddridge County Clerk

Edwin L. "Bo" Wriston. Doddridge County Flood Plain Manager




NATALIE HOOTON, M.S.

Staff Biologist

(412) 221-2236 (412) 639-2231 Cell, (412) 221-2267 Fax hooton@cesoinc.com www.cesoinc.com

800 Bursca Drive, Suite 804 Bridgeville, Pennsylvania 15017-1451







800 Bursca Drive, Suite 804
Bridgeville, Pennsylvania 15017-1451
(412) 221-2236
www.cesoinc.com

August 1, 2014

Mr. Edwin "Bo" Wriston Doddridge County Floodplain Manager 118 East Court Street West Union, WV 26456 2014 AUG -4 PM 1: 02

BETH A POOFRS
COUNTY CLERK
DODDRIDGE COUNTY, WV

RE:

CONSOL- OX11-OX13 Pipeline

Doddridge County Floodplain Permit

Dear Mr. Wriston:

CESO, Inc. is pleased to submit this information for a Doddridge County Floodplain Permit, for the proposed OX11-OX13 Pipeline. Cone Gathering, LLC (Cone), is proposing to construct a new pipeline gathering system within a portion of Doddridge County, West Virginia. The proposed project will begin at the OX13 natural gas well pad located at 39.168227 N Latitude, 80.748344 W Longitude (NAD83) which lies east of Porto Rico, West Virginia. The project starting location is bordered on the west by County Road 40 (Cain Run). The proposed pipeline traverses in a general west and northwesterly direction, prior to reaching its terminus at an interconnect with the EQT to OX11 pipeline located south of the County Route 40 and South Fork of Hughes River Road intersection at 39.173383 N Latitude, 80.760058 W Longitude (NAD83).

CESO, Inc. has identified a total of four (4) named and/or unnamed waterway crossings in Doddridge County as a result of this project. The Doddridge County Development Permit Application further describing project characteristics is presented in Attachment 1. According to the FEMA Flood Insurance Rate Maps, no waterways within the project vicinity exist within the 100-year floodplain. A map depicting the proposed alignment location as well as a table and map identifying stream crossings are also provided.

Waterway crossings associated with the pipeline installation will be the result of open cutting of the stream channel. However, all waterways will be returned to their pre-disturbance plan, profile, and dimension after the pipe has been installed. In addition, proper construction sequencing and implementation of an approved erosion and sediment control plan will ensure water quality impacts are minimized throughout the project area and the proposed activities are in compliance with Nationwide Permit General Conditions and Regional General Conditions.

Should you have any questions or comments please don't hesitate to contact me at 412-221-2236 ext. 2009 or through email at https://doi.org/10.2016/journal.com.

Sincerely,

CESO, Inc.

Natalie Hooton Staff Biologist





Table 1. Stream Crossings by Pipeline Activity

Stream Field ID	Stream Category	Stream Name or Tributary Of	Project Activity	Type of Crossing	Coordinates (NAD83) (dd)	Width (feet)	Crossing Size (linear feet)
ЕН	Ephemeral	UNT South Fork Hughes River	Pipeline	Open Cut/ Timber Matted	39.17350023, -80.75930857	1	47
EF	Intermittent	UNT South Fork Hughes River	Pipeline	Open Çut/ Timber Matted	39.17207587, -80.75695506	5.	119
EC	Ephemeral	UNT South Fork Hughes River	Pipeline	Open Cut/Timber Matted	39.16765218, -80.74984009	2	151
ЕВ	Perennial	South Fork Hughes River	Pipeline	Open Cut/Timber Matted	39.16765015, -80.74977009	3,	132

DODDRIDGE COUNTY FLOODPLAIN DEVELOPMENT PERMIT APPLICATION

SECTIO	N 1: GENERAL PROVISIONS (APPLICANT TO READ	AND SIGN TO CLERK
1	No work may start until a permit is issued	- WOUL COUNTY, WY

1. No work may start until a permit is issued.

APPLICANT'S SIGNATURE

- 2. The permit may be revoked if any false statements are made herein.
- 3. If revoked, all work must cease until permit is re-issued.
- 4. Development shall not be used or occupied until a Certificate of Compliance is issued.
- The permit will expire if no work is commenced within six months of issuance. 5.
- 6. Applicant is hereby informed that other permits may be required to fulfill local, state, and federal requirements.
- Applicant hereby gives consent to the Floodplain Administrator/Manager or his/her representative to make inspections to verify compliance.
- I THE APPLICANT CERTIFY THAT ALL STATEMENTS HEREIN AND IN ATTACHMENTS TO THIS APPLICATION ARE, TO THE BEST OF MY KNOWLEDGE TRUE AND ACCURATE.

SECTION 2: PROPOSED DEVELOPMENT (TO BE COMPLETED BY APPLICANT). IF THE APPLICANT IS NOT A NATURAL PERSON, THE NAME, ADDRESS, AND TELEPHONE NUMBER
OF A NATURAL PERSON WHO SHALL BE APPOINTED BY THE APPLICANT TO RECEIVE NOTICE PURSUANT
TO ANY PROVISION OF THE CURRENT DODDRIDGE COUNTY FLOODPLAIN ORDINANCE.
TO THE TOTAL OF THE COMMENT BODDINGSE COOKET FEODD EARL ONDINANCE.
APPLICANT'S NAME: Cone Gathering, LLC
ADDRESS: c/o Adam White, One Energy Drive PO Box 1248 Jane Lew, WV 26378
TELEPHONE NUMBER: 724.627.1300
CONTRACTOR NAME:
ADDRESS:
TELEPHONE #
WV CONTRACTOR LICENCE #
ENGINEER'S NAME: CESO, Inc.
ADDRESS: 2800 Corporate Exchange Drive, Suite 160, Columbus, OH 43231
TELEHONE NUMBER: 614.794.7080
PROJECT LOCATION:
NAME OF SURFACE OWNER/OWNERS (IF NOT THE APPLICANT) Please see Attachment A.
ADDRESS OF SURFACE OWNER/OWNERS (IF NOT THE APPLICANT) Please see Attachment A.
DISTRICT: Please see Attachment A.
LAND BOOK DESCRIPTION: Please see Attachment A.
DEED BOOK REFERENCE: Please see Attachment A.

	MAP REFERENCE								
	ING BUILDINGS,								
	NAME OF AT LEAST ONE ADULT RESIDING IN EACH RESIDENCE LOCATED UPON THE SUBJECT								
	ERTY Please see A								
				IN EACH	RESIDEN	CE LOCAT	ED UP	ON THE SUBJECT	
PROF	PERTY Please see A	.ttacnment /	٩.						
To av	oid delay in pro	cessing t	he application,	please pr	ovide en	ough info	rmatic	on to easily identify the	
proje	ct location.								
								hin a portion of Doddridge	
								ad located at 39.168227 N	
								he project starting location reses in a general west and	
								X11 pipeline located south	
								N Latitude, 80.760058 W	
_	ude (NAD83).								
	RIPTION OF WO			BLE BOXE	S)				
	TRUCTURAL DE	VELOPM	ENT						
ACTI				STRU	CTURAL				
[]	New Structur	re			[]		Residential (1 – 4 Family)		
[]	Addition				[]			nore than 4 Family)	
[]	Alteration				[]	Non-residential (floodproofing)			
[]	Relocation					[] Combined Use (res. & com		e (res. & com.)	
[]	Demolition				[]	Replace	ment		
[]	Manufacture	ed/Mobi	l Home						
В.	OTHER DEVELO	PLMENT	ACTIVITIES:						
[]	Fill	[]	Mining	[]	Drilling	g		Pipelining	
[]	Grading								
[]	•	•	r STRUCTURAL						
[]			on (including di			el modific	ation)		
[]			nts (including c		rk)				
[]		_	e Construction						
[]		_	g new expansio	n)					
[]	Individual W		•						
[]	Other (please	e specify)						
C.	STANDARD S	ITE PLAN	OR SKETCH						
1.	CHRMIT ALL	STANDAI	DU CITE DI VVIC	IE ANV LI	\\/E DEE*	I DDEDARG	:D /EN	GINEERING PLANS MUST	
	CNED AND CEAL		NO SHE FEMINS,	11 ANT 17	AAL DEEN	4 FIVER MINE	יט (בוא	GINELKING PLANS MICS	

- BE SIGNED AND SEALED).
- 2. IF STANDARD SITE PLANS HAVE NOT BEEN PREPARED: SKETCH ON A SEPARATE 8 ½ X 11 INCH SHEET OF PAPER THE SHAPE AND LOCATION OF THE LOT. SHOW THE LOCATION OF THE INTENDED CONSTRUCTION OR LAND USE INDICATING BUILDING SETBACKS, SIZE & HEIGHT. IDENTIFY EXISTING BUILDINGS, STRUCTURES OR LAND USES ON THE PROPERTY.

3. SIGN AND DATE THE SKETCH.	Please see Attachment B and Attachment C.
ACTUAL TOTAL CONSTRUCTION COSTS OF PROJECT WITHIN THE FLOODPLAIN \$ 0.0	OF THE COMPLETE DEVELOPMENT/ PROPOSED CONSTRUCTION
OF THE SURFACE TRACT (UP & DOWN S AND ALL OTHER SURFACE OWNERS UP & AFFECTED BY FLOODING AS IS DEMONS COMPLETED.	VNERS OF SURFACE TRACTS ADJACENT TO THE AREA STREAM) UPON WHICH THE PROPOSED ACTIVITY WILL OCCUR & DOWN STREAM) WHO OWN PROPERTY THAT MAY BE TRATED BY A FLOODPLAIN STUDY OR SURVEY (IF ONE HAS BEEN
NAME: Please see Attachment D. ADDRESS: Please see Attachment D.	ADDRESS:
NAME:ADDRESS:	NAME:ADDRESS:
ANY ADJACENT PROPERTY AT THE TIME AND ADDRESS OF AT LEAST ONE ADULT AFFECTED BY FLOODING AS IS DEMONS NAME: Refer to Attachment D.	ST ONE ADULT RESIDING IN EACH RESIDENCE LOCATED UPON THE FLOODPLAIN PERMIT APPLICATION IS FILED AND THE NAME RESIDING IN ANY HOME ON ANY PROPERTY THAT MAY BE TRATED BY A FLOODPLAIN STUDY OR SURVEY. NAME: ADDRESS:
E. CONFIRMATION FORM	
DAYS OF RECEIPT OF INVOICE BY THE CO APPLICATION PROCESS GREATER THAN I (A) PERSONAL SERVICE OF PROCESS PERMITTED BY LAW FOR SUCH SERVICE. (B) SERVICE BY CERTIFIED MAIL RET. (C) PUBLICATION. (D) COURT REPORTING SERVICES AT. (E) CONSULTANTS AND/OR HEARING ADMINISTRATOR/MANAGER OR FLOOD	
T LIMVITT.	IG EXPERTS UTILIZED BY DODDRIDGE COUNTY FLOODPLAIN PLAIN APPEALS BOARD FOR REVIEW OF MATERIALS AND/OR OF GRANTING OR DENYING THE APPLICANT'S FLOODPLAIN
NAME (PRINT): Natalie Hooton for CESO, Inc	PLAIN APPEALS BOARD FOR REVIEW OF MATERIALS AND/OR OF GRANTING OR DENYING THE APPLICANT'S FLOODPLAIN

After completing SECTION 2, APPLICANT should submit form and fees to Clerk of Doddridge County Court or his/her representative for review.

SECTION 3: FLOODPLAIN DETERMINATION (to be completed by Floodplain Administrator/Manager or his/her representative)

THE PROPOSED DEVELOPMENT: THE PROPOSED DEVELOPMENT IS LOCATED ON: Dated:-----[] Is NOT located in a Specific Flood Hazard Area (Notify applicant that the application review is complete and NO FLOOPLAIN DEVELOPMENT PERMIT IS REQUIRED). Is located in Special Flood Hazard Area. FIRM zone designation_____ 100-Year flood elevation is NGVD. Stream name _____ Profile # _____ N Unavailable []The proposed development is located in a floodway. []See section 4 for additional instructions. DATE SIGNED SECTION 4: ADDITIONAL INFORMATION REQUIRED FOR DEVELOPMENT IN SPECIAL FLOOD HAZARD AREA (To be completed by Floodplain Administrator/Manager or his/her representative) The applicant must submit the documents checked below before the application can be processed. A plan showing the location of all existing structures, water bodies, adjacent roads and proposed development. Development plans, drawn to scale, and specifications, including where applicable: details for anchoring structures, storage tanks, proposed elevation of lowest floor, (including basement or crawl space), types of water resistant materials used below the first floor, details of flood proofing of utilities located below the first floor and details of enclosures below the first floor. Also_____ Subdivision or other development plans (If the subdivision or development exceeds 10 lots or 2

acres, whichever is the lesser, the applicant must provide 100-year flood elevations if they are not

otherwise available).


[] Plans	s showing the extent of watercourse relocation and/or landform alterations.
[] Top (of new fill elevationFt. NGVD.
	loodproofing structures applicant must attach certification from registered engineer of
[] Certi	ification from a registered engineer that the proposed activity in a regulatory floodwa any increase in the height of the 100-year flood. A copy of all data and calculations his finding must also be submitted.
License and a	ufactured homes located in a Flood Hazard Area must have a West Virginia Contractor a Manufactured Home Installation License as required by the Federal Emergency t Agency (FEMA).
[] Othe	er:
SECTION 5: I	PERMIT DETERMINATION (To be completed by Floodplain Administrator/Manager or esentative)
Floodplain O	mined that the proposed activity (type is or is not) in conformance with provisions of the rdinance adopted by the County Commission of Doddridge County on May 21, 2013. The subject to the conditions attached to and made part of this permit.
SIGNED	DATE
	lain Administrator/Manager found that the above was not in conformance with the the Doddridge County Floodplain Ordinance and/or denied that application, the appli
APPEALS:	Appealed to the County Commission of Doddridge County? [] Yes {} No Hearing Date:
	County Commission Decision - Approved [] Yes [] No
CONDITIONS	:
SECTION 6.	AS-BUILT ELEVATIONS (To be submitted by APPLICANT before Certificate of Compliance
issued).	ASSOCIATELE VALIONS (TO be Submitted by APPLICANT before Certificate of Compilance
	g information must be provided for project structures. This section must be completer ofessional engineer or a licensed land surveyor (or attach a certification to this application to the content of the content
COMPLETE 1	OR 2 BELOW:
1 Actu	al (As-Built) Elevation of the top of the lowest floor (including basement or crawl spaceFT. NGVD.
2 Actu	al (As Built) elevation of floodproofing isFT. NGVD.

Note: Any work performed prior to submittal of the above information is at risk of the applicant. SECTION 7: COMPLIANCE ACTION (To be completed by the Floodplain Administrator/Manager or his/her representative).

The Floodplain Administrator/Manager or his/her representative will complete this section as applicable based on inspection of the project to ensure compliance with the Doddridge County Floodplain Ordinance.

Ordinance. INSPECTIONS:	
DATE:	BY:
DEFICIENCIES ? Y/N	
COMMENTS	
SECTION 8: CERTIFICATE OF COMPLIANCE (This/her representative).	o be completed by Floodplain Administrator/Manager or
Certificate of Compliance issued: DATI	E:BY:
CERTIFICATE OF COMPLIANCE FOR DEVELOPMENT IN SPECIAL FLOOD HAZA	RD AREA (OWNER MUST RETAIN)
PERMIT NUN	ИВЕR:
	E:
PURPOSE –	
CONSTRUCTION LOCATION:	
OWNER'S ADDRESS:	

THE FOLLOWING MUST BE COMPLETED BY THE FLO	OODPLAIN ADMINISTRATOR/MANAGER OR HIS/HER
COMPLIANCE IS HEREBY CERTIFIED WITH T ADOPTED BY THE COUNTY COMMISSION OF DODE	THE REQUIREMENT OF THE FLOODPLAIN ORDINANCE PRIDGE COUNTY ON MAY 21, 2013.
SIGNED	_DATE









Attachment A- Project Location-Surface Owner Information

TAX ID: 09-07-0010-0002-0000-6001

NAME OF SURFACE OWNER/OWNERS: I.L. Ike Morris

ADDRESS OF PROPERTY: Route 23, West Union, WV 26456

ADDRESS OF SURFACE OWNER/OWNERS: P.O. Box 397, Glenville, WV 26351

DISTRICT: Southwest

LAND BOOK DESCRIPTION:

DEED BOOK REFERENCE: Book 230/ Page 307

TAX MAP REFERENCE: MAP 10/ Parcel 2

EXISTING BUILDINGS/USES OF PROPERTY: There are currently several horizontal 6A wells with access roads located on the property. One residential (rented) structure is present on the property. The remaining portions of the parcel are forested and undeveloped.

NAME OF AT LEAST ONE ADULT RESIDING IN EACH RESIDENCE LOCATED UPON THE SUBJECT PROPERTY: Unknown

ADDRESS OF AT LEAST ONE ADULT RESIDING IN EACH RESIDENCE LOCATED UPON THE SUBJECT PROPERTY: Unknown

Attachment C-Construction Plans

VICINITY MAP

DRAWING INDEX DESCRIPTION SHEET NUMBER COVER SHEET SWPPP NOTES 2-3 SWPPP DETAILS PIPELINE PLAN 7-8 ROAD CROSSING DETAILS E&S TABLES AND QUANTITIES

VERTICAL DATUM NOTE

VERTICAL CONTROL IS BASED UPON THE NORTH AMERICAN VERTICAL DATUM OF 1983 (NAVD 83).

PLAN REPRODUCTION WARNING

THE PLANS HAVE BEEN CREATED ON ANSI D (22"x 34") SHEETS. FOR REDUCTIONS, REFER TO GRAPHIC SCALE.

THE PLANS HAVE BEEN CREATED FOR FULL COLOR PLOTTING, ANY SET OF THE PLANS THAT IS NOT PLOTTED IN FULL COLOR SHALL NOT BE CONSIDERED ADEQUATE FOR

*WARNING** INFORMATION MAY BE LOST IN COPYING AND/OR GRAY SCALE PLOTTING.


OX11-OX13 PIPELINE

DODDRIDGE COUNTY, WEST VIRGINIA

OX11-OX13 PIPELINE:

APPROX. START POINT: STA 0+00 (NAD 83) LAT: 39.173383 N / LONG: 80.760058 W (UTM) (ZONE 17) NORTHING: 247770.10 / EASTING: 1611280.38

APPROX. END POINT: STA 49+09 (NAD 83) LAT: 39.168227 N / LONG: 80.748344 W (UTM) (ZONE 17) NORTHING: 245845.81 / EASTING: 1614575.05



PROJECT AREA MAP





- THIS PLAN DOES NOT PURPORT TO BE A COMPREHENSIVE REPRESENTATION OF EXISTING UTILITIES IN THE PROJECT AREA. UTILITIES SHOWN ARE BEING PROVIDED FOR INFORMATIONAL PURPOSES ONLY, BASED ON SURFACE FEATURES OBSERVED IN THE FIELD. CESO, INC. MAKES PURPOSES ONLY, BASED ON SURFACE FEATURES OBSERVED IN THE FIELD. CESO, INC. MAKES NO GUARANIEE TO THEIR ACCURACY ANDIOR COMPLETENESS, FORTY-SIGHT (48) HOURS BEFORE DIGGING IS TO COMMENCE, THE CONTRACTOR SHALL NOTIFY THE STATEWIDE ONE CALL SYSTEM, MISS UTILITY OF WEST VIRGIMA, INC. (WW811) AT 1-800-245-4848. THE CONTRACTOR SHALL ALSO NOTIFY ALL OTHER AGENCIES WHICH MIGHT HAVE UNDERGROUND UTILITIES IN THE PROJECT AREA AND ARE NON-MEMBERS OF WW811.
- QUANTITIES LISTED ARE BASED ON SLOPE LENGTH, CONTRACTOR SHALL VERIFY ALL QUANTITIES.

UTILITY OWNERS

- NOTES:

 1. CONTRACTOR SHALL CALL THE STATEWIDE ONE CALL SYSTEM, MISS UTILITY OF WEST VIRGINIA, INC. (MV811) AT 1-800-245-4948 72 HOURS PRIOR TO CONSTRUCTION AND SHALL NOTIFY ALL UTILITY COMPANIES AT LEAST 48 HOURS PRIOR TO WORK IN THE VICINITY OF
- UTILITIES SHOWN ARE TAKEN FROM THE SURVEY AND RECORDS OF RESPECTIVE UTILITY
 COMPANIES AND DO NOT NECESSARY REPRESENT ALL UNDERGROUND UTILITIES ADJACENT
 TO OR UPON SITE SHOWN ON PLAN. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR
 TO LOCATE ALL EXISTING UTILITIES WHETHER SHOWN HEREIN OR NOT AND TO PROTECT THEM


DOMINION TRANSMISSION 445 W MAIN STREET CLARKSBURG, WV 26301 STEVEN D. GUM CONSOL ENERGY ONE ENERGY DRIVE JANE LEW, WV 26378 ADAM WHITE 240-506-7299 STEVEN.D.GUM@DOM.COM



APPROVED BY CONSOL:

REPRESENTATIVE

DATE



DATE

SUMMARY OF MATERIALS			REFER	REFERENCE DRAWINGS			REVISIONS		
MRKR#	QTY.	DESCRIPTION	DWG.	DESCRIPTION	NO.	DATE	DESCRIPTION		
1	5,093 LF	PIPELINE (SLOPE LENGTH)					- 7/72 A		
2	19 EA	Elbow, 45* Segmentable Fitting		-					
3	6 EA	PIPELINE WARNING SIGN	V-1						
			5						



OX11-OX13 PIPELINE

COVER SHEET

STATION(S)



200 EVERGREENE DRIVE WAYNESBURG, PA 15370

90126
BEM
BEM
ВЈМ

1 of 10

CONTRACTOR NOTES

- THIS PLAN DOES NOT PURPORT TO BE A COMPREHENSIVE REPRESENTATION OF EXISTING UTILITIES IN THE PROJECT AREA. UTILITIES SHOWN ARE BEING PROVIDED FOR INFORMATIONAL PURPOSES ONLY, BASED ON SURFACE FEATURES OBSERVED IN THE FIELD. CESO, INC. MAKES NO GUARANTEE TO THEIR ACCURACY AND/OR COMPLETENESS, FORTY-EIGHT (48) HOURS BEFORE DIGGING IS TO COMMENCE, THE CONTRACTOR SHALL NOTIFY THE STATEWIDE ONE CALL SYSTEM, MISS UTILITY OF WEST VIRGINIA, INC. (WV811) AT 1-800-245-4848. THE CONTRACTOR SHALL ALSO NOTIFY ALL OTHER AGENCIES WHICH MIGHT HAVE UNDERGROUND UTILITIES IN THE PROJECT AREA AND ARE NON-MEMBERS OF WV811.
- ALL CONTRACTORS/SUBCONTRACTORS PERFORMING WORK ON THIS PROJECT SHALL FAMILIARIZE THEMSELVES WITH THE SITE AND SHALL BE SOLELY RESPONSIBLE FOR ANY DAMAGE TO EXISTING FACILITIES RESULTING DIRECTLY OR INDIRECTLY FROM THEIR OPERATIONS. SAID EXISTING FACILITIES RESULTING DIRECTLY OR INDIRECTLY FROM THEIR OPERATIONS. SAID EXISTING IMPROVEMENTS SHALL INCLUDE, BUT NOT BE LIMITED TO, BERMS, DITCHES, FENCES AND PLANTS. ANY REMOVAL OR DAMAGE TO EXISTING IMPROVEMENTS SHALL BE REPLACED OR REPAIRED BY THE CONTRACTORS TO EXISTING OR BETTER CONDITIONS, AT THEIR EXPENSE, AND SHALL BE APPROVED BY
- ALL CONSTRUCTION, TESTING AND MATERIALS SHALL MEET OR EXCEED ALL REQUIREMENTS OF THE "PERMITTING ENTITY" AND LOCAL, STATE AND FEDERAL REGULATIONS.
- ALL NECESSARY TESTING SHALL BE PERFORMED BY AN APPROVED LABORATORY AT THE EXPENSE OF
- PRIOR TO CONSTRUCTION, ALL CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH THE CONTRACT DOCUMENTS AND SPECIFICATIONS AND ALL OTHER NECESSARY DETAILS AND SPECIFICATIONS RELEVANT TO THE PROPER COMPLETION OF THE WORK SPECIFIED. FAILURE ON THE PART OF THE CONTRACTOR TO FAMILIARIZE THEMSELVES WITH ALL STANDARDS OR SPECIFICATIONS PERTAININ THIS WORK SHALL IN NO WAY RELIEVE THE CONTRACTOR OF RESPONSIBILITY FOR PERFORMING T WORK IN ACCORDANCE WITH ALL SUCH APPLICABLE STANDARDS AND SPECIFICATIONS.
- THE CONTRACTOR SHALL HAVE IN THEIR POSSESSION PRIOR TO CONSTRUCTION ALL NECESSARY PERMITS, LICENSES, BONDS, INSURANCE, ETC. CONTRACTORS SHALL EACH HAVE AT LEAST ONE SET OF APPROVED ENGINEERING PLANS AND SPECIFICATIONS ON-SITE AT ALL TIMES.
- IN THE EVENT THAT AN ITEM IS NOT SPECIFICALLY COVERED IN THE PERTINENT AGENCIES CONSTRUCTION STANDARDS AND SPECIFICATIONS AND DETAILS, THECONTRACTOR SHALL NOTIFY THE OWNER AND PROJECT ENGINEER. THE OWNER SHALL HAVE THE FINAL DECISION ON ALL CONSTRUCTION
- THE CONTRACTORS MUST CONFINE THEIR ACTIVITIES TO THE WORK AREA AS SHOWN ON THE PLANS, NO ENCROACHMENTS OUTSIDE OF THE SPECIFIED AREAS SHALL BE ALLOWED. ANY DAMAGE RESULTING THERE FROM SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR.
- IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT ALL EXISTING PUBLIC AND PRIVATE UTILITIES THROUGHOUT THE CONSTRUCTION OF THE PROJECT. THE CONTRACTOR SHALL CONTACT THE APPROPRIATE UTILITY COMPANIES OR LINE LOCATION SERVICES PRIOR TO COMMENCEMENT OF CONSTRUCTION AND SHALL ASSUME FULL LIABILITY TO THOSE COMPANIES FOR ANY DAMAGES CAUSED
- TRENCH BEDDING SHALL BE AS PER WYDOH CONSTRUCTION AND MATERIAL SPECIFICATIONS. LATEST
- TOP OF NATURAL GAS PIPELINE SHALL BE A MINIMUM OF 3-0° BELOW THE FINISHED GROUND ELEVATION IN ALL VEGETATED AREAS, EXCEPT IN AGRICULTURAL FIELDS, WHICH THE DEPTH SHALL BE 4-0°. MINIMUM BURY UNDER ROADWAYS AND OTHER PAVED AREAS SHALL BE PER THE PERMITTING AUTHORITIES SPECIFICATIONS AND THE ASSOCIATED PERMIT & DRAWINGS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH STANDARD TRENCH SAFETY GUIDELINES AND THE U.S. DEPARTMENT OF LABOR AND OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) STANDARDS.
- THESE PLANS DO NOT CONSTITUTE A BOUNDARY SURVEY. BOUNDARY LINES AS SHOWN HEREON ARE BASED ON TAX MAPS AS PROVIDED BY OWNER.
- THE CONTRACTOR IS RESPONSIBLE FOR NOTIFICATION TO THE PROJECT MANAGER FOR ANY DEVIATION FOUND RELATIVE TO THE PROJECT.
- EXISTING EASEMENTS AND/OR RIGHT-OF-WAYS WERE NOT RESEARCHED AND SURVEYED DURING THIS PROJECT, OTHER THAN THOSE SHOWN WITHIN THE PLANS.
- FENCE LINES ENCOUNTERED DURING CONSTRUCTION SHOULD BE RELOCATED AND REPLACED PER
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING THE GOVERNING AUTHORITIES PRIOR TO ALL ROAD CROSSINGS. MAINTENANCE OF TRAFFIC IS TO BE IMPLEMENTED AS NECESSARY TO ENSURE THAT THE ROAD HAS CONTINUAL ACCESS. MAINTENANCE OF TRAFFIC SHALL BE PER THE LATEST EDITION OF THE WYDOH TEMPORARY TRAFFIC CONTROL FOR STREETS AND HIGHWAYS MANUAL

GENERAL CONSTRUCTION SEQUENCE

THE PIPELINE PROJECT CONSISTS OF ONE GENERAL CONSTRUCTION PHASE. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND THE WEST VIRGINIA DEPARTMENT OF NATURAL RESOURCES (WVDNR) AND WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (WVDEP) EROSION AND SEDIMENT CONTROL FIELD MANUAL.

THE CONSTRUCTION SEQUENCE IS INTENDED AS A GENERAL COURSE OF ACTION TO COMPLY WITH WVDNR AND WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (WVDEP) EROSION AND SEDIMENT CONTROL REGULATIONS. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL MEASURES NECESSARY TO MEET APPLICABLE RULES AND REGULATIONS ARE INSTALLED. MEASURES AS SHOWN ON THESE PLANS MAY BE ALTERED TO BETTER MEET SITE SPECIFIC CONDITIONS AT THE DISCRETION OF THE

BMP DETAILS AND CONSTRUCTION SPECIFICATIONS CAN BE FOUND ON THE STANDARD DETAIL SHEETS

- 1. A COPY OF THE FOR CONSTRUCTION PLANS MUST BE AVAILABLE ON THE PROJECT SITE AT ALL TIMES.
- AT LEAST THREE DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITY, ALL CONTRACTORS INVOLVED IN THESE ACTIVITIES SHALL NOTIFY THE WEST VIRGINIA ONE CALL SYSTEM BEFORE STARTING ANY CONSTRUCTION ACTIVITIES.
- PRIOR TO COMMENCEMENT OF ANY EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING, CONTRACTOR SHALL CLEARLY DELINEATE SENSITIVE AREAS, RIPARIAN FOREST BUFFER BOUNDARIES, THE LIMITS OF CLEARING, AND TREES THAT ARE TO BE CONSERVED WITHIN THE PROJECT SITE, AND INSTALL APPROPRIATE BARRIERS WHERE EQUIPMENT MAY NOT BE PARKED, STAGED. OPERATED OR LOCATED FOR ANY PURPOSE. APPROPRIATE BMP's SHOULD BE INSTALLED AND
- CONSTRUCTION FENCE SHALL BE INSTALLED AT LOCATIONS SHOWN ON THE PLANS. CONSTRUCTION FENCE SHALL BE CHECKED REGULARLY FOR WEATHER RELATED OR OTHER DAMAGE. ANY NECESSARY REPAIRS SHALL BE MADE IMMEDIATELY.
- INSTALLATION OF STONE CONSTRUCTION ENTRANCES AT ALL ACCESS LOCATIONS SHALL BE THE FIRST STEP OF CONSTRUCTION AND SHALL BE FOLLOWED BY INSTALLATION OF BMP's FOR ALL AREAS DESIGNATED FOR EQUIPMENT AND MATERIAL STAGING.
- INSTALL ROCK CHECK DAMS AT LOCATIONS SHOWN ON THE PLANS, INSPECT EACH CHECK DAM AT A MINIMUM ONCE EVERY SEVEN DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAT 0. INCHES OF RAIN PER 24 HOUR PERIODS. CHECK TO SEE IF WATER HAS FLOWED AROUND THE EDGE OF THE STRUCTURE, REPLACE STONE AND REPAIR DAM AS NECESSARY TO MAINTAIN THE CORRECT HEIGHT AND CONFIGURATION. SEDIMENT SHALL BE REMOVED FROM BEHIND THE CHECK DAMS WHEN IT HAS ACCUMULATED TO ONE HALF OF THE ORIGINAL HEIGHT OF THE DAM
- INSTALL PERIMETER BMP's (SILT FENCING OR FILTER SOCKS) WHERE NECESSARY ALONG CLEARING AND GRUBBING BOUNDARIES.
- BEGIN LAND CLEARING AND GRADING (IF NECESSARY) ONLY AFTER ALL DOWNSLOPE BMP'S HAVE BEEN INSTALLED. IF POSSIBLE, MINIMIZE CLEARING AND GRADING AT STREAM CROSSINGS UNTIL THE TIME OF
- APPLY TEMPORARY OR PERMANENT STABILIZATION MEASURES IMMEDIATELY TO ANY DISTURBED AREAS WHERE WORK HAS REACHED FINAL GRADE, HAS BEEN DELAYED OR OTHERWISE TEMPORARILY
- INSTALL TEMPORARY WATERBARS AT LOCATIONS SHOWN ON THE DRAWINGS, WATERBARS WILL BE INSTALLED WITH FILTER SOCKS AT THE DISCHARGE TO HELP CONTROL THE VOLUME AND SPEED OF
- INSTALL BMP's FOR TEMPORARY ROAD CROSSINGS OF WETLANDS AND WATER BODIES WITHIN T PIPELINE ROW AS NECESSARY, FOLLOW STREAM AND WETLAND CROSSING DETAILS FOR ACCESS ROAD CROSSINGS OF THESE FEATURES, FILTER SOCKS SHALL BE USED AT ALL STREAM CROSSINGS. SEE STREAM CROSSING PROCEDURES AND WETLAND CROSSING PROCEDURES FOR ADDITIONA
- CONSTRUCTION OF UTILITIES (INSTALL NATURAL GAS PIPELINE). WHEN TRENCH EXCAVATION TAKES PLACE IN AN AGRICULTURAL, WETLAND, OR RESIDENTIAL AREA, THEN SEGREGATION OF TOPSOIL AND SUBSOIL WILL BE PERFORMED PLACE TRENCH PLUGS AT THE REQUIRED SPACING DURING LITH ITS SUBSOIL WILL BE PERFORMED. PLACE THENCH PLUGS AT THE REQUIRED SPACING DURING UTILITY INSTALLATION, FOLLOW STREAM AND WETLAND CROSSING DETAILS LOCATED ON THE EROSION AND SEDIMENT CONTROL DRAWINGS FOR UTILITY CROSSINGS OF THESE FEATURES. SEE STREAM CROSSING PROCEDURES AND WETLAND CROSSING PROCEDURES FOR ADDITIONAL INFORMATION ON WATER BODY AND WETLAND CROSSING, DURING CONSTRUCTION, INSTALL AND MAINTAIN ANY ADDITIONAL EROSION AND SEDIMENT CONTROL BMP'S AND IMPLEMENT STRUCTURAL POST CONSTRUCTION STORMWATER NENT WATERBARS) THAT MAY BE REQUIRED. SEE UTILITY LINE INSTALLATION
- ANY WATER ENCOUNTERED WITHIN THE EXCAVATION AREAS DURING CONSTRUCTION SHALL BE REMOVED BY USING PUMPS, HOSES, AND PUMPED WATER FILTER BAGS WHICH SHALL BE DISCHARGED O UNDISTURBED WELL-VEGETATED UPLAND AREAS.
- BACKFILL AREAS EXCAVATED FOR THE INSTALLATION OF UTILITIES WITH SUITABLE EXCAVATED MATERIAL, IN AREAS WHERE TOPSOIL HAS BEEN SEGREGATED. THE SUBSOIL SHALL BE REPLACED FIRST, FOLLOWED BY THE TOPSOIL BEING SPREAD OVER THE AREA FROM WHICH IT WAS REMOVED. FINAL GRADES SHALL BE THE SAME AS PRE-CONSTRUCTION CONTOURS.
- AFTER CONSTRUCTION IS COMPLETE, FINAL SEEDING AND MULCHING OF ALL DISTURBED AREAS NOT YET STABILIZED SHALL BE COMPLETED. INSTALL EROSION CONTROL BLANKETING ON SLOPES WHICH ARE 3:1 OR STEEPER. STABILIZE AND SEED ALL OPEN AREAS INCLUDING BORROW AND SPOIL AREAS.
- REMOVAL OF ALL TEMPORARY BMP's CAN BE PERFORMED UPON ACHIEVEMENT OF A UNIFORM 70 PERCENT PERENNIAL VEGETATIVE COVER WITH A DENSITY CAPABLE OF RESISTING ACCELERATED EROSION FOR ALL AREAS WHICH WOULD CONTRIBUTE RUNOFF TO THE BMP's. STABILIZE ANY DISTURBANCES ASSOCIATED WITH THE REMOVAL OF THE BMP's.

WETLAND CROSSING SEQUENCE OF CONSTRUCTION

- INSTALL TEMPORARY EROSION AND SEDIMENT CONTROLS PRIOR TO EARTH DISTURBANCE.
- 2. SEDIMENT BARRIERS SHALL BE INSTALLED AT THE EDGE OF THE RIGHT-OF-WAY AND AROUND TOPSOIL AND SUBSOIL PILES.
- GEOTEXTILE SHALL BE PLACED UNDER SUBSOIL AND TOPSOIL PILES.
- WORKING SIDE OF TRENCH WILL BE STABILIZED WITH PRE-FABRICATED MATS, AS NEEDED, TO PROVIDE A FIRM SURFACE FOR CONSTRUCTION EQUIPMENT, FOR HEAVY SATURATED AREAS, GEOTEXTILE SHALL BE PLACED UNDER THE MATS TO PREVENT MOVEMENT OR PUMPING OF THE SOIL THROUGH THE MATS.
- IN WETLAND AREAS WITHOUT STANDING WATER OR SATURATED SOILS, TOPSOIL (TOP 12 INCHES) AND SUBSOIL SHALL BE SEGREGATED AND STOCKPILED DURING TRENCHING.
- UPON COMPLETION OF PIPE INSTALLATION THROUGH WETLAND, TRENCH PLUG(S) SHALL BE INSTALLED
- THE SEGREGATED TOPSOIL SHALL BE RESTORED TO IT'S ORIGINAL CONDITION DURING BACKFILLING. THE ORIGINAL TOPSOIL SHALL BE KEPT IN A CONDITION THAT WILL ALLOW IT TO MAINTAIN SUFFICIENT SEED AND ROOT MATERIAL AND TO PROVIDE VEGETATIVE COVER.
- ALL SEEDING SHOULD COMPLY WITH EITHER OPTION "A" OR OPTION "B" SEED MIXES LISTED UNDER THE SPECIAL NOTES SECTION FOR STREAMWETLAND CROSSINGS CONTAINED IN THESE DRAWINGS. SEEDING ONLY, WITH NO FERTILIZING, SHALL BE DONE IN CRITICAL AREAS (i.e. WITHIN 50" OF AN HQ OR EV STREAM CHANNEL OR WITHIN WETLANDS). DO NOT APPLY MULCH WITHIN WETLANDS.

"OPEN CUT" STREAM CROSSING (TEMPORARY) CONSTRUCTION SEQUENCE - PIPE INSTALLATION

- ALL IN-STREAM DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE SHOULD BE COMPLETED IN COMPLIANCE WITH WYDEP'S OFFICE OF CONSTRUCTION STORMWATER EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE MANUAL BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE.
- ALL WORK SHALL BE PERFORMED IN LOW FLOW CONDITIONS AND EACH CROSSING SHALL BE COMPLETED WITHIN 72 HOURS OF START OF WORK.
- POINTS OF INGRESS AND EGRESS TO STREAMS FOR EQUIPMENT SHALL BE WITHIN THE WORK SITE
- SURFACE DISTURBANCE WILL NOT EXTEND BEYOND THE RIGHT-OF-WAY LIMITS, STREAM CROSSINGS WILL BE CONDUCTED AS CLOSE TO A RIGHT ANGLE TO THE WATERCOURSE AS PRACTICAL AND THE AREA OF DISTURBANCE WILL BE LIMITED TO REDUCE IN STREAM ACTIVITY.
- INSTALL TEMPORARY COFFER DAM AT UPSTREAM EDGE OF PROPOSED WORK AREA. DEWATER THE COFFERDAM AS NECESSARY.
- OPEN CUT CHANNEL TO A WIDTH AND DEPTH THAT IS NO MORE THAN WHAT IS NECESSARY FOR INSTALLATION OF PIPE. DURING EXCAVATION, SEPARATE THE INITIAL ONE FOOT OF STREAM SUBSTRATE FROM THE SUBSURFACE MATERIAL INTO TWO SEPARATE PILES.
- INSTALL PIPE AS SHOWN ON PLANS.
- BACKFILL TRENCH BY FIRST ADDING SUBSURFACE MATERIAL, THEN THE STREAM SUBSTRATE MATERIAL, ENSURING THAT ORIGINAL GRADE, DIMENSIONS, AND CONTOURS OF THE CHANNEL ARE
- REMOVE COFFERDAM AND STABILIZE ANY REMAINING DISTURBED AREAS.

STREAM CROSSING (TEMPORARY) CONSTRUCTION SEQUENCE - ACCESS ROADS


- ALL IN STREAM DISTURBANCE ACTIVITY SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE SHALL BE COMPLETED IN COMPLIANCE WITH WYDEP, THE WEST VIRGINIA OFFICE OF LAND AND STREAMS (WYOLS), THE WDNR, AND THE U.S. ARMY CORPS OF ENGINEERS
- STREAM CROSSING SHALL MEET THE REQUIREMENTS OF THE WYDEP'S OFFICE OF CONSTRUCTION STORMWATER EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE MANUAL CHAPTER
- SEE CULVERT STREAM CROSSING FROM THE WYDEP'S OFFICE OF CONSTRUCTION STORMWATER EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE MANUAL.
- ALL WORK SHALL BE PERFORMED IN LOW FLOW CONDITIONS AND EACH CROSSING SHALL BE COMPLETED WITHIN 72 HOURS OF START OF WORK.
- POINTS OF INGRESS AND EGRESS TO STREAMS FOR EQUIPMENT SHALL BE WITHIN THE WORK SITE
- SURFACE DISTURBANCE WILL NOT EXTEND BEYOND THE RIGHT-OF-WAY LIMITS. STREAM CROSSINGS WILL BE CONDUCTED AS CLOSE TO A RIGHT ANGLE TO THE WATERCOURSE AS PRACTICAL AND THE AREA OF DISTURBANCE WILL BE LIMITED TO REDUCE IN STREAM ACTIVITY.
- INSTALL TEMPORARY COFFER DAM AT UPSTREAM EDGE OF PROPOSED WORK AREA. DEWATER THE COFFERDAM AS NECESSARY
- INSTALL ACCESS ROAD TEMPORARY CROSSING AS SHOWN ON PLANS
- REMOVE COFFERDAM AND STABILIZE ANY REMAINING DISTURBED AREAS.

UTILITY LINE INSTALLATION REQUIREMENTS

- THE CONTRACTOR SHALL LIMIT TRENCH EXCAVATION TO THE LENGTH OF PIPE PLACEMENT AND BACKFILL THAT CAN BE INSTALLED IN ONE DAY.
- THE CONTRACTOR SHALL GRADE TO FINAL CONTOURS, INSTALL REQUIRED EROSION CONTROL MEASURES, AND SEED AND MULCH ALL DISTURBED AREAS AT THE END OF EACH WEEK.
- DEWATER ALL TRENCHES PRIOR TO PIPE INSTALLATION AND BACKFILLING, ALL WATER TO BE PUMPED
- 4. ALL TRENCH EXCAVATION MATERIAL TO BE PLACED ON DOWNHILL SIDE OF TRENCH.
- IN THE EVENT THAT THESE REQUIREMENTS CAN'T BE MET DUE TO FIELD CONDITION, THE CONTRACTOR SHALL COORDINATE ALTERNATE REQUIREMENTS WITH OWNER'S REPRESENTATIVE.

UTILITY RIGHT-OF-WAY RESTRICTIONS

- CONSTRUCTION VEHICLES. VEHICLES WITH BOOMS AND EQUIPMENT OPERATING WITHIN OR ADJACENT TO A UTILITY RIGHT-OF-WAY MUST BE PROPERLY GROUNDED.
- CHANGES TO GRADE ELEVATION WITHIN THE UTILITY RIGHT-OF-WAY ARE NOT PERMITTED.
- GROUND DISTURBANCE OR EXCAVATIONS ARE NOT PERMITTED WITHIN 50 FEET OF ANY UTILITY STRUCTURES (POLES, TOWERS, GUYS, ETC.)
- EXPLOSIVES OR COMBUSTIBLE LIQUIDS, SUBSTANCES, OR MATERIALS ARE NOT PERMITTED WITHIN THE RIGHT-OF-WAY. PROHIBITED MATERIALS INCLUDE BUT ARE NOT LIMITED TO FUEL, WOOD CHIPS, MULCH,



CREATION TO COMPLETION www.cesoinc.com

OX11-OX13 PIPELINE

SWPPP NOTES

STATION(S):

CONSOL ENERGY 200 EVERGREENE DRIVE

WAYNESBURG, PA 15370

KIPROJECTSICONSCI, ENERGY/090129-00 - SHERWOOD SOUTH PIPELINE/DESIGN/BASE DWGS/09129-0

DATE: 08/01/14 JOB NO.: 90126 DESIGN: BEM DRAWN: BEM CHECKED: ВЈМ SHEET NO 2 of 10

EROSION AND SEDIMENT CONTROL NARRATIVE:

PLAN DESIGNER: CESO, INC

2800 CORPORATE EXCHANGE DRIVE, SUITE 160 COLUMBUS, OH 43231

ONE ENERGY DRIVE JANE LEW, WV 26378 CONTACT: BENJAMIN J. MILLER, PE

CONTACT: ADAM WHITE E: ADAMWHITE@CONSOLENERGY.COM

OWNER: CONE GATHERING, LLC

E: MILLER@CESOINC.COM

WV DEP PERMIT # WVRXXXXXX

PROJECT DESCRIPTION: THIS PROJECT CONSISTS OF CONSTRUCTING 2-30" AND 1-16" NATURAL GAS PIPELINES AND 1-16" WATER LINE IN DODDRIDGE COUNTY, WEST VIRGINIA

17.08 ACRES TOTAL PROJECT AREA 0 ACRES PROPOSED IMPERVIOUS AREA

0 CY CUT/ 0 CY FILL (BALANCED)

EXISTING SITE CONDITIONS: THE TOPOGRAPHY OF THIS SITE CONSISTS OF MANY RIDGES AND VALLEYS. THIS SITE CONSISTS PREDOMINATELY OF WOODS AND OPEN FIELDS. THIS SITE DRAINS TO CAIN RUN.

ADJACENT AREAS:

ADJACENT AREAS THAT MAY BE AFFECTED BY SITE DISTURBANCE INCLUDE WETLAND EC. WETLAND 1, AND CAIN RUN RD (CR 40).

CRITICAL AREAS

PIPELINE: STREAM EH, WETLAND EG, STREAM EF, STREAM EC, STREAM EB, AND WETLAND EA REQUIREMENTS FOR WORKING IN OR NEAR CRITICAL AREAS CAN BE FOUND ON SHEETS 2-6

SOILS

Soil name	Soll Mapping Unit	Erodibility (K Factor, Whole Soil)	Settleability (Unavailable)	Permeability	Depth (cm)	Texture	Soil Structure (Unavailable)
GILPIN-PEABODY COMPLEX, 15 TO 35 PERCENT SLOPES, VERY STONY	GSE	0.37		Well drained	84	Silt loam	,
GILPIN-PEABODY COMPLEX, 35 TO 70 PERCENT SLOPES, VERY STONY	GsF	0.37		Well drained	84	Sift loam	
GILPIN UPSHUR COMPLEX, 15 TO 25 PERCENT SLOPES	GuD	0.43		Well drained	84	Silt loam	
SENSABAUGH SILT LOAM	Se	0.37		Well drained	>200	Silt loam	-
SENSABAUGH SILT LOAM, 3 TO 8 PERCENT SLOPES, RARELY FLOODED	SeB	0.37		Well drained	>200	Silt loam	

THE DRAINAGE PATH LEADING FROM THE SITE TO THE RECEIVING BODY OF WATER CONSISTS OF VEGETATED SWALES, EXISTING EROSIONAL FEATURES, AND TRIBUTARIES OF STREAMS.

*Data obtained from NRCS-USDA Web Soil Survey

EROSION PROBLEM AREAS: POTENTIAL EROSION PROBLEMS ON THIS SITE EXIST ALONG STEEP SLOPES WHERE THE PIPELINE WILL BE LAID.

CONSTRUCTION STORMWATER THE SEGMENT CONTROL PLAN SHOWS ALL CLEARING LIMITS AND PROPOSED SEGMENT CONTROLS. THE GENERAL NOTES ADDRESS THE STARILIZATION OF SOILS SLOPE PROTECTION CONTROL OF OTHER ENANCE OF BMPs, MANAGEMENT OF THE PROJECT, AND STABILIZATION. TYPES OF BMPs USED ON THIS PROJECT INCLUDE FILTER SOCKS, WATER BARS, TRENCH PLUGS, SILT FENCE, AND SUPER SILT FENCE. REFER TO SHEETS 7-8 FOR LOCATIONS.

SCHEDULE:

CONSTRUCTION PHASING AND THE CONSTRUCTION SEQUENCE FOR THIS PROJECT CAN BE FOUND ON SHEET 2, WET SEASON CONSTRUCTION ACTIVITIES INCLUDE BUT ARE NOT LIMITED TO CLEARING, EROSION & SEDIMENT CONTROL INSTALLATION, ACCESS ROAD CONSTRUCTION, TRENCH EXCAVATION, UTILITY PLACEMENT, BACKFILLING, AND OPEN CUTTING OF STREAMS. CONSTRUCTION RESTRAINTS FOR ENVIRONMENTALLY CRITICAL AREAS

ENGINEERING CALCULATIONS: NO ENGINEERING CALCULATIONS ARE REQUIRED FOR THIS PROJECT.

<u>remporary</u>	SEEDING	CHART

-			PLS	
Common Name	Scientific Name	Planting Dates	Lbs/Acre	
Annual Ryegrass	Lolium multiflorum	2/16-5/15, 8/1-11/1	40	
Field Bromegrass	Bromus ciliatus	3/1-6/15, 8/1-9/15	40	
Spring Oats	Avena sativa	3/1-6/15	100	
Winter Rye	Secale cereale	8/15-2/28	170	
Winter Wheat	Triticum aestivum	8/18-2/28	180	
Japanese Millet	Echinochtoa crusgalli	5/15-8/15	30	
Redtop	Agrostis alba	3/1-6/15	10	
Annual Ryegrass and Spring Oats	Lolium multiflorum, Avena sativa	3/1-6/15	30, 70	
German, Foxtail Millet	Seteria italica	5/1-8/1	40	
Hairy Vetch	Vicia villosa	8/15-4/1	60	

- PRIOR TO SEEDING, INSTALL NECESSARY EROSION CONTROL PRACTICES SUCH AS DIKES, WATERWAYS, AND
- SEED SHALL BE EVENLY APPLIED WITH A BROADCAST SEEDER, DRILL, CULTIPACKER SEEDER, OR HYDROSEEDER. SWALL GRAINS SHALL BE PLANTED NO MORE THAN 1.5 INCHES DEEP. SMALL SEEDS, SUCH AS ANNUAL RYE, SHALL BE PLANTED NO MORE THAN A CHARTER INCH DEEP. OTHER GRASSES AND LEGUMES SHALL BE PLANTED NO MORE THAN A HALF INCH DEEP.
- TEMPORARY SEEDING CONDUCTED IN FALL FOR WINTER COVER AND DURING HOT AND DRY SUMMER MONTHS SHALL BE MULCHED WITH STRAW AND HAY ACCORDING TO THE STANDARD FOR MULCHING, HYDROMULCHES (FIBER MULCH) MAY NOT PROVIDE ADEQUATE TEMPERATURE AND MOISTURE CONTROL.

PERMANENT SEEDING CHART

Seed Mix	Common Name	Scientific Name	PLS Lbs/Acre
<u> </u>	Perennial Ryegrass	Lolium perenne	40
	Birdsfoot Trefoil	Lotus comiculatus	15
	Redtop	Agrostis alba	5
р	Serecia Lespedeza	Lespedeza cunata	40
	Orchardgrass	Dactylis glomerata	30
	Podion	Agmetic alba	

- ALL PERMANENT SEEDING SHALL CONFORM TO WY DEP EROSION AND SEDIMENT CONTROL BEST MANAGEMENT
- 2. SEED MIX O OR P SHALL BE USED FOR PERMANENT SEEDING.

EROSION & SEDIMENT CONTROL PLAN NOTES

- ALL EROSION AND SEDIMENTATION CONTROL SHALL BE PERFORMED ACCORDING TO: THIS PLAN; WEST VIRGINIA GENERAL WATER POLLUTION CONTROL PERMIT; ANY AND ALL REQUIRED PERMITS, REPORTS, AND RELATED DOCUMENTS. ALL CONTRACTORS AND SUBCONTRACTORS MUST BECOME FAMILIAR WITH
- CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES AS REQUIRED BY THE EROSION CONTROL PLAN. ADDITIONAL BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED AS DICTATED BY CONDITIONS AND GRADE CHANGES TO THE SITE AT NO ADDITIONAL COST TO OWNER THROUGHOUT ALL PHASES OF CONSTRUCTION
- CONTRACTOR SHALL MINIMIZE CLEARING AND DISTURBANCE TO THE ENVIRONMENT TO THE MAXIMUM EXTENT POSSIBLE OR AS REQUIRED BY THE GENERAL PERMIT.
- PERIMETER SEDIMENT BARRIERS SHALL BE IMPLEMENTED AS THE FIRST STEP OF GRADING WITHIN SEVEN (7) DAYS FROM THE START OF CLEARING AND GRUBBING. AND SHALL CONTINUE TO FUNCTION UNTIL THE SLOPE DEVELOPMENT AREA IS RESTABILIZED.
- STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN SEVEN DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS
- WHERE THE INITIATION OF STABILIZATION MEASURES BY THE SEVENTH DAY AFTER CONSTRUCTION ACTIVITY TEMPORARILY OR PERMANENTLY CEASES IS PRECUIDED BY SNOW COVER, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS CONDITIONS ALLOW.
- WHERE CONSTRUCTION ACTIVITY WILL RESUME ON A PORTION OF THE SITE WITHIN 14 DAYS FROM WHEN ACTIVITIES CEASED, (E.G., THE TOTAL TIME PERIOD THAT CONSTRUCTION ACTIVITY IS TEMPORARILY HALTED IS LESS THAN 14 DAYS) THEN STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE BY THE SEVENTH DAY AFTER CONSTRUCTION ACTIVITIES HAVE
- AREAS WHERE THE SEED HAS FAILED TO GERMINATE ADEQUATELY (UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 70%) WITHIN 30 DAYS AFTER SEEDING AND MULCHING MUST BE RESEEDED IMMEDIATELY, OR AS SOON AS WEATHER CONDITIONS ALLOW.
- TEMPORARY SEEDING SHALL BE IN ACCORDANCE WITH WYDEP'S OFFICE OF CONSTRUCTION STORMWATER EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE MANUAL, CHAPTER 3 10
- 10. PERMANENT SEEDING SHALL BE IN ACCORDANCE WITH WYDEP'S OFFICE OF CONSTRUCTION STORMWATER EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE MANUAL, CHAPTER
- 11. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION, ALL SLOPES 3:1 OR GREATER THAN 3:1 SHALL BE FERTILIZED, SEEDED, AND CURLEX BLANKETS BY AMERICAN EXCELSIOR COMPANY, NORTH AMERICAN GREEN, INC. OR AN ROVED EQUAL AS SPECIFIED IN THE PLANS SHALL BE INSTALLED ON THE SLOPES.
- 12. NO SOLID (OTHER THAN SEDIMENT) OR LIQUID WASTE, INCLUDING BUILDING MATERIALS, SHALL BE DISCHARGED IN STORM WATER RUNDER ALL NON-SEDIMENT POLITITANTS MUST BE DISPOSED OF IN DISCHARGEU IN STORM WATER KONDIFF. ALL NOTINSCHIMENT POLICUTARITY MUST BE LISTUED OF IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL GUIDELINES. WASH OUT OF CEMENT TRUCKS SHOULD CCCUR IN DESIGNATED PIT OR DIKED AREAS, WHERE WASHINGS CAN BE REMOVED AND PROPERLY DISPOSED OFF-SITE WHEN THEY HARDEN. STORAGE TANKS SHOULD ALSO BE LOCATED IN PIT OR DIKED AREAS. IN ADDITION, SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS TO CLEAN AND CONTAIN FUEL AND CHEMICAL SPILLS MUST BE KEPT ON SITE
- 13. IF THE ACTION OF VEHICLES TRAVELING OVER THE STABILIZED CONSTRUCTION EXIT DOES NOT SUFFICIENTLY REMOVE MOST OF THE DIRT AND MUD, THEN THE TIRES MUST BE WASHED BEFORE VEHICLES ENTER A PUBLIC ROAD. PROVISIONS MUST BE MADE TO INTERCEPT THE WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF THE SITE.
- RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DISPOSED INTO SEALED CONTAINERS. MATERIALS SHALL BE PREVENTED FROM LEAVING THE SITE THROUGH THE ACTION OF WIND OR STORM WATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS OF THE STATE.
- 15. DUST CONTROL USING APPROVED MATERIALS MUST BE PERFORMED AT ALL TIMES. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION IS PROHIBITED.
- 16. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED ONTO THE ROADWAYS OR INTO THE STORM SEWERS MUST BE REMOVED IMMEDIATELY.


EROSION & SEDIMENT CONTROL MAINTENANCE NOTES

ALL CONTROL MEASURES STATED IN THIS PLAN SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION LINTIL ALL CONTROL MEASURES STATE IN THIS PLAN SAILL BE MAINTAINED IN POLLY FUNCTIONAL CONDITION OF TEMPORARY OR PERMANENT STABILIZATION OF THE SITE IS ACHIEVED, ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSPECTED BY A QUALIFIED PERSON IN ACCORDANCE TO THE CONTRACT DOCUMENTS OR THE APPLICABLE PERMIT, WHICHEVER IS MORE STRINGENT, AND REPAIRED ACCORDING TO

- ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO ENSURE THAT A GOOD STANDING OF GRASS IS TAINED. AREAS SHOULD BE FERTILIZED, WATERED, AND RESEEDED AS NEEDED.
- SILT FENCES, AND CHECK DAMS SHALL BE REPAIRED TO THEIR ORIGINAL CONDITION IF DAMAGED. SEDIMENT ACCUMULATION MUST BE REMOVED WHEN SEDIMENT HEIGHT REACHES ONE-HALF THE HEIGHT OF THE SILT FENCE OR CHECK DAM.
- SEDIMENTATION TRAPS SHALL BE MAINTAINED IN OPERATIONAL CONDITIONS AT ALL TIMES. SEDIMENT MUST BE REMOVED FROM TRAPS WHEN THE DESIGN CAPACITY HAS BEEN REDUCED BY 40%.
- MINIMIZE OFF, SITE SEDIMENT TRACKING OF VEHICLES BY THE LISE OF STONE MATERIAL IN ALL MINIMIZE OF 7-31 SEDIMENT INACKING OF VEHICLES BY THE USE OF STARE WITH FAMILY CONSTRUCTION ENTRANCES, ALONG WITH REGULARLY SCHEDULED SWEEPINGGOOD HOUSEKEEPING.
 STABILIZED CONSTRUCTION ENTRANCES TO BE PROPERLY MAINTAINED BY GENERAL CONTRACTOR AND IN GOOD WORKING ORDER AT ALL TIMES; THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE STONE AS CONDITIONS DEMAND.
- THE TEMPORARY PARKING AND STORAGE AREA SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE) BY GENERAL CONTRACTOR. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING AS CONDITIONS DEMAND.
- CONTRACTORS AND SUBCONTRACTORS WILL BE RESPONSIBLE FOR REMOVING ALL SEDIMENT FROM THE SITE, INCLUDING SEDIMENT TRAPS AND STORM SEWER PIPES. SEDIMENT DEPOSITION DURING SITE STABILIZATION MUST ALSO BE REMOVED.
- ALL ROCK CHANNEL PROTECTION MUST BE PLACED OVER GEOTEXTILE FILTER.
- ROCK CHECK DAMS SHOULD BE ROUTINELY CLEANED ONCE SEDIMENT BEGINS TO APPEAR ON THE UPSTREAM SIDE OF THE ROCK.
- CONTAINERS SHALL BE AVAILABLE FOR DISPOSAL OF DEBRIS. TRASH, HAZARDOUS OR PETROL FLIM WASTES, ALL CONTAINERS MUST BE COVERED AND LEAK-PROOF, ALL WASTE MATERIAL SHALL BE DISPOSED OF AT FACILITIES APPROVED FOR THE PERTINENT MATERIAL.
- AREA SHALL BE DESIGNATED BY CONTRACTOR AND SHOWN ON SWPPP MAP FOR MIXING OR STORAGE OF COMPOUNDS SUCH AS FERTILIZERS, LIME ASPHALT, OR CONCRETE, THESE DESIGNATED AREAS SHALL BE LOCATED AWAY FROM WATERCOURSES, DRAINAGE DITCHES, FIELD DRAINS, OR OTHER STORMWATER DRAINAGE AREA.
- EQUIPMENT FUELING & MAINTENANCE SHALL BE IN DESIGNATED AREAS ONLY.
- 12. A SPILL PREVENTION CONTROL AND COUNTERMEASURE (SPCC) PLAN MUST BE DEVELOPED FOR SITES WITH ONE ABOVE GROUND STORAGE TANK OF 650 GALLONS OR MORE, TOTAL ABOVE GROUND STORAGE OF 1,330 GALLONS OR BELOW-GROUND STORAGE OF 4,200 GALLONS OF FUEL
- 13. ALL CONTAMINATED SOIL MUST BE TREATED AND/OR DISPOSED IN AN WYDEP APPROVED SOLID WASTE MANAGEMENT FACILITY OR HAZARDOUS WASTE TREATMENT, STORAGE OR DISPOSAL FACILITIES,
- THE CONTRACTOR SHALL CONTACT THE WYDEP, THE LOCAL FIRE DEPARTMENT AND THE LOCAL EMERGENCY PLANNING COMMITTEE IN THE EVENT OF A PETROLEUM SPILL (>25 GALLONS) OR THE PRESENCE OF SHEEN.

EROSION & SEDIMENT CONTROL MAINTENANCE NOTES

ALL EROSION AND SEDIMENT CONTROLS ON THE SITE SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES PER 24 HOUR PERIOD. ANY REQUIRED REPAIRS OR MAINTENANCE SHALL BE MADE IMMEDIATELY.





itecture • Survey • Construction Mgt • L

OX11-OX13 PIPELINE

SWPPP NOTES


N/A


STATION(S):



200 EVERGREENE DRIVE WAYNESBURG, PA 15370 DATE: 08/01/14 JOB NO : 90126 DESIGN: BEM DRAWN: BEM CHECKED: ВЈМ SHEET NO. 3 of 10

KAPROJECTS/CONSOLENERGY/090128-00 - SHERWOOD SOUTH PIPELINE/DESIGN/BASE DWGS/80128-0X13-0X13 IFC TABLES DWG-8/1/2014 11/21 A






NOT TO SCALE

M SEDIMENT FILTER BAG FOR PUMPED WATER DETAIL NOT TO SCALE

WELL VEGETATED AREA

PLAN VIEW

ELEVATION VEW



NOTES:

THE CHECK DAM SHALL BE CONSTRUCTED OF 48" DIAMETER STONE, PLACED SO THAT IT COMPLETELY COVERS THE WIDTH OF THE CHANNEL.

THE MIDTH OF THE CHANNEL.

MAXIMUM REBOIT OF CHECK DAM SHALL NOT EXCEED 3.0 FEET.


THE MIDPOINT OF THE ROCK CHECK DAM SHALL BE A MINIMUM OF & LOWER THAN THE SIDES IN ORDER TO DIRECT ACROSS THE CENTER AND MANY FROM THE CHANNEL SIDES.

THE BASE OF THE CHECK DAMS SHALL BE ENTRENCHED APPROXIMATELY 8 INCHES.

SPACING OF CHECK DAMS SHALL BE IN A MANNER SUCH THAT THE TOE OF THE UPSTREAM DAM IS AT THE SAME BLEVATION AS THE TOP OF THE DOWNSTREAM DAM.

A SPLANAL PROVINCE SHALL BE ON A SHALL BE CHECK DAMS ARE EXPECTED TO BE IN USE FOR AN A SPLANAL PROVINCE SHALL BE A SHALL BE CHECK DAMS SHALL BE CONSTRUCTED WHERE CHECK DAMS ARE EXPECTED TO BE IN USE FOR AN THE CHANNEL SHALL BE A SHALL BE

(I) ROCK CHECK DAM DETAIL



CROSS SECTION

(N) CONSTRUCTION FENCE DETAIL NOT TO SCALE

IFC		SUMMARY	OF MATERIALS	REFE	RENCE DRAWINGS			REVISIONS
iF(,	MRKR#	QTY.	DESCRIPTION	DWG.	DESCRIPTION	NO.	DATE	DESCRIPTION
•						_		
	-					+		
						+		
							ļ	
					<u> </u>			
08/01/14								
DATE	1 1	l l				1	I	I

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINI REQUIRED FOR DISPOSAL PURPOSES MUST BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY COME 1/2 FULL. SPARE BAGS SHALL BE KEPT AVAILABLE FOR

BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS, WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE FLOW PATH SHALL BE PROVIDED. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%.

THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 12 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHOULD BE FLOATING AND SCREENED.



CREATION TO COMPLETION www.cesoinc.com

OX11-OX13 PIPELINE

8" WYDOH ITEM 703

Scientific Name

Temporary Cover:

Temporary Cover:

Campanula american

GEOTEXTILE -

4" WVDOH ITEM 703

(J) STABILIZED CONSTRUCTION ENTRANCE

OPTION A

Common Name

Rice Cut Grass

Dark Green Rush

Prairie Cord Gras

Water Plantain Mi

Flat-Top Aste:

Buttonbush

Tail Belfflowe

Great Blue Lobelia

Ditch Stanecrop

Wild Golden Glov

NOTE: APPLY AT 32,8 PLS POUNDS PER ACRE.

STATION(S):

NOT TO SCALE

om JFNew or Ernst)

PLS

Ounces/Acre

2.00 4.00 1.50 3.00 1.00 1.00

4.00 20.00 2.00

2.00

2.00

1.00 44.50

360.00

100.00

3.00

1.00

0.75

0.25

2.50 0.50

0.25

2.00

0.75

2.00

0.25 1.25

0.50


0.50

0.75

2.00

19.75

SWPPP DETAILS



TYPICAL TIMBER MAT K FOR WETLAND CROSSING

Scientific Name	OPTION B Wetland Restoration Mixture Common Name	PLS Ounces/Acre
Avena sativa	Common Oat	480.00
Secale cereate	Cereal Rye	480.00
Panicum virgatum	Switch Grass	32.00
Panicum clandestinum	Deer-tongue Grass	32.00
Elymus riparlus	Riverbank Wild Rye	32.00
Poa palustris	March Bluegrass	32.00
Sorghastrum nutans	Indian Grass	16.00
Głyceria striata	Fowl Manna Grass	8.00
Carex crinita	Fringe Sedge	8.00
Carex lurida	Bottlebrush Sedge	8.00
Scirpus atrovirens	Dark Green Rush	8.00
Polygonum pensylvanicum	Pinkweed	8.00
Verbena hastata	Blue Vervain	8.00
Verbesina altemifolia	Wingstern	8.00
Senna hebecarpa	Wild Senna	8.00
STREAM/WETLAND CROSS	ING NOTES	Total 1168.00


ALL TREES AND WOODY DEBRIS REMOVED FROM STREAM OR WETLAND CROSSINGS MUST BE DISPOSED OF OUTSIDE THE RIPARIAN OR WETLAND CROSSING AREAS.

CONSTRUCTION TIMBER MATTING MUST BE USED WHEN EQUIPMENT IS CROSSING WETLANDS AND/OR SOF GROUND.

3. THE SEED MIX FOR STREAM/WETLAND CROSSING AREAS (OPTIONS A OR B) SHALL BE USED.

4. $\underline{\text{NO}}$ FERTILIZER OR LIME SHALL BE USED IN STREAMWETLAND CROSSING AREAS.

5. NO GRUBBING IS ALLOWED AT TEMPORARY ACCESS CROSSINGS OF STREAMS OR WETLANDS.



	REQUIRED SPACIN	G AND MATERIALS FOR TRENCH PLUGS
TRENCH SLOPE (%) SPACING (FT)		PLUG MATERIAL
< 5	•	•
5-15	500	" EARTH FILLED SACKS
15-25	300	" EARTH FILLED SACKS
25-35	200	" EARTH FILLED SACKS
35-100	100	" EARTH FILLED SACKS
> 100	50	CEMENT FILLED BAGS (WETTED) OR MORTARED STONE

TRENCH PLUG DETAIL


CONSOL ENERGY

DATE: 08/01/14 JOB NO.: 90126 DESIGN: BEM DRAWN: BEM CHECKED: ВЈМ SHEET NO.

200 EVERGREENE DRIVE WAYNESBURG, PA 15370

KAPROJECTS/CONSOL ENERGY090126-00 - SHERWOOD SOUTH PIPELINE/DESIGN/BASE DWGS/80126-0X11-0X13 IFC TABLES DWG - 8/1/2014


5 of 10




P TEMPORARY ACCESS BRIDGE DETAIL

NOTES:

1. THE STRUCTURE SHALL BE LARGE ENOUGH TO HANDLE A 1-YEAR FREQUENCY STORM, 24 HOUR DURATION.




- . CONTACT CONSOL AT LEAST 72 HOURS PRIOR TO CONSTRUCTION TO HAVE THE EXISTING TRANSMISSION LINE FLAGGED.
- 2. CONSOL REPRESENTATIVES MUST BE ON SITE DURING CONSTRUCTION TO APPROVE INSTALLATION.
- THE CURRENT PIPELINE COVER MUST BE MAINTAINED. DURING CONSTRUCTION, CONTRACTOR SHALL STRIP TOPSOIL AND PLACE MATTING BOARDS
 FOR EQUIPMENT CROSSING THE GAS TRANSMISSION EASEMENT. MATTING BOARDS BENEATH THE EMBANKMENT ARE TO REMAIN IN PLACE.
- 4. AIR BRIDGE IS TO BE REMOVED DURING SITE RESTORATION PHASE. CONSOL REPRESENTATIVES MUST BE ON SITE DURING REMOVAL FOR CONSTRUCTION APPROVAL. AFTER AIR BRIDGE IS REMOVED, FILL AIR GAP WITH SUBSOIL AND COMPACT TO SPECIFICATION. SEED AND MULCH FILL



DETAIL FIGURE II-9: STREAM CROSSING TEMPORARY, WITH CULVERT

NOTES:


- 1. THE STRUCTURE SHALL BE LARGE ENOUGH TO HANDLE A 1-YEAR FREQUENCY STORM, 24 HOUR DURATION.
- 2. DEPTH OF COVER OVER CULVERTS SHALL BE ½ THE DIAMETER OF THE CULVERTS USED OR 12 INCHES, WHICHEVER IS GREATER.
- 3. MULTI-CULVERTS SHOULD BE INSTALLED WITH SPACES BETWEEN THEM, EQUAL TO ½ THE PIPE DIAMETER.
- 4. LOW WATER CROSSINGS MAY BE USED, IF PROTECTED WHEN OVERFLOWING OCCURS. THIS CAN BE ACCOMPLISHED BY USING ROCK AND CONCRETE.
- 5. CROSS CRIBBING OF THE DOWNSTREAM SIDE OF CULVERT INSTALLATIONS MAY BE NEEDED TO AID IN REDUCING STRUCTURAL DAMAGE DURING HIGH VELOCITY WATER OVERFLOW PERIODS.
- 6. IF CULVERTS OR BRIDGES ARE NOT USED AND A STONE BASE DOESN'T EXIST, STONE SHALL BE INSTALLED, WITH THE ENTRANCE AND EXIT BEING STONED FOR APPROXIMATELY 100 FEET.
- 7. DITCH LINE EXIT POINTS AT STREAM CROSSINGS MUST HAVE SEDIMENT CONTROLS.




R STANDARD CONSTRUCTION DETAIL TIMBER MAT BRIDGE

NOTES:

- 1. THIS TYPE OF BRIDGE IS GENERALLY USED FOR SMALL STREAM CROSSINGS LESS THAN 20 FEET IN WIDTH IN COMBINATION WITH A PROPER STREAM BANK CONFIGURATION.
- 2. BRIDGE WILL BE TEMPORARILY REMOVED IF HIGH WATER RENDERS IT UNSAFE FOR CROSSING.
- 3. BRIDGE TO REMAIN IN PLACE UNTIL THE COMPLETION OF FINAL RESTORATION.
- 4. SILT FENCE, SAND BAGS, DRIVABLE BERMS, OR OTHER APPROPRIATE EROSION CONTROL MAY BE USED INTERCHANGEABLY.
- 5. A "SKIRT" FORMED OF SILT FENCE, GEOTEXTILE FABRIC, OR EQUIVALENT SHALL BE PLACED ON THE SIDES AND BOTTOM OF THE BRIDGE TO TRAP SEDIMENT AS NECESSARY
- 6. INDIVIDUAL MATS SHALL BE ANCHORED AND BUTTED TIGHTLY TO MINIMIZE THE INTRODUCTION OF SEDIMENT TO THE WATERBODY.





WHEN TRENCH EXCAVATION TAKES PLACE IN AN AGRICULTURAL, WETLAND, OR RESIDENTIAL AREA, THEN SECREGATION OF TOPSOIL AND SUBSOIL WILL BE PERFORMED. PLACE TRENCH PLUGS AT THE REQUIRED SPACING DURING UTILITY INSTALLATION. FOLLOW STREAM AND WETLAND CROSSING BETAILS LOCATED ON THE EROSION AND SEDIMENT CONTROL DRAWINGS FOR UTILITY CROSSINGS OF THESE FEATURES. SEE STREAM CROSSING PROCEDURES AND WETLAND CROSSING PROCEDURES FOR ADDITIONAL INFORMATION ON WATER BODY AND WETLAND CROSSING. DURING CONSTRUCTION, INSTALL AND MAINTAIN ANY ADDITIONAL EROSION AND SEDIMENT CONTROL BMP'S AND IMPLEMENT STRUCTURAL POST CONSTRUCTION STORMWATER BMP'S (PERMANENT WATERBARS) THAT MAY BE REQUIRED. SEE UTILITY LINE INSTALLATION REQUIREMENTS NOTES FOR LIMITS OF WORK.

ANY WATER ENCOUNTERED WITHIN THE EXCAVATION AREAS DURING CONSTRUCTION SHALL BE REMOVED BY USING PUMPS, HOSES, AND PUMPED WATER FILTER BAGS WHICH SHALL BE DISCHARGED INTO UNDISTURBED WELL-VEGETATED UPLAND AREAS.

BACKFILL AREAS EXCAVATED FOR THE INSTALLATION OF UTILITIES WITH SUITABLE EXCAVATED MATERIAL. IN AREAS WHERE TOPSOIL HAS BEEN SEGREGATED, THE SUBSOIL SHALL BE REPLACED FIRST, FOLLOWED BY THE TOPSOIL BEING SPREAD OVER THE AREA FROM WHICH IT WAS REMOVED, FINAL GRADES SHALL BE THE SAME AS PRE-CONSTRUCTION CONTOURS.

AFTER CONSTRUCTION IS COMPLETE, FINAL SEEDING AND MULCHING OF ALL DISTURBED AREAS NOT YET STABILIZED SHALL BE COMPLETED. INSTALL EROSION CONTROL BLANKETING ON SLOPES WHICH ARE 3:1 OR STEEPER. STABILIZE AND SEED ALL OPEN A

CONSOL ENERGY

SUMMARY OF MATERIALS REFERENCE DRAWINGS REVISIONS

MRKR # QTY. DESCRIPTION DWG. DESCRIPTION NO. DATE DESCRIPTION

08/01/14

DATE

Ces®

CREATION TO COMPLETION
WWW.cesoinc.com

OX11-OX13 PIPELINE


SWPPP DETAILS


STATION(S):


LS 200 EVERGREENE DRIVE WAYNESBURG, PA 15370


DATE:	08/01/14
JOB NO.:	90126
DESIGN:	BEM
DRAWN:	BEM
CHECKED:	ВЈМ
SHEET NO.	

6 of 10











OX11-OX13 PIPELINE

ROAD CROSSING DETAILS

STATION(S):

CONSOL ENERGY	CF	CONSOL	ENERGY
---------------	----	--------	--------

200 EVERGREENE DRIVE WAYNESBURG, PA 15370

OX	(11-OX13 WAT	ER BAR SPACI	NG*
STATION BEGIN	STATION END	% SLOPE (AVERAGE)	WATER BAR SPACING (FT)
0+88	1+36	41	75
8+74	8+84	28	75
9+38	9+49	28	75
10+23	10+49	57	75
11+48	11+75	31	75
12+26	12+61	31	75
13+01	13+40	31	75
13+89	14+00	40	75
14+61	14+75	40	75
15+47	15+48	40	75
16+23	16+28	40	75
16+94	17+11	40	75
17+68	17+93	40	75
19+56	20+41	33	75
36+59	37+37	28	75
37+29	38+25	28	75
38+24	38+79	53	75
42+63	43+44	15	125
45+69	45+70	33	75
46+33	46+75	33	75
47+13	47+39	33	75
47+90	48+11	33	75

		OX1	1-OX13 FILTER	SOCK SIZING C	HART**	
SOCK#	SIZE (in.)	SLOPE (%)		MAX SLOPE LENGTH (ft.)	SOCK LENGTH (fL)	APPROXIMATE LOCATION
FS-1	12	25	100	100	33	17+50
FS-2	12	18	125	125	106	19+00
FS-3	12	20	120	125	46	30+00
FS-4	8	19	91	100	44	30+50
FS-5	8	13	39	140	34	31+00
FS-6	В	18	42	100	57	31+00
FS-7	8	20	86	100	44	31+50
FS-8	8	10	34	200	87	32+00
FS-9	18	24	106	110	186	32+50
FS-10	8	16	27	100	76	33+00
FS-11	18	25	110	110	41	33+50
FS-12	8	18	25	100	100	34+00

OX11-OX13 TI LOCATION	
PLUG #	STATION
1	0+53
2	1+53
3	8+25
4	10+47
5	10+72
6	10+96
7	11+37
8	12+53
9	13+53
10	14+52
11	15+52
12	16+53
13	17+53
14	18+52
15	21+12
16	24+48
17	34+69
18	37+69
19	38+69
20	39+69
21	43+72
22	44+51
23	45+69
24	46+69
25	48+69

EROSION AND SEDIMENT CONTROL BMP PRACTICES							
ВМР	UNITS	QUANTITY					
8" COMPOST FILTER SOCK	FT	442					
12" COMPOST FILTER SOCK	FT	185					
18" COMPOST FILTER SOCK	FT	227					
SUPER SILT FENCE	FT	1910					
SILT FENCE	FT	615					
STABILIZED CONSTRUCTION ENTRANCE	EA	4					
TRENCH PLUG	EA	25					
TEMPORARY WATERBARS	EA	22					
TIMBER MATS (10 FT WIDTH, ASSUME 8 FT SECTION LENGTHS)	LF	144					
STREAM CROSSING - FLUME PIPE CROSSING (SEE DETAIL SHEET #4)	EA	4					
TOB TO TOB (PIPELINE CONST.)	LF	11					

STREAM CROSSINGS - PIPELINE					
STREAM ID	TÓB	тов	LENGTH (LF)	TIMBER MAT LENGTH (LF)	
STREAM EH	2+27	2+28	1	32	
STREAM EF	11+12	11+17	5	16	
STREAM EC	43+54	43+56	2	16	
STREAM EB	44+15	44+18	3	16	
		TOTAL:	11	80	

WETLAND CROSSINGS - PIPELINE					
WETLAND ID	EDGE	EDGE	LENGTH (LF)	TIMBER MAT LENGTH (LF)	
WETLAND EG	10+54	10+81	27	32	
WETLAND EA	44+44	44+72	28	32	
		TOTAL:	55	64	

ROAD CROSSINGS - PIPELINE				
ROAD	EOP	EOP	LENGTH (LF)	PAVED / UNPAVED
CAIN RUN (CR 40)	45+28	45+38	10	UNPAVED
		TOTAL:	10	

"WATER BAR SPACING IS BASED ON THE WEST VIRGINIA EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE MANUAL TABLE 3,18,1: RIGHT-OF-WAY DIVERSION SPACKING, SOME WATER BARS HAVE BEEN OVER-DESIGNED AT THE DISCRETION OF THE ENGINEER BASED ON EXISTING FIELD CONDITIONS.

"FILTER SOCK DESIGN BASED ON THE TABLE FOUND IN THE FILTREXX LOW IMPACT DESIGN MANUAL, VERSION 8, SECTION 1: EROSION & SEDIMENT CONTROL, PAGE 324.

"TRENCH PLUG DESIGN BASED ON THE TABLE PROVIDED ON THE TRENCH PLUG DETAIL ON SHEET 5, SOME TRENCH PLUGS HAVE BEEN OVER-DESIGNED AT THE DISCRETION OF THE ENGINEER BASED ON EXISTING FIELD CONDITIONS.

SUMMARY OF MATERIALS REFERENCE DRAWINGS REVISIONS IFC NO. DATE 08/01/14



OX11-OX13 PIPELINE

E&S TABLES AND QUANTITIES

STATION(S):



200 EVERGREENE DRIVE WAYNESBURG, PA 15370

DATE:	08/01/14
JOB NO.:	90126
DESIGN:	ВЕМ
DRAWN:	BEM
CHECKED:	ВЈМ
SHEET NO.	
10 c	of 10



Attachment D- Project Location-Adjacent and/or Affected Landowners

TAX ID: 09-06-0003-0002-0000-6001

NAME OF SURFACE OWNER/OWNERS: I.L. Ike Morris

ADDRESS OF PROPERTY: Route 23, West Union, WV 26456

ADDRESS OF SURFACE OWNER/OWNERS: P.O. Box 397, Glenville, WV 26351

TAX ID: 09-07-0015-0003-0001-0000

NAME OF SURFACE OWNER/OWNERS: Jerry L. and Sharon Leggett

ADDRESS OF PROPERTY: Route 40, New Milton, WV 26411

ADDRESS OF SURFACE OWNER/OWNERS: Rt. 1 Box 59A, New Milton, WV 26411

THE HERALD RECORD

LEGAL-ADVERTISEMENT:

THE CONTRACT THE PERSON

Alloodplan Solva poderinge accounty Journal County
Ploodplain Managemen has no regulator, authority. Any
Ploodplain Managemen has no regulator, authority. Any
interested persons who desire to comment shall present
the same in writing by September 8, 2014

Delivered to the
Clerkof the County Court

118 E. Court Street West Union: W V-26456

Beth A. Rogers, Doddridge County Clerk
Edwin L. "Bo" Wriston, Doddridge County Flood Plain
Management Manager 1 3.3 7 28-19-2xb

STATE OF WEST VIRGINIA, COUNTY OF DODDRIDGE, TO WIT I, Virginia Nicholson, Editor of THE HERALD RECORD, a weekly newspaper published regularly, in Doddridge County, West Virginia, Do Hereby Certify That the Accompanying Legal Notice Entitled: was published in said paper for ... 2. successive weeks beginning with the issue ending with the issue of that said notice contains 1.89amounts to the sum of \$ FOR FIRST PUBLICATION, SECOND **PUBLICATION IS 75% OF THE FIRST PUBLICATION** and each publication thereafter SWORN TO AND SUBSCRIBED . DAY

OFFICIAL SEAL Notary Public, State Of West Virginia LAURA J ADAMS 212 Edmond Street West Union, WV 26456 My Commission Expires June 14, 2023

NOTARY PUBLIC