

Floodplain Development Permit

Doddridge County, WV Floodplain Management

This permit gives approval for the development/ project listed that impacts the FEMA-designated floodplain and/or floodway of Doddridge County, WV, pursuant to the rules and regulations established by all applicable Federal, State and local laws and ordinances, including the Doddridge County Floodplain Ordinance. This permit must be posted at the site of work as to be clearly visible, and must remain posted during entirety of development.

Permit #: 16-414

Date Approved: April 1, 2016 Expires: April 1, 2017

Issued to: Antero Midstream LLC POC: Rachel Grzybek

Company Address: 1615 Wynkoop Street, Denver, CO. 80202

Project Address: Cabin Run Rd. Doddridge County, WV

Firm: 54017C0200C (10/4/11) Lat/Long: 39.242545, -80.895094

Purpose of development: Buried 16" Water Line and 10" Low Pressure Gas Line

Issued by: George C. Eidel, Doddridge County FPM (or designee)

Date: April 1, 2016

DIM	NEWAY			By:	CJF
RETTEW					2/15/2016
We answe	E II V Voi			Checked by:	
We allow	,			Date:	
	otson Holland Addendum				
16" HDPE I	Pipeline Construction Cost Estimate - Construction w	ithin the 100-yr	Floodplain in I	Doddridge Co	inty
RETTEW Pr	oject No. 095454000				
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	ITEM TOTAL
	16" HDPE PIPE (COMPLETE-IN-PLACE)	LF	50	\$ 150.00	\$ 7,500.00

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	ITI	EM TOTAL
	16" HDPE PIPE (COMPLETE-IN-PLACE)	LF	50	\$ 150.00	\$	7,500.00
	FILTER SOCK, 12" DIAMETER	LF	200	\$ 8.00	\$	1,600.00
	SITE RECLAMATION (SEEDING AND MULCHING)	AC	1	\$ 4,000.00	\$	4,000.00
	SAFETY FENCE	LF	500	\$ 10.00	\$	5,000.00
			10% Cor	ntingency	\$	1,810.00

Total: \$ 19,910.00

Notes:

Unit prices provided by Antero.





3020 Columbia Avenue, Lancaster, PA 17603 • Phone: (800) 738-8395

E-mail: rettew@rettew.com • Web site: rettew.com

February 15, 2016

Engineers
Planners
Surveyors
Landscape
Architects
Environmental

Consultants

Mr. George Eidel Floodplain Manager Doddridge County Office of Emergency Services 118 East Court Street, Room 102 West Union, WV 26456

RE:

Doddridge County Floodplain Development Permit Application

Dotson Pipeline—Dotson Holland Addendum Doddridge and Ritchie Counties, West Virginia

Dear Mr. Eidel,

Doddridge County previously approved a Floodplain Development Permit Application for the Dotson Pipeline Project (Attachment A) located in Doddridge and Ritchie Counties, West Virginia. On behalf of our client, Antero Midstream LLC (Antero), RETTEW Associates, Inc. is submitting a Floodplain Development Permit for a related project located in the same project area as the Dotson Pipeline Project.

The Dotson Holland Addendum Pipeline project will include a 16-inch buried waterline proposed to be constructed within most of the previously cleared Dotson Pipeline ROW. The approximately 3.3-mile pipeline addendum route will begin at the Clearwater Treatment Facility (39.268850, -80.891276) and will follow the existing corridor to the approximate southern end of the original LOD where it would tie into the Primm West Pipeline (39.234175, -80.895326). Please refer to **Figures 1 and 2** in **Attachment B** for project mapping. The crossing location from the original Dotson Pipeline Project within the floodplain of Cabin Run will be used for the new waterline. Only existing access roads will be used for the Dotson Holland Addendum project. No aboveground structures will be constructed within the floodplain, therefore there will be no negative effects to the floodplain. A large portion of the Cabin Run floodplain within the project area is located in Richie County; a Floodplain Permit Application has already been submitted to Ritchie County's Floodplain Manager.

Pipeline installation methods will remain the same as they were for the Dotson Pipeline. All disturbance will be temporary, and there will be no change to the base flood elevation of Cabin Run. The Dotson Run floodplain will be avoided completely by the Dotson Holland Addendum project. The Floodplain Development Permit Application is included in **Attachment C**, the Property Owner Table is included in **Attachment D**, and the Site Plan is included in **Attachment E**. Please contact me at teby@rettew.com or (717) 394-3721 with any questions regarding the permit application.

Sincerely.

The R. Ely


Environmental Scientist

Enclosures

copy: Rachel Grzybek, Antero


I:\Projects\09545\095454000-Gas\NS\Floodplain Coordination\Doddridge County\Ltr-Dotson Holland Addendum Floodplain Application.docx





Br. Gradler Bir.

2016 FEB 24 AM 11: 15





Antero Resources 535 White Oaks Blvd. Bridgeport, WV 26330 Office 304.842.4100 Fax 304.842.4102

February 12, 2016

Doddridge County Commission Attn: George Eidel, Doddridge County Floodplain Manager 118 East Court Street, Room 102 West Union, WV 26456

Mr. Eidel:

Antero Midstream, LLC would like to submit a Doddridge County Floodplain permit application for our Dotson Holland Addendum Pipeline. Our project is located in Doddridge County, Central District where the pipeline will be begin at the Clearwater Treatment Facility at coordinates 39.268850 N, 80.891276 W and will continue to Ritchie County at coordinates 39.234175 N, 80.895326 W. Per the FIRM Map #54017C0200C, this location is <u>in</u> the floodplain.

Attached you will find the following:

- ➤ No-Rise Certificate (RETTEW)
- > Original Dotson Pipeline Floodplain Permit (#14-200)
- > Project Mapping
- > Doddridge County Floodplain Permit Application
- > Surface Property Owner Information
- ➤ Site Plan
- ▶ Bid Sheet

If you have any questions please feel free to contact me at (304) 842-4008.

Thank you in advance for your consideration.

hold Del


Sincerely,

Rachel Grzybek

Environmental Specialist I Antero Midstream, LLC

Enclosures

FILED



Permit#	
Project Name:	
Permittees Name:	

Doddridge County, WV

Floodplain Development Permit Application

This document is to be used for projects that impact/potentially impact the FEMA—designated floodplain and/or floodway of Doddridge County, WV pursuant to the rules and regulations established by all applicable Federal, State and local laws and ordinances, including the Doddridge County Floodplain Ordinance.

SECTION 1: GENERAL PROVISIONS (APPLICANT TO READ AND SIGN)

- 1. No work may start until a permit is issued.
- 2. The permit may be revoked if any false statements are made herein.
- 3. If revoked, all work must cease until permit is re-issued.
- 4. Development shall not be used or occupied until a Certificate of Compliance is issued.
- 5. The permit will expire if no work is commenced within six months of issuance.
- 6. Applicant is hereby informed that other permits may be required to fulfill local, state, and federal requirements.
- 7. Applicant hereby gives consent to the Floodplain Administrator/Manager or his/her representative to make inspections to verify compliance.
- 8. I THE APPLICANT CERTIFY THAT ALL STATEMENTS HEREIN AND IN ATTACHMENTS TO THIS APPLICATION ARE, TO THE BEST OF MY KNOWLEDGE, TRUE AND ACCURATE.

APPLICANT'S SIGNATURE	Brian Aus	in-
DATE	2-16-16	

Applicant Information:

Please provide all pertinent data.

Applicant Information	Marie Barille Bereit	
Responsible Company Name: Antero Midstream	LLC	
Corporate Mailing Address: 1615 Wynkoop Stre	et	
City: Denver	State: CO	Zip: 80202
Corporate Point of Contact (POC): Rachel Grzybe	ek	
Corporate POC Title:		
Corporate POC Primary Phone: (304) 842-4008		
Corporate POC Primary Email: rgrzybek@antero	resources.com	
Corporate FEIN:	Corporate DU	INS:
Corporate Website:		
Local Mailing Address:		
City:	State:	Zip:
Local Project Manager (PM):		
Local PM Primary Phone:		
Local PM Secondary Phone:		
Local PM Primary Email:		
Person Filing Application:		
Applicant Title:		
Applicant Primary Phone:		
Applicant Secondary Phone:	-	
Applicant Primary Email:		

Project Narrative:

Describe in detail the proposed development including project name/title, type of development, estimated start and completion timeline, and its potential impact on the floodplain. Use additional copies of this page as needed.

Project-Narrative:
The Dotson Holland Addendum Pipeline project will include one 16" buried
waterline proposed to be constructed within most of the previously cleared
Dotson Pipeline ROW. The pipeline addendum route will begin at the
Clearwater Treatment Facility (39.268850, -80.891276). The approximately
3.3-mile waterline will follow the existing corridor to the approximate
southern end of the original LOD where it would tie into the Primm West
Pipeline (39.234175, -80.895326). The crossing location within the 100-year
floodplain of Cabin Run from the original Dotson Pipeline Project will be used
for the new pipeline, and is approximately 65 feet in length. Only existing
access roads will be used for the Dotson Holland Addendum project. No
above-ground structures will be constructed within the floodplain, and no
permanent impacts to the floodplain are proposed. Construction is expected
to begin in March of 2016 and be completed in October of 2016.

Proposed Development:

Please check all elements of the proposed project that apply.

DESCRIPTION OF WORK (CHECK ALL APPLICABLE BOXES)

A. STRUCTURAL DEVELOPMENT

	AC	IIVIIY				STRUCTU	RAL TYPE	
[]	New Struct	ture			[]	Residential	(1 – 4 Family)	
[]	Alteration				[]	Residential (more than 4 Family Non-residential (floodproofing)		
[]					[]			
[]					0	Combined I	Jse (res. & com.)	
[]	Demolition	1			[]	Replaceme	nt	
[]	Manufacti	ured/Mo	bil Home					
В.	OTHER DE	VELOP	LMENT ACTI	VITIES:	:			
[]	Fill	[]	Mining	[]	Drilling	· [3]	Pipelining	
[]	Grading							
[]	Excavation	(except	for STRUCTUR	RAL DEVE	ELOPMENT	Γ checked at	oove)	
[]	Watercour	se Altera	ation (including	g dredgi	ng and cha	nnel modifi	cation)	
[]	Drainage Ir	nproven	nents (includin	ig culver	t work)			
[]	Road, Stree	et, or Bri	dge Construct	ion				
[]	Subdivision	ı (includi	ng new expan	sion)				
[]	Individual \	Water or	Sewer Systen	n				
[]	Other (plea	ase speci	fy)					

Development Site/Property Information:

Property Designation: 1 of 1

Please provide physical description of the site/property, along with pertinent ownership (surface and mineral rights) data as applicable. Attach appropriate maps from the WV Flood Tool showing location of proposed development. Use additional copies of this page if development spans multiple property boundaries. Designate each property by number (i.e. Property 1 of 1, Property 2 of 7, etc.)

Site/Property Information:	· · · · · · · · · · · · · · · · · · ·		·					
Legal Description:								
Physical Address/911 Address	S:		WH. JI W					
Decimal Latitude/Longitude:	39.242545, -80.89	95094	***					
DMS Latitude/Longitude: N 3	9° 14' 33.1614", W	80° 53' 42.3384"						
District: Central Tax District	District: Central Tax District Map∓IRM 54017C0200C (10/4/11) Parcel:							
Land Book Description: CABI	N RUN 111.1 AC A	SSESSED SUR	· · · · · · · · · · · · · · · · · · ·					
Deed Book Reference:								
Tax Map Reference:								
Existing Buildings/Use of Prop	erty: No building	- · · · · · · · · · · · · · · · · · · ·						
3	- 140 building							
Floodplain Location Data: (to I	e completed by F	loodplain Manag	er or desi	gnee)				
	mber:	Panel:		Suffix:				
Location (Lat/Long):		Approximate E	levation:					
		F 1999						
Is the development in the floor	lway?	Estimated BFE						
Is the development in the floodway? Is the development in the floodplain?								
Yes No		Yes	No	Zone:				
Notes:								

Property Owner Data:

Please provide data on current site/property landowner(s), both surface and mineral rights (as applicable). Use additional copies of this page as needed. Designate each page in relation to each property listed above.

Property Designation: of		
Property Owner Data:		
Name of Primary Owner (PO): See attached Pro	perty Owner Table	>
PO Address:	· · · · · · · · · · · · · · · · · · ·	
City:	State:	Zip:
PO Primary Phone:		
PO Secondary Phone:		
PO Primary Email:	······································	
ouriace raging owner Data.		
Name of Primary Owner (PO):		
PO Address:		
City:	State:	Zip:
PO Primary Phone:		
PO Secondary Phone:		
PO Primary Email:		
Mineral Rights Owner Data: (As Applicable):		
Name of Primary Owner (PO):		
PO Address:		
City:	State:	Zip:
PO Primary Phone:		
PO Secondary Phone:		
<u> </u>		

Contractor Data:

Property Designation:

of_

Please provide all pertinent data for contractors and sub---contractors that may be participating in this project. Use additional copies of this page as needed. Designate each page in relation to each property listed above.

Contractor/Sub-Contractor (C/SC) Information							
C/SC Company Name: TBD							
C/SC WV License Number:							
C/SC FEIN: C/SC DUNS:							
Local C/SC Point of Contact (POC):							
Local C/SC POC Title:							
C/SC Mailing Address:							
City: State: Zip-Code:							
Local C/SC Office Phone:							
Local C/SC POC Phone:							
Local C/SC POC E-Mail:							
		•					
Engineer Firm Information:	·						
Engineer Firm Name: RETTEW Associates, Inc.							
Engineer WV License Number: 19074							
Engineer Firm FEIN: 23-1712637	Engineer Firm	n DUNS:					
Engineer Firm Primary Point of Contact (POC):	Eric Hershey						
Engineer Firm Primary POC Title: Senior Engine	er						
Engineer Firm Mailing Address: 3020 Columbia Ave							
City: Lancaster	State: PA	Zip-Code: 17603					
Engineer Firm Office Phone: (800) 738-8395							
Engineer Firm Primary POC Phone:		•					
Engineer Firm Primary POC E-Mail: ehershey@r	ettew.com						

Adjacent and/or Affected Landowners Data

Please provide data for all adjacent and/or affected surface owners (both up and down stream) whose property may be impacted by proposed development as demonstrated by a floodplain study or survey. Use additional copies of this page as needed.

Adjacent Property Owner Data: Upstream		
Name of Primary Owner (DO).	roperty Owner 1	
Physical Address:		
City:	State:	Zip:
PO Primary Phone:	<u></u>	
PO Secondary Phone:		
PO Primary Email:		
Adjacent Property Owner Data: Upstream		
Name of Primary Owner (PO):		
Physical Address:		
City:	State:	Zip:
PO Primary Phone:	-1.	
PO Secondary Phone:		
PO Primary Email:		
Adjacent Property Owner Data: Downstream		
Name of Primary Owner (PO):		
Physical Address:		
City:	State:	Zip:
PO Primary Phone:	<u>.</u>	
PO Secondary Phone:		
PO Primary Email:		
Adjacent Property Owner Data: Downstream		
Name of Primary Owner (PO):		
Physical Address:		
City:	State:	Zip:
PO Primary Phone:	<u> </u>	
PO Secondary Phone:		
PO Primary Email:		

Site Plan

A Site Plan is an accurate and detailed map of the proposed development for this project. It shows the size, shape, location and special features of the project property, and the size and location of any development planned to the property, especially as that development will impact the floodplain and/or floodway. Site plans show what currently exists on the project property, and any changes or improvements you are proposing to make. A certified and licensed engineering firm should complete site plans.

A SITE PLAN MUST CONTAIN THE FOLLOWING INFORMATION:

- 1. Legal description of the parcel, north arrow and scale
- 2. All property lines and their dimensions
- 3. Names of adjacent roads, location of driveways
- 4. Location of sloughs, tributaries, streams, rivers, wetlands, ponds, and lakes, with setbacks indicated, and including FEMA floodplain data based on most updated FIRM.
- 5. Location, size, shape of all buildings, existing and proposed, with elevation of lowest floor indicated.
- 6. Location and dimensions of existing or proposed on-site sewage systems.
- 7. Location of all propane tanks, fuel tanks or other liquid storage tanks whether above ground or below ground level.
- 8. Location and dimensions of any proposed pipeline placement(s) into floodplain/floodway.
- 9. Location and dimensions of any roadway development into floodplain/floodway. (Includes initial development access roads)
- 10. Location and dimensions of any bridge and/or culvert development into floodplain/floodway.
- 11. Location and dimensions of any storage yard or facility into the floodplain/floodway.
- 12. Location of any existing utilities and/or proposed utility placement and/or displacement.
- 13. Location, dimensions and depth of any existing or proposed fill on site.
- 14. A survey showing the **existing ground elevations** of at least location on the building site. **ELEVATION NOTE**: All vertical datum will reference either NGVD 29 or NAVD 88. Assumed datum will not be acceptable unless the property is located in an area where vertical datum has not been published. For those areas where vertical datum has not been established, a site plan with contours, elevations using assumed datum, high water marks and existing water levels of sloughs, rivers, lakes or streams and proposed lowest floor elevation.

Applicant

Please read print name, sign and date below:

- I certify that I am authorized to submit this application for the primary project developer.
- I certify that the information included in this application is to the best of my knowledge true and
- I certify that all required Federal, State, and local permits required by law and/or ordinance for the above described development of this project have been properly attained, are current and valid, and must be presented with this application before a Doddridge County Floodplain Permit
- I understand that if in the course of the development project additional permits become required that were not needed during the initial proposal, the primary developer must notify the Doddridge County Floodplain Manager within 48 hours of such need, and that a "Stop Work" order may be issued for all project work directly impacting the floodplain or floodway, until such time the required additional permits are acquired.
- I understand that once the floodplain permit is submitted, the application will be entered into official public record at the next regularly scheduled Doddridge County Commission meeting after the date of submittal.
- I understand that from the date of submittal of the fully completed permit application, the Doddridge County Floodplain Manager has ninety (90) days to make a determination to either grant or deny said permit application. During this approval period, the Doddridge County Floodplain Manager may, at his or her discretion, conduct a review and/or additional study of provided documentation by means of an independent engineering firm. All costs associated with said review and/or study must be reimbursed to the County before Issuance of approved permit.
- I understand that during the approval period, the Doddridge County Floodplain Manager of designee may at his or her discretion conduct site visits and document conditions of proposed development pursuant to the permit application.
- I understand that once the Floodplain Permit is granted, the permit will be entered into official public record at the next scheduled Doddridge County Commission meeting after the date of issuance. Appeals to the permit may be made no later than twenty (20) days after said issuance. If a valid appeal is submitted, as determined by the Doddridge County Floodplain Manager, a "Stop Work" order will be issued for all project development directly involving the floodplain or floodway. A public hearing by the Doddridge County Appeals Board will be scheduled no less than ten (10) days after the next regularly scheduled Doddridge County Commission meeting.
- I understand that all decisions of the Doddridge County Appeals Board shall be final.
- I understand Issuance of a Floodplain Permit authorizes me to proceed with construction as proposed. A Certificate of Compliance is required upon substantial completion of the project.
- In signing this application, the primary developer hereby grants the Doddridge County Floodplain Manager or designee the right to enter onto the above—described location to inspect the development work proposed, in progress, and/or completed.
- I understand that if I do not follow exactly the site—plan submitted and approved by this permit that a "Stop Work" order may be issued by the Wirt County Floodplain Manager and that I must stop all construction immediately until discrepancies of actual work vs. proposed work is resolved.

ATTACHMENT D PROPERTY OWNER TABLE

Property Owner Table - Doddridge County Floodplain Permit (Cabin Run)

Antero Midstream LLC - Dotson Holland Addendum

Property Owner Name	Mailing Address	Floodplain Crossing	Parcel ID	Deed Book Reference	Land Book Description		
·	HOST PRO	PERTY (INSIDE FLOODP	LAIN)				
Morris, I L (Ike)	PO BOX 397 GLENVILLE WV 26351	Cabin Run	3-37-1	Book 255, Page 718	CABIN RUN 111.1 AC ASSESSED SUR		
PROPERTY OWNERS ABUTTING HOST PROPERTIES (INSIDE FLOODPLAIN)							
Coastal Lumber Co	P.O. BOX 709 BUCKHANNON WV 26201 0709	Cabin Run	3-32-8	Book 226, Page 655	CABIN RUN 39.09 A(LOT #8) SUR CO RD 10		
Church, Earvin	P.O. BOX 668 PINEVILLE WV 24874 0668	Cabin Run	3-32-9.1	Book 266, Page 547	CABIN RUN 2 AC SURF CO RD 10		
Coastal Lumber Co	P.O. BOX 709 BUCKHANNON WV 26201 0709	Cabin Run	3-32-7	Book 226, Page 655	CABIN RUN 57.6 CO RD 10/2		
Church, Earvin	P.O. BOX 668 PINEVILLE WV 24874 0668	Cabin Run	3-32-9	Book 266, Page 547	CABIN RUN 5.86 AC SUR CO RD 10		
MacKay, Jack D & Peale Anita G	Jack D. Mackay Rt 1 Box 206-2, West Union, WV 26456-9727	Cabin Run	2 27 2 2	3 Book 280, Page 972	19 99 I VAIAL CAMAD CO BD 10/4		
	Anita G. Peale 105 Colechester Lane, Palm Coast, FL 32137-9062		3-37-3.3		18.88 LYNN CAMP CO RD 10/4		
Morris, I L (Ike)	PO BOX 397 GLENVILLE WV 26351	Cabin Run	1-11-8	Book 230, Page 307	CABIN RUN 259.50 AC RT.19		
Heartwood Forestland Fun	2911 EMERSON AVE SUITE A PARKERSBURG WV 26104	Cabin Run	1-11-6	Book 253, Page 671	CABIN RUN 73.92 AC OFF RT.19 OVER 3		

ATTACHMENT E SITE PLAN


ATTACHMENT A

ORIGINAL DOTSON PIPELINE FLOODPLAIN DEVELOPMENT PERMIT


Shayelyn Marshall

From: Sent: To: Subject:	Lorena Slater Vednesday, May 21, 2014 10:58 AM Shayelyn Marshall APPROVED PERMIT #14-200 DOTSON P/L
Commercial/Industrial Floodplai	Development Permit Doddridge County, WV Floodplain Management
associated with this permit that pursuant to the rules and regula	TERO, and is for the approved commercial and/or industrial development project npacts the FEMA-designated floodplain and/or floodway of Doddridge County, WV, ons established by all applicable Federal, State and local laws and ordinances, including Ordinance. This permit must be posted at the site of work as to be clearly visible, and ty of development.
Permit: #14-200	
Date Approved:05/21/2014	Expires:05/21/2015
Issued to: ANTERO RESOURCES (ST DENVER Project Address: COUNTY RT. 19	303-357-6412 Company Address: 1615 WYNKOOP
Firm: 54017C0100C/54017C0	OC Lat/Long: 39.272881/-80.873298 39.234034/-80.895810
Issued by: Edwin L. "Bo" Wristor	Doddridge County FPM (or designee)
	Date:05/21/2014

ATTACHMENT B PROJECT MAPPING



WV Flood Map









Flood Point of Interest

Disclaimer

The online map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. To obtain more detailed information in areas where Base Flood Elevations have been determined, users are encouraged to consult the latest Flood Profile data contained in the official flood insurance study. These studies are available online at www.msc.fema.gov. WV Flood Tool (http://www.MapWV.gov/flood) is supported by FEMA, WV NFIP Office, and WV GIS Technical Center.

Map created on February 11, 2016

Flood Hazard Area:

Flood Hazard Area: Location is WITHIN the FEMA 100-year floodplain.

FEMA Issued Flood Map: 54017C0200C

Watershed (HUC8): Little Kanawha (5030203)

Elevation: About 801 ft


Location (long, lat): (80.895160 W,39.244891 N)

Location (UTM 17N): (509047, 4343957)


Contacts: Doddridge

CRS Information: N/A

Parcel Number:



ATTACHMENT C FLOODPLAIN DEVELOPMENT PERMIT APPLICATION





DOTSON HOLLAND ADDENDUM WATERLINE & GASLINE

ANTERO MIDSTREAM PARTNERS LP DODDRIDGE AND RITCHIE COUNTIES, WEST VIRGINIA




T LEAST 45 HOURS, BUT NOT MORE THAN 10 WORKING DAYS (EXCLUDING EEKENDS AND HOUDAYS), PRIOR TO TO STARTING ANY EARTH DISTURBANCE CTIVITIES, ALL CONTRACTORS INVOLVED IN THESE ACTIVITIES SHALL CONTRACTORS UTULTY OF WEST VIRGINA AT 811 OR 1-800-245-4848.

ESIGN PHASE TICKET # 1528785559, DATE: 10/15/2015 RICKEE COUNTY.

ESTIMATED QUANTIFIED MATERIAL LIST

1.	WATERBARS (EA)	102			
2.	TRENCH BREAKERS (EA)	69			
3.	ROCK CONSTRUCTION ENTRANCE (EA)	5			
4.	EROSION CONTROL MATTING (SY)	130,166			
5.	SILT SAVER PRIORITY 1 (LF)	6,961			
6.	SILT SAVER PRIORITY 2 (LF)	10,778			
7.	ROCK FILTER (EA)	5			
8.	ORANGE CONSTRUCTION FENCE (LF)	120			



VICINITY MAP



PROJECT SUMMARY

LINE NAME	HORIZONTAL LENGTH	SLOPE LENGTH		
WATER LINE	17,873 FT	18,324 FT		
GAS LINE	4,381 FT	4,501 FT		

January, 2016

SHEET INDEX:

No.	SHEET NAME	DESCRIPTION					
01	WV-CLEARWATER-COVER-ENS	COVER SHEET					
02	WV-CLEARWATER-GNOT1-ENS	GENERAL NOTES SHEET					
03	WY-CLEARWATER-INDEX-ENS	INDEX SHEET					
04	WV-CLEARWATER-ALIGN1-ENS	RWATER-ALIGN1-ENS ALIGNMENT STA 0+00-15+00					
05	WV-CLEARWATER-ALIGN2-ENS	ALIGNMENT STA 15+00-44+00					
06	WV-CLEARWATER-ALIGN3-ENS	ALIGNMENT STA 44+00-70+00					
07	WV-CLEARWATER-ALIGN4-ENS	ALIGNMENT STA 70+00-98+00					
08	WV-CLEARWATER-ALIGN5-ENS	ALIGNMENT STA 98+00-123+00					
09	WV-CLEARWATER-ALIGN6-ENS	ALIGNMENT STA 123+00-151+00					
10	WV-CLEARWATER-ALIGN7-ENS	ALIGNMENT STA 151+00-178+75					
11	WV-CLEARWATER-ACES1-ENS	ACCESS ROAD DETAIL SHEET 1					
12	WV-CLEARWATER-ACES2-ENS	ACCESS ROAD DETAIL SHEET 2					
13	WV-CLEARWATER-ACES3-ENS	ACCESS ROAD DETAIL SHEET 3					
14	WV-CLEARWATER-ACES4-ENS	ACCESS ROAD DETAIL SHEET 4					
15	WV-CLEARWATER-ACES5-ENS	ACCESS ROAD DETAIL SHEET 5					
16	WV-CLEARWATER-DETI-ENS	ENS NOTES SHEET 1					
17	WV-CLEARWATER-DET2-ENS	ENS NOTES SHEET 2					
18	WV-CLEARWATER-DET3-ENS	ENS DETAILS SHEET 3					
19	WV-CLEARWATER-DET4-ENS	ENS DETAILS SHEET 4					
20	WV-CLEARWATER-DET5-ENS	ENS DETAILS SHEET 5					

PIPELINE COVER REQUIREMENTS

ROCK AREAS 3 FT.
WOODED AREAS 4 FT.
DRIVING SURFACES 5 FT.
AGRICULTURAL 4 FT.
STREAMS/WETLANDS 5 FT.

NOTE: THESE ARE MINIMUM REQUIREMENTS TO TOP OF PIPE



Email: rettew@rettew.com Website: www.rettew.com

GENERAL NOTES:

- I. EXISTING UTILITIES SHOWN ON PLANS WHERE EVIDENCE HAS BEEN FOUND OR PROVIDED BY LOCAL UTILITIES. EXACT DEPTH AND LOCATION OF UTILITY LINES NOT KNOWN, CONTRACTOR TO VERIFY UTILITY LOCATIONS PRIOR TO CROSSING BY CONTACTING MISS UTILITY AT 1-800-245-4848 AND LOCAL UTILITY COMPANIES AS LISTED AND/OR NOT LISTED ON THIS SHEET. CONTRACTOR TO LOCATE GAS, WATER AND UTILITY SERVICES BEFORE BORING AND
- 2. IN THE EVENT THAT AN ERROR WITH THE PLANS SEEMS APPARENT, THE MATTER MUST BE TAKEN UP WITH THE ENGINEER FOR REVIEW BEFORE PROCEEDING WITH ANY CONSTRUCTION.
- 3. ALL PERMITS MUST BE SECURED PRIOR TO CONSTRUCTION.
- 4. THE CONTRACTOR SHALL COORDINATE ALL PROPOSED STREAM CROSSING INSTALLATIONS SO NOT TO DELAY THE CONSTRUCTION PROCESS. STREAM CROSSINGS ARE TO BE CONSTRUCTED USING AN OPEN CUT CROSSING METHOD.
- 5. ALL WYDDH ROAD CROSSINGS ARE TO BE CONSTRUCTED USING AN OPEN CUT CROSSING METHOD. WYDDH TO BE NOTIFIED AT LEAST 48 HOURS
- 6. ALL CONSTRUCTION TO BE DONE IN THE PROPOSED WATER AND GASLINE LIMITS OF DISTURBANCE AS SHOWN.
- 7. CONTRACTOR SHALL VERIFY EXISTING PIPE TYPES AND O.D. PRIOR TO CONNECTION.
- 8. PROPERTY LINES SHOWN ON PLANS WERE OBTAINED FROM PARTIAL FIELD SURVEY AND RESEARCHED INFORMATION TAKEN FROM VARIOUS RECORDS ON FILE IN THE LOCAL COUNTY COURTHOUSE. TO OBTAIN A MORE ACCURATE BOUNDARY LINE LOCATION, A FULL PROPERTY SURVEY IS RECOMMENDED.
- 9. THE EXISTING 2' CONTOURS UTILIZED IN THIS PLAN SET TO SHOW THE EXISTING GRADE ARE FROM BEST AVAILABLE THREE (3) METER DATA FROM WEST VIRGINIA GIS TECHNICAL CENTER (WVGISTC) AND THE STATE ADDRESSING AND MAPPING BOARD (SAMB). EXISTING STRUCTURES, ROADWAYS, AND UTILITIES HAVE BEEN ADDED AS APPLICABLE BASED ON ORTHO IMAGES AND SHOULD BE VERIFIED BY CONTRACTOR PRIOR TO CONSTRUCTION.
- 10. PROPERTY BOUNDARIES, LANDOWNER INFORMATION AND ROAD NETWORKS SHOWN ON THIS PLAN ARE BASED ON AVAILABLE COUNTY GIS PARCEL DATA. PROPERTY OWNER INFORMATION INCLUDES NAME AND TAX MAP PARCEL IDENTIFICATION NUMBER OBTAINED FROM GIS TAX ASSESSMENT DATA.
- 11. CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPLACEMENT OF DAMAGED OR DESTROYED LANDSCAPE AND LAWNS.
- 12. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING A COPY OF ALL PERMITS RELATED TO THE CONSTRUCTION SHOWN ON THESE PLANS ON THE JOB SITE AT ALL TIMES.
- 13. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK ZONE TRAFFIC SAFETY AS MANDATED BY WYDOT, OSHA, LOCAL MUNICIPALITY AND OTHER
- 14. CONTRACTOR SHALL VERIFY ALL DIMENSIONS ON THE PROJECT SITE PRIOR TO THE START OF CONSTRUCTION
- 15. AT THE LOCATION OF ALL ROAD ACCESS POINTS CONTRACTOR SHALL ENSURE THAT POSITIVE DRAINAGE IS MAINTAINED IN THE VICINITY OF EACH INDIVIDUAL ACCESS DURING CONSTRUCTION AND ONCE THE FINAL SITE ACCESS IS ESTABLISHED IF A POLICABLE. IF A ROADSIDE DITCH IS PRESENT CONTRACTOR TO PROVIDE A MINIMUM 12" DIAMETER HDPE CULVERT TO MAINTAIN POSITIVE DRAINAGE IN THE DITCH. FOR ACCESS ONTO STATE ROADWAYS REFER TO THE APPROVED WYDOT HOP PLANS.
- 16. LIMITS OF EXISTING FACILITIES AND ACCESS DRIVES PERMITTED BY OTHERS AND INCLUDED HEREIN ARE APPROXIMATE AND ARE FOR CONTRACTOR REFERENCE ONLY AND ARE NOT A PART OF THIS PROJECT/PERMIT.
- 17. THE CONTRACTOR SHALL BE RESPONSIBLE OF PREPARING AND IMPLEMENTING AN ENGINEERING PREPAREDNESS, PREVENTION AND CONTINGENCY PLAN FOR THE CHOSEN CONSTRUCTION METHODS IN THE EVENT OF UNFORSEEN CIRCUMSTANCES, SUCH AS EXTREME WEATHER, OR DRILLING MUD SPILL.
- 18. HORIZONTAL STATIONING IS USED ON THE PLAN AND PROFILE DRAWINGS. THE CONTRACTOR IS TO DETERMINE THE TRUE LENGTH OF THE PIPE PRIOR TO BIDDING AND PRIOR TO ORDERING MATERIALS.
- 19. WVDOH HIGHWAY OCCUPANCY PERMITS ARE REQUIRED PRIOR TO GAINING ACCESS OFF OF STATE ROUTES AND ARE BEING SUBMITTED IN ASSOCIATION WITH THIS PLAN.
- 20. STREAM CROSSINGS SHOULD BE CONSTRUCTED AT LOW FLOW PERIODS WHEN PRACTICABLE.
- 21. IN-STREAM ACCESS MAY ONLY BE GAINED FROM WITHIN THE DESIGNATED LIMITS OF DISTURBANCE.
- 22. AQUATIC RESOURCE CROSSING CONSTRUCTION SHOULD BE COMPLETED WITHIN A 72-HOUR PERIOD
- 23. CONSTRUCTION SHOULD BE HALTED AND PROPER AUTHORITIES NOTIFIED IF PREVIOUS UNKNOWN REMAINS OR ARTIFACTS ARE DISCOVERED.
- 24. ALL TEMPORARILY EXCAVATED OR EXCESS MATERIAL IS TO BE STORED IN UPLAND AREAS ONLY.
- 25. ALL APPLICABLE BMPS NEED TO BE IN PLACE DURING CONSTRUCTION.
- 26. STREAM STABILIZATION AND REVEGETATION NEAR AQUATIC RESOURCES WILL BE COMPLETED, AS APPROPRIATE, IMMEDIATELY FOLLOWING CONSTRUCTION.
- 27. VEGETATION CLEARING AND SURFACE DISTURBANCE MUST REMAIN WITHIN DEFINED LIMITS OF DISTURBANCE.
- 28. A COPY OF THE PERMITS AND ASSOCIATED PLANS SHOULD REMAIN ON—SITE DURING CONSTRUCTION.
- 29. HERBICIDE USE WITHIN WETLANDS IS PROHIBITED.
- 30. HYDRIC SOILS EXCAVATED FROM WETLANDS SHALL BE STOCKPILED AND RETURNED TO WETLAND AREA.
- 31. NO GRADING IS PROPOSED AS PART OF THIS PROJECT, IF PROPOSED SLOPES NEED TO BE ADJUSTED FOR FIELD CONDITIONS THEY SHALL NOT BE GREATER THAN 2:1 OR 50% ANY PROPOSED SLOPES OVER 30 DEGREES (57.7%) IS CONSIDERED EXCESSIVE AND COULD CAUSE A FAILURE OR SLIP.
- 32. NO GRADING OVER 50% IS PROPOSED AS PART OF THIS PROJECT, IF PROPOSED SLOPES NEED TO BE ADJUSTED FOR FIELD CONDITIONS THEY SHALL NOT BE GREATER THAN 2:1 OR 50%. ANY PROPOSED SLOPES OVER 30 DEGREES (57.7%) IS CONSIDERED EXCESSIVE AND COULD CAUSE A FAILURE OR SLIP.

EROSION AND SEDIMENT CONTROL NOTES:

- 1. ALL EROSION AND SEDIMENT MEASURES TO BE IN ACCORDANCE WITH WEST VIRGINIA ONLINE BMP MANUAL FOR STANDARD GUIDELINES AND SPECIFICATIONS AVAILABLE AT: HTTPS://APPS.DEP.WV.GOV/DWWM/STORMWATER/BMP/INDEX.HTML
- 2. EROSION AND SEDIMENTATION CONTROL MEASURES HAVE BEEN SHOWN ON PLANS AND DETAILED IN SPECIFICATIONS.
- 3. EXPOSED SOILS SHALL BE STABILIZED BY APPLICATION OF EFFECTIVE BMP'S THAT PROTECT THE SOIL FROM THE EROSIVE FORCES OF RAINDROPS, FLOWING WATER AND WIND.
- 4. CLEARING AND GRUBBING IS TO OCCUR WITHIN THE NOTED LIMITS OF DISTURBANCE (LOD) ONLY.
- 5. ALL GRADED AREAS THAT ARE AT FINAL GRADE MUST BE SEEDED AND MULCHED WITHIN 7 DAYS AND AREAS THAT WILL NOT BE WORKED AGAIN FOR 14 DAYS OR MORE MUST BE SEEDED AND MULCHED WITHIN 7 DAYS.
- 6. AREAS WHERE THE SEED HAS FAILED TO GERMINATE ADEQUATELY (UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 70%) WITHIN 30 DAYS AFTER SEEDING AND MULCHING MUST BE RE-SEEDED IMMEDIATELY, OR AS SOON AS WEATHER CONDITIONS ALLOW.
- 7. TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL BMP'S SHALL BE MAINTAINED AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. MAINTENANCE AND REPAIR SHALL BE CONDUCTED IN
- 8. EROSION AND SEDIMENT CONTROL BMP'S SHALL BE INSPECTED AT LEAST ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES PER 24 HOUR PERIOD. ANY NECESSARY OR REQUIRED REPAIRS
- 9. CONTRACTOR TO COORDINATE THE SUBJECT WORK WITH ANY EROSION & SEDIMENT CONTROLS THAT MAY EXIST AT THE VARIOUS ADJACENT FACILITIES. EXISTING CONTROLS TO BE REPLACED/RESTORED IF DISTURBED OR CONTACT THE ENGINEER IF MODIFICATION IS REQUIRED.

ENVIRONMENTAL NOTES:

- 1. PLEASE REFER TO ENVIRONMENTAL REPORT FOR INFORMATION ON PROJECT SPECIFIC ENVIRONMENTAL CONSTRAINTS
- 2. AN AQUATIC RESOURCE DELINEATION WAS PERFORMED BY RETTEW ASSOCIATES, INC. IN OCTOBER 2015. WETLAND AND STREAM BOUNDARY LOCATIONS ARE SHOWN ON THE PLAN.
- 3. NATIONWIDE PERMITTING FOR STREAM AND WETLAND CROSSINGS IS REQUIRED PRIOR TO CONSTRUCTION AND IS BEING SUBMITTED IN ASSOCIATION WITH THIS PLAN.

CONSTRUCTION NOTES:

- . DATUM BASED ON WEST VIRGINIA STATE PLANE COORDINATE SYSTEM, NAD 83 NORTH ZONE, NAVD 88. ELEVATIONS MSL, DERIVED FROM GPS OBSERVATION.
- 2. EXISTING UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS GENERATED FROM PREVIOUS MAPS AND SURVEY.
 CONTRACTOR SHALL VERIFY EXACT LOCATION AND ELEVATION OF ALL EXISTING UTILITIES IN AREA OF WORK PRIOR TO CONSTRUCTION AND CALL 811 AND ALL OTHER UTILITY COMPANIES AT LEAST 2 WORKING DAYS (48 HOURS) PRIOR TO CONSTRUCTION.

UTILITY AGENCIES SERVING PROJECT AREA:

MISS UTILITY: 1-800-245-4848

WEST VIRGINIA DIVISION OF HIGHWAYS WVDOH DISTRICT #4 304-842-1576

RESPONSE TEAMS:

NATIONAL RESPONSE CENTER FOR REPORTING SPILLS 1-800-424-8802

STATE EMERGENCY SPILL NOTIFICATION 1-800-642-3074

EMERGENCY AMBULANCE, FIRE, LAW ENFORCEMENT 911

PRODUCT TRANSPORTED: WATER & GAS

UNT TO CAMP MISTAKE RUN CAMP MISTAKE RUN PRATT RUN JEFFERSON RUN UNT TO JEFFERSON RUN

RECEIVING WATER

UTILITY NOTES:

- . ALL TRENCH EXCAVATION SHALL BE IN ACCORDANCE WITH THE U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATOR'S STANDARDS. CONTRACTOR IS RESPONSIBLE FOR ALL TRENCH SAFETY.
- 2. TWO-FOOT MINIMUM VERTICAL AND HORIZONTAL CLEARANCE MUST BE MAINTAINED BETWEEN INSTALLED PIPELINE AND CROSSED OR ADJACENT UTILITIES.
- 3. THE UTILITIES SHOWN ON THIS PLAN ARE FOR REFERENCE PURPOSES ONLY. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE EXACT LOCATION PRIOR TO ANY EXCAVATION BY CALLING 811 OR 800-245-4848. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL ABOVE AND BELOW GROUND UTILITIES AND STRUCTURES AND WILL BE RESPONSIBLE FOR THE PROTECTION OF THESE UTILITIES AND STRUCTURES AT ALL TIMES. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THE EXISTING UTILITIES AND MAINTAIN UNITERRUPTED SERVICE AND ANY DAMAGE ON THE CONTRACTORS NEGLIGENCE SHALL BE REPAIRED IMMEDIATELY AND COMPLETELY AT HIS EXPENSE. CONTRACTOR SHALL NOTIFY ALL UTILITIES FOR VERIFICATION AND LOCATION OF UTILITIES PRIOR TO CONSTRUCTION.
- 4. UTILITY OWNER OF ADJACENT FACILITIES MUST BE CONTACTED AND WORK SHALL BE SCHEDULED TO ALLOW A DESIGNATED REPRESENTATIVE FROM THE UTILITY OWNER TO BE PRESENT FOR ALL CONSTRUCTION ACTIVITIES ADJACENT TO THEIR OWNED FACILITIES.

GENERAL INFORMATION


THIS SHEET IS INTENDED TO BE PRINTED OUT 22" X 34".
 LEGEND IS TYPICAL NOT ALL ITEMS IN LEGEND APPEAR IN DRAWING, ITEMS APPEARING IN DRAWING THAT DO NOT APPEAR IN LEGEND SHALL BE CLEARLY LABELED.








	ESTIMATED QUANTIFIED MATERIAL LIST		REFERENCE DRAWINGS				REVISION					Antero
				,	-				ļ. —		<u> </u>	Midstream Partners LP
										_		DOTSON HOLLAND ADDENDUM GENERAL NOTES SHEET
		-			+	\vdash			┼─		-	EROSION & SEDIMENT CONTROL PLAN
					1					ļ		ANTERO MIDSTREAM PARTNERS LP DODDRIDGE AND RITCHIE COUNTIES, WEST VIRGINIA
		-+			+	-			<u> </u>			DATE: 1/4/16 AFE No.: SCALE: AS SHOWN SEGMENT ID:
					1	1.26.16	PER DEP COMMENTS	PJF		PJF PROJ.	X ENG.	ORIGINATE NAME: NOV. CLEADWATER CNOT1 FINS REV.
NO.	DESCRIPTION	QTY	DWG. NO.	DESCRIPTION	NO.	DATE	DESCRIPTION	BY	CH'KD	ENGR.	APPR.	SHT. NAME: WV-CLEARWATER-GNOT1-ENS REV. 0


LEGEND: © WATER PIPELINE © GAS PIPELINE € ROAD PROPERTY/R.O.W. LINE PERMANENT EASEMENT WORKSPACE EASEMENT CONTOUR - MAJOR CONTOUR - MINOR UNDERGROUND ELECTRIC FOREIGN PIPELINE FENCE LINE Θ POWER- POLE SIGN **(W)** WELL ELECTRIC TRANSMISSION TOWER STRUCTURE INTENDED FOR HUMAN OCCUPANCY ADDITIONAL/TEMPORARY WORKSPACE SLOPE MATTING OR HYDROSEED SILT SAVER PRIORITY 1* SILT SAVER PRIORITY 2* WATERBAR W/ OUTLET PROTECTION TRENCH BREAKER OUTLET PROTECTION ******* ROCK CONSTRUCTION ENTRANCE STREAM WETLAND NOTE:
LECEND IS TYPICAL. NOT ALL ITEMS IN LECEND APPEAR IN DRAWING.
ITEMS APPEARING IN DRAWING THAT DO NOT APPEAR IN LECEND
SHALL BE
CLEARLY LABELED.
PERMETER CONTROL SHALL BE INSTALLED AND MAINTAINED AS
DESCRIBED ON SHEET IS UNDER THE "SCHEDULE OF MAINTENANCE OF
EROSION & SEDIMENT CONTROLS".



































EROSION AND SEMMENT CONTROL MEASURES SHALL BE IMPLEMENTED DURING THE CONSTRUCTION AND POS-CONSTRUCTION PERIOD TO PREVENT SOIL EROSION. AND PREVENT SEMMENT, AND OTHER POLLUTANTS FROM ENTERING STREAMS, NEIGHBORING PROPERTIES, ROADS, ETC. THESE MEASURES INCLUDE FILTER SOCKS, TOPSOIL STOCKPILES, STABILIZED CONSTRUCTION ENTRANCE, ETC. AS SHOWN ON THE DRAWINGS.

THE CONTRACTOR WILL BE REQUIRED TO INCORPORATE ALL APPLICABLE EROSION AND SEDIMENT CONTROL FEATURES INTO THE PROJECT AT THE EARLIEST PRACTICAL TIME, RESPONSIBILITY FOR IMPLEMENTING EROSION AND SEDIMENT CONTROL SHALL BE DESIGNATED TO A MINIMUM OF ONE INDIVIDUAL WHO WILL BE PRESENT AT THE PROJECT SITE DURING ACTIVE CONSTRUCTION.

TEMPORARY FROSION CONTROL MEASURES

- TEMPORARY VEGETATION SHALL BE ESTABLISHED IMMEDIATELY ON ALL SLOPES, ON STOCKPILED TOPSOIL AND ON ALL UNSTABILIZED DISTURBED AREAS. DISCONTINUED EARTHMOVING ACTIVITY WILL BE IMMEDIATELY STABILIZED.
- 2. DURING CONSTRUCTION, THE AMOUNT OF DISTURBED SOILS SHALL BE KEPT TO A MINIMUM AND, WHENEVER POSSIBLE, A SUITABLE VECETATIVE BUFFER WILL BE MAINTAINED AROUND ALL CONSTRUCTION AREAS.
- 3. ALL EARTHMOVING ACTIVITIES SHALL BE CARRIED OUT IN SUCH A MANNER AS TO MINIMIZE THE AMOUNT OF DISTURBED AREA.
- 4. WHEREVER POSSIBLE, PLACE ALL EXCAVATED MATERIAL UPSLOPE FROM DISTURBED AREAS. STOCKPILES SHALL BE SET PARALLEL TO GRADE TO REDUCE RUNOFF. ALL SOIL STOCKPILES ARE TO BE IMMEDIATELY SEEDED WITH A TEMPORARY GRASS COVER.
- 5. UPON GENERAL COMPLETION OF THE FINAL GRADING, TOPSOIL SHALL BE PLACED AND FINAL GRADING PASSES SHALL BE MADE PERPENDICULAR TO THE DIRECTION OF RUNOFF.
- 6. RE-SEED AND REESTABLISH ANY BARREN AND DISTURBED AREAS NOT HAVING ESTABLISHED GROUND COVER.
- FILTER SOCK AND/OR SILT FENCE SHALL BE PLACED AT CRITICAL EROSION AREAS. AS SHOWN ON THE PLAN, IN ORDER TO PREVENT SEDIMENT FROM ENTERING ONTO ADJACENT PROPERTIES, ROADWAYS AND WATERWAYS.
- 8. FILTER SOCK SHALL BE INSTALLED AND MAINTAINED PER THE MANUFACTURER'S INSTRUCTIONS.
- WHERE DUST OR WIND EROSION IS EVIDENT, THE SURFACE(S) SHALL BE SPRINKLED WITH WATER OR OTHER SUITABLE DUST SUPPRESSOR. WASHING OF ROADWAYS IS NOT PERMITTED.
- 10. ANY WATER PUMPED FROM ANY EXCAVATION, FOR ANY REASON, SHALL BE DIRECTED THROUGH A SEDIMENT FILTER BAG.
- 11. THE CONTRACTOR SHALL EMPLOY MEASURES DURING CONSTRUCTION TO PREVENT SPILLS OF FUELS OR LUBRICANTS. IF A SPILL OCCURS, IT SHALL BE CONTROLLED IMMEDIATELY TO PREVENT ITS ENTRY INTO
- 12. EXPOSED AND UNWORKED SOILS SHALL BE STABILIZED BY APPLICATION OF EFFECTIVE BMPS THAT PROTECT THE SOIL FROM THE EROSIVE FORCES OF RAINDROPS, FLOWING WATER, AND WIND. THE GENERAL PERMIT REQUIRES THAT ALL GRADED AREAS THAT AREA THATAL GRADE MUST BE SEEDED AND MULCHED WITHIN 7 DAYS AND AREAS THAT WILL NOT BE WORKED AGAIN FOR 14 DAYS OR MORE MUST BE SEEDED AND MULCHED WITHIN 7 DAYS.
- 13. CONTRACTORS SHALL INSTALL THE BEDDING MATERIALS, ROADBEDS, STRUCTURES, PIPEUNES, OR UTILITIES AND RE-STABILIZE THE DISTURBED SOILS SO THAT THE 7-DAY REQUIREMENTS ARE MET.
- 14. SELECTED SOIL STABILIZATION MEASURES SHALL BE APPROPRIATE FOR THE TIME OF YEAR, SITE CONDITIONS, AND ESTIMATED DURATION OF USE.

PERMANENT EROSION CONTROL MEASURES.

- 1. PERMANENT SOIL PROTECTION WILL BE COMPLETED AS EARLY AS PRACTICAL
- ALL E&S BMP'S SHALL BE IMPLEMENTED AND MAINTAINED UNTIL PERMANENT STABILIZATION IS COMPLETED, ONCE PERMANENT STABILIZATION HAS BEEN ESTABLISHED TEMPORARY E&S BMP'S M REMOVED, ANY AREAS DISTURBED IN THE ACT OF REMOVING TEMPORARY E&S BMP'S SHALL BE PERMANENTLY STABILIZED.
- 3. TEMPORARY AND PERMANENT SEEDING SHALL ADHERE TO THE SPECIFICATIONS PROVIDED IN THIS PLAN.
- 4. ALL EROSION AND SEDIMENT CONTROLS WILL BE INSPECTED WEEKLY AND AFTER ALL RUNOFF EVENTS.
- 5. THE PERMITTEE AND CO-PERMITTEE SHALL TAKE ALL REASONABLE STEPS TO MINIMIZE OR PREVENT ANY DISCHARGE IN MOLATION OF THIS PERMIT THAT HAS A REASONABLE LIKELIHOOD OF ADVERSELY AFFECTING HUMAN HEALTH OR THE ENVIRONMENT.
- APPROVED EROSION AND SEDIMENT CONTROL PLANS MUST BE AVAILABLE AT THE SITE OF THE CONSTRUCTION ACTIVITY AT ALL TIMES.
- IF FUEL OR OTHER DANGEROUS CHEMICALS ARE STORED ON SITE, THEN A PREPAREDNESS, PREVENTION AND CONTINGENCY (PPC) PLAN MUST BE DEVELOPED AND KEPT ON SITE.

CONSTRUCTION SEQUENCE

ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE SHALL BE COMPLETED BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE.

AT LEAST AB HOURS, BUT NOT MORE THAN 10 WORKING DAYS, PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY MISS UTILITY OF WEST VIRIGINA BY CALLING BIT OR 1-800-245-4846 FOR THE LOCATION OF EXISTING UTILITIES. WHERE NOTED ON PLANS, UTILITY OWNERS OF ADJACENT FACILITIES MUST BE CONTACTED AND WORK SHALL BE SCHEDULED TO ALLOW A DESIGNATED REPRESENTATIVE FROM THE FACILITY OWNER TO BE PRESENT FOR ALL CONSTRUCTION ACTIVITIES ADJACENT TO THEIR OWNED FACILITIES.

IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.

- 1. THE CONTRACTOR SHALL FIELD MARK ALL LIMITS OF DISTURBANCE FOR CONSTRUCTION ACTIVITIES.
- INSTALL STABILIZED CONSTRUCTION ENTRANCE. ALL VEHICLES ENTERING THE SITE SHALL DO SO VIA
 THE STABILIZED CONSTRUCTION ENTRANCE. ALL MUD OR SECIMENT TRACKED ONTO EXSTING ROADWAY
 SHALL BE REMOVED BY THE CONTRACTOR AT THE END OF EACH WORKING DAY. WASHING OF THE
 ROADWAY IS NOT PERMITTED.
- ROADWAY IS NOT PERMITTED.

 3. INSTALL ALL PERMIETER EROSION AND SEDIMENT CONTROL DEVICES. THE DUFF LAYER, NATIVE TOPSOIL, AND NATURAL VEGETAION SHALL BE RETAINED IN AN UNDISTURBED STATE TO THE MAXMUM EXTENT PRACTICABLE. PRIOR TO LEAVING A CONSTRUCTION SITE, SURFACE WATER RUNOFF FROM DISTURBED AREAS SHALL PASS THROUGH AN APPROPRIATE AND APPROVED SEDIMENT REMOVAL BMP. BMPS INTENDED TO TRAP SEDIMENT FOR STATE SHALL BE CONSTRUCTED AS ONE OF THE FIRST STEPS IN GRADING. THESE BMPS SHALL BE FUNCTIONAL BEFORE OTHER LAND DISTURBING ACTIVITIES TAKE PLACE.

 4. CONSTRUCTION OF THE PIPELINE TO PROCEED IN SECTIONS DETERMINED BY AVAILABLE CONSTRUCTION ACCESS ROADS CONSTRUCTION ACCESS ROADS. CONSTRUCTION TO THE PIPELINE CONSTRUCTION. TEMPORARY ACCESS ROADS TO BE RETIRED AND RESTORED, AND PERMANENT ACCESS ROADS TO BE PREMARENTLY STABILIZED AS SOON AS PRACTICABLE AFTER CONSTRUCTION USE IS CONCILIDED.
- 5. CLEAR AND GRUB AREAS AS REQUIRED TO BEGIN PIPELINE CONSTRUCTION
- 6. TOPSOIL AND SOIL SPOILS SHALL BE STOCKPILED WITHIN THE LIMITS OF DISTURBANCE. FILTER SOCK OR SILT FENCE SHALL BE PLACED DOWNGRADIENT OF STOCKPILES.
- 7. EXCAVATE TRENCH AND INSTALL PIPING, PLACE SUITABLE BACKFILL MATERIAL INTO TRENCH IN ONE FOOT LIFTS AND COMPACT, FILL MATERIAL SHALL BE FREE OF ROOTS, SOD, AND OTHER ORGANIC MATERIAL, FROZEN SIGL AND ROCK AND DISCARDED CONSTRUCTION MATERIAL. THE FILL SHALL BE PLACED IN LAYERS BEING COMPACTED PRIOR TO THE MEXT LAYER BEING PLACED. WHEN THE AREA REACHES PRESCRIBED ELEVATION, THE BACKFILL SHOULD BE THROUGH, IN FOLICULD AND COMPACTE TO ELIMINATE SOFT OR UNSETTLED AREAS. AS WORK PROCRESSES, PERMANENTY STRABLIZE TRENCH WITH TOPSOIL. SEED, AND MUCH OR MATTING TO PROTECT FROM ACCELERATED EROSION AND SEDIMENTATION.
- 8. CONSTRUCT ONLY THE LENGTH OF PIPE THAT CAN BE TRENCHED, INSTALLED, TESTED, BACKFILLED AND STABLIZED SUCH THAT NO MORE THAN 5,000 FEET OF TRENCH REMAINS OPEN. RESTORE SEDIMENT DEVICES DURING INSTALLATION.
- 9. STREAM CROSSINGS TO BE MADE AS INDICATED ON PLANS AND SHOWN IN DETAILS. SEDIMENT LADEN

- WATER TO BE DIRECTED AWAY FROM STREAMS. VEHICULAR TRAFFIC TO AVOID CROSSING STREAMS WITHOUT APPROPRIATE MEASURES BEING IN PLACE AS INDICATED IN DETAILS.
- 10. DURING CONSTRUCTION ALL EROSION AND SEDIMENT CONTROL BMPS MUST BE MAINTAINED AS PRESCRIBED IN THE SCHEDULE OF MAINTENANCE NOTES.
- 11. PROCEDURES WHICH ENSURE THAT THE PROPER MEASURES FOR THE RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THE PROJECT SITE WILL BE UNDERTAKEN IN ACCORDANCE WITH
- 12. ALL BMP'S MUST REMAIN IN PLACE AND FUNCTIONAL UNTIL ALL AREAS WITHIN THE LIMIT OF DISTURBANCE ARE COMPLETED AND PERMANENTLY STABILIZED. MAINTENANCE MUST INCLUDE INSPECTION OF ALL EROSION AND SEDIMENT CONTROLS AFTER EACH RUNOFF EVENT IN EXCESS OF 0.5" AND ON A WEEKLY BASIS.
- WEEKLY BASIS.

 3. THE CONSTRUCTION SITE SHOULD BE STABILIZED AS SOON AS POSSIBLE AFTER COMPLETION. ESTABLISHMENT OF FINAL COVER MUST BE INITIATED NO LATER THAN 7 DAYS AFTER REACHES FINAL GRADE. A NOTICE OF TERMINATION MUST BE FILED WITH THE DEF WHEN THE SITE REACHES FINAL STABILIZATION. FINAL STABILIZATION MEANS THAT ALL SOIL—DISTURBING ACTIVITIES ARE COMPLETED, AND THAT ETHER A PERMANENT VEGETATIVE COVER WITH A DENSITY OF 70% OR GREATER HAS BEEN ESTABLISHED OR THAT THE SURFACE HAS BEEN STABILIZED BY HARD COVER SUCH AS PAVEMENT OR BUILDINGS. IT SHOULD BE NOTIO THAT THE 70% REQUIREMENT REFERS TO THE TOTAL AREA VEGETATED AND NOTI JUST A PERCENT OF THE SITE.
- 14. ALL PERIMETER SEDIMENT CONTROL MEASURES CAN BE REMOVED AFTER THE SITE IS PERMANENTLY STABILIZED AND APPROVAL IS RECEIVED FROM THE WYDEP.
- ANY AREAS DISTURBED BY REMOVAL OF CONTROLS SHALL BE REPAIRED, STABILIZED AND PERMANENTLY SEEDED.

SCHEDULE OF MAINTENANCE OF EROSION & SEDIMENT CONTROLS

THE SOIL EROSION AND SEDIMENT CONTROLS UTILIZED IN THE DEVELOPMENT OF THIS PLAN SHALL BE MAINTAINED AND REPAIRED IN ORDER TO KEEP THEM IN EFFECTIVE CONDITION UNTIL PERMANENT STABILIZATION OCCURS. THE CONTROLOGY SHALL INSPECT AT A MINIMUM ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5" OF RAIN PER 24 HOUR PERIOD. IN ORDER TO ASSURE PROPER FUNCTION, MAINTENANCE OF THE CONTROLS SHALL INCLUDE, AT A MINIMUM, THE FOLLOWING MAINTENANCE PROCEDURES FOR UTILIZED CONTROLS.

INSPECTIONS MUST BE BY A QUALIFIED PERSON TRAINED AND EXPERIENCED IN EROSION AND SEDIMENT CONTROL A WRITTEN REPORT OF EACH INSPECTION SHALL BE KEPT AND DOCUMENTED IN AN INSPECTION LOG TO BE MAINTAINED ON SITE AT ALL TIMES.

ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN-OUT, REPAIR, REPLACEMENT, RE-SEEDING, RE-MULCHING, AND RE-NETTING, MUST BE PERFORMED IMMEDIATELY.

MISCELLANEOUS ADJUSTMENTS AND CORRECTIONS SHALL BE MADE TO ANY EROSION CONTROL STRUCTURE AS DEEMED NECESSARY BY THE ENVIRONMENTAL INSPECTOR. IF EROSION AND SEDIMENT CONTROL BMPS FALL TO PERFORM AS EXPECTED, REPLACEMENT BMPS OR MODIFICATIONS OF THOSE INSTALLED WILL BE

STABILIZED CONSTRUCTION ENTRANCE

- 1. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDMENT ONTO PUBLIC RICHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDMENT. ALL SEDMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
- WHEELS ON ALL VEHICLES SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-DF-WAY, IF WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO APPROVED SEDIMENT TRAPPING DEVICE, PRECAUTIONS MUST BE TAKEN TO PREVENT MUDDY WATER FROM RUNNING INTO WATERWAYS OR STORM SEWERS.

TEMPORARY CONSTRUCTION ROAD, WORK AND PARKING AREA STABILIZATION

- BOTH TEMPORARY AND PERMANENT ROADS, LAYDOWN AND WORK AREAS AND PARKING AREAS MAY REQUIRE PERIODIC TOP DRESSING WITH NEW GRAVEL.
- SEEDED AREAS ADJACENT TO THE ROADS AND PARKING AREAS SHOULD BE CHECKED PERIODICALLY TO ENSURE THAT A VIGOROUS STAND OF VEGETATION IS MAINTAINED.
- ROADSIDE DITCHES AND OTHER DRAINAGE STRUCTURES SHOULD BE CHECKED REGULARLY TO ENSURE THAT THEY DO NOT BECOME CLOGED WITH SILT OR OTHER DEBRIS.

- SAFETY FENCE SHALL BE CHECKED REGULARLY FOR WEATHER-RELATED OR OTHER DAMAGE. ANY NECESSARY REPAIRS MUST BE MADE IMMEDIATELY.
- CARE SHOULD BE TAKEN TO SECURE ALL ACCESS POINTS (GATES) AT THE END OF EACH WORKING DAY. ALL LOCKING DEVICES MUST BE REPAIRED OR REPLACED AS NECESSARY.

- 1. AFTER TOPSOIL APPLICATION, FOLLOW PROCEDURES FOR SEEDBED PREPARATION.
- 2. TAKE CARE TO AVOID EXCESSIVE MIXING OF TOPSOIL INTO THE SUBSOIL.
- 3. PERMANENTLY STABILIZE THE SITE FOLLOWING APPROPRIATE PRACTICE STANDARDS AS QUICKLY AS PRACTICABLE.
- 4. PERIODICALLY INSPECT THE SITE UNTIL PERMANENT STABILIZATION IS ACHIEVED
- 5. MAKE NECESSARY REPAIRS TO ERODED AREAS OR AREAS OF LIGHT VEGETATIVE COVER.
- 6. TOPSOIL WILL NOT BE SEGREGATED UNLESS SPECIFIED BY LANDOWNER AGREEMENT

AREAS THAT FAIL TO ESTABLISH A VEGETATIVE COVER ADEQUATE TO PREVENT RILL EROSION SHOULD BE RE-SEEDED AS SOON AS SUCH AREAS ARE IDENTIFIED.

EXEMPTION STATEMENT OF THE MOST SEEDING OPERATIONS, FAILURES OCCUR. WHEN IT IS CLEAR THAT PLANTS HAVE NOT CERMINATED ON AN AREA OR HAVE DIED. THESE AREAS MUST BE PREPARED AND RESEEDED IMMEDIATELY TO PREVENT EROSION DAMAGE. IT IS EXTREMELY IMPORTANT TO DETERMINE MAY DECRIMINATION DIO NOT TAKE PLACE AND MAKE ANY NECESSARY CORRECTIVE ACTIONS. HEALTHY VEGETATION IS THE MOST EFFECTIVE EROSION CONTROL AVAILABLE. SOME HIGHLY ACIDIC SOILS (ESPECIALLY AROUND VARIOUS COAL SEAMS IN THE COALFELDS) WILL RESIST THE BEST EFFORTS TO REVECETATE THEM. IN THESE CASES, TOPSOLING WILL BE THE ONLY WAY TO ESTABLISH VEGETATION.

MULCHING INCLUDING FLEXIBLE GROWTH MEDIUM AND BONDED FIBER MATRIX

- ALL MULCHES AND SOIL COVERINGS SHOULD BE INSPECTED PERIODICALLY (PARTICULARLY AFTER RAINSTORMS AND HIGH MINDS) TO CHECK FOR EROSION AND DISPLACEMENT. WHERE EROSION IS OBSERVED IN MULCHED AREAS, ADDITIONAL MULCH SHOULD BE APPLIED AND EROSION REPAIRED IF NECESSARY.
- . NETS AND MATS SHOULD BE INSPECTED AFTER RAINSTORMS FOR DISLOCATION OR FAILURE. IF WASHOUTS OR BREAKAGE OCCUR, REINSTALL NETTING OR MATTING AS NECESSARY AFTER REGRADING TO REPAIR DAMAGE TO THE SLOPE OR DITCH. INSPECTIONS SHOULD TAKE PLACE UP UNTIL GRASSES ARE FRIMILY ESTABLISHED OR THE AREA IS REDISTURBED.

BASIC MONITORING SHOULD CONSIST OF VISUAL INSPECTIONS TO DETERMINE MAT INTEGRITY AND ATTACHMENT PERFORMANCE. RILL DEVELOPMENT BENEATH THE MAT OR EDGE LIFTING IS EVIDENCE INADEQUATE ATTACHMENT. UNTIL THE VECETATION IS FULLY ESTABLISHED. THE GROUND SURFACE SHOULD BE INSPECTED FOR SIGNS OF RILL OR GULLY EROSION BELOW THE MATTING.

2. ANY SIGNS OF EROSION, TEARING OF THE MATTING, OR AREAS WHERE THE MATTING IS NO LONGER ANCHORED FIRMLY TO THE GROUND SHOULD BE REPAIRED. REPAIR ANY DAMAGED AREAS IMMEDIATE BY RESTORING SOIL TO FINISHED GRADE. RE-APPLING SOIL AMEDIDATINS AND SEED, AND REPLACIT THE R.E.C.P.S. ADDITIONAL STAKING AND TRENCHING CAN BE EMPLOYED TO CORRECT DEFECTS. RECENTLY PLACED MATS MAY BE REPLACED, BUT ONCE VEGETATION BECOMES ESTABLISHED, REPLACEDMENT IS NOT A REASONABLE OPTION UNLESS LARGE FAILURES HAVE OCCURRED. IF THE R.E.C.P.S ARE VEGETATED, THE VEGETATION SHOULD BE WATERED AS NEEDED. GETTING GRASS ESTABLISHED AS QUICKLY AS POSSIBLE IS VERY IMPORTANT.

TEMPORARY DIVERSION

- INSPECT THE DIKE, FLOW CHANNEL AND OUTLET FOR DEFICIENCIES OR SIGNS OF EROSION. RESEED OR OTHERWISE STABILIZE THE DIKE A NEEDED TO MAINTAIN ITS STABILITY. INSPECT FOR SEDIMENT DEPOSITS, CONSTRICTIONS AND BLOCKAGES. REMOVE ANY SIGNOCHAGE MIMEDIATELY.
- DAMAGES CAUSED BY CONSTRUCTION ACTIVITIES OR TRAFFIC MUST BE REPAIRED IMMEDIATELY DURING REPAIRS, PROPERLY COMPACTED ANY MATERIAL ADDED TO THE DIKE.
- VEGETATED SWALE CHANNELS SHOULD BE INSPECTED REGULARLY TO CHECK FOR POINTS OF SCOUR, BANK FAILURE OR INADEQUATE VEGETATIVE COVER; RUBBISH OR CHANNEL OBSTRUCTION; RODENT HOLES OR EXCESSIVE WEAR FROM PEDESTRIAN OR CONSTRUCTION TRAFFIC. UNED SWALE CHANNELS SHOULD BE CHECKED REGULARLY FOR DETERIORATION FROM FREEZING, SALT OR CHEMICALS; SCOUR OR UNDERMINIOR AT THE INLET AND OUTLET; OR POINTS OF SEDIMENT DEPOSITION.
- 4. ANY NEEDED REPAIRS SHALL BE MADE PROMPTLY.

OUTLET PROTECTION /RIPRAP

- INSPECT AFTER HIGH FLOWS FOR EVIDENCE OF SCOUR BENEATH THE RIPRAP OR FOR DISLODGED STONES.
- 2. IF A SIGNIFICANT NUMBER OF STONES HAVE BEEN DISLODCED IT WILL BE NECESSARY TO RECALCULATE STONE SIZE AND REPLACE THE EXISTING STONE WITH PROPERLY SIZED STONE.
- 3. ANY REPAIRS MUST BE MADE IMMEDIATELY.

RIGHT OF WAY DIVERSION

IN AREAS WHERE CONSTRUCTION IS ACTIVELY OCCURRING, DIVERSIONS SHOULD BE INSPECTED DAILY, AND DAMAGE CAUSED BY CONSTRUCTION TRAFFIC OR OTHER ACTIVITY REPAIRED BEFORE THE END OF EACH WORKING DAY.

FLUME BYPASS / COFFERDAM & PUMP AROUND

- LUSE DAM AND PUMP METHOD ON NARROW WATERCOURSES WITH LIMITED STREAM FLOW TO PREVENT SEDIMENTATION AND INTERRUPTION OF STREAM FLOW DURING CROSSING CONSTRUCTION. IF FISH PASSAGE IS A CONCERN, HIS METHOD IS NOT APPROPRIATE.

 2. SCHEDULE CONSTRUCTION DURING LOW FLOW PERIOD.
- SET UP PUMP AND HOSE AS SHOWN, OR USE OTHER PRACTICAL ALTERNATIVES. PUMP SHOULD HAVE TMCE THE PUMPING CAPACITY OF ANTICPATED FLOW. HAVE STANDBY PUMP ON SITE.
- INSTALL USTREAM DAM COMPOSED OF SANDBASS OR CLEAN GRAVEL WITH PLASTIC LINER, INSTALL DOWNSTREAM DAM IF REQUIRED TO KEEP STREAM BED DRY.
- EXCAVATE TRENCH AND LOWER IN PIPE UNDER HOSE, MOVE HOSE AS REQUIRED OR DISCONNECT IF TEMPORARY FLOW BLOCKAGE IS ACCEPTABLE. BACKFILL TRENCH. DISMANTLE DOWNSTREAM DAM, THEN UPSTREAM DAM, KEEP PUMP RUNNING TO MAINTAIN FLOW. MONITOR DAM AND PUMP FOR PROPER OPERATION THROUGHOUT THE CROSSING INSTALLATION.
- 8. IN HIGH QUALITY (HQ) OR EXCEPTIONAL VALUE (EV) STREAMS, USE 12" FILTER SOCK IN PLACE OF SLT FENCE.
- 9. ENSURE DISTURBED AREAS ARE SEEDED AND MULCHED USING SEED MIXTURES SPECIFIED IN THE INCLUDED TABLE.

- PERIODIC INSPECTION MUST BE PERFORMED TO ENSURE THAT THE BRIDGE, CULVERTS, STREAMBED AND STREAM BANKS ARE MAINTAINED AND NOT DAMAGED, THAT SEDIMENT IS NOT ENTERING THE STREAM. NEVER ALLOW THE STRUCTURE TO BECOME CLOGGED WITH DEBRIS REMOVE ANY OBSTRUCTION.
- 2. SEDIMENT AND DEBRIS REMOVED SHALL BE DISPOSED OF OUTSIDE OF THE FLOODPLAIN AND STABILIZED.

. THE FILTER FABRIC SYSTEM SHOULD BE INSPECTED PERIODICALLY TO DETERMINE IF HIGH FLOWS HAVE CAUSED SCOUR BENEATH THE FABRIC OR DISLODGED ANY OF THE FABRIC. IF REPAIRS ARE NEEDED, THEY SHOULD BE COMPLETED IMMEDIATELY.

SILT FENCE/SUPER SILT FENCE/SILT-SAVER/BELTED SILT RETENTION FENCE

- 1. IMMEDIATELY REPAIR DAMAGED SILT FENCE RESULTING FROM END RUNS AND UNDERCUTTING.
- SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.
- FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE OR PARALLEL TO THE CONTOURS, BOTH ENDS OF THE FENCE SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.
- 4. FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY AREA IS PERMANENTLY STARILIZED.
- SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE— HALF THE HEIGHT OF THE BARRIER.
- IF ANY SECTION OF SILT FENCE IS KNOCKED DOWN DURING A RAIN EVENT THEN OTHER MEASURES SUCH AS A SEDIMENT TRAP AND DIVERSION OR SUPER SILT FENCE MUST BE INSTALLED.
- 7. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.

- 1. DURING INSPECTION, LOOK FOR WATER RUNNING DOWN THE ROAD AND FOR SCOUR IN THE DITCH LINES. LOOK FOR WATER COMING OUT OF CUT SLOPES AND FOR UPSLOPE CONCENTRATED FLOWS NOT GOING TO CULVERTS. IF WATER BARS OR BROAD-BASED DIPS ARE USED, THEY MUST BE DEEP ENQUOH TO CAPTURE ROAD SURFACE RUNOFF. IF RUNOFF GOES PAST EITHER PRACTICE, REPAIR IMMEDIATELY.

- THE ACCUMULATED SEDIMENT THAT IS REMOVED FROM A DEWATERING DEVICE MUST BE SPREAD ON-SITE AND STABILIZED OR DISPOSED OF AT AN APPROVED DISPOSAL SITE AS PER APPROVED PLAN.

INSPECT THE BERN, FLOW CHANNEL AND OUTLET FOR DEFICIENCIES OR SIGNS OF EROSION, RESEED OR OTHERWISE STABILIZE THE DIKE AS NEEDED TO MAINTAIN ITS STABILITY.

- 2. INSPECT FOR SEDIMENT DEPOSITS, CONSTRICTIONS AND BLOCKAGES. REMOVE ANY BLOCKAGE IMMEDIATELY.
- 3. DAMAGES CAUSED BY CONSTRUCTION ACTIVITIES OR TRAFFIC MUST BE REPAIRED IMMEDIATELY.
- 4. DURING REPAIRS, PROPERLY COMPACT ANY MATERIAL ADDED TO THE BERM
- 5. VEGETATED SWALE CHANNELS SHOULD BE INSPECTED REGULARLY TO CHECK FOR POINTS OF SCOUR, BANK FAILURE OR IMADEQUATE VEGETATIVE COVER, RUBBISH OR CHANNEL OBSTRUCTION, RODENT HOLES OR EXCESSIVE WEAR FROM PEDESTRAIN OR CONSTRUCTION TRAFFIC INJECT SWALE CHANNELS SHOULD BE CHECKED REGULARLY FOR DETERIORATING FROM FREZING, SALT OR CHEMICALS, SCOUR OR UNDERMINING AT THE INLET AND OUTLET, OR POINTS OF SEDIMENT DEPOSITION.

PIPELINE CONSTRUCTION

- ALL BURIED LINES SHALL BE INSTALLED WITH A MINIMUM OF THREE (3) FEET OF COVER, EXCEPT WHERE SOLID ROCK IS ENCOUNTERED IN WHICH CASE THE MINIMUM GOVER SHALL BE TWO (2) FEET. IN AGRICULTURAL FIELDS, A MINIMUM OF FOUR (4) FEET OF COVER SHALL BE INSTALLED, AND UNDERNEATH ROADS, A MINIMUM OF FIVE (5) FEET SHALL BE INSTALLED.
- 2. WHENEVER A BURIED LINE CROSSES A PRE-EXISTING PUBLIC OR PRIVATE ROADWAY, THE LOCATION OF THE LINE SHALL BE CLEARLY MARKED AT THE POINT OF CROSSING BY AN APPROPRIATE MARKER.
- A SUITABLE CONDUCTIVE WIRE SHALL BE INSTALLED WITH PLASTIC PIPE TO FACILITATE LOCATING IT WITH AN ELECTRONIC PIPE LOCATOR; PROVIDED, THAT ANY OTHER SUITABLE MATERIAL OR MEANS FOR ACCOMPLISHING THIS PURPOSE MAY BE EMPLOYED.

RECYCLING & DISPOSAL

- ALL POLLUTANTS, INCLUDING WASTE MATERIALS AND DEMOLITION DEBRIS, THAT OCCUR ON SITE DURING CONSTRUCTION SHALL BE HANDLED AND DISPOSED OF IN A MANNER THAT DOES NOT CAUSE CONTAMINATION OF SURFACE WATER. WOODY DEBRIS MAY BE CHOPPED AND SPREAD ON SITE.
- 2. COVER, CONTAINMENT, AND PROTECTION FROM VANDALISM SHALL BE PROVIDED FOR ALL CHEMICALS, LIQUID PRODUCTS, PETROLEUM PRODUCTS, AND NON-INERT WASTES PRESENT ON THE SITE.
- 3. MAINTENANCE AND REPAIR OF HEAVY EQUIPMENT AND VEHICLES INVOLVING OIL CHANGES, HYDRAULIC SYSTEM DRAIN DOWN, SOLVENT AND DE-GREASING CLEANING OPERATIONS, FUEL TANK ORAIN DOWN AND REMOVAL, AND OTHER ACTIVITIES WHICH MAY RESULT IN DISCHARCE OF SPILLAGE OF POLLUTANTS TO THE GROUND OR INTO SUFFACE WATER RUNDET MUST BE CONDUCTED USING SPILL PREVENTION MEASURES, SUCH AS DRIP PANS. CONTAMINATED SURFACES SHALL BE CLEANED IMMEDIATELY FOLLOWING ANY DISCHARGE OR SPILL INCIDENT. EMERGENCY REPAIRS MAY BE PERFORMED ON-SITE USING TEMPORARY PLASTIC PLACED BENEATH AND, IF RAINING, OVER THE VEHICLE.
- WHEEL WASH OR TIRE BATH WASTEWATER SHALL BE DISCHARGED TO A SEPARATE ON-SITE TREATMENT SYSTEM OR TO THE SANITARY SEMEN.
- APPLICATION OF AGRICULTURAL CHEMICALS INCLUDING FERTILIZERS AND PESTICIDES SHALL BE CONDUCTED IN A MANNER AND AT APPLICATION RATES THAT WILL NOT RESULT IN LOSS OF CHEMICAL TO SURFACE WATER RUNOFF. MANUFACTURERS' RECOMMENDATIONS FOR APPLICATION RATES AND PROCEDURES SHALL BE FOLLOWED.
- 6. BMPS SHALL BE USED TO PREVENT OR TREAT CONTAMINATION OF SURFACE WATER RUNOFF BY pH MODIFYING SOURCES. THESE SOURCES INCLUDE BULK CEMENT, CEMENT KILN DUST, FLY ASH, NEW CONCRETE WASHING AND CURING WATERS, WASTE STREAMS GENERATED FROM CONCRETE GRINDING AND SAWING, EXPOSED AGGREGATE PROCESSES, AND CONCRETE PUMPING AND MIXER WASHOUT WATERS.
- PROCEDURES, WHICH ENSURE THAT THE PROPER MEASURES FOR THE RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THE PROJECT SITE, WILL BE UNDERTAKEN IN ACCORDANCE WITH WY DEP REGULATIONS, INDIVIDUALS RESPONSIBLE FOR THE DISPUBBINE ACCORDANGE WITH THAT PROPER MECHANISMS ARE IN PLACKISSIES FOR WASTE MATERIALS, CONSTRUCTION WASTES INCLUDE, BUT ARE NOT LIMITED STATES AND MATERIALS, BUILDING MATERIALS, CONCRETE WASH WATER, SANITARE NOT LIMITED. THAT COLLID ADVERSELY IMPACT WATER QUALITY. THE CONTRACTOR WATER, SANITARE AND MEDICAL THAT COLLID ADVERSELY IMPACT WATER QUALITY. THE CONTRACTOR CONTROL DURING CONSTRUCTION, WHEREVER POSSIBLE, RECYLING OF EXCESS MATERIALS IS PREFERRED. RATHER THAN DISPOSAL OF CONSTRUCTION WASTES SHALL BE IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL QUIDELINES AND REGULATIONS.

GENERAL INFORMATION

THIS SHEET IS INTENDED TO BE PRINTED OUT 22" X 34".
 LEGEND IS TYPICAL. NOT ALL ITEMS IN LEGEND APPEAR IN DRAWNG, ITEMS APPEARING IN DRAWNG THAT DO NOT APPEAR IN LEGEND SHALL BE CLEARLY LABELED.





	L
TO THE PARTY OF TH	
Q134	
	Г
3/81	Г
	Г
THE DESCRIPTION OF THE PERSON	r
Teary	r
	r

Antero REVISION ESTIMATED QUANTIFIED MATERIAL LIST REFERENCE DRAWINGS Midstream Partners or DOTSON HOLLAND ADDENDUM CONSTRUCTION DETAILS EROSION & SEDIMENT CONTROL PLAN ANTERO MIDSTREAM PARTNERS LP DODDRIDGE AND RITCHIE COUNTIES, WEST VIRGINIA 1/4/16 AFE No.: AS SHOWN SEGMENT ID: PJF DM PJF X 1 1.26.16 PER DEP COMMENTS PROJ. ENG. SHT. NAME: WV-CLEARWATER-DETI-ENS REV. O I ву Існ'ко. NO. DATE DESCRIPTION DESCRIPTION OTY DWG. NO.

1. OBJECTIVES

IL UBINECTIVES

PROVIDE SUFFCIENT VEGETATION TO CONTROL EROSION AND SEDIMENTATION ON AND OFF THE SITE —
A VECETATIVE COVER OF 70% OR GREATER IS REQUIRED. THE STANDARDS REQUIRED BY THESE PLANS
MAY BE MODIFIED ONLY WITH PRIOR AND DOCUMENTED APPROVAL
2. ACREAGE CALCULATION.

APPLICATION RATES LISTED ON THESE PLANS ARE ON A "PER ACRE" BASIS. TO CALCULATE ACREAGE, MEASURE THE AVERAGE LENGTH AND WIDTH (IN FEET) OF EACH AREA TO BE TREATED. ACREAGE IS DETERMINED BY MULTIPLYING THE LENGTH BY THE WIDTH, THEN DIVIDING THE TOTAL BY 43,560.

S SITE PREPARATION

1. WATER_CONTROL

INSTALL NEEDED SURFACE WATER CONTROL MEASURES, DIVERSION DITCHES, WATER BARS, SEDIMENT CONTROLS PRIOR TO SEEDING AND MULCHING.

2. SEEDBED PREPARATION THE SEEDBED MUST BE LOOSE AT THE TIME OF SEEDING. APPLICATIONS OF SEED ON HARD GROUND WILL RESULT IN A POOR STAND OF VEGETATION. THE SOIL SURFACE MUST BE LOOSENED (MINIMUM

C. SEEDING

1. TEMPORARY SEEDING

1. TEMPORARY SEEDING

a. TEMPORARY SEEDING APPLIES WHERE EXPOSED SOIL SURFACES ARE NOT TO BE FINE-GRADED OR WORKED FOR PERIODS LONGER THAN 14 DAYS. TEMPORARY VEGETATIVE COVER WITH SEDIMENT CONTROLS MUST BE ESTABLISHED WHERE RUNOFF WILL OO DIRECTLY INTO A STREAM, IMMEDIATELY UPON CONSTRUCTION OF THE SITE (SITE INCLUDES ROAD AND LOCATION), VEGETATION MUST BE ESTABLISHED ON ROAD BANK AND LOCATION SLOPES. A PERMANENT VEGETATIVE COVER SHALL BE APPLIED TO REAS THAT WILL BE LEFT UNWORKED FOR A PERIOD OF MORE THAN 6 MONTHS.

b. SEED MIXTURES AND PLANTING DATES REFER TO THE TRABLES FOR RECOMMENDED ATES TO SETABLISH VEGETATIVE COVER AND THE APPROVED LISTS OF TEMPORARY AND PERMANENT PLANT SPECIES, AND PLANTING RATES. THE THABLE GIVES RECOMMENDED TYPES OF TEMPORARY VEGETATION, AND OPTIMUM SEEDING DATES. IN SITUATIONS WHERE ANOTHER COVER IS DESIRED CONTACT THE LOCAL SOIL CONSERVATION DISTRICT FOR SEEDING RECOMMENDATIONS. c. SEED APPLICATION

E. SEED APPLICATION
APPLY SEED BY BROADCASTING, DRILLING, OR BY HYDROSEEDING ACCORDING TO THE RATES INDICATED IN THE TABLE, PERFORM ALL PLANTING OPERATIONS AT RIGHT ANGLES TO THE SLOPE.
NECESSARY SITE PREPARATION, ROUGHENING OF THE SOIL SURFACE, SHOULD BE DONE JUST PRIOR TO SEEDING. SEEDBED PREPARATION MAY NOT BE REQUIRED ON NEWLY DISTURBED AREAS.

2. PERMANENT SEEDING

a. GENERAL

Q._CENEAL

PERMANENT VEGETATIVE COVER MILL BE ESTABLISHED WHERE NO FURTHER SOIL DISTURBANCE IS ANTIOPATED OR NEEDED. SOIL FERTILITY AND OH LEVEL SHOULD BE TESTED AND ADJUSTED ACCORDING TO SEED SPECIES PLANTED. PLANTING OF PERMANENT VEGETATIVE COVERS NUST BE PERFORMED ON ALL DISTURBED AREAS AFTER THE COMPLETION OF THE DRILLING PROCESS. ANY SITE THAT CONTAINS SCIONIFICANT AMOUNTS OF TOPSOIL SHALL HAVE THE TOPSOIL PRUMOVED AND STOCKPILED WHEN FEASIBLE. TOPSOIL SHOULD NOT BE ADDED TO SLOPES STEEPER THAN 2:1 UNLESS A GOOD BONDING TO THE SUB-LAYER CAN BE ACHIEVED. AFTER PROPER GRADING AND SEEDBED PREPARATION, THE VEGETATION MILL REESTABLISH GROUND COVER FOR THE CONTROL OF SURFACE WATER RUNDEY AND ERSON. ALL REQUIRED SEEDBED PREPARATION, LOSSENING OF SOIL BY DISKING OR DOZER TRACKING, SHOULD BE PERFORMED. JUST PRIOR TO SEEDING, IF SEEDBED PREPARATION IS NOT FEASIBLE, 50% MORE SEED SHALL BE ADDED TO THE RECOMMENDED RATES SHOWN IN THE TABLES.

MUNE SEED SHALL BE ADDED TO THE RECOMMENDED RATES SHOWN IN THE TABLES. WHEN THORSEEDING, SEEDED PREPARATION MAY NOT BE NECESSARY IF ADECUATE SITE PREPARATION WAS PERFORMED. INCORPORATION HEAD PROPERTIES AMOUNT OF LIME AND/OF FERTILIZER IN THE SURRY MIX WHEN THORSEEDING.

FERTILIZER IN THE SLURRY MIX WHEN HYDROSELING.
WHEN HYDROSEDING, RISTS MIX THE LIBE, FERTILIZER, AND HYDRO-MULCH IN THE RECOMMENDED AMOUNT OF WATER. MIX THE SEED AND INQUILANT TOGETHER WITHIN ONE HOUR PRIOR TO PLANTING, AND ADD TO THE SLURRY JUST BEFORE SEEDING, APPLY THE SLURRY JUSTED WITH SECOND THE PREPARED SITE. ASSURE THAT AGITATION IS CONTINUED THROUGHOUT THE SEEDING OPERATION AND THAT THE MIX IS APPLIED WITHIN ONCE HOUR OF INITIAL MIXING.

b. LIME AND FERTILIZER

LIME AND FERTILIZER

I LIME SHALL BE APPLIED TO ALL PERMANENT SEEDINGS. THE PH OF THE SOIL IS TO BE DETERMINED AND LIME APPLIED ACCORDINGLY. ONCE THE PH IS KNOWN, SELECT THE AMOUNT OF LIME TO BE APPLIED FROM THE TABLE.

II. FERTILIZER SHALL BE APPLIED IN ALL PERMANENT SEEDINGS. APPLY THE EQUIVALENT OF 200 LBS. MINIMUM 10-20-20 FERTILIZER PER ACRE OR USE THE AMOUNT OF FERTILIZER AND LIME RECOMMENDED BY A CERTIFIED SOIL TEST.

III. APPLICATION: FOR BEST RESULTS AND MAXIMUM BENEFITS THE LIME AND FERTILIZER ARE TO BE APPLIED AT THE TIME OF SEEDBED PREPARATION.

c. PERMANENT SEED MIXTURES CONTRACTOR SHOULD TAKE INTO CONSIDERATION THE SPECIES MAKEUP OF THE EXISTING PASTURE AND THE LANDOWNER'S FUTURE PASTURE MANAGEMENT PLANS WHEN SELECTING SEED MIXTURES. SELECTION: IF NOT SPECIFIED BY LANDOWNER, SELECT FROM THE PERMANENT

SEEDING TABLE. NOTES:

, ALL LEGUMES MUST BE PLANTED WITH THE PROPER INOCULANT PRIOR TO SEEDING.

II. 'LATHCO' FLATPEA IS POTENTIALLY POISONOUS TO SOME LIVESTOCK.

III. ONLY ENDOPHYTE FREE VARIETIES OF TALL FESCUE SHOULD BE USED. TALL FESCUE AND CROWNVETCH ARE ALSO A VERY INVASIVE SPECIES NON-NATIVE TO WV.

III. FOR UNPREPARED SEEDBEDS OR SEEDING OUTSIDE THE OPTIMUM TIMEFRAMES, ADD 50% MORE SEED TO THE SPECIFIED RATE.

d. SEEDING FOR WILDLIFE HABITAT

A. SPEDING FOR MULDIFE HABILAL
CONSIDER THE USE OF NATIVE PLANTS OR LOCALLY ADAPTED PLANTS WHEN SELECTING COVER
TYPES AND SPECIES FOR WILDLIFE HABITAT. WILDLIFE FRIENDLY SPECIES OR MIKES THAT IT
WILTIPLE VALUES SHOULD BE CONSIDERED. SEE WILDLIFE FRIENDLY SPECIES WITKTURES IN TABLE
IV—48. CONSIDER SELECTING NO OR LOW MAINTENANCE LIN-LIVED PLANTS ADAPTABLE TO
SITES WHICH MAY BE DIFFICULT TO MAINTAIN WITH EQUIPMENT.

O MILI CHING

1. GENERAL ORGANIC MULCHES

GENERAL ORGANIC MULCHES

THE APPLICATION OF STRAW, HAY OR OTHER SUITABLE MATERIALS TO THE SOIL SURFACE TO PREVENT EROSION. STRAW MADE FROM WHEAT OR OATS IS THE PREFERRED MULCH, THE USE OF HAY IS PERMISSIBLE, BUT NOT ENCOURAGED DUE TO THE RISK OF SPREADING INVASIVE SPECIES. MULCH MUST BE APPLED TO ALL TEMPORARY AND PERMANENT SEEDING ON ALL DISTURVED AREAS. DEPENDING ON SITE CONDITIONS, IN CRITICAL AREAS SUCH AS WATERWAYS, OR STEEP SLOPES, ADDITIONAL OR SUBSTITUTE SOIL PROTECTIVE MEASURES MAY BE USED IF DEEMED NECESSARY. EXAMPLES INCLUDE JUTE MESH, AND SOIL STABILIZATION BLANKETS OR EROSION CONTROL MATTING.

AREAS THAT HAVE BEEN TEMPORARILY OR PERMANENTLY SEEDED SHOULD BE MULCHED IMMEDIATELY FOLLOWING SEEDING, MULCHES CONSERVE DESTRABLE SOIL PROPERTIES, REDUCE SOIL MOSTURE LOSS, PREVENT CRUSTING AND SELING OF THE SOIL SURFACE AND PROVIDE A SUITABLE MICROCLIMATE FOR SEED GERMINATION.

SEED GEMINIATION.

ARRAS THAT CANNOT BE SEEDED BECAUSE OF THE SEASON SHOULD BE MULCHED TO PROVIDE SOME PROTECTION TO THE SOIL SUFFACE. AN ORGANIC MULCH, STRAW OR HAY, SHOULD BE USED AND THE AREA THEN SEEDED AS SOON AS WEATHER OR SEASONAL CONDITIONS PERMIT. ON HOT USE FIRST MULCH (CELLULOSE—HYDROSEED) ALONE FOR THIS PRACTICE: AT NORMAL APPLICATION RATES IT MILL NOT GIVE THE SOIL PROTECTION OF OTHER TYPES OF MULCH.

WOOD CELLULOSE FIBER MULCH, IS USED IN HYDROSEEDING OPERATIONS AND APPLIED AS PART OF THE SILURRY, IT CREATES THE BEST SEE—SQIL CONTACT WHEN APPLIED OVER TOP OF (AS A SEPARATE OPERATION) NEMLY SEEDED AREAS, FIBER MULCH DOES NOT ALONE PROVIDE SUFFICIENT PROTECTION ON HIGHLY ERODIBLE SOILS, OR DURING LESS THAN FAVORABLE GROWING CONDITIONS, FIBER MULCH SHOULD NOT BE USED ALONE DURING THE DRY SUMMER MONTHS OR WHEN USED FOR LATE FALL MULCH COVER. USE STRAW MULCH DURING THESE PERIODS, AND FIBER MULCH MAY BE USED TO TACK (ANCHOR) THE STRAW MULCH. FIBER MULCH IS WELL SUITED FOR STEEP SLOPES, CRITICAL AREAS, AND AREAS SUSCEPTIBLE TO WIND.

AREAS SUSCEPTIBLE TO WIND.

2. CHEMICAN MULCHES. SOLD IBINDERS. AND TACKIFIERS.

A WIDE RANGE OF SYNTHETIC, SPRAY-ON MATERIALS IS MARKETED TO STABILIZE AND PROTECT THE SOIL SUFFACE. THESE ARE MIXED WITH WATER AND SPRAYED OVER THE MULCH AND TO THE SOIL. THEY MUST BE USED ALONE IN SOME CASES AS TEMPORARY STABILIZERS, OR IN CONJUNCTION WITH FIBER MULCH, STRAW OR HAY.

WHEN USED ALONE MOST CHEMICAL MULCHES DO NOT HAVE THE CAPABILITY TO INSULATE THE SOIL OR RETAIN SOIL MOISTURE THAT ORGANIC MULCHES HAVE.

S. SPECIFICATIONS: FROM THE TABLE SELECT THE TYPE OF MULCH AND RATE OF APPLICATION THAT WILL BEST SUIT THE CONDITIONS AT THE SITE.

4. ANCHORING ADMINISTRATION ON THE FIELD SITUATION, MULCH MAY NOT STAY IN PLACE BECAUSE OF WIND ACTION OR RAPID WATER RUNOFF. IN SUCH CASES, MULCH IS TO BE ANCHORED MECHANICALLY OR WITH MULCH NETTING.

g. MECHANICAL ANCHORING MECHAGINAL ARUDINITIES.
APPLY MULCH AND PULL A MULCH ANCHORING TOOL OVER THE MULCH. WHEN A DISK IS USED, SET THE DISK STRAIGHT AND PULL ACROSS THE SLOPE. MULCH MATERIAL SHOULD BE TUCKED INTO THE SOIL ABOUT THREE INCHES

b. MULCH NETTING FOLLOW MANUFACTURER'S RECOMMENDATIONS WHEN POSITIONING AND STAPLING THE MULCH NETTING IN THE SOIL.

E. FENCING

ENGING:

LIVESTOCK SHALL BE CONTROLLED OR EXCLUDED AS NECESSARY TO ALLOW FOR ESTABLISHMENT AND
MAINTENANCE OF THE DESIRED VEGETATIVE COVER. WHERE LIVESTOCK ARE PRESENT, THE OPERATOR
SHOULD CONSULT WITH THE AFFECTED LANDONNER TO COORDINATE THE FENCE THE AND LAYOUT.
ALSO, PERMANDIN FENCING MAY NEED INSTALLED AS A PROTECTIVE MEASURE AROUND WELL SITE
FIXTURES, SENSITIVE AREAS OR AREAS PRONE TO RECURRING DISTURBANCE AND ENGSON (e.g. SUPS)

MINIMUM STANDARDS FOR INSTREAM CONSTRUCTION ACTIVITIES

GENERAL REQUIREMENTS FOR ALL INSTREAM ACTIVITIES

ALL APPROPRIATE PERMITS SHOULD BE OBTAINED PRIOR TO BEGINNING INSTREAM CONSTRUCTION

ACTIVITIES SUCH AS CREATING A RESTRICTION OR IMPEDIMENT OF FLOW.

2. ISOLATING THE WORK AREA AND "WORKING IN THE DRY" IS THE ONLY EFFECTIVE WAY OF CONTROLLING SPINIFFIT

3. ALL INSTREAM CONSTRUCTION SHOULD BE SCHEDULED TO OCCUR DURING LOW FLOW PERIODS, TYPICALLY DURING THE SUMMER AND FALL MONTHS. IF CONSTRUCTION MUST BE ACCOMPLISHED DURING HIGHER FLOWS, THE WORK AREA MUST BE ISOLATED FROM THE STREAM BY A STRUCTURAL MEASURE SUCH AS A NON-ERCOIBLE COFFERDAM OR SHEET PILING. EMERGENCY REPAIRS OF PUBLIC UTILITIES OR PUBLIC ROADS ARE EXEMPTED.

ALL STREAMBANKS ARE TO BE STABILIZED WITH AN APPROPRIATE PROTECTIVE MATERIAL SUCH AS RIPRAP, REVEGETATION, GEOTEXTILES, REVETMENTS, ETC. IMMEDIATELY UPON COMPLETION OF THE FINAL

THE CHOICE OF STABILIZATION MATERIALS (VEGETATIVE OR STRUCTURAL) SHOULD BE BASED ON SOUND ENGINEERING PRACTICES AND WILL INCLUDE INVESTIGATIONS OF THE SOIL'S ERODIBILITY AND THE ANTICIPATED VELOCITIES OF THE STREAM.

INLET AND CUTLET PROTECTION IS REQUIRED FOR ALL CULVERTS (BOTH TEMPORARY AND PERMANENT). OUTLET PROTECTION CAN CONSIST OF RIPRAP, GABION BASKETS, OR OTHER APPROVED MATERIALS.

EVERY EFFORT SHOULD BE MADE TO LIMIT THE AMOUNT OF INSTREAM WORK. UTILITY LINES SHOULD NO' BE INSTALLED WITHIN THE STREAM, WITH THE EXCEPTION OF STREAM CROSSING, WITHOUT IRREFUTABLE PROOF THAT ALTERNATE AVENUES OF ALIGNMENT ARE NOT AVAILABLE. CONVENIENCE IS NOT A JUSTIFIABLE REASON TO INSTALL A UTILITY LINE DOWN A STREAM.

8. UTILITY LINES AND ROADWAYS SHOULD CROSS THE STREAM AT RIGHT ANGLES (± 15') TO THE FLOW OF THE WATER.

EACH STREAM CROSSING SHOULD BE TREATED AS A SEPARATE PROJECT AND WORK SHOULD PROGRESS UNTIL THE APPROACHES AND STREAM BANKS ARE COMPLETELY STABILIZED. IN NO CASE SHOULD STABILIZED TO NO THE STREAM BANK EXCEED 24 HOURS FROM COMPLETION OF THE SACKFILL.

10. STREAM SIDE VEGETATION SHOULD BE LEFT INTACT TO THE GREATEST EXTENT POSSIBLE. RIPARIAN BUFFER ZONES ARE TO BE ENHANCED WHENEVER POSSIBLE.

11. WHEN WORK IS PERFORMED IN A FLOWING STREAM, PRECAUTIONS SHOULD BE TAKEN TO MINIMIZE ENCROACHMENT, CONTROL SEDIMENT TRANSPORT AND STABILIZE THE WORK AREA TO THE GREATEST EXTENT POSSIBLE DURING CONSTRUCTION. USE ONLY NON-EROBILE MATERIAL FOR THE CONSTRUCTION OF CAUSEWAYS, STREAM DIVERSIONS AND BERMS AND COFFERDAMS. EARTHEN FILL MAY BE USED FOR COFFERDAMS IF ARMORED BY NON- ERODIBLE COVER MATERIALS SUCH AS FILTER FABRIC AND APPROPMATELY SIZED STOME.

12. ALL WATER PUMPED FROM A WORK AREA ALONG, IN OR NEAR A STREAM MUST BE TREATED IN AN APPROVED STRUCTURE LOCATED OUTSIDE THE WATERWAY BEFORE BEING DISCHARGED INTO A WATERWAY.

13. GREEN CONCRETE IS TOXIC TO AQUATIC LIFE AND MUST NOT BE PLACED IN CONTACT WITH FLOWING WATER.

14. STREAMBED EXCAVATION SHOULD BE UNDERTAKEN FROM THE TOP OF STREAM BANKS WHENEVER

WHEN INSTREAM WORK IS REQUIRED, THE USE OF RUBBER-TIRED VEHICLES AND EXCAVATORS IS RECOMMENDED.

16. EXCAVATED MATERIAL TO BE REUSED FOR TRENCH BACKFILL SHOULD BE STOCKPILED OUTSIDE THE STREAM CHANNELL SURROUND THE STORAGE AREA BY SLIT FENCE OR SIMILAR BARRIER TO PREVENT SEDIMENT AND MUD FROM RUNNING BACK INTO THE STREAM, MATERIAL NOT USED FOR BACKFILL SHOULD BE REMOVED TO AN APPROPRIATE SOIL DISPOSAL AREA LOCATED OUTSIDE THE FLOODPLAIN AND PROPERLY STABILIZED.

17, TEMPORARY ACCESS ROADS IN CLOSE PROXIMITY TO A STREAM SHOULD BE STABILIZED USING THE SAME REQUIREMENTS FOR A STABILIZED CONSTRUCTION ENTRANCE.

18. DO NOT USE THE STREAM AS A VEHICULAR RIGHT-OF-WAY. DO NOT USE THE STREAM TO DELIVER MATERIALS OR TO MOVE CONSTRUCTION EQUIPMENT FROM ONE SECTION TO ANOTHER.

19 SPILL CONTAINMENT KITS SHOULD BE READILY AVAILABLE ONSITE.

LIME AND FERTILIZER APPLICATION TABLE

FERTILIZER	UME
10/20/20	PELLETIZED
200 LBS PER ACRE	1.5 TON PER ACRE

TABLE 3101 TEMPORARY STABILIZATION SEEDING

SEED	RATES IN LOS PER ACRE	RECOMMENDED DATA						
ANNUAL RYEGRASS	250-350	MAR. 15 TO SEPT. 15						
ANNUAL WINTER WHEAT	100-125	SEPT. 15 TO MAR. 15						

TABLE 3.12.1 MULCH MATERIALS RATES AND USES

MULCH MATERIAL	MINIMUM RATES PER ACRE
STRAW	2 TONS

PERMANENT SEEDING


Antero Midstream Default Pasture Mix (200 - 225 LBS per Acre)								
Named Variety of Forage Perennial Ryegrass	20%							
Named Variety of Forage Tall Fescue (not Fown)	20%							
Climax Timothy	15%							
Orchardgrass	10%							
Birdsfoot Trefoil	10%							
Medium Red Clover	5%							
Ladino Clover	5%							
Kentucky Bluegrass VNS	5%							
Alsike Clover	5%							
Alfalfa	5%							

^{*} All seed mixes require double inoculation

Antero Midstream Default Wildlife Mix (150 - 175 LBS per Acre)								
Medium Red Clover	20%							
Buckwheat	10%							
ts (Spring & Summer) or Wheat (Foll & Winter)	10%							
Ladino White Clover	20%							
Birdsfoot Trefoil	10%							
Alfafa	10%							
Named Variety of Forage Perennial Ryegrass	10%							
Annual Ryegrass	10%							

^{*} All seed mixes require double inoculati

Antero Midstream Genera (200 - 250 LBS pe	
Named Variety of Forage Tall Fescue (not Fown)	50%
Named Variety of Forage Perennial Ryegrass	20%
Annual Ryegrass	15%
Ladino Clover	5%
Alsike Clover	5%
Birdsfoot Trefoil	5%



TYPICAL SLOPE PROTECTION DETAIL


GENERAL INFORMATION


THIS SHEET IS INTENDED TO BE PRINTED OUT 22" X 34".
 LEGEND IS TYPICAL. NOT ALL ITEMS IN LEGEND APPEAR IN DRAWING. ITEMS APPEARING IN DRAWING THAT DO NOT APPEAR IN LEGEND SHALL BE CLEARLY LABELED.






ESTIMATED QUANTIFIED MATERIAL LIST			REFE	RENCE DRAWINGS			REVISION					
					\perp			├	-			Midstream Partners LP
												DOTSON HOLLAND ADDENDUM CONSTRUCTION DETAILS
									ļ. —			EROSION & SEDIMENT CONTROL PLAN ANTERO MIDSTREAM PARTNERS LP
				·	-							DODDRIDGE AND RITCHIE COUNTIES, WEST VIRGINIA
					+	1.26.16	PER DEP COMMENTS	PJF	DM	PJF	×	DATE: 17-4710 PCF MSS. SCALES: AS SHOWN SECRETY ID: DRAWN BD: SHEET 17 OF 20 GREGGES: TLS SHEET 17 OF 20
NO.	DESCRIPTION	QTY	DWG. NO.	DESCRIPTION		DATE	DESCRIPTION			PROJ. ENCR.	ENG. APPR.	SHT. NAME: WV-CLEARWATER-DET2-ENS REV. O







BROAD BASED DIP - LOW GRADIENT (<5%) ROADWAYS

TOTAL DIP LENGTH: 100 FT. DIP ALIGNED STRAIGHT ACROSS ROAD

> MINIMUM DEPTH=12 IN. PROFILE VIEW

BROAD-BASED DIPS SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN AND AT THE LOCATIONS SHOWN ON THE PLAN DRAWNIGS.

DIPS SHALL BE ORIENTED SO AS TO DISCHARGE TO THE LOW SIDE OF THE ROADWAY.


DIPS SHALL BE INSPECTED DAILY. DAMAGED OR NON-FUNCTIONING DIPS SHALL BE REPAIRED BY THE END OF THE WORKDAY.

MAXIMUM SPACING OF BROAD-BASED DIPS SHALL BE EQUAL TO 400' / % GRADE + 75'.

USE OUTLET PROTECTION AS DEPICTED IN WATERBAR/BROAD BASED DIP OUTLET PROTECTION DETAIL

BROAD BASED DIP FOR HIGH GRADIENT (5%-10%) ROADWAYS

STONE ACCESS DRIVE SECTION




135 CROSS DRAIN/WATERBAR

CROSS DRAIN DETAIL

SPACING OF CROSS DRAINS

HYDROCOVER ** EZFLO ** BLEND, HYDRAULICALLY APPLIED EROSION CONTROL FRODUCT (HECP)



SPECIFICATION: Section 32 92 16.16 - Hydraulic Seeding: Hydraulic Mulch - Blend

This section specifies a hydrautically-applied, 100% biodegradable Hydrautic Mulch (HM) - Blend comp of 100% recycled long strand, thermally refined (within a pressure vessel) wood fibers that have been of 100% recycled long strand, thermally refined (within a pressure vessel) wood inters that have been pressure treated to 80 - 55 psi (552 - 568 kPa) with steam and heat treated for 15 minutes at 380 - 440 degrees Fahrenheit (193 - 226 degrees Celsius) and 100% recycled cellulose fiber. The HM is phytosantifized, free from plastic netting and forms a bond with the soil surface to create a porcus and absorbent erostion layer that enhances germination and plant growth. All components of the HM shall be pro-packaged by the Manufacturer to assure both material performance and compliance with the following the state of the degree of the compliance of feetilizer (limit and this institute) and the processing should be the compliance of the compliance of feetilizer (limit and this institute) and the should be should be seen that the compliance of feetilizer (limit and this institute) and the should be sh values. No chemical additives with the exception of fertilizer, liming and biostimulant materials should be

INSTALLATION

Strictly comply with equipment manufacturer's installation instructions and recommendations. Use approved hydro-spraying machines with fan-type nozzle (50-degree tip). To achieve optimum soil surface coverage, apply HM from opposing directions to soil surface. Rough surfaces (rocky terrain, cat tracks and ripped soils) may require higher application rates to achieve 75% cover. Slope interruption devices or water diversion techniques are recommended when slope lengths exceed 23 feet (7 m). Maximum slope length is for product applications on a 4H:1V slope. For application on steeper slopes, slope interruption lengths may need to be decreased based on actual site conditions. Not recommended for channels or areas with concentrated water flow. No chemical additives with the exception of 'ortilizer, liming and biostimulant materials should be added to this product. For Erosion Control and Revegetation: To ensure proper analication rates. measure and stake area

1. Apply fertilizer with spozified prescriptive agranomic formulations, seed and HM at a rate of 50 to per 100 gallons (23 kg / 380 liters) of water over property prepared surfaces. Confirm leading rates with equipment manufacturer.

On not apply on saturated soils or substrates. Do not apply if precipitation is anticipated within 24-48 hours.

APPLICATION RATES: These application rates are for standard conditions. Designers may need to increase application rates on rough surfaces. Consult application and loading charts to

Slope Gradient / Condition ≤ 4H to 1V > 4H to 1V and ≤ 3H to 1V

SEE COMPREHENSIVE CSI FORMATTED SPECIFICATION FOR FURTHER DETAILS

PLEASE NOTE THAT THE INFORMATION PRESENTED HEREIN IS CENERAL INFORMATION ONLY. IT IS FOR CONCEPTUAL USE ONLY AND NOT INTENDED TO BE USED FOR CONSTRUCTION. WHILE EVERY EFFORT HAS BEEN MADE TO ENSURE ITS ACCURACY, THIS INFORMATION SHOULD NOT BE USED FOR A SPECIFIC APPUADION WITHOUT INDEPENDENT PROFESSIONAL EXAMINATION AND VERIFICATION OF ITS SUITABILITY, APPULGABLITY AND ACCURACY.


HydroCover

HYDROCOVER™ EZFLO™ BLEND (0)CAD Details **IECA** Slope

CONTACT NUMBER: 800-508-868

WEB SITE: www.profilep

DRAWN BY: NEA DATE: 12/23/10 SCALE: NOT TO SCALE CHECKED BY: SHEET I OF I



DITCH SHALL BE EXCANTED TO A DEPTH AND GRADE. TO CLUMENT.

DITCH BOTTOM WILL HAVE A FIRM FOUNDATION FOR THE CULVERT, GRAVEL MAY BE USED TO STABLUZ THE DITCH BOTTOM.

STABLUZ THE DITCH BOTTOM.

BUTCH BOTTOM BOTTOM.


THE BOTH BOTTOM BOTTOM.

THE BOTH BOTTOM BOTTOM.

RECOMMENDED INSTALLATION IS WITH A BACKHOE RATHER THAN A DOZER.

CULVETTS WILL HAVE CULLET FORDECTION (IC. FIELD ROCK OR RIPRAP, AND SEDIMENT BARRIERS) AS WELL AS NATURAL FILTER STRIP AREAS.

DITCH RELIEF CULVERT



STREAM CROSSING WITH CULVERT

GENERAL INFORMATION

THIS SHEET IS INTENDED TO BE PRINTED OUT 22" X 34".
 LEGEND IS TYPICAL. NOT ALL ITEMS IN LEGEND APPEAR IN DRAWING. ITEMS APPEARING IN DRAWING THAT DO NOT APPEAR IN LEGEND SHALL BE CLEARLY LABELED.



2° CAP (CLEAN 2B STONE)



	NOT TO SCALE	ES/M4004										
	ESTIMATED QUANTIFIED MATERIAL LIST		REFE	RENCE DRAWINGS			REVISION					
						_		+	┼	\vdash	\vdash	
\dashv		+-	 		\vdash			士	士			
\dashv								_	—	—	\vdash	
\Box		-			\vdash	_		+-	+-	\vdash		ER
		+	 		T							
					Т				<u> </u>			DAYE: SCALE: DRAWN BY CHECKED:
-			 		1	1.26.16	PER DEP COMMENTS	PJF		PJF	×	CHECKED:
NO.	DESCRIPTION	QTY	DWG. NO.	DESCRIPTION	NO.	DATE	DESCRIPTION	BY	сн'ко	PROJ. ENGR.	ENG. APPR.	SHT.

MAntero Midstream Partners u

DOTSON HOLLAND ADDENDUM

CONSTRUCTION DETAILS

ROSION & SEDIMENT CONTROL PLAN ANTERO MIDSTREAM PARTNERS LP DODDRIDGE AND RITCHIE COUNTIES, WEST VIRGINIA

SHEET 20 OF 20 . NAME: WV-CLEARWATER-DET5-ENS REV.O



DEPARTMENT OF THE ARMY

HUNTINGTON DISTRICT, CORPS OF ENGINEERS 502 EIGHTH STREET HUNTINGTON, WEST VIRGINIA 25701-2070

REPLY TO ATTENTION OF

MAR 11 2016

Regulatory Division
Energy Resource Branch
LRH-2016-0088-LKR-Dotson Run

PRELIMINARY JURISDICTIONAL DETERMINATION AND NATIONWIDE PERMIT NO. 12 VERIFICATION

Ms. Patricia Kazimier Antero Resources Corporation 1615 Wynkoop Street Denver, CO 80202

Dear Ms. Kazimier:

I refer to the Pre-Construction Notification (PCN) received in office on January 19, 2016 with supplemental information received on February 29, 2016 requesting a Department of the Army (DA) authorization to discharge dredged and/or fill material into waters of the United States (U.S.) in association with the construction of the Dotson Holland Addendum Project. The proposed project will involve the construction of a 16-inch buried waterline and a 10-inch buried low pressure gas line. The proposed project will be located approximately 0.36 mile south of Greenwood, in Doddridge and Ritchie Counties, West Virginia. The PCN has been assigned the following file number: LRH-2016-0088-LKR-Dotson Run. Please reference this number on all future correspondence related to this project.

The U.S. Army Corps of Engineers (Corps) authority to regulate waters of the U.S. is based on the definitions and limits of jurisdiction contained in 33 CFR 328 and 33 CFR 329. Section 404 of the Clean Water Act (Section 404) requires a DA permit be obtained prior to discharging dredged or fill material into waters of the U.S., including wetlands. Section 10 of the Rivers and Harbors Act of 1899 (Section 10) requires a DA permit be obtained for any work in, on, over or under a navigable water.

Preliminary Jurisdictional Determination:

Based on a review of the information provided, three (3) perennial streams, totaling 1,697 linear feet, four (4) intermittent streams, totaling 2,632 linear feet, twenty-one (21) ephemeral streams, totaling 4,622 linear feet and three (3) wetlands totaling 1.128 acre are located within the preliminary jurisdictional determination (PJD). On-site waters have a surface hydrological connection to Dotson, Leason, and Cabin Run all tributaries to the Little Kanawha River. Refer to the enclosed PJD Form for a detailed description of jurisdictional waters. This office has determined these may be waters of the U.S. in accordance with the Regulatory Guidance Letter (RGL) for Jurisdictional Determinations (JDs) issued by the Corps on June 26, 2008 (RGL No. 08-02).

issued by the West Virginia Department of Environmental Protection. A copy of this NWP can be found on our website at http://www.lrh.usace.army.mil/Missions/Regulatory.aspx.

In view of the above, your utility line project is authorized subject to the terms and conditions of the enclosed material, including the enclosed special conditions. It is your responsibility to ensure that your work conforms to all of the environmental management conditions listed within the enclosed material. Please be aware this NWP verification does not obviate the requirement to obtain any state or local assent required by law for the activities.

This verification is valid until the expiration date of the NWPs, unless the NWP authorization is modified, suspended, or revoked. The verification will remain valid if the NWP authorization is reissued without modification or the activity complies with any subsequent modification of the NWP authorization. All of the existing NWPs are scheduled to be modified, reissued, or revoked on March 18, 2017. Prior to this date, it is not necessary to contact this office for re-verification of your project unless the plans for the proposed activity are modified. Furthermore, if you commence or under contract to commence this activity before March 18, 2017, you will have twelve (12) months from the date of the modification or revocation of the NWP to complete the activity under the present terms and conditions of this NWP.

A copy of this NWP and verification letter must be supplied to your project engineer responsible for construction activities. A copy of the verification letter must be kept at the site during construction.

Upon completion of the work, the enclosed certification must be signed and returned to this office. If you have any questions concerning the above, please contact Mr. Aca Ramey at (304) 399-5166 or by email at aca.c.ramey@usace.army.mil

Sincerely,

Christopher L. Carson

Regulatory Project Manager

Energy Resource Branch

Enclosures

Nationwide Permit Verification Special Conditions Antero Resources Corporation LRH-2016-0088-LKR-Dotson Run Dotson Holland Addendum Project Doddridge and Ritchie Counties, West Virginia

Page 1 of 1

- 1. Should new information regarding the scope and/or impacts of the project become available that was not submitted to this office during our review of the proposal, the permittee will submit written information concerning proposed modification(s) to this office for review and evaluation, as soon as practicable.
- 2. Section 7 obligations under Endangered Species Act must be reconsidered if new information reveals impacts of the project that may affect federally listed species or critical habitat in a manner not previously considered, the proposed project is subsequently modified to include activities which were not considered during Section 7 consultation with the United States Fish and Wildlife Service, or new species are listed or critical habitat designated that might be affected by the subject project.
- 3. In the event any previously unknown historic or archaeological sites or human remains are uncovered while accomplishing the activity authorized by this nationwide permit you must immediately and contact local, state and county law enforcement offices (only contact law enforcement on findings of human remains), the Corps at (304) 399-5610 and West Virginia State Historic Preservation Office at (304) 558-0220. You must, to the maximum extent practicable, avoid construction activities that may affect the remains and artifacts until the required coordination has been completed. The Corps will initiate the Federal, state and tribal coordination required to comply with the National Historic Preservation Act and applicable state and local laws and regulations. Federally recognized tribes are afforded a government-to-government status as sovereign nations and consultation is required under Executive Order 13175 and 36 CFR Part 800.
- 4. Upon completion of the activity authorized by this nationwide permit verification, the enclosed activity completion certification must be signed and returned to this office.
- 5. No area for which grading has been completed will be unseeded or un-mulched for longer than 14 days. All disturbed areas will be seeded and/or re-vegetated with native species and approved seed mixes (where practicable) after completion of construction activities for stabilization and to help preclude the establishment of non-native invasive species.



The Doddridge Independent **PUBLISHER'S CERTIFICATE**

I, Michael D. Zorn, Publisher of The Doddridge Independent, A newspaper of general circulation published in the town of West Union, Doddridge County, West Virginia, do hereby certify that:

Floodplain Permit Application # 16-414

Please take notice that on the 24th day of February, 2016

Antero Midstream, LLC

filed an application for a Floodplain Permit to develop land located at or about:

Central District - 39.234175N, 80.895326W Description - Pipeline

was published in The Doddridge Independent 2 times commencing on Friday, March 4, 2016 and Ending on Friday, March 11, 2016 at the request of:

George Eidel, Doddridge County Floodplain Manager& Doddridge County Commission

Given under my hand this Friday, March 11, 2016

The publisher's fee for said publication is:

\$ 25.27 1st Run/\$ 18.95 Subsequent Runs This Legal Ad Total: \$ 44.22

Notary Public in and for Doddridge County

My Commission expires on

Public Notice • Legal Notice

Doddridge County

Floodplain Permit Application # 16-414

Please take notice that on the 24th day of Lebruary, 2016

Antero Midstream, LLC

filed an application for a Floodplain Permit to develop land located at or about:

Central District - 39.234175N, 80.895326W

Description - Pipeline

Permit Application# 16-414

Date Received 02/24/2016

Date Announced to Commission - 3/1/2016
Publication Date - Week of 3/1/16
20 Day Comment Period (from Commission Meeting Date)

The Application is on file with the Clerk of the County Court and may be inspected or copied during regular business hours. As this project is outside the FEMA identified floodplain of Doddridge County, Doddridge County Floodplain Management has no regulatory authority. Any interested persons who desire to comment shall present the same in writing by March 21, 2016, delivered to:

Ending: 03/21/2016

Clerk of the County Court 118 E. Court Street, West Union, WV 26456 Beth A Rogers, Doddridge County Clerk George Eidel. Doddridge County Flood Plain Manager

3/04 - 3/1

AAHUD LESOUTES Conporation ATTN: Rachel Graybuk 535 White Ociks Blud Bridgeputh WV 262380





Doddridge County FPM ATTN: George Fichel 108 Court St, Svite 102 West Union, LUN ZU456