

### Floodplain Development Permit

### Doddridge County, WV Floodplain Management

This permit gives approval for the development/ project listed that impacts the FEMA-designated floodplain and/or floodway of Doddridge County, WV, pursuant to the rules and regulations established by all applicable Federal, State and local laws and ordinances, including the Doddridge County Floodplain Ordinance. This permit must be posted at the site of work as to be clearly visible, and must remain posted during entirety of development.

Permit: #17-492

Date Approved: December 18, 2017 Expires: December 18, 2018

Issued to: Antero Midstream, LLC POC: Rachel McKinney

Company Address: 535 White Oaks Blvd. Bridgeport, WV 26330


**Project Address: Sherwood to Smithburg** 

Firm: 54017C0140C Lat/Long: 39.268408N, -80.734558W

Purpose of Development: Sherwood to Smithburg Pipeline Extension


Issued by: George C. Eidel, CFM, OEM Director/Doddridge County FPM (or designee)

Date: December 18, 2017



22	U.S. Postal Service <sup>™</sup> CERTIFIED MAIL <sup>®</sup> REC Domestic Mail Only	EIPT
75	For delivery information, visit our website	at www.usps.com*. USE
0660 0000 2275	Certified Mail Fee \$  Extra Services & Fees (check box, add (s) as appropriate)   Return Receipt (hardcopy)	Postmark OCT 196 2017
7017	Sinet To Ronald L. Law Sinet and Apit No., or PO Box No. City, State, ZIP+48 PS Form 3800, April 2015 PSN 7530-02-000-9047	

	U.S. Postal Service <sup>™</sup> CERTIFIED MAIL <sup>®</sup> REC	:FIPT
721.5	Domestic Mail Only	
7	For delivery information, visit our website	e at www.usps.com .
7	OFFICIAL	. USE
227	Certified Mail Fee 3.35	UNION
9000	Extra Services & Fees (check box, add fee as appropriate)   Return Receipt (hardcopy) \$   Return Receipt (electronic) \$   Certified Mail Restricted Delivery \$   Adult Signature Required \$	OCI Postmant )
0660 (	Adult Signature Restricted Delivery \$	USO5 264569
	Total Postage and Fees	\$.
7017	Spail To Columbia Gas Transm Street and Apt. No., or PO Box No. 1700 MacCorkle Ave.	
, -	City, State, 219-49  Char Leston, LV 25314 PS Form 3800, April 2015 PSN 7530 02-000-9047	See Reverse for Instructions
	U.S. Postal Service <sup>™</sup>	



#### COMPLETE THIS SECTION ON DELIVERY SENDER: COMPLETE THIS SECTION A. Signature Complete items 1, 2, and 3, ☐ Agent Print your name and address on the reverse □ Addressee so that we can return the card to you. B. Received by (Printed Name) O. Date of Delivery Attach this card to the back of the mailpiece. or on the front if space permits. Article Addressed to: □.Yes D. Is delivery address different from item 1? If YES, enter delivery address below: ☐ No olumbia Gas Transmission, LLC 1700 MacCorkle Avenue SE OCT 3 0 201 Charleston, WV 25314 Service Type ☐ Priority Mail Express® ☐ Adult Signature ☐ Registered Mail™ ☐ Adult Signature Restricted Delivery ☐ Registered Mail Restricted □ Certified Mail® Delivery Return Receipt for □ Certified Mail Restricted Delivery 9590 9402 2859 7069 5380 93 Merchandise □ Collect on Delivery □ Signature Confirmation™ ☐ Collect on Delivery Restricted Delivery 2. Article Number (Transfer from service label) ☐ Signature Confirmation ☐ Insured Mail Restricted Delivery ☐ Insured Mail Restricted Delivery (over \$500) PS Form 3811, July 2015 PSN 7530-02-000-9053 Domestic Return Receipt





United States Postal Service • Sender: Please print your name, address, and ZIP+4® in this box®

### Doddridge County OEM/CFM George Eidel

250 NEE 1 616C2211/03/17
FORWARD TIME EXP RTN TO SEND
DODDRIDGE CO PUBLIC LIBRARY
170 MARIE ST
WEST UNION WY 76456-1132

FWD

RETURN TO SENDER


4	1
SENDER: COMPLETE THIS SECTION	COMPLETE THIS SECTION ON DELIVERY
<ul> <li>Complete items 1, 2, and 3.</li> <li>Print your name and address on the reverse so that we can return the card to you.</li> <li>Attach this card to the back of the mailpiece, or on the front if space permits.</li> <li>Article Addressed to:</li> </ul>	A. Signature  X. S. S. L. T. J. B. F. J. L. Agent  B. Received by (Printed Name)  C. Date of Delivery  C. Date of Delivery  C. Date of Delivery  J. L. L. L. L. L. J.
Elwood P. & Elizabeth Rill 4619 Glenville Road Glen Rock PA 17327	
9590 9402 2859 7069 5381 09  2. Article Number ( <i>Transfer from service label</i> )	3. Service Type  □ Adult Signature □ Adult Signature Restricted Delivery □ Certified Mail® □ Collect on Delivery □ Collect on Delivery Restricted Delivery □ Insured Mail □ Insured Mail Restricted Delivery (over \$500) □ Priority Mail Express® □ Registered Mail™ □ Registered Mail Restricted Delivery □ Delivery Herturn Receipt for Merchandise □ Signature Confirmation™ □ Signature Confirmation Restricted Delivery
PS Form 3811, July 2015 PSN 7530-02-000-9053	Domestic Return Receipt

USPS TRACKING#

<u>9590 9402 2859 7069 5381 09</u>

Permit No. G-10

United States Postal Service



գՈւլինինինիների բնակնգիկին այդ արև այդ այդ

#### SENDER: COMPLETE THIS SECTION Complete items 1, 2, and 3. Print your name and address on the reverse

- so that we can return the card to you. Attach this card to the back of the mailpiece,
- or on the front if space permits. 1. Article Addressed to:

Ronald L. Law 472 Tent Church Road

# Colliers, WV 26 035

9590 9402 2859 7069 5380 86 2. Article Number (Transfer from service label)

#### COMPLETE THIS SECTION ON DELIVERY A. Sibnature

Received by (Printed Name)

C. Date of Delivery

☐ Yes

☐ Agent

□ Addressee

D. Is delivery address different from item 1? If YES, enter delivery address below:

3. Service Type

☐ Adult Signature

Certified Mail® 25

☐ Collect on Delivery

☐ Insured Mail

☐ Priority Mail Express®

□ No

□ Registered Mail™ ☐ Adult Signature Restricted Delivery □ Registered Mail Restricted Delivery ☐ Certified Mall Restricted Delivery

☐ Return Receipt for Merchandise ☐ Signature Confirmation™ □ Signature Confirmation

PS Form 3811, July 2015 PSN 7530-02-000-9053

☐ Insured Mail Restricted Delivery (over \$500)

☐ Collect on Delivery Restricted Delivery.

Restricted Delivery





Sender: Please print your name, address, and ZIP+4® in this box

First-Class Mail Postage & Fees Paid USPS Permit No. G-10

United States Postal Service

Doddridge County OEM/CFM
George Eidel
105 Court Street, Suite 3
West Union, WV 26456

իլինակիրակիութիրագեներակութիրակիրակիրակի



ANTERO MIDSTREAM LLC 1615 WYNKOOP STREET **DENVER, COLORADO 80202** 

Vendor Name	Vendor No.	Date	Check Number	Check Total
DODDRIDGE COUNTY COMMISSION	43312	Oct-18-2017	108384	\$1,750.00

INV DATE DESCRIPTION AMOUNT DISCOUNTS NET AMOUNT SR10182017-1 10/18/17 FLOODPLAIN PERMIT SHERWOOD TO SMITH 1,750.00 0.00 1,750.00

FP#17-492

COPY

COPY

COPY

PM

1,750.00

0.00

1,750.00

**DETACH AND RETAIN FOR TAX PURPOSES** 

Midstream Partners up

ANTERO MIDSTREAM LLC 1615 WYNKOOP STREET DENVER, COLORADO 80202

Wells Fargo

Check No. 108384

800 - AP ACCT WELLS FARGO

EXACTIVE 1.750dols00cts

One Thousand Seven Hundred Fifty Dollars and Zero Cents

Void After 90 Days

CHECK NUMBER DATE PAY EXACTLY 108384 Oct-18-2017 \$1,750.00

TO THE ORDER

DODDRIDGE COUNTY COMMISSION 118 E COURT ST STE 1~ WEST UNION, WV 26456



# 108384# #O41203824#

9657481710#



Vendor Name	, Vendor No.	Date	Check Number	Check Total
DODDRIDGE COUNTY COMMISSION	43312	Oct-18-2017	108384	\$1,750.00

INV #	INV DATE	DESCRIPTION	•	AMOUNT	DISCOUNTS	NET AMOUNT
SR10182017-1	10/18/17	FLOODPLAIN PERMIT	SHERWOOD TO SMITH	1,750.00	0.00	1,750.00

FP#17-492

## Doddridge County, West Virginia

O: 9897			DATE: 2017/10/30				
FROM	: ANTERO	MIDSTREAM	<u></u>	– AMC	OUNT: \$	1,7	50.00
JSAND :	SEVEN HUI	NDRED FIFTY	DOLLARS	AND 00	CENTS		
FOR	: #17-492	2 FLOODPLAI	N PERMIT	SHERWO	OD TO SM	ITH	
08384	FP-BUILI	DING PERMIT	S		020-318	TOTAL:	\$1,750.00
		URER		·	-	MEC CLERK	
	FOR  08384	FROM: ANTERO USAND SEVEN HUI FOR: #17-492 08384 FP-BUILI	FROM: ANTERO MIDSTREAM USAND SEVEN HUNDRED FIFTY FOR: #17-492 FLOODPLAIN 08384 FP-BUILDING PERMIT	FROM: ANTERO MIDSTREAM  USAND SEVEN HUNDRED FIFTY DOLLARS  FOR: #17-492 FLOODPLAIN PERMIT  D8384 FP-BUILDING PERMITS  ICHAEL HEADLEY	FROM: ANTERO MIDSTREAM AMO USAND SEVEN HUNDRED FIFTY DOLLARS AND 00  FOR: #17-492 FLOODPLAIN PERMIT SHERWOO 08384 FP-BUILDING PERMITS  ICHAEL HEADLEY	FROM: ANTERO MIDSTREAM  AMOUNT: \$  USAND SEVEN HUNDRED FIFTY DOLLARS AND 00 CENTS  FOR: #17-492 FLOODPLAIN PERMIT SHERWOOD TO SM  D8384 FP-BUILDING PERMITS  020-318	FROM: ANTERO MIDSTREAM AMOUNT: \$ 1,7  USAND SEVEN HUNDRED FIFTY DOLLARS AND 00 CENTS  FOR: #17-492 FLOODPLAIN PERMIT SHERWOOD TO SMITH  D8384 FP-BUILDING PERMITS  020-318 TOTAL:  CCHAEL HEADLEY  MEC

**Customer Copy** 

TOTAL INVOICES PAID ====>

1,750.00

0.00

1,750.00

DETACH AND RETAIN FOR TAX PURPOSES

#### FLOODPLAIN PERMIT #17-492

#### Antero Midstream/ Sherwood to Smithburg Pipeline Extension

TASK	COMPLETE (DATE)	NOTES
CHECK RECEIVED	10/26/17	
US ARMY CORP. ENGINEERS (USACE)	11/6/17	
US FISH & WILDLIFE SERVICES (USFWS)	11/6/17	
WV DEPT. NATURAL RESOURCES (WVDNR)	11/6/17	
WV DEPT. ENVIROMENTAL PROTECTION (WVDEP)		
STATE HISTORIC & PRESERVATION OFFICE (SHPO)	11/6/17	
OFFICE of LAND & STREAM (OLS)	11/6/17	
DATE OF COMMISSION READING	11/7/2017	
DATE AVAILABLE TO BE GRANTED	11/27/2017	
PERMIT GRANTED		
COMPLETE		

7017 0660 0000 2275 7208

3073 OPPO 0000 5512 J572

7017 0660 0000 2275 7222

7017 0660 0000 2275 7239



#### **Doddridge County Floodplain Permits**

(Week of November 6, 2017)

Please take notice that on the 26<sup>th</sup> day of October, 2017, Antero Midstream, LLC. filed an application for a Floodplain Permit (#17-492) to develop land located at or about 2991 Route 18 S. Coordinates 39.268408 N, -80.734558 W. The Application is on file with the Clerk of the County Court and may be inspected or copied during regular business hours. Any interested persons who desire to comment shall present the same in writing by November 27, 2017 (20 calendar days after the announcement at the regularly scheduled Doddridge County Commission Meeting) delivered to the Clerk of the County Court at 108 Court Street Ste. 1, West Union, WV 26456. This project is the Sherwood to Smithburg Pipeline Extension.



October 20, 2017

**Doddridge County Commission** Attn: George Eidel, Doddridge County Floodplain Manager 118 East Court Street, Room 102 West Union, WV 26456

Mr. Eidel:

Antero Midstream LLC would like to submit a Doddridge County Floodplain permit application for our Sherwood to Smithburg Extension Pipeline project. Our project is located in Doddridge County beginning at coordinates 39.275897N, 80.716342W, and continues to coordinates 39.268622N, 80.731367W. Per the FIRM Map #54017C0140C, this location is in the floodplain.

Attached you will find the following:

- ➤ Doddridge County Floodplain Permit Application
- ➤ No-Rise Certificate
- > WV Flood Tool Map
- FIRM Maps
- Design Plans

If you have any questions please feel free to contact me at (304) 842-4008.

Thank you in advance for your consideration.

Sincerely,

Roch Muy Rachel McKinney

Environmental Specialist II Antero Resources Corporation

**Enclosures** 



Permit# 1/ 7/ 0

Sherwood to
Project Name: Smithburg Pipelink
Extension

Permittees Name: MTCO

### Doddridge County, WV

# Floodplain Development Permit Application

This document is to be used for projects that impact/potentially impact the FEMA—designated floodplain and/or floodway of Doddridge County, WV pursuant to the rules and regulations established by all applicable Federal, State and local laws and ordinances, including the Doddridge County Floodplain Ordinance.

#### SECTION 1: GENERAL PROVISIONS (APPLICANT TO READ AND SIGN)

- 1. No work may start until a permit is issued.
- 2. The permit may be revoked if any false statements are made herein.
- 3. If revoked, all work must cease until permit is re-issued.
- 4. Development shall not be used or occupied until a Certificate of Compliance is Issued.
- 5. The permit will expire if no work is commenced within six months of issuance.
- 6. Applicant is hereby informed that other permits may be required to fulfill local, state, and federal requirements.
- 7. Applicant hereby gives consent to the Floodplain Administrator/Manager or his/her representative to make inspections to verify compliance.
- 8. I THE APPLICANT CERTIFY THAT ALL STATEMENTS HEREIN AND IN ATTACHMENTS TO THIS APPLICATION ARE, TO THE BEST OF MY KNOWLEDGE, TRUE AND ACCURATE.

APPLICANT'S SIGNATURE_	Brian Duarmoras	
DATE	10-25-17	

### Applicant Information:

Please provide all pertinent data.

Applicant Information								
Responsible Company Name: Antero Midstream LLC								
Corporate Mailing Address: 1615 Wynkoop Street								
City: Denver	State: CO	Zip: 80202						
Corporate Point of Contact (POC):	•							
Corporate POC Title:								
Corporate POC Primary Phone:								
Corporate POC Primary Email:								
Corporate FEIN:	Corporate DUN	IS:						
Corporate Website: www.anteroresources.com	'n							
Local Mailing Address: 535 White Oaks Blvd								
City: Bridgeport	State: WV	Zip: 26330						
Local Project Manager (PM):								
Local PM Primary Phone:								
Local PM Secondary Phone:								
Local PM Primary Email:								
Person Filing Application: Rachel McKinney								
Applicant Title: Environmental Specialist II								
Applicant Primary Phone: (304) 842-4008								
Applicant Secondary Phone: (304) 641-2396								
Applicant Primary Email: rmckinney@anteror	esources.com							

#### **Project Narrative:**

Describe in detail the proposed development including project name/title, type of development, estimated start and completion timeline, and its potential impact on the floodplain. Use additional copies of this page as needed.

Project Narrative:
The Sherwood to Smithburg Extension Pipeline project is located south of U.S. Route 50
near Smithburg. A portion of the proposed project is located within the Meathouse Fork
Zone AE Flood Hazard area, according to the Flood Insurance Rate Map (FIRM) for Doddridge
County, map panel 54017C0140C with a revised date of October 4, 2011. The proposed work that
will take place in the floodplain includes the installation of permanent water bars and the
installation of the pipeline by HDD bore method. The material needed to construct the permanent
water bars will be excavated from the up-gradient side of the berm. Therefore, a net loss of
floodplain storage is not expected. One HDD bore pit will be located in the floodplain; however,
this impact will be temporary and the ground will be restored upon completion of the bore.
All other disturbed areas will be returned to existing conditions at the conclusion of the work.
As a result, the project will not result in a decrease of the available floodplain storage area and
will not adversely affect the existing base flood elevation of Meathouse Fork.

#### **Proposed Development:**

Please check all elements of the proposed project that apply.

#### **DESCRIPTION OF WORK (CHECK ALL APPLICABLE BOXES)**

#### A. STRUCTURAL DEVELOPMENT

<u>ACTIVITY</u>						STRUCTURAL TYPE		
[]	New Structure				[]	Residential (1 – 4 Family)		
[]	Addition []				[]	Residential (more than 4 Family)		
[]	Alteration				[]	Non-reside	ntial (floodproofing)	
[]	Relocation				[]	Combined (	Jse (res. & com.)	
[]	Demolition	1			[]	Replaceme	nt	
[]	Manufact	ured/Mo	bil Home					
В.	OTHER DE	VELOPI	MENT ACTI	VITIES:				
[]	Fill	[]	Mining	[]	Drillin	g [X]	Pipelining	
[]	Grading							
[]	Excavation	(except	for STRUCTUR	RAL DEVE	LOPMEN	T checked ab	ove)	
[]	Watercour	se Altera	ation (including	g dredgii	ng and ch	annel modifi	cation)	
[]	Drainage I	mproven	nents (includir	ng culver	t work)			
[]	Road, Stre	et, or Bri	dge Construct	ion				
[]	Subdivisio	n (includi	ng new expan	ision)				
[]	Individual	Water or	Sewer Systen	n				
[]	Other (ple	ase speci	fy)					
							<del></del>	

#### **Development Site/Property Information:**

Property Designation:1	of <u>6</u>					
Site/Property Information	:		, , , ,			
Legal Description: MEATH		5.5 AC	***************************************		•	
Physical Address/911 Add	ress: STATE	ROUTE 1	18	-		
Decimal Latitude/Longitud	ie: 39.26840	08, -80.7	34558			
DMS Latitude/Longitude:	39°16′06.27″	'N, 80°44	'04.41"W			
District: 06	Мар:	1		Parcel:	6	
Land Book Description:						
Deed Book Reference: Dee	ed Book 372,	Page 12	1			
Tax Map Reference: 09 06	0001 0006 0	000 000	0			
Existing Buildings/Use of Pr	operty: Hous	e, Outbui	lding, Wooded			
Floodulain Location Data:	Floodplain Location Data: (to be completed by Floodplain Manager or designee)					
Community:	Number:	round any tra	Panel:	<del></del>	Suffix:	
Location (Lat/Long):	L		Approximate I	Elevation	:	
Estimated BFE:						
Is the development in the f	Is the development in the floodway?  Is the development in the floodway?					
$\square_{\mathrm{Yes}}  \square_{\mathrm{No}}$			$\square_{Yes}$	$\square_{No}$	Zone:	
Notes:						
		<del>****</del>				
					4	

#### **Development Site/Property Information:**

Property Designation: 2 of 6							
Site/Property Information:							
Legal Description: MEATHOUSE 57.7 AC							
Physical Address/911 Add	ress: OFF RT	18-SNO	WBIRD RD				
Decimal Latitude/Longitud	le: 39.27256	9, -80.73	32536				
DMS Latitude/Longitude:	39°16′21.25″i	N, 80°43	'57.13"W	,			
District: 06	Мар:	1		Parcel:	2		
Land Book Description:							
Deed Book Reference: De	ed Book 163,	Page 68	7				
Tax Map Reference: 09 06	0001 0002 0	000 000	0				
Existing Buildings/Use of Pr	operty: House	e, Out Bu	ildings, Wooded				
Floodplain Location Data:	1	ted by Fl	oodplain Manag	er or des	ignee)		
Community:	Number:		Panel:		Suffix:		
Location (Lat/Long): Approximate Elevation:							
Estimated BFE:  Is the development in the floodway?  Is the development in the floodplain?							
	ioouway:		i —	_	me noouplam:		
U <sub>Yes</sub> U <sub>No</sub>			Yes	U <sub>No</sub>	Zone:		
Notes:							

#### **Development Site/Property Information:**

Property Designation:3	<u>6</u> of <u>6</u>			
Site/Property Information	:			<del>,</del>
Legal Description: MEATH	· · · · · · · · · · · · · · · · · · ·	95.12 AC		
Physical Address/911 Add	ress: OFF RT 18-	SNOWBIRD RD		
Decimal Latitude/Longitue	le: 39.274194, -8	0.724228	•	
DMS Latitude/Longitude:	39°16′27.10″N, 80	°43′27.22″W		
District: 06	Мар: 1		Parcel:	3
Land Book Description:				
Deed Book Reference: De	ed Book 0165, Pag	ge 0010		
Tax Map Reference: 09 06	0001 0003 0000	0000		
Existing Buildings/Use of Pr	operty: Wooded		·	
Floodplain Location Data:	(to be completed b	v Floodplain Manac	aer or des	rianee)
Community:	Number:	Panel:		Suffix:
Location (Lat/Long):		Approximate	Elevation	l:
		Estimated BFI	E:	
Is the development in the	floodway?			the floodplain?
$\square_{\mathrm{Yes}}  \square_{\mathrm{No}}$		□ <sub>Yes</sub>	$\Box_{No}$	Zone:
Notes:				

#### **Development Site/Property Information:**

	on: 4_ of 6_		
Property Designati	<u> </u>		
Site/Property Infor	mation:		
	MEATHOUSE 43 AC		
Physical Address/9	)11 Address: OFF RT 18	-SNOWBIRD RD	
Decimal Latitude/L	ongitude: 39.274683,	-80.719739	
DMS Latitude/Long	ritude: 39°16′28.86″N, 8	80°43′11.06″W	
District: 06	Мар: 1		Parcel: 4
Land Book Descrip	tion:		alama anagana aya
Deed Book Referen	ce: Deed Book 0165, Pa	age 0010	
Tax Map Reference	: 09 06 0001 0004 0000	0 0000	
Tax Map Reference	: 09 06 0001 0004 0000	0 0000	
	: 09 06 0001 0004 0000 Jse of Property: Wooded		
Existing Buildings/U	Jse of Property: Wooded		aer or designee)
Existing Buildings/U			ger or designee) Suffix:
Existing Buildings/U Floodplain Location Community:	Jse of Property: Wooded  n Data: <i>(to be completed</i> Number:	by Floodplain Mana, Panel:	Suffix:
Existing Buildings/U	Jse of Property: Wooded  n Data: <i>(to be completed</i> Number:	by Floodplain Mana	Suffix:
Existing Buildings/U Floodplain Location Community: Location (Lat/Long	Jse of Property: Wooded  n Data: <i>(to be completed</i> Number:	Panel: Approximate Estimated BF	Suffix: Elevation:
Existing Buildings/U Floodplain Location Community:	Jse of Property: Wooded  n Data: <i>(to be completed</i> Number:	Panel: Approximate Estimated BF	Suffix: Elevation:
Existing Buildings/U Floodplain Location Community: Location (Lat/Long	Jse of Property: Wooded  n Data: <i>(to be completed</i> Number:	Panel: Approximate Estimated BF	Suffix: Elevation:

#### **Development Site/Property Information:**

Property Designation:5	of <u>6</u>					
		<del></del>		,		
Site/Property Information		· · · · · · · · · · · · · · · · · · ·		· · · · · · · · · · · · · · · · · · ·		
Legal Description: M I CRE	EK 148 AC					
Physical Address/911 Add	ress: ROUTE 16					
Decimal Latitude/Longitud	le: 39.277306,	-80.723269				
DMS Latitude/Longitude:	39°16′38.30″N 8	0°43′23.77″W				
District: 08	Map: 16		Parcel:	15.2		
Land Book Description:						
Deed Book Reference: DE	ED BOOK 310, P.	AGE 243				
Tax Map Reference: 09 08	0016 0015 0002	2 0000				
Existing Buildings/Use of Pr	operty: WOODEI					
	2	If mi I I i ag		·		
Floodplain Location Data:	<del></del>		ger or aes			
Community:	Number:	Panel:		Suffix:		
Location (Lat/Long):	Location (Lat/Long): Approximate Elevation:					
		Estimated BFI	E:			
Is the development in the	loodway?	Is the develop	ment in t	the floodplain?		
$\square_{\mathrm{Yes}}  \square_{\mathrm{No}}$	-	$\Box_{Yes}$	$\square_{No}$	Zone:		
Notes:						
			······································			

#### **Development Site/Property Information:**

Site/Property Informa	ation:		
Legal Description: DC	OUGLAS CAMP 107 AC		
	-		
Physical Address/911	Address: OFF RT 18	3/5 DOUGLAS RUN	
Decimal Latitude/Lon	ngitude: 39.275894, -	80.716344	
DMS Latitude/Longitu	ıde: 39°16'33.22"N,	80°42′58.84″W	
District: 06	Map: 2	Pare	cel: 1
Land Book Descriptio	n:		
Deed Book Reference	· DEED BOOK 214 PA	GE 644	
	. DEED BOOK ETTIT		
Deca Book Reservice	. DEED BOOK 21117		
Tax Map Reference: 0			
	09 06 0002 0001 0000	0 0000	
Tax Map Reference: 0	09 06 0002 0001 0000	0 0000	
Tax Map Reference: 0  Existing Buildings/Use	09 06 0002 0001 0000 of Property: Wooded	0 0000	decigned
Tax Map Reference: O  Existing Buildings/Use  Floodplain Location E	of Property: Wooded  Oata: (to be completed	0 0000 by Floodplain Manager or	
Tax Map Reference: 0  Existing Buildings/Use	09 06 0002 0001 0000 of Property: Wooded	0 0000	designee) Suffix:
Tax Map Reference: O  Existing Buildings/Use  Floodplain Location E	of Property: Wooded  Oata: (to be completed	0 0000 by Floodplain Manager or	Suffix:
Tax Map Reference: O Existing Buildings/Use Floodplain Location D Community:	of Property: Wooded  Oata: (to be completed	by Floodplain Manager or	Suffix:
Tax Map Reference: O Existing Buildings/Use Floodplain Location D Community:	of Property: Wooded  Oata: (to be completed  Number:	by Floodplain Manager or Panel: Approximate Eleva	Suffix: tion:
Tax Map Reference: C  Existing Buildings/Use  Floodplain Location E  Community:  Location (Lat/Long):	of Property: Wooded  Oata: (to be completed  Number:	by Floodplain Manager or Panel: Approximate Elevate Estimated BFE:	Suffix: tion: in the floodplain?
Tax Map Reference: O  Existing Buildings/Use  Floodplain Location D  Community:  Location (Lat/Long):	of Property: Wooded  Oata: (to be completed  Number:	by Floodplain Manager or Panel: Approximate Elevate Estimated BFE: Is the development	Suffix: tion: in the floodplain?

#### **Property Owner Data:**

Property Owner Data:		
Name of Primary Owner (PO): COI	LUMBIA GAS TRANSMISSIO	N, LLC
PO Address: 1700 MACCORKLE AV	/E SE	
City: CHARLESTON	State: WV	Zip: 25314
PO Primary Phone:		
PO Secondary Phone:		
PO Primary Email:		
Surface Rights Owner Data:		
Name of Primary Owner (PO):		
PO Address:		
City:	State:	Zip:
PO Primary Phone:	<u> </u>	
PO Secondary Phone:		
PO Primary Email:		
Mineral Rights Owner Data: (As Ap	plicable)	·
Name of Primary Owner (PO):		
PO Address:		
City:	State:	Zip:
PO Primary Phone:		
PO Secondary Phone:		
PO Primary Email:		

#### **Property Owner Data:**

Property Designation: 2 of 6			
Property Owner Data:			
Name of Primary Owner (PO): DODD	RIDGE CO COURT		
PO Address: 108 COURT ST #4			
City: WEST UNION	State: WV	Zip: 26456	
PO Primary Phone:			
PO Secondary Phone:			
PO Primary Email:			
Surface Rights Owner Data:		2	
Name of Primary Owner (PO):			
PO Address:			
City:	State:	Zip:	
PO Primary Phone:			
PO Secondary Phone:			
PO Primary Email:			
Mineral Rights Owner Data: (As Appli	icable)		
Name of Primary Owner (PO):			
PO Address:			
City:	State:	Zip:	
PO Primary Phone:			
PO Secondary Phone:			
PO Primary Email:			

#### **Property Owner Data:**

Property Owner Data:		
Name of Primary Owner (PO): RILL,	ELWOOD P. & ELIZABET	Н
PO Address: 4619 GLENVILLE RD		
City: GLEN ROCK	State: PA	Zip: 17327
PO Primary Phone:		
PO Secondary Phone:		
PO Primary Email:		
Surface Rights Owner Data:		
Name of Primary Owner (PO):		
PO Address:		
City:	State:	Zip:
PO Primary Phone:	<del>.</del>	<u>L</u>
PO Secondary Phone:		
PO Primary Email:		
	· · · · · · · · · · · · · · · · · · ·	
Mineral Rights Owner Data: (As Appl	icable)	
Name of Primary Owner (PO):		
PO Address:		
City:	State:	Zip:
PO Primary Phone:	I	
PO Secondary Phone:		

#### **Property Owner Data:**

Property Designation: _5_ of 6		
Property Owner Data:		
Name of Primary Owner (PO): MA		REAM & RESOURCES, LLC
PO Address: 1515 ARAPAHOE ST	TOWER 1 STE 1	
City: DENVER	State: CO	Zip: 80202
PO Primary Phone:	<u> </u>	
PO Secondary Phone:		
PO Primary Email:		
Surface Rights Owner Data:	1	
Name of Primary Owner (PO):		
PO Address:		
City:	State:	Zip:
PO Primary Phone:		t.
PO Secondary Phone:		
PO Primary Email:		
Mineral Rights Owner Data: (As A	pplicable)	
Name of Primary Owner (PO):		
PO Address:		
City:	State:	Zip:
PO Primary Phone:	l	
PO Secondary Phone:		
PO Primary Email:		

#### **Property Owner Data:**

Property Owner Data:		
Name of Primary Owner (PO): LA	W, RONALD L	
PO Address: 472 TENT CHURCH F	RD	
City: COLLIERS	State: WV	Zip: 26426
PO Primary Phone:		, , , , , , , , , , , , , , , , , , ,
PO Secondary Phone:		
PO Primary Email:		
Surface Rights Owner Data:	AMMYS THE	
Name of Primary Owner (PO):		
PO Address:		
City:	State:	Zip:
PO Primary Phone:		· · · · · · · · · · · · · · · · · · ·
PO Secondary Phone:		
PO Primary Email:		
Mineral Rights Owner Data: (As A	pplicable)	
Name of Primary Owner (PO):		
PO Address:		
City:	State:	Zip:
PO Primary Phone:		
PO Secondary Phone:		
PO Primary Email:		

#### **Contractor Data:**

Property Designation: \_

of\_\_

Please provide all pertinent data for contractors and sub---contractors that may be participating in this project. Use additional copies of this page as needed. Designate each page in relation to each property listed above.

Contractor/Sub-Contractor (C/SC) Inform	ation:	
C/SC Company Name:		
C/SC WV License Number:		
C/SC FEIN:	C/SC DUN	S:
Local C/SC Point of Contact (POC):		
Local C/SC POC Title:		
C/SC Mailing Address:	The right of	
City:	State:	Zip-Code:
Local C/SC Office Phone:		
Local C/SC POC Phone:		
Local C/SC POC E-Mail:	· · ·	1.11.12.1.12
Engineer Firm Information:		
Engineer Firm Name:		
Engineer WV License Number:		
Engineer Firm FEIN:	Engineer	Firm DUNS:
Engineer Firm Primary Point of Contact (	POC):	
Engineer Firm Primary POC Title:		
Engineer Firm Mailing Address:		
City:	State:	Zip-Code:
Engineer Firm Office Phone:		
Engineer Firm Primary POC Phone:		
Engineer Firm Primary POC E-Mail:		

#### Adjacent and/or Affected Landowners Data

Please provide data for all adjacent and/or affected surface owners (both up and down stream) whose property may be impacted by proposed development as demonstrated by a floodplain study or survey. Use additional copies of this page as needed.

Adjacent Property Owner Data: Upstream				
Name of Primary Owner (PO): SUTTON, JERE	MY W & AMANDA	A L		
Physical Address: PO BOX 57				
City: SMITHBURG	State: WV	Zip: 26436		
PO Primary Phone:		-		
PO Secondary Phone:				
PO Primary Email:				
Adjacent Property Owner Data: Upstream				
Name of Primary Owner (PO):				
Physical Address:				
City:	State:	Zip:		
PO Primary Phone:				
PO Secondary Phone:				
PO Primary Email:				
Adjacent Property Owner Data: Downstream				
Name of Primary Owner (PO): BOWYER, DAVID E				
Physical Address: 12088 MIDDLE ISLAND RD				
City: ALMA	State: WV	Zip: 26320		
PO Primary Phone:				
PO Secondary Phone:				
PO Primary Email:				
Adjacent Property Owner Data: Downstream				
Name of Primary Owner (PO): HAMILTON, WI	LLIAM M AND			
Physical Address: 1648 SNOWBIRD RD				
City: WEST UNION	State: WV	Zip: 26456		
PO Primary Phone:				
PO Secondary Phone:				
PO Primary Email:				

#### Site Plan

A Site Plan is an accurate and detailed map of the proposed development for this project. It shows the size, shape, location and special features of the project property, and the size and location of any development planned to the property, especially as that development will impact the floodplain and/or floodway. Site plans show what currently exists on the project property, and any changes or improvements you are proposing to make. A certified and licensed engineering firm should complete site plans.

#### A SITE PLAN MUST CONTAIN THE FOLLOWING INFORMATION:

- 1. Legal description of the parcel, north arrow and scale
- 2. All property lines and their dimensions
- 3. Names of adjacent roads, location of driveways
- 4. Location of sloughs, tributaries, streams, rivers, wetlands, ponds, and lakes, with setbacks indicated, and including FEMA floodplain data based on most updated FIRM.
- 5. Location, size, shape of all buildings, existing and proposed, with elevation of lowest floor indicated.
- 6. Location and dimensions of existing or proposed on-site sewage systems.
- 7. Location of all propane tanks, fuel tanks or other liquid storage tanks whether above ground or below ground level.
- 8. Location and dimensions of any proposed pipeline placement(s) into floodplain/floodway.
- 9. Location and dimensions of any roadway development into floodplain/floodway. (Includes initial development access roads)
- 10. Location and dimensions of any bridge and/or culvert development into floodplain/floodway.
- 11. Location and dimensions of any storage yard or facility into the floodplain/floodway.
- 12. Location of any existing utilities and/or proposed utility placement and/or displacement.
- 13. Location, dimensions and depth of any existing or proposed fill on site.
- 14. A survey showing the **existing ground elevations** of at least location on the building site. **ELEVATION NOTE**: All vertical datum will reference either NGVD 29 or NAVD 88. Assumed datum will not be acceptable unless the property is located in an area where vertical datum has not been published. For those areas where vertical datum has not been established, a site plan with contours, elevations using assumed datum, high water marks and existing water levels of sloughs, rivers, lakes or streams and proposed lowest floor elevation.

#### **Applicant**

Please read print name, sign and date below:

- I certify that I am authorized to submit this application for the primary project developer.
- I certify that the Information included in this application is to the best of my knowledge true and complete.
- I certify that all required Federal, State, and local permits required by law and/or ordinance for
  the above described development of this project have been properly attained, are current and
  valid, and must be presented with this application before a Doddridge County Floodplain Permit
  may be issued.
- I understand that if in the course of the development project additional permits become
  required that were not needed during the initial proposal, the primary developer must notify the
  Doddridge County Floodplain Manager within 48 hours of such need, and that a "Stop Work"
  order may be issued for all project work directly impacting the floodplain or floodway, until such
  time the required additional permits are acquired.
- I understand that once the floodplain permit is submitted, the application will be entered into
  official public record at the next regularly scheduled Doddridge County Commission meeting
  after the date of submittal.
- I understand that from the date of submittal of the fully completed permit application, the
  Doddridge County Floodplain Manager has ninety (90) days to make a determination to either
  grant or deny said permit application. During this approval period, the Doddridge County
  Floodplain Manager may, at his or her discretion, conduct a review and/or additional study of
  provided documentation by means of an independent engineering firm. All costs associated with
  said review and/or study must be reimbursed to the County before issuance of approved permit.
- I understand that during the approval period, the Doddridge County Floodplain Manager of
  designee may at his or her discretion conduct site visits and document conditions of proposed
  development pursuant to the permit application.
- I understand that once the Floodplain Permit is granted, the permit will be entered into official public record at the next scheduled Doddridge County Commission meeting after the date of issuance. Appeals to the permit may be made no later than twenty (20) days after said issuance. If a valid appeal is submitted, as determined by the Doddridge County Floodplain Manager, a "Stop Work" order will be issued for all project development directly involving the floodplain or floodway. A public hearing by the Doddridge County Appeals Board will be scheduled no less than ten (10) days after the next regularly scheduled Doddridge County Commission meeting.
- I understand that all decisions of the Doddridge County Appeals Board shall be final.
- I understand issuance of a Floodplain Permit authorizes me to proceed with construction as proposed. A Certificate of Compliance is required upon substantial completion of the project.
- In signing this application, the primary developer hereby grants the Doddridge County Floodplain
   Manager or designee the right to enter onto the above—described location to inspect the development work proposed, in progress, and/or completed.
- I understand that If I do not follow exactly the site—plan submitted and approved by this permit
  that a "Stop Work" order may be issued by the Wirt County Floodplain Manager and that I must
  stop all construction immediately until discrepancies of actual work vs. proposed work is
  resolved.

Applicant Signature: Bruss	Luarmora	Date: <u>/0-25-</u> /7
Applicant Printed Name: Brian		



October 18, 2017

Doddridge County Commission Attn: George Eidel, Doddridge County Floodplain Manager 118 East Court Street, Room 102 West Union, WV 26456

Subject:

Antero Midstream, LLC.

Sherwood to Smithburg Extension Pipeline (AFE #A05924)

No-Rise Certificate

Doddridge County, West Virginia

CEC Project 174-537

Civil & Environmental Consultants, Inc. (CEC) is pleased to evaluate the potential floodplain impacts for the above referenced project on behalf of Antero Midstream, LLC., 535 White Oaks Blvd, Bridgeport, WV 26330. Antero Midstream, LLC. proposes to install a 30" High Pressure Steel Gas Line. A portion of the proposed project is located within the Meathouse Fork Zone AE Flood Hazard area, according to the Flood Insurance Rate Map (FIRM) for Doddridge County, map panel 54017C0140C with a revised date of October 4, 2011. The proposed work that will take place in the floodplain includes the installation of permanent water bars and the installation of the pipeline by HDD bore method. The material needed to construct the permanent water bars will be excavated from the up-gradient side of the berm. Therefore, a net loss of floodplain storage is not expected. One HDD bore pit will be located in the floodplain; however, this impact will be temporary and the ground will be restored upon completion of the bore. All other disturbed areas will be returned to existing conditions at the conclusion of the work. As a result, the project will not result in a decrease of the available floodplain storage area and will not adversely affect the existing base flood elevation of Meathouse Fork.

This no-rise certificate is provided in support of the floodplain development permit application. Your time and effort in reviewing this floodplain development permit application is appreciated. Please feel free to contact me at 304-933-3119 or via e-mail at <a href="mailto:adarnell@cecinc.com">adarnell@cecinc.com</a> or contact Mrs. Rachel McKinney at 304-842-4008 or via e-mail at <a href="mailto:rmckinney@anteroresources.com">rmckinney@anteroresources.com</a> if you have questions or need additional information.

Respectfully submitted,


CIVIL & ENVIRONMENTAL CONSULTANTS, INC.

Andrew P. Darnell, E.I.

Assistant Project Manager

Joshua N. Diaz P.E. Senior Project Manager

### WV Flood Map



**User Notes:** 

Antero Midstream LLC
AFE# A05924
SHERWOOD TO SMITHBURG EXT
Pipeline



Flood Hazard Zone



#### Flood Point of Interest

#### Disclaimer:

The online map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. To obtain more detailed information in areas where Base Flood Elevations have been determined, users are encouraged to consult the latest Flood Profile data contained in the official flood insurance study. These studies are available online at www.msc.fema.gov. WV Flood Tool (http://www.MapWV.gov/flood) is supported by FEMA, WV NFIP Office, and WV GIS Technical Center.

Map created on October 12, 2017

#### Flood Hazard Area:

Flood Hazard Area: Location is NOT WITHIN identified flood hazard area, but within 75 feet of an

FEMA Issued Flood Map: 54017C0140C

Watershed (HUC8): Little Musringum-Middle Island (5

Elevation: About 874 ft

**Location (long, lat):** (80.731370 W,39.268626 N)


Location (UTM 17N): (523173, 4346621)

Contacts: Doddridge

CRS Information: N/A

Parcel Number: 09-06-0001-0006-0000

### WV Flood Map



**User Notes:** 

Floodway

Flood Hazard Zone

Approximate Study (Zone A)

Detailed Study (AE, AH, AO)

High: 134.442

Low: 6.10352e-005

#### Disclaimer:

The online map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. To obtain more detailed information in areas where Base Flood Elevations have been determined, users are encouraged to consult the latest Flood Profile data contained in the official flood insurance study. These studies are available online at www.msc.fema.gov. WV Flood Tool (http://www.MapWV.gov/flood) is supported by FEMA, WV NFIP Office, and WV GIS Technical Center.

#### Flood Hazard Area:

Flood Hazard Area: Location is WITHIN the FEMA 100-year floodplain.

Flood Hazard Zone: AE

Stream: Meathouse Fork FEMA Issued Flood Map: 54017C0140C

Watershed (HUC8): Little Musringum-Middle Island (5030

Advisory Flood Height: N/A

Water Depth: About 20.0 ft (Source: HAZUS)

Elevation: About 794 ft

**Location (long, lat):** (80.731811 W,39.267948 N)

Location (UTM 17N): (523135, 4346545)


Contacts: Doddridge

Special State

CRS Information: N/A Flood Profile: 54017


Flood Profile: 54017\_016 HEC-RAS Model: N/A

Parcel Number: No Parcel




# **ANTERO MIDSTREAM LLC ISSUED FOR PERMITTING PLANS FOR THE** PROPOSED SMITHBURG TO MXP **30" RESIDUE PIPELINE AFE #A05924** 101-050-6467 **DODDRIDGE COUNTY, WEST VIRGINIA SEPTEMBER 2017**

**AERIAL MAP** 



VICINITY MAP FULL SCALE: 1"=3,000" HALF SCALE: 1"=6,000"

BASE CONTOUR DATA PROVIDED BY THE WEST VIRGINIA OFFICE OF GIS AT TWO FOOT



# PLAN REPRODUCTION WARNING

THESE PLANS ARE INTENDED TO BE PLOTTED ON ANSI D (22" X 34") SHEETS. FOR REDUCTIONS, REFER TO GRAPHIC SCALE.

THESE PLANS HAVE BEEN CREATED FOR FULL COLOR PLOTTING. ANY SET OF THESE PLANS THAT IS NOT PLOTTED IN FULL COLOR SHALL NOT BE CONSIDERED ADEQUATE FOR CONSTRUCTION PURPOSES.

\*\*WARNING\*\*: INFORMATION MAY BE LOST IN COPYING AND/OR GRAY SCALE PLOTTING.

THE INFORMATION CONTAINED HEREIN IS THE SOLE PROPERTY OF THE THRASHER GROUP INC. REPRODUCTION OF THESE DOCUMENTS IN WHOLE OR IN PART, FOR ANY REASON WITHOUT PRIOR WRITTEN PERMISSION, IS STRICTLY PROHIBITED.

COPYRIGHT & 2017 THE THRASHER GROUP INC.

DANIEL E. FERRELL, WV P.E. # 13462

Know what's at stake-

MidstreamPartners LP

PHONE: (303) 357-7310 | FAX: (303) 357-7315 1615 WYNKOOP STREET DENVER, CO 80202

**ENGINEER OF RECORD** 

PHONE: (304) 624-4108 | FAX: (304) 624-7831

600 WHITE OAKS BLVD., P.O. BOX 940

BRIDGEPORT, WV 26330

ISSUED FOR PERMITS

BY: \_\_\_

ISSUED FOR CONSTRUCTION

DATE: BY:

BENCHMARK.

HORIZONTAL - NAD 83 WEST VIRGINIA STATE PLANE, NORTH ZONE, US SURVEY FOOT

VERTICAL - NAVD 88 (GEOID12B), US SURVEY FOOT

THE THRASHER GROUP

ROAD DESIGNATIONS OBTAINED FROM WV-DOH (http://www.transportation.wv.gov)

600 WHITE OAKS BLVD., P.O. BOX 940 BRIDGEPORT, WV 26330

EXISTING INFORMATION SOURCES

SUPPLEMENTAL SPOT ELEVATIONS AND ALIGNMENT PROVIDED BY:

THE FOLLOWING NOTES APPLY TO ALL PROJECT PLAN SHEETS: ALL METER SETTINGS ACROSS PAVED ROADS SHALL BE BORED OR MOLED, UNLESS OPEN CUT HAS BEEN APPROVED BY WIVID HI AND SPECIFICALLY INDICATED ON PLANS

2. NOTIFICATION OF PROPOSED EXCAVATION, DEMOLITION OR ANY OTHER EARTH DISTURBING ACTIVITIES ARE REQUIRED TO BE PLACED TO MISS UTILITY OF WEST VIRGINIA (1-800-245-4848) NOT LESS THAN FORTY EIGHT (48) BUSINESS HOURS BEFORE ANY SUCH WORK IS TO BEGIN.

3. BEDDING SHALL BE PLACED ON ASPHALT SURFACE TO PROTECT THE PAVEMENT WHEN A TRENCHER OR TRACKED VEHICLE IS USED.

4. THE WEST VIRGINIA DIVISION OF HIGHWAYS PUBLICATIONS "STANDARD SPECIFICATIONS ROADS AND BRIDGES" AND "ACCOMMODATIONS OF LITHLITIES ON HIGHWAY RIGHT OF WAY" LATEST EDITION ARE PART OF THE PROJECT SPECIFICATIONS AND WILL BE ADHERED TO BY THE CONTRACTOR

5 ALL DAMAGE TO ROAD SURFACE SHALL BE REPAIRED ACCORDING TO THE WEST VIRGINIA DIVISION OF HIGHWAYS STANDARD SPECIFICATIONS AND DETAILS.

 ALL EXISTING DUMP ROCK OR RIP RAP DITCHES DISTURBED BY THE UTILITY LINECONTRACTOR SHALL BE RESTORED WITH THE SAME SIZE, GRADE AND QUALITY OF ROCK AFTER THE UTILITY LINE HAS BEEN INSTALLED. NEW DUMP ROCK (RIP RAP) IS TO BE PLACED IN ALL LOCATIONS WHERE THE DITCH LINE GRADE IS GREATER THAN 5% AND THERE IS NO EXISTING RIP RAP.

7. TRAFFIC CONTROL SHALL CONFORM TO THE W.V.D.O.H. PUBLICATION "TRAFFIC CONTROL FOR

STREET AND HIGHWAY CONSTRUCTION AND MAINTENANCE" OPERATION LATEST EDITION.

8. ALL BACKFILL MATERIAL AND COMPACTION REQUIREMENT SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS IN THE ACCOMMODATION OF UTILITIES ON HIGHWAY RIGHT OF WAY AND ADJUSTMENT AND RELOCATION OF UTILITY FACILITIES ON HIGHWAY PROJECTS AND SUBJECT TO D.O.H. APPROVAL. EVIDENCE OF PROPER COMPACTION BY TESTING WILL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE TESTING SHALL BE ONE (1) PER DAY OR EVERY 500 LINEAL FEET OR AS DETERMINED BY THE DISTRICT MANAGER (ENGINEER) OR HIS AUTHORIZED REPRESENTATIVE.

9. UTILITY LINES OR OTHER LINES SHALL BE PLACED EITHER AROUND, UNDER OR OVER DRAINAGE CULVERTS AS SHOWN ON PLANS.

10. AGGREGATE SHOULDER STONE IS TO BE PLACED ON THE SHOULDER AT A THICKNESS EQUAL TO 6" OR ITS ORIGINAL THICKNESS WHICHEVER IS GREATER. PAVED SHOULDERS WILL BE PAVED.

11. MAGNETIC MARKING TAPE SHALL BE INSTALLED AT A DEPTH OF 12" TO 18" BELOW THE SURFACE AND DIRECTLY ABOVE ALL LINES OR PIPE.

12. REPAIR TO DRIVEWAYS ON W.V.D.O.H. RIGHT OF WAYS SHALL CONFORM TO THE APPROPRIATE W.V.D.O.H. TYPICAL REPAIR DETAIL.

13. CLEANUP WILL BE ACCOMPLISHED DAILY, RIGHT OF WAYS SHALL CONFORM TO THE APPROPRIATE W.V.D.O.H. REPAIR. ALL CULVERTS AND DRAINAGE DITCHES SHALL BE OPEN AND MAINTAINED DURING CONSTRUCTION. SHOULDERS WILL BE RESTORED AND STABILIZED WITH

STONE DAILY WITH APPROPRIATE STONE AT THE DISCRETION OF W.V.D.O.H.

14. ALL DISTURBED AREAS SHALL BE SEEDED AND MULCHED WITHIN SEVEN DAYS OF COMPLETION OF BACK FILL OPERATION

15. NO EXCESS EXCAVATION MATERIAL SHALL BE WASTED ON W.V.D.O.H. RIGHT OF WAYS WITHOUT THE AGREEMENT OF THE W.V.D.O.H.

16. THE W.V.D.O.H. RESERVES THE RIGHT TO RELOCATE WATERLINES, FIRE HYDRANTS, AND VALVES AS DEEMED NECESSARY

17. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING UTILITY COMPANIES, PRIOR TO CONSTRUCTION TO OBTAIN UTILITY LOCATIONS AND PERFORMING EXPLORATORY WORK TO DETERMINE SUBSURFACE MATERIALS AND STRUCTURES THAT MAY AFFECT ITS WORK.

18. PRIOR TO THE START OF ANY WORK WITHIN STATE HIGHWAY RIGHT-OF-WAY, THE CONTRACTOR SHALL GIVE THE WEST VIRGINIA DEPARTMENT OF TRANSPORTATION 48 HOURS NOTICE.

19. THE CONTRACTOR IS RESPONSIBLE FOR ANY OFFSITE DISPOSAL REQUIRED. DISPOSAL SHALL BE TO AN ACCEPTABLE LEGAL SITE. CONTRACTOR IS RESPONSIBLE FOR EROSION CONTROL AT DISPOSAL SITES.

ALL ELEVATION GRADES AND DISTANCES SHALL BE CHECKED AND VERIFIED BY THE CONTRACTOR AT THE SITE PRIOR TO CONSTRUCTION.

21. ALL CONSTRUCTION SHALL MAINTAIN 5' FROM EDGE OF PAVEMENT OR BOTTOM OF DITCH UNLESS NO OTHER PRACTICAL MEANS OF CONSTRUCTION EXISTS.

22. PERFORM ACCEPTABLE REPAIR OF ANY AND ALL SUB-BASE FAILURES THAT ARE CAUSED BY THE CONTRACTOR'S OPERATION ON A DAILY BASIS.

23. PERFORM TOTAL REPAIR AND/OR REPLACEMENT OF ANY DAMAGED ASPHALT SURFACE AS DETERMINED BY THE W.V.D.O.H REPRESENTATIVE.

24. PRIOR TO ANY CONSTRUCTION, THE CONTRACTOR SHALL MAKE A COMPLETE VIDEO SHOWING THE ROAD SURFACE OF THE ENTIRE PROJECT OF ROADS TO BE UTILIZED IN THE CONSTRUCTION OF THE PROJECT AND PRESENT IT TO UTILITY SUPERVISOR W.V.D.O.H

25. REMOVE DITCH-LINE OBSTACLES AND/OR RECONSTRUCTION OF THE DITCH-LINE. 26. IN THE CASE OF MANHOLES OR VALVES IF AT ALL POSSIBLE SHALL BE PLACED OUTSIDE THE

ROADWAY, SHOULDER, OR DITCH LINE IF PLACED IN THE SHOULDER THERE IS TO BE A MINIMUM OF 6 INCHES OF COVER IN THE DITCH LINE THERE IS TO BE 12 INCHES OF COVER BETWEEN THE MANHOLE AND THE INVERT OF THE DITCH. 27. ANY MANHOLES OR VALVES OR VALVE BOXES PLACED IN THE ROADWAY WILL BE ON THE

SAME PLANE AS THE ROADWAY AND SET FLUSH WITH ROADWAY.
28. ANY ROADS REQUIRING AN H.L.B.C. OVERLAY, FULL WIDTH OR PARTIAL, SHALL HAVE SHOULDER STONE FROM AN APPROVED SOURCE PLACED AS PER D.O.H. SPECIFICATIONS.

29. THE DEPARTMENT OF HIGHWAYS REQUIRES THERE BE NO WORK WITHIN THE DEPARTMENT'S RIGHT-OF-WAY DURING SNOW AND ICE REMOVAL. THERE MAY BE EXCEPTIONS FOR EMERGENCY AND CASE BY CASE SITUATIONS WITH NOTIFICATION TO THE DEPARTMENT.

### **UTILITY AGENCIES SERVING PROJECT AREA**

MISS UTILITY 1-800-245-4848

**WEST VIRGINIA DIVISION** 

OF HIGHWAYS WVDOH DIST #4

P.O. BOX 4220 CLARKSBURG, WV 26301-4220 (304) 842-1576

(304) 842-1507 FAX
DAVE SCHEARER - UTILITY SUPERVISOR - CROSSINGS
DENISE RONCONE - PERMIT SUPERVISOR - TEMP. ACCESSES

GAS DOMINION TRANSMISSION INC. 1-888-264-8240

ANTERO RESOURCES CORPORATION 1-303-357-7310

ENERGY CORPORATION OF AMERICA (ECA) 1-304-925-6100 (RICK JETT) 1-304-678-7446

> KEY OIL COMPANY -304-269-7102 (GREG KELLY) 1-304-588-7610

RITCHIE PETROLEUM 1-304-659-2123 (JUSTIN SMITH) 1-304-266-6332

ALLIANCE PETROLEUM CORPORATION (APC) 1-330-493-0440 (GENE DILLON) 1-304-629-9120

1-800-686-0022

CARLE

1-304-216-4100

SEWER NO PUBLIC SEWER IN PROJECT AREA

WATER

NO PUBLIC WATER IN PROJECT AREA

TELEPHONE

VERIZON TELECOMMUNICATIONS 1-800-275-2355

RESPONSE TEAMS: NATIONAL RESPONSE CENTER FOR REPORTING **CHEMICAL OR OIL SPILLS** 

STATE EMERGENCY SPILL

NOTIFICATION

-800-642-3074

EMERGENCY AMBULANCE, FIRE, LAW **ENFORCEMENT** 

# DRAWING INDEX

01	COVER	COVER SHEET
02	GNOTS	GENERAL NOTES SHEET
03	SPECS	GENERAL CONSTRUCTION SPECS SHEET
04	INDEX	INDEX SHEET
05-08	PLAN1-PLAN4	PROPOSED ALIGNMENT PLAN AND PROFILE SHEETS
09	AR1	ACCESS ROAD SHEET
10	HDD BORE	PROPOSED HOD BORE SHEET
11	нтр	HYDROSTATIC TEST PROFILE SHEET
12	S&WC1	STREAM & WETLAND CROSSING SHEET
13-22	ESCP1-ESCP10	ESCP DETAIL SHEETS

#### **GENERAL NOTES**

EXISTING UTILITIES SHOWN ON PLANS WHERE EVIDENCE HAS BEEN FOUND OR PROVIDED BY LOCAL UTILITIES. EXACT DEPTH AND LOCATION OF UTILITY LINES NOT KNOWN. CONTRACTOR TO VERIFY UTILITY LOCATIONS PRIOR TO CROSSING BY CONTACTING MISS UTILITY AT 1-800-245-4848 AND LOCAL UTILITY COMPANIES AS LISTED AND/OR NOT LISTED ON THIS SHEET. CONTRACTOR TO LOCATE WATER AND UTILITY SERVICES BEFORE BORING AND

IN THE EVENT AN ERROR WITH THE PLANS SEEMS APPARENT, THE MATTER MUST BE TAKEN UP WITH THE ENGINEER FOR REVIEW BEFORE PROCEEDING WITH CONSTRUCTION.

ALL PERMITS MUST BE SECURED PRIOR TO CONSTRUCTION.
THE CONTRACTOR SHALL COORDINATE ALL STREAM CROSSING INSTALLATIONS PROPOSED SO NOT TO DELAY THE CONSTRUCTION PROCESS. STREAM CROSSINGS ARE TO BE CONSTRUCTED USING AN OPEN CUT CROSSING METHOD UNLESS OTHERWISE SPECIFIED ON THE PLANS.

ALL WYDOH ROAD CROSSINGS TO BE CONSTRUCTED USING AN OPEN CUT CROSSING METHOD UNLESS OTHERWISE SPECIFIED ON THE PLANS. WYDOH TO BE NOTIFIED AT LEAST 48 HOURS PRIOR TO ANY WORK WITHIN WYDOH R/W ALL CONSTRUCTION TO BE DONE IN THE PROPOSED PIPELINE LIMITS OF

DISTURBANCE AS SHOWN 7. ALL CONSTRUCTION SHALL CONFORM TO THE APPLICABLE STANDARDS AND SPECIFICATIONS PROVIDED IN A SEPARATE BOUND VOLUME

CONTRACTOR SHALL FIELD VERIFY EXISTING PIPE TYPES AND O.D. PRIOR TO CONNECTION.

PROPERTY LINES SHOWN ON PLANS WERE OBTAINED FROM PARTIAL FIELD SURVEY AND RESEARCHED INFORMATION TAKEN FROM VARIOUS RECORDS ON FILE IN THE LOCAL COUNTY COURTHOUSE. TO OBTAIN A MORE ACCURATE BOUNDARY LINE LOCATION, A FULL PROPERTY SURVEY IS RECOMMENDED.

#### **EROSION & SEDIMENT CONTROL NOTES**

1. ALL FROSION AND SEDIMENT MEASURES TO BE IN ACCORDANCE WITH WEST VIRGINIA ONLINE 8MP MANUAL FOR STANDARD GUIDELINES AND SPECIFICATIONS AVAILABLE AT:

HTTPS://APPS.DEP.WV.GOV/DWWM/STORMWATER/BMP/INDEX.HTML
2. EROSION AND SEDIMENT CONTROL MEASURES HAVE BEEN SHOWN ON PLANS AND DETAILED IN SPECIFICATIONS

3. EXPOSED SOILS SHALL BE STABILIZED BY APPLICATION OF EFFECTIVE BMPs
THAT PROTECT THE SOIL FROM THE EROSIVE FORCES OF RAINDROPS, FLOWING WATER, AND WIND,

4. CLEARING AND GRUBBING IS TO OCCUR IN THE NOTED LIMITS OF DISTURBANCE (L.O.D.) ONLY.

ALL GRADED AREAS THAT ARE AT FINAL GRADE MUST BE SEEDED AND MULCHED WITHIN 7 DAYS AND AREAS THAT WILL NOT BE WORKED AGAIN FOR 21 DAYS OR MORE MUST BE SEEDED AND MULCHED WITHIN 7 DAYS.

6. AREAS WHERE THE SEED HAS FAILED TO GERMINATE ADEQUATELY (UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 70%) WITHIN 30 DAYS AFTER SEEDING AND MULCHING MUST BE RE-SEEDED IMMEDIATELY, OR AS SOON AS WEATHER CONDITIONS ALLOW.

TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL BMPs SHALL BE MAINTAINED AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. MAINTENANCE AND REPAIR SHALL BE CONDUCTED IN ACCORDANCE WITH BMPs.

8. EROSION AND SEDIMENT CONTROL BMPs SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES PER 24 HOUR PERIOD. ANY NECESSARY OR REQUIRED REPAIRS SHOULD BE MADE IMMEDIATELY.

## CONSTRUCTION SEQUENCE OF EVENTS

CALL MISS UTILITY (1-800-245-4848)

INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES.

CONSTRUCTION OF PIPELINE WITH RESTORATIONS. TESTING OF PIPELINE AND APPURTENANCES.

PROJECT CLOSE-OUT, PUNCH LIST, CLEAN UP, REPAIRS, FINAL SEEDING

### **LEGEND / ABBREVIATIONS** = EXISTING PIPELINE VENT = EXISTING WELL (AS NOTED) = EXISTING GAS METER = EXISTING RECTIFIERS = EXISTING PIPELINE MARKER = EXISTING GAS VALVE

= EXISTING MONUMENT FOUND (AS NOTED)

= EXISTING UTILITY POLE G ---- = EXISTING PIPELINE X --- = FXISTING FENCE

-- UGC --- = EXISTING UNDERGROUND UTILITY

= PROPERTY LINE --- = DOH RIGHT-OF-WAY LINE

---- = PROPOSED PERMANENT RIGHT-OF-WAY = PROPOSED CONSTRUCTION RIGHT-OF-WAY

= PROPOSED ANTERO BASELINE

W - PROPOSED ANTERO WATER LINE

---- = EXISTING GROUND PROFILE = PROPOSED PIPELINE PROFILE -\_ 4250--- = CONTOUR

- - - = PROJECT AREA-OF-INTEREST = PROPOSED ORANGE SAFETY FENCE = PROPOSED SILT SAVER BSRF-P1

ssz = PROPOSED SILT SAVER BSRF-P2 PROPOSED COMPOST FILTER SOCK

= PROPOSED PERMANENT WATER BAR (PLAN) = DELINEATED STREAMS = DELINEATED STREAMS (PROPOSED PERMANENT FILL)

= DELINEATED WETLANDS (PROPOSED PERMANENT FILL)

0 = DELINEATED GROUNDWATER SEEP/SPRING = USFWS PROTECTIVE AQUATIC BUFFER

ROLLED EROSION CONTROL PRODUCT = (INDICATES AREAS WHERE SLOPE IS 3:1 OR GREATER)

= ADDITIONAL TEMPORARY WORKSPACE = STONE CONSTRUCTION ENTRANCE

= TEMPORARY TIMBERMAT CROSSING = PROPOSED ACCESS ROAD

M P = PIPELINE MILE POST = PROPOSED PERMANENT WATER BAR (PROFILE) = PROPOSED EARTH TRENCH BREAKER (PROFILE)

> = PROPOSED TRENCH PLUG DRAIN (PROFILE) = PROPOSED GAS LINE MARKER

= PROPOSED TEST STATION

= PROPOSED ANODE = PROPOSED RECTIFIER = PROPOSED INSULATION KIT = PROPOSED AC COUPON

43-3-4-31.1 = PARCEL IDENTIFICATION

\*LEGEND IS TYPICAL. NOT ALL ITEMS IN LEGEND APPEAR IN DRAWING

### PROPOSED CONSTRUCTION RIGHT-OF-WAY

LIMITS-OF-DISTURBANCE ĕ C.L. PROPOSED CORRIDOR ĕ

CONSTRUCTION R/W LIMITS-OF-DISTURBANCE



ISSUED FOR PERMITTING

XX/XX/XXXX

AFE # A05924

	SUMMARY OF MATERIALS (3D)			SUMMARY OF MATERIALS (3D)		
0	30" STEEL API 5L PSL-2, X-70, 0.625" WALL, FBE COATED PIPE	4,594 LF				$\neg$
2	30" STEEL API 5L PSL-2, X-70, 0.625" WALL, ARO COATED PIPE	2,345 LF	П			
RECP	ROLLED EROSION CONTROL PRODUCT	523,148 SF	$\Box$			
SS1	SILT SAVER BSRF-P1	417 LF				
SS2	SILT SAVER BSRF-P2	9,474 UF	NO.	DESCRIPTION	ат	Υ
TB	EARTH TRENCH BREAKERS	17		DEVICION		
WB	PERMANENT WATERBARS	11		REVISION		
GM	GAS LINE MARKERS	. 14				
TS	TEST STATIONS	7				
NO.	DESCRIPTION	QTY	NO.	DESCRIPTION	DATE	BY

GENERAL INFORMATION

FIELD DELINEATION PERFORMED AND PROVIDED BY: KLEINFELDER, INC. 2. THIS SHEET IS INTENDED TO BE PLOTTED ON ANSI D (22" X 34"). FOR REDUCTIONS, REFER TO GRAPHIC SCALE.

*©*Antero Midstream Partners UP

SMITHBURG TO MXP RESIDUE PIPELINE **GENERAL NOTES** 

PROPOSED 30" HIGH PRESSURE STEEL GAS LINE DODDRIDGE COUNTY, WEST VIRGINIA

9/8/2017 AFE No. JOJ, RJL (TTG) AR, JRH (TTG) . NAME: 050-6467\MXP\GNOTS

SHEET 02

### 2. COMPANY FOREIGN LINE AND UTILITY CROSSINGS

CONTRACTOR SHALL CONFIRM THE LOCATION OF ALL SUCH CROSSINGS AND NOTIFY THE OWNER PRIOR TO ANY DITCHING ACTIVITY IN THE VICINITY OF THE CROSSINGS. A MINIMUM CLEARANCE OF 12 in., OR AS REQUIRED BY THE OWNER/OPERATOR, SHALL BE MAINTAINED FROM THE FOREIGN CROSSING. THE CONTRACTOR SHALL MAKE ALL REQUIRED "ONE-CALL" NOTIFICATIONS, AND KEEP DOCUMENTATION OF NOTIFICATIONS. THE CONTRACTOR SHALL KEEP THE MARKINGS REFRESHED AS NECESSARY DURING THE LENGTH OF THE CONSTRUCTION ACTIVITIES, MAKING NECESSARY RE-NOTIFICATIONS AS REQUIRED. COMPANY WILL LOCATE AND MARK LOCATIONS OF KNOWN COMPANY-OWNED FACILITIES WITHIN EXISTING OPERATING LOCATIONS.

IN AREAS WHERE UNDERGROUND FACILITIES. SUCH AS PIPELINES, ELECTRICAL LINES, FIBER OPTIC CABLES, ETC. EXISTING, EXCAVATION BY MACHINE SHALL BE LIMITED TO NO CLOSER THAN 2 FEET (IN ANY DIRECTION) TO THE FACILITY. THE FACILITY SHALL THEN BE EXPOSED AND POSITIVELY LOCATED BY HAND EXCAVATION. AFTER THE FACILITY IS EXPOSED, AND ONLY WHILE A COMPANY REPRESENTATIVE IS ON-SITE, EXCAVATION BY MACHINE IS PERMITTED TO WITHIN 1 FOOT (IN ANY DIRECTION) OF THE FACILITY. THE REMAINING EXCAVATION MUST BE HAND

DITCH WIDTH AND DEPTH - UNLESS OTHERWISE STATED ON THE DRAWINGS OR RIGHT-OF-WAY LINE LIST, THE DITCH SHALL BE A MINIMUM OF 12 in. WIDER THAN THE PIPE BEING LAID FOR PIPE DIAMETERS LESS THAN 12 in. AND A MINIMUM OF 18 in. WIDER FOR PIPE DIAMETERS 12 in. AND GREATER AND OF SUCH DEPTH THAT THE PIPE SHALL HAVE 36 in. MINIMUM COVER IN SOIL AND 24 in. IN CONSOLIDATED ROCK, MEASURED FROM THE TOP OF THE PIPE TO THE AVERAGE LEVEL OF THE ORIGINAL OR RESTORED GROUND ON THE TWO SIDES OF THE

CONSOLIDATED ROCK - CONSOLIDATED ROCK IS DEFINED AS ROCK LAYERS WHERE THE UPPERMOST SURFACE EXISTS AT A HIGHER ELEVATION THAN THE ELEVATION OF THE TOP OF THE PIPE. THIS CONDITION PROVIDES PROTECTION AGAINST DAMAGE FROM EXTERNAL FORCES AND JUSTIFIES COVER

DITCH GRADING - THE BOTTOM OF THE DITCH SHALL BE CUT TO A UNIFORM GRADE SO THAT THE FULL WIDTH OF THE DITCH SHALL BE AVAILABLE FOR PROVIDING SLACK IN THE LINE WHEN LAID.

BEND EXCAVATIONS - AT OVER-BENDS AND SIDE-BENDS, THE CONTRACTOR SHALL EXCAVATE THE DITCH TO ALLOW PROPER CLEARANCE BETWEEN THE INSIDE BEND OF THE PIPE AND THE BOTTOM OR SIDE OF THE DITCH TO MAINTAIN THE MINIMUM COVER.

ROCK - IN ALL CASES WHERE ROCK, OR ANY BOULDER LARGER THAN TWO IN. IN DIAMETER IS ENCOUNTERED IN THE BOTTOM OF THE DITCH, THE DITCH SHALL BE EVENLY PADDED WITH SOIL, SAND OR OTHER PADDING MATERIAL IN ORDER TO PREVENT THE ROCK OR BOULDERS FROM COMING INTO CONTACT WITH THE PIPE

THE SPOIL BANK FROM THE DITCHING OPERATIONS SHALL NOT BE PLACED ON ANY LOOSE DEBRIS OR FOREIGN MATTER WHICH MIGHT BECOME MIXED DURING PADDING AND BACKFILLING OPERATIONS. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN CAPS OR OPENINGS IN THE SPOIL BANK ACROSS CULTIVATED FIELDS, SO THAT EXCESSIVE RAINS DO NOT CAUSE WATER TO BACK UP AND FLOOD CULTIVATED SECTIONS. EXTREME CARE SHALL BE EXERCISED TO KEEP ALL DRAIN DITCHES AND WATER COURSES OPEN AND USEFUL.

## 5. TEMPORARY BRIDGES

WHEN THE DITCH IS EXCAVATED THROUGH LANDS WHERE LIVESTOCK/WILDLIFE IS CONFINED OR THROUGH AGRICULTURAL FIELDS WHERE THE COMPANY DETERMINES IT IS DESIRABLE FOR THE LANDOWNER OR TENANT TO HAVE A PASSAGEWAY ACROSS THE DITCH, THE CONTRACTOR SHALL PLUG THE DITCH OR PROVIDE SAFE, TEMPORARY BRIDGES FOR CROSSING THE DITCH AND LEAVE AN OPENING IN THE SPOIL BANK.

### 6. EXCAVATING NEAR IN-SERVICE PIPELINES

WHEN DITCHING PARALLEL TO AN EXISTING PIPELINE IN THE SAME RIGHTS-OF-WAY, NEAR THE EXISTING LINE AND DEEPER THAN THE EXISTING LINE, CARE SHOULD BE TAKEN TO LEAVE SUFFICIENT DISTANCE AND SUPPORT TO ENSURE SAID LINE DOES NOT SLOUGH OFF INTO NEW EXCAVATION. IF PARALLEL LINE IS A COUPLED HIGH PRESSURE LINE, IT IS NOT PERMITTED TO EXPOSE MORE THAN ONE COUPLING AT A TIME. IN ALL INSTANCES, THE WORK SHOULD BE PLANNED SUCH THAT THE EXCAVATION IS OPEN A MINIMUM AMOUNT OF TIME

THE CONTRACTOR SHALL HAUL AND STRING PIPE. CASING AND OTHER MATERIALS TO THE RIGHT-OF- WAY OR WORK AREA. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY TRUCKS AND EQUIPMENT FOR THE HAULING AND SPOTTING OF ALL MATERIALS. THE CONTRACTOR SHALL FURNISH SKIDS AND PLACE PIPE ON SKIDS ON THE RIGHT-OF-WAY IN A MANNER WHICH KEEPS BOTH ENDS FREE OF DIRT AND DEBRIS.

FIELD BENDING — WHERE IT IS NECESSARY TO BEND PIPE, ONLY COLD BENDS SHALL BE EMPLOYED. THE BENDS SHALL BE FREE FROM BUCKLING, FLATTENING, CRACKS OR OTHER EVIDENCE OF MECHANICAL DAMAGE AND ALL BENDS SHALL NOT HAVE A DIFFERENCE BETWEEN THE MAXIMUM AND MINIMUM DIAMETERS IN EXCESS OF 2.5 % OF THE NOMINAL DIAMETERS. ALL BENDS SHALL MEET THE CRITERIA SET FORTH IN DOT PART 192.

### GENERAL CONSTRUCTION SPECIFICATIONS

SLACK AND LONGITUDINAL WELDS — ALL OVER-BENDS, SAGS AND SIDE-BENDS SHALL BE MADE TO PROVIDE AN ADEQUATE AMOUNT OF SLACK IN THE PIPELINE. ON PIPE HAVING A LONGITUDINAL WELD, THE LONGITUDINAL WELD MUST BE LOCATED AS NEAR AS PRACTICABLE TO THE NEUTRAL AXIS OF THE BEND.

BENDING MACHINE — EACH BEND SHALL BE MADE USING A COMPANY APPROVED BENDING MACHINE HAVING A FULL CIRCLE BENDING SHOE WITH A NEOPRENE OR URETHANE LINING TO PRODUCE A SMOOTH, SYMMETRICAL BEND, UNLESS SPECIFIED OTHERWISE BY THE COMPANY. ON PIPE CONTAINING A LONGITUDINAL WELD, THE LONGITUDINAL SEAM MUST BE AS NEAR AS PRACTICAL TO NEUTRAL AXIS OF THE BEND UNLESS THE BEND IS MADE WITH AN INTERNAL BENDING MANDREL OR THE PIPE IS 12 in. OR LESS IN OUTSIDE DIAMETER OR HAS A DIAMETER-TIO-WALL THICKNESS RATIO LESS THAN 70. IF THE PIPE IS INTERNALLY COATED, THE BEARING SURFACES OF THE MANDREL SHALL BE CONSTRUCTED TO AVOID PERMANENTLY MARKING OR DAMAGING THE INTERNAL COATING. NO APPRECIABLE STRETCHING OR THINNING OF THE PIPE WALL THICKNESS SHALL BE RECENTED.

BENDING LIMITATION - DEFLECTION SHALL BE LIMITED TO A MAXIMUM OF ONE AND ONE-HALF DEGREES PER PIPE DIAMETER MEASURED LONGITUDINALLY ALONG THE PIPE. A COMPANY ACCEPTED METHOD OF MEASUREMENT SHALL BE USED BY THE CONTRACTOR WHEN MARKING THE PIPE IN PREPARATION FOR MAKING FIELD BENDS. BENDING SHALL NOT BE ALLOWED IN A CIRCUMFERENTIAL WELD AND NOT CLOSER THAN 6 ft. TO

#### 9. SWABBING AND CLOSING OPEN ENDS

SWABBING - EACH PIPE JOINT SHALL BE SWABBED AS NECESSARY TO REMOVE ALL DIRT AND FOREIGN MATTER FROM THE INSIDE OF THE PIPE BEFORE THE JOINTS ARE ALIGNED AND WELDED. THE SWABBING OPERATION SHALL NOT BE CARRIED ON MORE THAN FOUR JOINTS AHEAD OF THE FIRING LINE WELDERS OR

CLOSING OF PIPE ENDS. — WHERE THE LINE IS WELDED IN LONG SECTIONS BY THE FIRING LINE METHOD, THE ENDS OF THE LONG SECTIONS SHALL BE CLOSED AND KEPT CLOSED IN A MANNER APPROVED BY THE COMPANY UNTIL THE LONG SECTIONS ARE FINALLY JOINED. DURING THE LAYING OPERATIONS, CLOSE ATTENTION SHALL BE GIVEN TO OPEN ENDS TO ENSURE A COMPLETELY OPEN AND CLEAN LINE FREE OF ANY OBSTRUCTIONS. ALL REASONABLE PRECAUTIONS SHALL BE TAKEN TO PREVENT WATER FROM ENTERING THE LINE.

PREVENTION OF FOREIGN MATTER IN THE PIPELINE - THE OPEN END OF THE LINE SHALL BE SECURELY CLOSED AT THE END OF EACH DAY'S WORK TO PREVENT ENTRANCE OF SMALL ANIMALS OR THE INTRODUCTION OF FOREIGN MATTER OF ANY NATURE AND SHALL NOT BE REOPENED UNTIL WORK IS RESUMED. ANY OBSTRUCTIONS REMAINING IN THE LINE AFTER THE COMPLETION THEREOF SHALL BE REMOVED.

#### 10. POSITING OF LONGITUDINAL SEAM

IN INSTANCES WHERE PIPE OTHER THAN SEAMIESS IS FURNISHED BY THE COMPANY THE LONGITUDINAL SEAMS OF SUCH PIPE SHALL BE STAGGERED BY NOT MORE THAN 45'. LONGTUDINAL WELD SEAMS SHALL HAVE A MINIMUM FOUR-INCH CIRCUMFRENTIAL OFFSET BETWEEN ABUTTING JOINTS, UNLESS OTHERWISE SPECIFIED, THE LONGITUDINAL SEAMS ON ADJACENT PIPE SHALL BE STAGGERED, PLACING ONE APPROXIMATELY IN THE 10 O'CLOCK POSITION AND THE OTHER APPROXIMATELY IN THE 2 O'CLOCK POSITION.

### 11. LOWERING-IN PIPE

OVER-BENDS. SIDE-BENDS AND SAG-BENDS - ALL OVER-BENDS SHALL BE MADE AND INSTALLED TO CLEAR THE HIGH POINT OF THE BOTTOM OF THE DITCH BY AT LEAST 12 IN. AT THE POINT OF BEND. AT SIDE-BENDS, THE PIPE SHALL BE BENT AND LOWERED TO LAY AGAINST THE OUTSIDE WALL AT THE BOTTOM OF THE DITCH. ALL SAG- BENDS SHALL CONTINUOUSLY LIE ON FIRM GROUND AT THE BOTTOM OF THE DITCH.

PIPE SLINGS AND CRADLES - THE CONTRACTOR SHALL PROVIDE PADDED SLINGS FOR HANDLING COATED AND WRAPPED PIPE. THE USE OF BELTING REINFORCED WITH WIRE CABLE SHALL NOT BE PERMITTED. ANY METHOD OF LOWERING-IN WHICH PREVENTS DAMAGE TO THE COATING SHALL BE ACCEPTABLE; HOWEVER, THE USE OF

CONDITION OF DITCH - PRIOR TO LOWERING-IN THE CONTRACTOR SHALL PROVIDE, TO THE SATISFACTION OF THE COMPANY, A DITCH WHICH IS FREE FROM EXCESS DEBRIS, LARGE ROCKS AND ROOTS, WELDING RODS, SKIDS OR OTHER SUCH OBJECTS WHICH CAN CAUSE DAMAGE TO THE PIPE AND ITS PROTECTIVE COATING DURING LOWERING—IN OPERATIONS. THE CONTRACTOR SHALL PUMP WATER FROM THE DITCH, BELL HOLES OR OTHER

ROCK DITCH PADDING - IN ALL CASES WHERE ROCKS 2 in. AND LARGER ARE ENCOUNTERED IN THE BOTTOM OF THE DITCH AND NO ADDITIONAL PIPE COATING PROTECTION IS PROVIDED, THE CONTRACTOR SHALL PROVIDE PADDING MATERIAL PLACED EVENLY AND CONTINUOUSLY TO A MINIMUM DEPTH OF 8 in. ALONG THE BOTTOM OF

SUPPORTS - THE CONTRACTOR SHALL CONSTRUCT THE PIPELINE TO LIE ON THE BOTTOM OF THE PIPE TRENCH.

ALL BENDS SHALL BE MADE TO FIT THE PIPE DITCH. WHERE PIPE CANNOT BE DIRECTLY SUPPORTED BY THE
BOTTOM OF THE TRENCH, SUPPORT SHALL BE PROVIDED BY SANDBAGS OR OTHER COMPANY APPROVED MATERIALS. SANDBAGS SHALL BE PLACED AT POINTS TO PROVIDE STRESS—FREE SUPPORT FOR THE PIPELINE SUBSEQUENT TO BACKFILLING. SPACING INTERVALS FOR SANDBAG SUPPORTS SHALL BE 15 FT. OR LESS AS REQUIRED BY THE COMPANY. SUPPORTS COMPRISED OF MATERIALS OTHER THAN SANDBAGS SHALL BE CONSTRUCTED IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS AND AT SPACING INTERVALS NO GREATER THAN THE APPROPRIATE MAXIMUM INTERVAL RECOMMENDED BY THE MANUFACTURER. SUPPORT SHALL BE PLACED AT POINTS TO PROVIDE A STRESS-FREE INSTALLATION SUBSEQUENT TO BACKFILL. THE CONTRACTOR SHALL NOT USE ANY SUPPORT METHOD WITHOUT THE PRIOR APPROVAL OF THE COMPANY AND WITHOUT PROVIDING THE COMPANY WITH THE MANUFACTURER'S RECOMMENDED INSTALLATION DIRECTIONS FOR

<u>TIE-INS</u> - SECTIONS OF THE PIPELINE EXCAVATED FOR TIE-INS SHALL BE SUPPORTED WITH SANDBAGS OR OTHER APPROVED MATERIALS AT INTERVALS INDICATED ABOVE. SUPPORTS SHALL BE PLACED IMMEDIATELY AFTER FINAL TIE-IN TO PROVIDE A STRESS-FREE INSTALLATION SUBSEQUENT TO THE BACKFILLING OPERATION.

## 12. BACKFILLING

AFTER LOWERING—IN HAS BEEN COMPLETED, BUT BEFORE BACKFILLING, THE DITCH SHALL BE PUMPED DRY IN UPLAND AREAS AND THE LINE SHALL BE INSPECTED TO ENSURE THAT NO SKIDS, BRUSH, STUMPS, TREES, BOULDERS OR DEBRIS ARE IN THE DITCH. NO SUCH MATERIALS OR DEBRIS ARE TO BE BACKFILLED INTO THE DITCH. AFTER THE PIPE HAS BEEN INSPECTED AND APPROVED BY THE COMPANY, AFTER ALL DAMAGE TO THE PROTECTIVE COATING HAS BEEN REPAIRED AND AFTER THE COATING ON THE PIPE HAS HAD SUFFICIENT TIME TO CURE, THEN THE CONTRACTOR SHALL BACKFILL THE DITCH SUFFICIENTLY TO PREVENT FLOATING. THE CONTRACTOR SHALL COMPLETE THE FILLING OF THE DITCH TO PRODUCE A TRIM BACKFILL. EXCAVATED MATERIAL SHALL BE PLACED IN THE DITCH. TOPSOIL, WHERE IT HAS BEEN SEGREGATED, SHALL BE BACKFILLED AS CLOSE

ROCK, TWO INCHES IN DIAMETER AND LARGER, OR LIKE MATERIALS SHALL NOT BE BACKFILLED DIRECTLY ONTO THE PIPE. WHERE SUCH MATERIALS ARE ENCOUNTERED, THE CONTRACTOR SHALL HAUL, IF NECESSARY, SUFFICIENT EARTH OR SAND TO BE BACKFILLED AROUND AND OVER THE PIPE TO FORM A PROTECTIVE PADDING OR CUSHION TO A MINIMUM OF EIGHT INCHES OR, AS OTHERWISE SPECIFIED IN THE SCOPE OF WORK, IN DEPTH BETWEEN THE PIPE AND ANY GRAVEL OR SMALL BROKEN ROCK TO BE BACKFILLED. LARGE ROCK OR BOULDERS N EXCESS OF 24 in. IN DIAMETER, WIDTH OR LENGTH, SHALL NOT BE BACKFILLED INTO THE DITCH. SUCH ROCK SHALL BE DISPOSED OF PROPERLY.

THE CONTRACTOR SHALL INSTALL EROSION BREAKERS IN THE DITCH OVER, UNDER AND AROUND THE PIPE TO PROVIDE FULL PROTECTION AGAINST BACKFILL WASHING AT VARIOUS POINTS ALONG THE PIPELINE. BREAKER INSTALLATIONS AND SPACING SHALL COMPLY WITH THE FOLLOWING SPECIFICATIONS AS WELL AS COMPANY,

- BREAKER MATERIALS SHALL INCLUDE, BUT ARE NOT BE LIMITED TO, DECOMPOSABLE BAGS, SAND AND ANY OTHER MATERIALS REQUIRED TO FACILITATE THE PROPER PLACEMENT OF THE BREAKER MATERIAL IN THE DITCH
- BREAKER INSTALLATIONS MAY BE COMPRISED OF EITHER A MULTIPLE SANDBAG CONFIGURATION OR BY OTHER APPROVED METHODS. ALL BREAKER INSTALLATIONS SHALL MEET WITH THE APPROVAL OF THE COMPANY.

   BREAKER SIZE IS DEPENDENT ON THE EXTENT AND CONDITION OF THE DITCH IN DEPTH, WIDTH, SLOPE AND
- GRADE, AT A MINIMUM, BREAKERS SHALL EXTEND THE WIDTH AND DEPTH OF THE DITCH.
- · BREAKERS, SHALL BE SPACED ALONG THE DITCH IN ACCORDANCE WITH THE COMPANY'S ENVIRONMENTAL

THE CONTRACTOR SHALL INSTALL ROCK-FREE DIRT PADDING IN AREAS DESIGNATED BY THE COMPANY. TOPSOIL SHALL NOT BE USED FOR PADDING THE DITCH. DIRT PADDING SHALL BE INSTALLED IN THE BOTTOM OF THE DITCH TO A MINIMUM DEPTH OF 8 IN., PRIOR TO LOWERING-IN THE PIPELINE, IF OTHER ACCEPTABLE SUPPORT FOR PROTECTING THE BOTTOM OF THE PIPE IS NOT UTILIZED. A MINIMUM OF 8 IN. OF DIRT PADDING SHALL BE INSTALLED AS COVER ON TOP OF THE LINE AS PROTECTION PRIOR TO BACKFILLING. ACCEPTABLE ROCK-FREE PADDING MATERIAL MAY BE OBTAINED DIRECTLY FROM THE SPOIL, OR BY USING A PADDING MACHINE WITH MATERIAL TAKEN DIRECTLY FROM THE SPOIL OR ROCK-FREE PADDING MATERIAL CAN BE HAULED IN BY THE

### 15. CLEAN-UP

THE CONTRACTOR SHALL KEEP THE RIGHT-OF-WAY CLEAR OF LITTER, SKIDS, DEFECTIVE MATERIALS, AND ALL OTHER CONSTRUCTION DEBRIS IMMEDIATELY BEHIND ITS OPERATIONS, TO THE SATISFACTION OF THE COMPANY. UPON COMPLETION OF THE BACKFILL, THE CONTRACTOR WILL CLEAN THE RIGHT-OF-WAY IN A NEAT AND ACCEPTABLE CONDITION. SURPLUS MATERIALS SHALL BE ASSEMBLED AND DELIVERED BY CONTRACTOR TO A LOCATION DESIGNATED BY THE COMPANY. FENCES SHALL BE RECONSTRUCTED TO THE ORIGINAL LINE AND GATES INSTALLED AS INDICATED BY THE COMPANY. THE CONTRACTOR SHALL FURNISH GATES, FENCING AND

THE RIGHT-OF-WAY SHALL BE DISKED, LIMED, SEEDED AND FERTILIZED DURING THE CLEAN-UP OPERATION, THE CONTRACTOR SHALL FURNISH THE LIME, SEED AND FERTILIZER. SEEDING, FERTILIZING AND MULCHING MUST BE DONE WITHIN 6 DAYS OF FINAL CLEAN UP OR IN ACCORDANCE WITH COMPANY ENVIRONMENTAL REQUIREMENTS.

PIPELINE MARKERS SHALL BE INSTALLED AT POINTS DESIGNATED BY THE COMPANY DURING CLEAN-UP OPERATIONS. THE COMPANY SHALL FURNISH LINE AND AERIAL MARKERS.

THRASHER

T	SUMMARY OF MATERIALS (3D)			SUMMARY OF MATERIALS (3D	)	
F			+		-	
F			$\Box$		7	
$\vdash$			NO.	DESCRIPTION	٥	τΥ
F			-	REVISION		
L						
L		<u> </u>				
N	IO. DESCRIPTION	QTY	NO.	DESCRIPTION	DATE	BY

**GENERAL INFORMATION** 

1. THIS SHEET IS INTENDED TO BE PLOTTED ON ANSI D (22" X 34"). FOR REDUCTIONS, REFER TO GRAPHIC SCALE.



SMITHBURG TO MXP RESIDUE PIPELINE **GENERAL CONSTRUCTION SPECS** 


> PROPOSED 30" HIGH PRESSURE STEEL GAS LINE DODDRIDGE COUNTY, WEST VIRGINIA


SHEET 03


HT NAME: 050-6467\MXP\SPECS


XX/XX/XXXX AFE # A05924


ISSUED FOR PERMITTING
























HYDROSTATIC TEST (METER SITE TO MXP)	Station	Elevation (ft msl)
Start Point	0+00	1,346
Low Point (0.625 wt X-70)	50+44.199	714
High Point (0.625 wt X-70)	0+00	1,346
End Point	61+76.88	870
Differential (0.625 wt X-70)		632
Static Head Pressure @ 714' (0.625 wt X-70) PSI	27	73.8456

HYDROSTATIC TEST (TO SMITHBURG)	Station	Elevation (ft msl)
Start Point	20+91	1,288
Low Point (0.625 wt X-70)	26+47.59	1,041
High Point (0.625 wt X-70)	20+91	1,288
End Point	26+47.59	1,041
Differential (0.625 wt X-70)	•	247
Static Head Pressure @ 1,041' (0.625 wt X-70) PSI	1	07.0251





	SUMMARY OF MATERIALS (3D)			SUMMARY OF MATERIALS (3D) SUMMARY OF MATERIALS (3D)						
Ш							1			
$\vdash$							] 2			
							] 3			
$\sqcup$			NO.	DESCRIPTION	וֹסֶ	Y	1			
$\vdash$			-	REVISION			4			
							] 5			
$\vdash\vdash$	<u> </u>		<del> </del>				┨			
			1 1			T	1			
NO.	DESCRIPTION	QTY	NO.	DESCRIPTION	DATE	BY	1			

								_		
1.	PROPOSED	HIÇH	PRESSURE	GAS	LINE	MAOP	=	1,440	psig	

- . REFER TO ANTERO MIDSTREAM PRESSURE TESTING PROCEDURE.
- COORDINATE SYSTEM USED FOR MAPPING AND TOPOGRAPHY: HORIZONTAL - NAO B3 WEST VIRGINIA STATE PLANE, NORTH ZONE, U.S. SURVEY FOOT VERTICAL - NAVO 88 (GEODIZB), U.S. SURVEY FOOT
- ALL STATIONING SHOWN IS HORIZONTAL STATIONING.
- 5. THIS SHEET IS INTENDED TO BE PLOTTED ON ANSI D (22" X 34"). FOR REDUCTIONS, REFER TO GRAPHIC SCALE.


**GENERAL INFORMATION** 



MidstreamPartners of
SMITHBURG TO MXP RESIDUE PIPELINE
HYDROSTATIC TEST PROFILE

PROPOSED 30" HIGH PRESSURE STEEL GAS LINE DODDRIDGE COUNTY, WEST VIRGINIA

	DODDRIDGE	COUNTY, WI	ES1	VIRGINIA	
ATE:	9/7/2017				A059
CALE: RAWN BY: HECKED:	AS SHOWN JOJ, RJL (TTG) AR, JRH (YTG)	SHEE	Т	11	
	AMF: 050-646		•		REV. 0



- 2. ANY DISCREPANCIES FOUND BETWEEN THE DRAWINGS AND SPECIFICATIONS AND SITE CONDITIONS OR ANY INCONSISTENCIES OR AMBIGUITIES IN DRAWINGS OR SPECIFICATIONS SHALL BE IMMEDIATELY REPORTED TO THE PROJECT MANAGER, IN WRITING, WHO SHALL PROMPTLY ADDRESS SUCH PROBLEMS. WORK DONE BY THE CONTRACTOR AFTER THE DISCOVERY OF SUCH DISCREPANCIES, INCONSISTENCIES OR AMBIGUITIES SHALL BE DONE AT THE CONTRACTOR'S
- WORK ON THIS PROJECT SHALL CONFORM TO THE LATEST EDITIONS OF THE WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (DWWM)
  EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE HANDBOOK. IN THE EVENT OF CONFLICT BETWEEN THE DESIGN, SPECIFICATIONS, OR
- 4. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL PUBLIC OR PRIVATE UTILITIES WHICH LIE IN OR ADJACENT TO THE CONSTRUCTION SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR. AT HIS OR HER EXPENSE. OF ALL EXISTING UTILITIES DAMAGED DURING CONSTRUCTION. FORTY-EIGHT HOURS PRIOR TO ANY EXCAVATION THE CONTRACTOR SHALL CALL WEST VIRGINIA 811.
- 5. INSTALLATION OF CONCRETE, CORRUGATED METAL OR HDPE STORM PIPE SHALL BE IN CONFORMANCE WITH THESE DRAWINGS
- 6. ALL MATERIALS USED FOR FILL OR BACK FILL SHALL BE FREE OF WOOD, ROOTS, ROCKS, BOULDERS, ORGANIC MATERIAL, OR ANY OTHER NON-COMPACTABLE SOIL TYPE MATERIALS. UNSATISFACTORY MATERIALS ALSO INCLUDE MAN MADE FILLS AND REFUSE DEBRIS DERIVED FROM ANY SOURCE.
- A PRE-CONSTRUCTION KICK-OFF MEETING SHALL BE HELD PRIOR TO THE START OF CONSTRUCTION
- 8. IF SPRINGS OR SEEPS AND/OR AN ACCUMULATION OF GROUND WATER IS OBSERVED ON A SIDE CUT OR CUT SLOPE PIPE TRENCH, IMMEDIATELY INFORM THE ON-SITE INSPECTOR FOR AN EVALUATION AND CONSIDERATION OF THE INSTALLATION OF A FRENCH
- 9. EROSION CONTROL BLANKETS ARE REQUIRED FOR SLOPES OF 30 PERCENT OR GREATER.
- 10. HYDROMULCH CAN BE UTILIZED AS A SUBSTITUTE TO EROSION CONTROL BLANKETS WITH APPROVAL FROM ANTERO, EXCEPT FOR ON RESTORED STREAM BANKS AND ROAD BANKS. HYDROMULCH SHALL ONLY BE A VALID SUBSTITUTE FOR EROSION CONTROL BLANKETS DURING GRASS GROWING SEASONS.
- 11. HYDROSTATIC PRESSURE TEST POTABLE WATER FROM ANTERO APPROVED SOURCES ONLY TO BE USED FOR HYDROTEST. NO DEWATERING IS PERMITTED WITHOUT PRIOR ANTERO APPROVAL AND APPLICABLE PERMITS. NOTIFICATION REQUIRED TO ANTERO ENVIRONMENTAL PRIOR TO HYDROTEST.

#### EROSION AND SEDIMENT CONTROL PLAN NARRATIVE/CONSTRUCTION SEQUENCES

THE EROSION AND SEDIMENT (E&S) CONTROL MEASURES FOR THE PIPELINE CONSTRUCTION ACTIVITIES CONSIST OF COMPOST FILTER SOCK, SILT FENCE, RIGHT-OF-WAY (ROW) DIVERSIONS, TRENCH BREAKERS (PLUGS), AND TEMPORARY AND PERMANENT SEEDING AND MULCHING. BMP SPECIFICATIONS FOR THE EAS CONTROL PLAN (ESSEP) JAREA TO BE UTILIZED BY THE CONSTRUCTION CONTRACTOR ACCORDING TO THE PROVIDED PLAN. STRAWHAY BALES WILL NOT BE USED AS AN EAS CONTROL, HOWEVER, THEY MAY BE ACCEPTABLE TO USE AS A VELOCITY DISSIPATER.

GENERAL CONSTRUCTION SEQUENCE PER PIPELINE SEQUENCE.

- PRIOR TO BEGINNING LAND DISTURBING ACTIVITIES, CLEARLY MARK ALL CLEARING LIMITS, SENSITIVE AREAS AND THEIR BUFFERS, AND TREES THAT ARE TO BE PRESERVED WITHIN THE CONSTRUCTION AREA, THESE SHALL BE CLEARLY MARKED, BOTH IN THE FIELD AND ON THE PLANS, TO PREVENT DAMAGE AND OFFSITE IMPACTS
- 2. INSTALL STONE CONSTRUCTION ENTRANCES AT ALL LOCATIONS WHERE TEMPORARY ACCESS ROADS WILL BE ACCESSING A PAVED ROADWAY
- 3. INSTALL TEMPORARY E&S CONTROLS (SILT FENCE, ROW DIVERSIONS, ETC.) PRIOR TO ANY EARTH DISTURBING ACTIVITY, WHICH INCLUDES GRUBBING AND EXCAVATION, TO ENSURE, TO THE MAXIMUM EXTENT PRACTICABLE, THAT NO SIGNIFICANT EROSION OR SEDIMENTATION OCCURS.
- 4. ROW DIVERSIONS AND/OR OTHER EROSION AND SEDIMENT CONTROL DEVICES WILL BE INSTALLED AS NEEDED. IF CLEARING AND GRUBBING IS REQUIRED, SEE BELOW REGARDING THE MANAGEMENT AND DISPOSAL OF DEBRIS.
- AFTER ACCESS TO AND ALONG THE PROPOSED UTILITY LINE HAS BEEN PROVIDED, THE GENERAL CLEARING AND GRUBBING OF THE TREES AND BRUSH ALONG THE ROW FOR PIPE TRENCHING MAY COMMENCE TO THE WIDTH SPECIFIED IN THE EAS PLANS. TREES SHALL BE WINDROWED ON LOW SIDE OF RIGHT-OF-WAY, ALL POLLUTANTS, INCLUDING WASTE MATERIALS AND DEMOLITON DEBRIS, THAT OCCUP ON-SITE DURING CONSTRUCTION SHALL BE HANDLED AND DISPOSED OF IN A MANNER THAT DOES NOT CAUSE CONTAMINATION OF SURFACE WATERS. WOODY DEBRIS MAY BE CHOPPED AND SPREAD ON-SITE, UNLESS LANDOWNER STIPULATIONS SPECIFY OTHERWISE.
- MINOR GRADING WITHIN THE ROW WILL BE CONDUCTED WHERE NECESSARY TO PROVIDE AN EVEN SURFACE FOR SAFE AND EFFICIENT OPERATION OF CONSTRUCTION EQUIPMENT. GRADING WILL BE THE MINIMUM AMOUNT NECESSARY AND BMPS WILL BE INSTALLED PROMPTLY. TREE STUMPS, AND LARGE ROCKS AND BOULDERS WILL ALSO BE REMOVED FOR SAFETY AT THIS TIME.
- 7. EXCAVATE PIPELINE TRENCH, A MINIMUM COVER OF 3' SHALL BE PROVIDED ABOVE PIPELINE AT ALL LOCATIONS EXCEPT FOR WETLANDS AND STREAMS. A MINIMUM COVER OF 5' SHALL BE PROVIDED ALONG PIPELINE AT WETLAND AND STREAM CROSSINGS.
- 8. THE PROPOSED CONSTRUCTION ROW WILL BE USED AS A WORK AREA FOR TRENCH EXCAVATION, EQUIPMENT MOVEMENT, AND THE STORAGE OF SOIL STOCKPILES, AS NEEDED. EQUIPMENT SOIL STOCKPILES, AND OTHER MATERIALS AREA TO REMAIN UPSLOPE OF BMPS DURING CONSTRUCTION ACTIVITIES.
- SEGREGATION OF TOPSOIL AND SUBSOIL WILL BE PERFORMED WHERE TRENCH EXCAVATION TAKES PLACE IN AN AGRICULTURAL, WETLAND, OR RESIDENTIAL AREA. IT IS BEST MANAGEMENT PRACTICE TO SALVAGE AND SEGREGATE TOPSOIL WHERE APPLICABLE.
- 10. TEMPORARY E&S CONTROLS FOR STREAM CROSSINGS SHALL BE INSTALLED AT LOCATIONS SHOWN ON THE E&SCP AND ASSOCIATED DETAIL SHEETS.
- 11. STREAM AND RIVER PIPELINE CROSSING CONSTRUCTION METHODS WILL BE INSTALLED AT LOCATIONS SHOWN ON THE EAS PLAN SHEETS AND AS SPECIFIED ON THE DETAIL SHEETS. WATERBODIES WILL BE CROSSED WITH TEMPORARY BRIDGES, SUCH AS TIMBER MATS OR APPROVED EQUAL CROSSINGS, PRIOR TO CROSSING THE CONVEYANCE. STREAMBANK STABILIZATION WILL BE PERFORMED IMMEDIATELY FOLLOWING COMPLETION OF THE PIPELINE INSTALLATION.
- 12. WETLAND CROSSING WIDTHS FOR UTILITY CROSSINGS WILL BE KEPT TO A MINIMUM AND WILL BE STABILIZED BY PLACING TIMBER MATS, RIPRAP, OR PRE-FABRICATED SWAMP MATS, AS SHOWN ON THE DETAIL SHEETS. ALL MATERIALS USED TO STABILIZE ACCESS ROADS IN WETLAND AREAS WILL BE REMOVED FROM THE WETLAND UPON COMPLETION OF THE PIPELINE CONSTRUCTION. A BARRIER (GEOTECH FABRIC) SHOULD BE USED TO PREVENT
- 13. PIPELINE SECTIONS WILL BE TRANSPORTED TO THE WORK AREA AND STRUNG ALONG THE WORKING SIDE OF THE ROW PARALLEL TO THE TRENCH LINE. THE PIPELINE WILL BE BENT TO CONFORM TO THE TRENCH CONTOUR, ALIGNED, WELDED AND PLACED ON TEMPORARY SUPPORTS ALONGSIDE THE TRENCH. WELDS WILL BE VISUALLY AND RADIO-GRAPHICALLY INSPECTED AND REPAIRED AS NECESSARY. THE PIPE SECTION WILL BE LOWERED INTO THE TRENCH AND PLACED ON PADDING MATERIAL LAID ON THE TRENCH BOTTOM TO PROTECT THE PIPE COATING. ANY WETNESS ENCOUNTERED DURING CONSTRUCTION WORK WILL BE DEWATERED BY USING PUMPS, HOSES, AND DEWATERING BAGS, AND WILL BE DISCHARGED TO A WELL-VEGETATED UPLAND
- 14. INSTALL TRENCH BREAKERS (PLUGS) AT LOCATIONS AS SHOWN ON THE E&S PLAN SHEETS AND AS SPECIFIED ON THE DETAIL SHEETS.

15. THE TRENCH WILL BE SUBSEQUENTLY BACKFILLED WITH SUITABLE EXCAVATED MATERIAL. THE BACKFILL MATERIAL WILL BE SLIGHTLY CROWNED IN UPLAND AREAS TO ALLOW FOR SETTLEMENT THAT MAY OCCUR. CROWNING THE SOIL SLIGHTLY OVER THE PIPELINE WILL HELP PREVENT FUTURE STORMWATER-RELATED PROBLEMS FROM THE SETTLING OF THE BACKFILLED AREA NO CROWNING OF THE SOILS WILL TAKE PLACE IN WETLANDS, STREAMS, OR FLOODPLAINS, DISTURBED AREAS WILL BE RESTORED TO THEIR ORIGINAL TOPOGRAPHIC CONTOURS.

- 16. EXPOSED AND UNWORKED SOILS SHALL BE STABILIZED BY APPLICATION OF EFFECTIVE BMPS THAT PROTECT THE SOIL FROM EROSIVE FORCES OF RANDROPS, FLOWING WATER AND WIND, ALL DISTURBED AREAS THAT ARE AT FINAL GRADE MUST BE SEEDED AND MULCHED WITHIN SEVEN DAYS AND DAYS AND AREAS THAT WILL NOT BE WORKED AGAIN FOR 21 DAYS OR MORE MUST BE SEEDED AND MULCHED WITHIN SEVEN DAYS, FOR DISTURBED AREAS WITH SLOPES OF 3:1 OR GREATER, THE AREA WILL BE VETTICALLY TRACKED AND EROSION CONTROL FABRIC SHALL BE INSTALLED AFTER SEED, MULCH, AND SOIL SUPPLEMENTS HAVE BEEN APPLIED. THE TEMPORARY/PERMANENT SEEDING AND MULCH TABLE ON THE DETAIL SHEETS CONSIST OF THE TYPE OF SEED AND APPLICATION RATE THAT SHALL BE APPLIED, INCLUDING THE NURSE CROP THAT SHALL BE USED DURING CERTAIN TIME OF THE YEAR TO PROMOTE STABILIZATION OF THE SOIL UNTIL THE PERENNIAL SEEDLINGS
- 17. IN THE UNLIKELY EVENT THAT THERE ARE EXCESS EXCAVATED MATERIALS REMAINING AFTER THE TRENCH HAS BEEN BACKFILLED, THE MATERIAL WILL BE DISPOSED OF WITHIN THE EXISTING ROW IN AN UPLAND AREA. MATERIAL WILL BE SPREAD IN A THIN LAYER AND TIED INTO EXISTING CONTOURS TO CREATE POSITIVE DRAINAGE FOR STORMWATER RUNOFF
- 18. ALL E&S CONTROLS WILL BE INSPECTED, AT A MINIMUM, ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5-INCH PER 24-HOUR PERIOD UNTIL THERE IS A UNIFORM, PERENNIAL TO PERCENT VEGETATIVE COVERAGE ESTABLISHED. TEMPORARY BMPS WILL BE REMOVED UPON A CHIEVING VEGETATIVE STABILIZATION. THE 70 PERCENT REQUIREMENT REFERS TO THE TOTAL AREA VEGETATED AND NOT A PERCENT OF THE SITE.
- NO SEDIMENT TRACKING ON THE ROADWAY IS ALLOWED. IN THE EVENT THAT SEDIMENT IS INADVERTENTLY TRACKED ONTO THE ROAD, THE ROAD SHALL BE CLEANED THOROUGHLY BY THE END OF EACH DAY. SEDIMENT SHALL BE REMOVED FROM ROADS BY SHOVELING OR PICKUP SWEEPING AND SHALL BE TRANSPORTED TO A CONTROLLED SEDIMENT STO THE STORM DRAIN SYSTEM IS NOT ALLOWED. IF STREET WASH WASTEWATER CAN BE CONTROLLED FROM ENTERING THE STORM DRAINAGE SYSTEM, THEN IT SHALL BE PUMPED BACK ONTO THE SITE, CONTAINED AND DISPOSED OF PROPERLY
- 20. CONSTRUCTION ACCESS RESTORATION SHALL BE EQUAL OR BETTER THAN THE PRE-CONSTRUCTION CONDITION AND GRADES THAT WERE ALTERED DURING CONSTRUCTION ACTIVITIES SHALL BE RESTORED TO ORIGINAL GRADES AND MATCH EXISTING DRAINAGE PATTERNS.
- 21. APPLICABLE PRACTICES INCLUDE, BUT ARE NOT LIMITED TO, TEMPORARY AND PERMANENT SEEDING, SODDING, MULCHING, EROSION CONTROL FABRICS AND MATTING, THE EARLY APPLICATION OF GRAVEL BASE ON AREAS TO BE PAVED, AND DUST CONTROL
- 22. SELECTED SOIL STABILIZATION MEASURES SHALL BE APPROPRIATE FOR THE TIME OF YEAR, SITE CONDITIONS, AND ESTIMATED DURATION OF
- 23. SOIL STOCKPILES MUST BE STABILIZED AND PROTECTED WITH SEDIMENT TRAPPING MEASURES.
- 24. LINEAR CONSTRUCTION ACTIVITIES SUCH AS RIGHT-OF-WAY AND EASEMENT CLEARING, ROADWAY DEVELOPMENT, PIPELINES, AND TRENCHING FOR VILLITIES, SHALL BE CONDUCTED TO MEET THE SOLIS TABILIZATION TIMEFRAME REQUIREMENTS. CONTRACTORS SHALL INSTALL THE BEDDING MATERIALS, ROADBEDS, STRUCTURES, PIPELINES, OR UTILITIES AND RE-STABILIZE THE DISTURBED SOILS SO THAT THE
- 25. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES, CONSISTENT WITH SAFETY AND SPACE CONSIDERATIONS.

#### PIPELINE BMPS INSTALLATION AND REMOVAL SEQUENCE

TEMPORARY AND PERMANENT BMPs WILL BE USED DURING CONSTRUCTION ACTIVITIES TO AVOID AND/OR MINIMIZE ADVERSE ENVIRONMENTAL

INSPECTIONS OF ALL E&S CONTROLS SHALL BE CONDUCTED, AT A MINIMUM, ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5-INCH PER 24-HOUR PERIOD, ALL NECESSARY CLEANING, REPAIR ANDIOR MAINTENANCE SHALL BE MADE AS SOON AS POSSIBLE AFTER THE INSPECTION. IT SHALL BE THE RESPONSIBILITY OF THE CONTROLTOR TO ENSURE THAT INSPECTIONS AND REPAIRS ARE MADE AS OUTLINED HEREIN. ALL SEDIMENT COLLECTED FROM THE MAINTENANCE OF ESS CONTROL MEASURES SHALL BE SPREAD ON-SITE AND SEEDED AND MULCHEQ. OR DISPOSED OF PROPERLY AT A W DEPARTMENT OF ENVIRONMENTAL PROTECTION (WVDEP)-APPROVED LOCATION. THE FOLLOWING MAINTENANCE WILL BE PERFORMED UNTIL STABILIZATION HAS BEEN ACHIEVED:

- TEMPORARY EROSION AND SEDIMENT CONTROL BMPS SHOULD BE REMOVED FOLLOWING CONFIRMATION THAT 70 PERCENT PERENNIAL VEGETATIVE COVERAGE IS ESTABLISHED. TRAPPED SEDIMENT SHALL BE REMOVED OR STABILIZED ON-SITE. DISTURBED SOIL RESULTING FROM REMOVAL OF BMPS OR VEGETATION SHALL BE PERMANENTLY STABILIZED.
- WHENEVER INSPECTION AND/OR MONITORING REVEALS THAT THE BMPs IDENTIFIED IN THE E&SCP ARE INADEQUATE, THE E&SCP SHALL BE MODIFIED, AS APPROPRIATE, IN A TIMELY MANNER.
- MAINTENANCE OF THE E&SCP THE E&SCP SHALL BE RETAINED ON-SITE. THE E&SCP SHALL BE MODIFIED WHENEVER THERE IS A SIGNIFICANT CHANGE IN THE DESIGN, CONSTRUCTION, OPERATION, OR MAINTENANCE OF ANY BMP. THE DEP MUST IS B NOTIFIED OF ANY CHANGES TO THE CONSTRUCTION SWPP. DEPENDING ON THE SIGNIFICANCE OF THE REVISION, A PERMIT MODIFICATION MAY NEED TO BE SUBMITTED TO THE

THE FOLLOWING IS A GENERAL BMP INSTALLATION SEQUENCE FOR PIPELINE CONSTRUCTION ACTIVITIES:

- . A STONE CONSTRUCTION ENTRANCE SHALL BE PROVIDED AT ALL LOCATIONS WHERE CONSTRUCTION TRAFFIC WILL BE ACCESSING A PAVED ROAD DIRECTLY FROM A DISTURBED AREA.
- TEMPORARY SEDIMENT BARRIERS, INCLUDING APPROPRIATELY SIZED SILT FENCE WILL BE PLACED DOWN SLOPE OF WORK AREAS AND AROUND SOIL STOCKPILES, AS NEEDED.
- APPROPRIATELY SIZED FENCING WILL BE PLACED AROUND WETLANDS AND WATERBODIES ADJACENT TO THE WORK AREA PRIOR TO ANY TRENCHING ACTIVITIES.
- . STOCKPILE SLOPES WILL BE TWO TO ONE OR FLATTER, AND STOCKPILES WILL NOT EXCEED 35 FEET IN HEIGHT
- TEMPORARY STREAM AND WETLAND CROSSINGS SHALL BE INSTALLED AS INDICATED ON THE E&S PLAN SHEETS AND AS PER THE E&S DETAIL SHEETS. FOR ALL OTHER SURFACE OR STORMWATER CONVEYANCES THAT ARE NOT IDENTIFIED ON THE PLAN SHEETS AS STREAMS DUE TO LACK OF DEFINED BED AND BANK CONDITIONS, A TEMPORARY BRIDGE SUCH AS A TIMBER MAT OR AN APPROVED EQUAL SHALL BE INSTALLED PRIOR TO CROSSING THE CONVEYANCE IF THERE IS FLOWING WATER PRESENT AT TIME OF CONSTRUCTION IN THAT AREA.
- TEMPORARY ROW DIVERSIONS WILL BE INSTALLED IMMEDIATELY AFTER INITIAL DISTURBANCE OF THE SOIL IN ACCORDANCE WITH THE DETAILS AND SPACING SIZING REQUIREMENTS. TEMPORARY ROW DIVERSIONS WILL BE CONSTRUCTED OF SOIL TO REDUCE RUNOFF VELOCITY AND DIVERT WATER OFF OF THE PIPELINE ROW. TEMPORARY ROW DIVERSIONS WILL BE MAINTAINED UNTIL PERMANENT ROW DIVERSIONS HAVE
- TRENCH DEWATERING, IF NEEDED, WILL BE CONDUCTED USING A PUMP AND HOSE. WATER WILL BE RELEASED INTO A FILTER BAG THAT WILL BE LOCATED IN A WELL-VEGETATED UPLAND AREA.
- TRENCH BREAKERS (PLUGS) WILL BE INSTALLED IN SLOPING AREAS GREATER THAN FIVE PERCENT AND ON SLOPES ADJACENT TO STREAMS, WETLANDS, AND ROADS CROSSINGS TO PREVENT SUBSURFACE EROSION. TRENCH BREAKERS (PLUGS) WILL BE INSTALLED IN ACCORDANCE
- THE WORK AREA WILL BE BACKFILLED FOLLOWING PIPELINE INSTALLATION OR OTHER EXCAVATION WORK. IN AREAS WHERE TOPSOIL HAS BEEN SEGREGATED, THE SUBSOIL WILL BE REPLACED FIRST, AND THEN THE TOPSOIL WILL BE SPREAD OVER THE AREA FROM WHICH IT WAS REMOVED. DISTURBED AREAS WILL BE RESTORED TO THEIR ORIGINAL TOPOGRAPHIC CONTOURS.
- ROW DIVERSIONS, WHEN REQUIRED, WILL BE CONSTRUCTED WITH A 5 TO 10 PERCENT (TYPICAL) OUTSLOPE TO DIVERT SURFACE FLOW TO A WELL-VEGETATED STABLE AREA.
- IMMEDIATELY FOLLOWING BACKFILLING, ALL DISTURBED AREAS WILL BE GRADED IN PREPARATION FOR SEEDING AND MULCHING. THE
  CONSTRUCTION SITE SHOULD BE STABILIZED AS SOON AS POSSIBLE AFTER COMPLETION. ESTABLISHMENT OF FINAL COVER MUST BE INITIATED
  NO LATER THAN SEVEN DAYS AFTER REACHING FINAL GRADE.

- FOR THREE TO ONE OR STEEPER SLOPES THE DISTURBED AREA WILL BE VERTICALLY TRACKED, EROSION CONTROL FABRIC WILL BE INSTALLED.
- TEMPORARY SEDIMENT BARRIERS WILL BE MAINTAINED, UNTIL VEGETATION HAS BECOME ESTABLISHED WITH A UNIFORM COVERAGE OF DENSITY OF 70 PERCENT OR MORE WITHIN THE DISTURBED ROW. ONCE THIS COVERAGE HAS BEEN OBTAINED, APPROPRIATE CONTROLS WILL BE REMOVED FROM THE WORK AREA AREAS DISTURBED DURING THE ERMOVID OF THE EROSION CONTROLS WILL BE STABILIZED IMMEDIATELY. THE 70 PERCENT REQUIREMENTS REFERS TO THE TOTAL AREA VEGETATED AND NOT A PERCENT OF
- ALL WASTE MATERIAL WILL BE TRANSPORTED OFF-SITE FOR RECYCLING AND/OR DISPOSAL. WHERE FEASIBLE, CONSTRUCTION WASTE MATERIALS WILL BE RECYCLED OR WILL BE TAKEN TO AN APPROVED FACILITY FOR DISPOSAL. AS STATED PREVIOUSLY, EXCESS SOIL MATERIAL, IF ANY, WILL BE SPREAD AND REVEGETATED WITHIN THE ROW. OFF-SITE SPOIL AND/OR BORROW SITES MUST BE OPERATED UNDER A CURRENT NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT.
- EROSION CONTROL BLANKETS SHALL NOT BE INSTALLED ON AGRICULTURAL AREAS EVEN IF SLOPES ARE STEEPER THAN THREE TO ONE. THESE AREAS MAY REQUIRE SPECIAL ATTENTION/RESTORATION UNTIL ADEQUATE GROWTH IS ACHIEVED.
- TÉMPORARY STOCKPILES NEED SILT FENCE / SOCK PLACED ADJACENT TO ROW.
- CONTRACTOR IS EXPECTED TO MINIMIZE DISTURBANCE WITHIN THE ROW

#### MAINTENANCE SCHEDULE

AFTER CONSTRUCTION IS COMPLETED, ALL BMPS WILL BE REMOVED AND ANY LAND DISTURBED BY REMOVAL WILL BE PERMANENTLY STABILIZED. UNLESS OTHERWISE SPECIFIED, ALL MAINTENANCE MUST BE COMPLETED IMMEDIATELY AFTER AN INSPECTION IDENTIFIES

- IF DURING CONSTRUCTION, CONCENTRATED FLOW AREAS FORM DUE TO A STORM EVENT AND ANY AREA BECOMES UNSTABLE, THE
  AREA WILL BE STABILIZED BY PLACING SIZE DS0 (FOUR-INCH DIAMETER) STONE IN THE CONCENTRATED FLOW AREAS, ANY
  REQUIRED REPAIRS OR MAINTENANCE SHALL BE MADE IMMEDIATELY.
- ALL E&S CONTROLS WILL BE INSPECTED, AT A MINIMUM, ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5-INCH PER 24-HOUR PERIOD DURING THE ENTIRE PROJECT.
- SEDIMENT MUST BE REMOVED WERE ACCUMULATION REACHES ONE-HALF THE ABOVE GROUND HEIGHT OF A SILT FENCE (ALL
- SILT FENCE SECTIONS, WHICH HAVE BEEN UNDERMINED OR TOPPED, SHOULD IMMEDIATELY BE REPAIRED
- LOGS OF SEDIMENT CONTROL INSPECTION MUST BE KEPT WITH THE INSPECTORS CONSTRUCTION RECORDS AND INCLUDE DATE,
   TIME, AND CONDITION OF BMPS AND ANY NECESSARY MAINTENANCE. A BMP INSPECTION REPORT IS INCLUDED IN APPENDIX I.
- TEMPORARY AND PERMANENT E&S CONTROL BMPS SHALL BE MAINTAINED AND REPAIRED AS NEEDED TO ASSURE CONTINUED
  PERFORMANCE OF THEIR INTENDED FUNCTION. MAINTENANCE AND REPAIR SHALL BE CONDUCTED AT LEAST ONCE EVERY SEVEN
  CALENDAR DAYS AND AFTER ANY STORM EVENT GREATER THAN 0.5-INCH OF RAIN PER 24-HOUR PERIOD.
- TEMPORARY E&S CONTROL BMPS SHOULD BE REMOVED FOLLOWING CONFIRMATION THAT 70 PERCENT PERENNIAL VEGETATIVE COVERAGE IS ESTABLISHED. TRAPPED SEDIMENT SHALL BE REMOVED OR STABILIZED ON-SITE. DISTURBED SOIL RESULTING FROM REMOVAL OF BMPS OR VEGETATION SHALL BE PERMANENTLY STABILIZED.

#### MATERIAL WASTE HANDLING AND RECYCLING

- GARBAGE DISPOSAL IS HANDLED THROUGH ONE OF THE LOCAL WASTE MANAGEMENT PROVIDERS/FACILITIES. THE CONTRACTOR
  WILL LEASE A DUMPSTER FOR THE DURATION OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED MUNICIF

  OF THE PROJECT WHICH WILL BE DISPOSED OF AT A LICENSED/PERMITTED WILL BE DISPOSED OF AT A LICENSED/PERMITTED WILL BE DISPOSED OF AT A LICENSED WILL BE DISPOSED OF A LICENSED WILL BE DISPOSED WILL BE DISPOSED WILL BE DISPOSED OF A LICENSED WILL BE DISPOSED WIL
- 2. THE CONTRACTOR WILL DISPOSE OF ALL SCRAP MATERIAL. THE SCRAP MATERIAL MUST BE REMOVED FROM THE SITE AND DISPOSED OF OR RECYCLED AT A PROPERLY LICENSED/PERMITTED FACILITY. THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY PERMITS AND/OR DISPOSAL FEES. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE TO ASSURE THAT ALL MATERIALS ARE HANDLED AND DISPOSED OF IN ACCORDANCE WITH APPLICABLE LAWS, RULES, AND REGULATIONS, INCLUDING BUT NO LIMITED TO THOSE ISSUED BY THE ENVIRONMENTAL PROTECTION AGENCY, WYDEP, AND OCCUPATIONAL SAFETY AND HEALTH
- 3. CONSTRUCTION WASTE MATERIALS, INCLUDING BUT NOT LIMITED TO BENTONITE, POLY PIPE SHAVINGS, AND SANDBAGS, WILL BE RECYCLED OR WILL BE TAKEN TO THE NEAREST APPROVED FACILITY FOR DISPOSAL. EXCESS SOIL MATERIAL, IF ANY, WILL BE SPREAD AND REVEGETATED WITHIN THE ROW. OFF-SITE SPOIL AND/OR BORROW SITES MUST BE OPERATED UNDER A CURRENT

SEE DETAILS 25-27 FOR TEMPORARY SEEDING, PERMANENT SEEDING, AND MULCHING REQUIREMENTS.

- . ALL POLLUTANTS, INCLUDING WASTE MATERIALS AND DEMOLITION DEBRIS, THAT OCCUR ON SITE DURING CONSTRUCTION SHALL BE HANDLED AND DISPOSED OF IN A MANNER THAT DOES NOT CAUSE CONTAMINATION OF SURFACE WATER, WOODY DEBRIS MAY BE CHOPPED AND SPREAD ON SITE.
- COVER, CONTAINMENT, AND PROTECTION FROM VANDALISM SHALL BE PROVIDED FOR ALL CHEMICALS, LIQUID PRODUCTS, PETROLEUM PRODUCTS, AND NON-INERT WASTES PRESENT ON THE SITE.
- MAINTENANCE AND REPAIR OF HEAVY EQUIPMENT AND VEHICLES INVOLVING OIL CHANGES. HYDRAULIC MAINTENANCE AND REPAIR OF HEAVY EQUIPMENT AND VEHICLES INVOLVING OIL CHANGES, HYDRAULIC SYSTEM DRAIN DOWN, SQLYENT AND DE-GREASING CLEANING OPERATIONS, FUEL TANK DRAIN DOWN AND REMOVAL, AND OTHER ACTIVITIES WHICH MAY RESULT IN DISCHARGE OR SPILLAGE OF POLLUTANTS TO THE GROUND OR INTO SURFACE WATER RUNOFF MUST BE CONDUCTED USING SPILL REVENTION MEASURES, SUCH AS DRIP PANS, CONTAMINATED SURFACES SHALL BE CLEANED IMMEDIATELY FOLLOWING ANY DISCHARGE OR SPILL INCIDENT. EMERGENCY REPAIRS MAY BE PERFORMED ON-SITE USING TEMPORARY PLASTIC PLACED BENEATH AND, IF RAINING, OVER THE VEHICLE.
- APPLICATION OF AGRICULTURAL CHEMICALS INCLUDING FERTILIZERS AND PESTICIDES SHALL BE CONDUCTED IN A MANNER AND AT APPLICATION RATES THAT WILL NOT RESULT IN LOSS OF CHEMICAL TO SURFACE WATER RUNOFF. MANUPACTURERS' RECOMMENDATIONS FOR APPLICATION RATES AND PROCEDURES HALL BE
- BMPS SHALL BE USED TO PREVENT OR TREAT CONTAMINATION OF SURFACE WATER RUNOFF BY PH MODIFYING SOURCES. THESE SOURCES INCLIDE BULK CEMENT, CEMENT KILN DUST, FLY ASH, NEW CONCRETE WASHING AND CURING WATERS, WASTE STREAMS GENERATED FROM CONCRETE GRINDING AND SAWING, EXPOSED AGGREGATE PROCESSES, AND CONCRETE PUMPING AND MIXER WASHOUT WATERS.
- REPORT SPILLAGE OR DISCHARGE OF POLLUTANTS WITHIN 24-HOURS.

THRASHER

**SUMMARY OF MATERIALS (3D) SUMMARY OF MATERIALS (3D)** ISSUED FOR PERMITTING QTY DESCRIPTION REVISION XX/XX/XXXX AFE # A05924 DESCRIPTION DESCRIPTION

GENERAL INFORMATION

THIS SHEET IS INTENDED TO BE PLOTTED ON ANSI D (22" X 34"). FOR REDUCTIONS, REFER TO GRAPHIC SCALE.


**MAntero** Midstream Partners LP


SMITHBURG TO MXP RESIDUE PIPELINE **ESCP DETAILS** 


> PROPOSED 30" HIGH PRESSURE STEEL GAS LINE DODDRIDGE COUNTY, WEST VIRGINIA


> > SHEET 13


SHT. NAME: 050-6467\MXP\ESCP1












1) PREPARE SOIL BEFORE INSTALLING EROSION CONTROL PRODUCTS. INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED.


2) FOR CULVERT AND OUTFALL APPLICATIONS, SCOUR PROTECTION SHOULD EXTEND A MINIMUM WIDTH OF 3-4 TIMES THE PIPE DIAMETER AND A MINIMUM LENGTH OF 4-5 TIMES THE PIPE DIAMETER (SEE PLAN VIEW). WITH STEEPER CHANNEL GRADIENTS, THE LENGTH OF SCOUR PROTECTION MAY NEED TO BE


3) PLACE STAPLES/ANCHORS IN THE APPROPRIATE PATTERN. IN SOFT OR HIGHLY ERODIBLE SOILS, PERCUSSION EARTH ANCHORS MAY BE REQUIRED.

(SEE MANUFACTURERS RECOMMENDATIONS FOR ADDITIONAL INSTALLATION INSTRUCTIONS).


9 TRENCH PLUG DRAIN OUTFALL EROSION PROTECTION DETAIL











**GENERAL INFORMATION** 

THIS SHEET IS INTENDED TO BE PLOTTED ON ANSI D (22" X 34"). FOR REDUCTIONS, REFER TO GRAPHIC SCALE.

*©*Antero Midstream Partners UP


SMITHBURG TO MXP RESIDUE PIPELINE ESCP DETAILS


> PROPOSED 30" HIGH PRESSURE STEEL GAS LINE DODDRIDGE COUNTY, WEST VIRGINIA


SHEET 16

SHT. NAME: 050-6467\MXP\ESCP4

REV. 0








1. INSTALL TEMPORARY EROSION AND SEDIMENT CONTROLS PRIOR TO EARTH DISTURBANCE


2 SEDIMENT BARRIERS WILL BE INSTALLED AT THE EDGE OF THE ROW.

SECTION A-A

4 WETLAND MATERIAL WILL BE STRIPPED, SEGREGATED, AND RESTORED UPON COMPLETION OF THE CROSSING








8. ALL AREAS DISTURBED DURING BRIDGE INSTALLATION SHALL BE STABILIZED IMMEDIATELY.

PLYWOOD SPLASH PROTECTION (OR APPROVED EQUAL) SHALL BE WELL MAINTAINED, CLEARING SEDIMENT WHEN NECESSARY.

FILTER SOCK SHALL BE PLACED ALONG BOTH ENTRANCES OF THE BRIDGE WHEN NOT IN USE FOR MORE THAN 24 HOURS AND/OR PRIOR TO PRECIPITATION EVENTS. DO NOT DRIVE OVER FILTER SOCK.

24A TYPICAL EROSION AND SEDIMENT CONTROL FOR STREAM CROSSINGS





**GENERAL INFORMATION** 

THIS SHEET IS INTENDED TO BE PLOTTED ON ANSI D (22" X 34"). FOR REDUCTIONS, REFER TO GRAPHIC SCALE.

# *©*Antero Midstream Partners LP


SMITHBURG TO MXP RESIDUE PIPELINE ESCP DETAILS

PROPOSED 30" HIGH PRESSURE STEEL GAS LINE DODDRIDGE COUNTY, WEST VIRGINIA

9/7/2017 AFE No.: AS SHOWN JDJ, RJL (TTG) AR, JRH (TTG) SHEET 18

SHT. NAME: 050-6467\mxP\ESCP6

REV. 0




26	PERMANENT SEEDING CHART
	NTS





2 tons per acre





THRASHER

IFP ISSUED FOR PERMITTING DATE: XX/XX/XXXX

AFE # A05924

250 - 350 lbs per acre

100 - 125 lbs per

Annual Rye

**SUMMARY OF MATERIALS (3D) SUMMARY OF MATERIALS (3D)** NO. QTY DESCRIPTION REVISION DESCRIPTION DESCRIPTION

GENERAL INFORMATION

THIS SHEET IS INTENDED TO BE PLOTTED ON ANSI D (22" X 34"). FOR REDUCTIONS, REFER TO GRAPHIC SCALE.


**Antero** Midstream Partners LP


SMITHBURG TO MXP RESIDUE PIPELINE **ESCP DETAILS** 


PROPOSED 30" HIGH PRESSURE STEEL GAS LINE
DODDRIDGE COUNTY, WEST VIRGINIA

SHEET 19 SHT. NAME: 050-6467\MXP\ESCP7

REV. 0







2:1 OR FLATTER 3

WHEN CLEARING THE LOCATION FOR THE DIVERSION, ONLY CLEAR ENOUGH ROOM FOR CONSTRUCTION AND MAINTENANCE EQUIPMENT ACCESS. DO NOT CLEAR ANY ADDITIONAL AREA UNTIL ALL EROSION CONTROL DEVICES ARE IN PLACE REMOVE ALL STUMPS, ROOTS, AND OTHER DEBRIS AND DISPOSE OF THEM PROPERLY. INSTALL DIVERSION AND COMPACT AS SHOWN IN DETAIL INSURE POSITIVE DRAINAGE DURING CONSTRUCTION OF BERM. SCARIFY, SEED, MULCH AND TACK DISTURBED AREAS IMMEDIATELY UPON COMPLETION OF BERM INSTALL EROSION CONTROL MAT NORTH AMERICAN GREEN C12SN PER MANUFACTURER'S RECOMMENDATIONS AND KEY INTO SIDES OF CHANNEL TO PREVENT WATER FROM UNDERMINING OR DAMAGING CHANNEL LINER.

#### NOTES:


TEMPORARY BERMS SHALL BE PLACED, MAINTAINED, AND ADJUSTED CONTINUOUSLY UNTIL 90% VEGETATIVE GROWTH IS ESTABLISHED ON THE EXTERIOR SLOPES WITH PERMANENT STORM DRAINAGE FACILITIES FUNCTIONING.
BERMS SHALL OUTLET TO SLOPE PIPES, CHANNELS, OR OTHER APPROVED MEANS OF CONVEYING RUNOFF TO A SEDIMENT TRAP, SEDIMENT BASIN, OR COLLECTOR CHANNEL.
CHANNEL BEHIND BERM SHALL HAVE POSITIVE GRADE TO OUTLET AND AN APPROPRIATE PROTECTIVE LINNING.
BERM SHALL BE ADGRADETED A COLLECTOR OF THE PROTECTIVE LINNING.


PROTECTIVE LINNING.
BERM SHALL BE ADEQUATELY COMPACTED TO PREVENT FAILURE.
AN ACCEPTABLE ALTERNATIVE TO TOP-OF-SLOPE BERM IS TO CONTINUOUSLY GRADE THE TOP OF
FILL TO DIRECT RUNOFF AWAY FROM THE FILLSLOPE TO A COLLECTOR CHANNEL, SEDIMENT TRAP,
OR SEDIMENT BASIN.

#### MAINTENANCE:

INSPECT TEMPORARY DIVERSIONS ONCE A WEEK AND AFTER EVERY RAINFALL. IMMEDIATELY REMOVE SEDIMENT FROM THE FLOW AREA AND REPAIR THE DIVERSION RIDGE. CAREFULLY CHECK OUTLETS AND MAKE TIMELY REPAIRS. REMOVE THE RIDGE AND THE CHANNEL TO BLEND WITH THE NATURAL GROUND LEVEL AND APPROPRIATELY STABILIZE IT.








NOTES:
DITCH CHECKS WILL BE CONSTRUCTED IN CHANNELS TO MINIMIZE EROSION. THE CONSTRUCTION OF THE DITCH CHECKS WILL BE CONSTRUCTED SO THAT THE ELEVATION OF THE TOP OF THE DOWNSTREAM DITCH CHECK IS EQUAL TO THE ELEVATION OF THE BASE OF THE DITCH CHECK ABOVE. THIS CREATES A SITUATION WHERE THE CHANNEL HAS NO CHANNELIZED FLOW PER SAY. THE WATER FLOWING DOWN THE DITCH WILL CASCADE FROM THE POOL CREATED BY ONE DITCH CHECK ITO THE POOL CREATED BY ONE DITCH CHECK INTO THE POOL CREATED BY THE DOWNSTREAM DITCH CHECK THIS DISSIPATES ENERGY AND SLOWS THE WATER FLOW REDUCING EROSION AND ALLOWING ANY SEDIMENT IN THE DRAINAGE TO FALL OUT.






# LEVEL SPREADER DETAIL

NOTE: TO BE PLACED AT THE ENDS OF DITCHES CALLING FOR LEVEL SPREADERS LEVEL SPREADERS WILL BE CUT INTO THE CONTOUR OF THE EXISTING SLOPE.

NOTES:
LEVEL SPREADER TO BE CONSTRUCTED IN AREAS WHERE A CULVERT OR CHANNEL MUST EMPTY
ONTO GROUND WITH NO ASSOCIATES CHANNELIZED FLOW. THE PURPOSE OF THE LEVEL
SPREADER IS TO DISSIPATE ENERGY AND SPREAD THE FLOW OUT OVER A SIGNIFICANT AREA. THIS WILL TAKE A CHANNELIZED FLOW AND ESSENTIALLY CONVERT IT BACK TO A SHEET FLOW OVER THE GROUND SURFACE, THE SHEET FLOW WILL HAVE LESS CHANCE FOR EROSION CONSIDERING THE LOWER VELOCITIES AND FLOW VOLUMES IN ANY PARTICULAR AREA. THEY MAY BE CONSTRUCTED MUCH LIKE A SUMP WHERE THE CHANNEL OR CULVERT EMPTIES INTO THE SUMP AND THEN OVERTOPS THE BERMED AREA, BUT THEY MAY OFTEN CONTAIN GRAVEL IN THE SUMPED AREA, THEY WILL ALLOWS BE CONSTRUCTED ALONG THE GROUND CONTOUR







TYPICAL CULVERT & CULVERT INLET/OUTLET PROTECTION DETAIL

NOTES:
INLET AND OUTLET PROTECTION IS ESSENTIALLY GRAVELS AND/OR RIP RAP PLACED AT BOTH THE INLET AND OUTLET SIDES OF CULVERTS. THE GRAVELS WILL HELP TO SLOW THE FLOW OF WATER, AND DISSIPATE ENERGY. THIS WILL IN TURN DECREASE THE CHANCES OF EROSION AND ALSO ALLOW ANY SEDIMENT IN THE WATER TO SETTLE OUT.









GENERAL INFORMATION


THIS SHEET IS INTENDED TO BE PLOTTED ON ANSI D (22" X 34"). FOR REDUCTIONS, REFER TO GRAPHIC SCALE.

**O**Antero Midstream Partners LP


SMITHBURG TO MXP RESIDUE PIPELINE ESCP DETAILS

> PROPOSED 30" HIGH PRESSURE STEEL GAS LINE DODDRIDGE COUNTY, WEST VIRGINIA


SHEET 20 SHT. NAME: 050-6467\MXP\ESCP8



PLAN VIEW



36 TRIPLE STACK FILTER SOCK SEDIMENT TRAP



NOTES:
TEMPORARY SEDIMENT TRAPS ARE ESSENTIALLY SMALL SEDIMENT PONDS. THEY GIVE THE WATER A PLACE TO POOL AND SLOW DOWN THIS REDUCES THE CHANCES OF ADDITIONAL EROSION WHILE ALLOWING ANY SEDIMENT IN THE WATER TO SETTLE OUT. THE OUTLET IS DESIGNED OUT OF GRAVELS OF DIFFERENT DIMENSIONS WHICH




NOTES:

ON MOST LOCATIONS ANTERO WILL ALSO CONSTRUCT EROSION AND SEDIMENT (E&S) CONTROLS ABOVE AND BEYOND THE E&S CONTROLS LISTED ON THE PLAN SHEETS. THESE CONTROLS WILL BE CATEGORIZED AS PHASE I, PHASE II, AND PHASE III CONTROLS. THESE CONTROLS WILL BE INSTALLED TO BOTH PROVIDE EXTRA EAS PROTECTION, AND TO ELIMINATE THE CHANCES OF MATERIALS SUCH AS SOIL OR GRAVEL BEING PLACED IN A STREAM OR WETLAND. THE SITE PLANS AND DELINEATIONS ARE REVIEWED AND THESE CONTROLS ARE SPECIFIED IN ANTERO'S CONSTRUCTION RELEASE WHICH IS SENT OUT JUST PRIOR TO CONSTRUCTION BEGINNING. THE PHASE I, II, AND III CONTROLS WILL BE CONSTRUCTED AS FOLLOWS:



PHASE I:
THIS IS ESSENTIALLY ORANGE SAFETY FENCE LIKE SHOWN ABOVE. THIS MEASURE IS PUT IN PLACE TO LET CONTRACTORS KNOW THAT NO WORK IS TAKE PLACE BEYOND THIS POINT. THIS CONTROL IS TYPICALLY UTILIZED WHEN THERE IS A WETLAND OR STREAM LOCATED IN THE AREA BUT NOT WITHIN APPROXIMATELY 100 FEET OF THE DISTURBANCE.

38A SUPPLEMENTAL 404 CWA BMP CONTROLS
DETAIL PROVIDED BY ANTERO MIOSTREAM LLC



PHASE II:
THIS CONTROL CONSISTS OF TYPICAL SILT FENCE, SUPER SILT FENCE, OR FILTER SOXX. THIS CONTROL
WILL BE INSTALLED AS DESCRIBED IN THE PREVIOUS SECTIONS. THIS CONTROL WILL TYPICALLY BE
USED WHEN WETLANDS OR STREAMS ARE LOCATED WITHIN 100 FEET OF THE DISTURBED AREA.





PHASE III:
THIS CONTROL CONSISTS OF METAL Q-DECKING WHICH IS STOOD ON ITS EDGE AND SECURED TO METAL POSTS. THIS CONTROL IS USE TO PREVENT SOILS OR GRAVELS FROM ENTERING STREAMS OR WETLANDS DURING CONSTRUCTION. THE DECKING CAN BE BURIED OR USED IN CONJUNCTION WITH OTHER E&S METHODS. THIS CONTROL IS USED IN AREAS WHERE STREAMS OR WETLANDS ARE WITHIN APPROXIMATELY SO FEET OF THE DISTURBED AREA. IF THE METAL DECKING IS BURIED NO OTHER E&S
CONTROLS ARE REQUIRED, BUT IF THE DECKING IS PLACED ON TOP OF THE GROUND SURFACE AND ADDITIONAL E&S CONTROL SUCH AS SILT FENCE OR SILT SOXX WILL BE USED TO PROTECT THE GAPS BETWEEN THE BOTTOM OF THE DECKING AND THE UNEVEN GROUND SURFACE.

"NOTE THAT THE DISTANCES MENTIONED IN THE PHASE I, II, AND III CONTROLS ARE A GUIDELINE NOT A RULE FOR THE DECISION OF WHEN AND WHERE TO USE THESE



#### DEFINITIONS:

RIP RAP - LOOSE STONE USED TO FORM A FOUNDATION FOR A BREAKWATER OR OTHER STRUCTURE. THIS STONE IS TYPICALLY 3 INCHES OR GREATER IN DIAMETER.

FILTER CLOTH - TYPICALLY TYPAR OR ANOTHER SUCH MATERIAL (USUALLY WOVEN) WHICH IS DESIGNED TO ALLOW WATER TO FLOW BUT RETAIN SEDIMENT.

AGGREGATE - TERM USED TO IDENTIFY ANY TYPE SOLID DENSE MATERIAL USED DURING CONSTRUCTION TYPICALLY GRAVELS, SANDS, AND STONES.

EMBANKMENT - A WALL OR BANK OF EARTH OR STONE.

CLASS 1 RIP RAP - TYPICAL RIP RAP WITH STONES OF A DIAMETER BETWEEN 8 AND 18 INCHES.

39	DEFINITIONS	
	NTS	DETAIL PROVIDED BY ANTERO MIDSTREAM LLC

ISSUED FOR PERMITTING

**SUMMARY OF MATERIALS (3D) SUMMARY OF MATERIALS (3D)** DESCRIPTION **REVISION** DESCRIPTION

**GENERAL INFORMATION** 

THIS SHEET IS INTENDED TO BE PLOTTED ON ANSI D (22" X 34"). FOR REDUCTIONS, REFER TO GRAPHIC SCALE.





SMITHBURG TO MXP RESIDUE PIPELINE ESCP DETAILS

PROPOSED 30" HIGH PRESSURE STEEL GAS LINE DODDRIDGE COUNTY, WEST VIRGINIA

SHT. NAME: 050-6467\MXP\ESCP9

XX/XX/XXXX AFE # A05924





NOTE:

IF EVIDENCE OF A SEEP/SPRING IN A CUT SLOPE IS OBSERVED, THE CONTRACTOR SHOULD INSTALL A FRENCH DRAIN PER DETAIL 36 ABOVE.





SLOPE	6:1	5:1	4:1	3:1	2:1	1.5:1	1:1
Soll Stabilizer (gals/acre)	4	5	6	7	8	9	10
Fiber (lb/acre)	1,500	1,500	1,500	1,800	2,000	2,500	3,000

Maximum Rainfand for Site Win			
SLOPE	≤5:1	4:1	≥3:1
Soil Stabilizer (gals/acre)	6	8	10
Fiber (Ib/acre)	2,000	2,500	3,000

### NOTES:

A BONDED FIBER MATRIX (BMF) IS AN EFFECTIVE METHOD OF STABILIZING STEEP SLOPES WHEN USED PROPERLY. BMF8 MAKE USE OF A CROSS-LINKED HYDROCOLLOID TACKFIBER TO BOND THERMALLY PROCESSED WOOD FIBERS. APPLICATION RATES VARY ACCORDING TO SITE CONDITIONS. FOR SLOPES UP TO 3H:1V THE BFM SHOULD BE APPLIED AT A RATE OF 3,000 LB/ACRE. STEEPER SLOPES MAT NEED AS MUCH AS 4,000 LB/ACRE.


BFMs SHOULD ONLY BE USED WHEN NO RAIN IS FORECASTED FOR AT LEAST 48 HOURS FOLLOWING THE APPLICATION. THIS IS TO ALLOW THE TACKIFIER SUFFICIENT TIME TO CURE PROPERLY. ONCE PROPERLY APPLIED, A BRM IS TYPICALLY 90% EFFECTIVE IN PREVENTING ACCELERATED EROSION. BFMs SHOULD NOT BE APPLIED BETWEEN SEPTEMBER 30 AND APRIL 1.

A POLYMER STABILIZED FIBER MATRIX (PSFM) CAN ALSO BE AN EFFECTIVE METHOD OF STABILIZING STEEP SLOPES WHEN USED PROPERTY. PSFM® MAKE USE OF A LINEAR SOIL STABILIZING TACKIFIER THAT WORKS DIRECTLY ON SOIL TO MAINTAIN SOIL STRUCTURE, MAINTAIN PORE SPACE CAPACITY AND FLOCCULATE DISLODGED SEDIMENT THAT WILL SIGNIFICANTLY REDUCE RUNOFF TURBIDITY. PROPERLY APPLIED, A PSFM MAY BE AS MUCH AS 99% EFFECTIVE.

### NOTES:

UNLIKE ROLLED BLANKETS, THERE IS NO NEED TO SMOOTH THE SLOPE PRIOR TO APPLICATION OF HYDRAULICALLY APPLIED BLANKETS. IN FACT SOME ROUGHEINING OF THE SURFACE, EITHER NATURAL OR MECHANICALLY INDUCED, IS PREFERABLE, HOWEVER, LARGE ROCKS, THOSE >9 INCHES, AND EXISTING RILLS SHOULD BE REMOVED PRIOR TO APPLICATION. TRACKING OR GROOVING OF SLOPES SHOULD BE CONSIDERED TO SLOW WATER FLOWS DURING A STORM EVENT. SLOPE INTERRUPTION DEVICES SUCH AS STARS TEST GRADING OR BENCHING SHOULD BE APPLIED PRIOR TO THE APPLICATION. MIXING AND APPLICATION RATES SHOULD FOLLOW MANUFACTURER'S RECOMMENDATIONS.

HYDRAULICALLY APPLIED BLANKETS ARE TYPICALLY APPLIED IN TWO STAGES. UNLESS SPECIFICALLY RECOMMENDED TO BE APPLIED IN ONE APPLICATION BY THE MANUFACTURER, THE SEED MIXTURE AND SOIL AMENDMENTS SHOULD BE APPLIED FIRST. IF THE SEED IS APPLIED AT THE SAME TIME AS THE HYDRAULICALLY APPLIED BLANKET, THE BONDED FIBERS MAY KEEP THE SEED FROM MAXING SUFFICIENT CONTACT WITH THE SOIL TO GERMINATE AFTER THE SEED MIXTURE IS APPLIED, THE BFM, FGM, OR PSFM SHOULD BE SPRAYED OVER THE AREA AT THE REQUIRED APPLICATION RATE. (SEE ABOVE TABLES)




1. WHERE SPRINGS OR SEEPS ARE ENCOUNTERED DURING CONSTRUCTION, DRAINABLE FILL AND PERFORATED PIPES (FRENCH DRAINS) SHOULD BE INSTALLED TO PROVIDE A DRAINAGE PATH FOR SEEPAGE FROM THE EXISTING SLOPE.

2. THE FRENCH DRAIN SHOULD CONSIST OF A 6 INCH DIAMETER PERFORATED PIPE SURROUNDED BY DRAINABLE FILL, INSTALLED IN AN 18 INCH DEEP TRENCH ALONG THE EXISTING DRAINAGE FEATURE OR SEEP, PRIOR TO DRAINABLE FILL PLACEMENT, THE TRENCH SHOULD BE LINED WITH A LAYER OF GEOFABRIC SUCH AS MIRAFI 140N, OR APPROVED EQUAL, WITH SUFFICIENT OVERLAP TO PROVIDE AN ENVELOP AROUND THE PIPE TRENCH TO PREVENT THE MIGRATION OF FINES INTO THE FRENCH DRAIN.

3. THE FRENCH DRAIN SHOULD DAYLIGHT BEYOND THE TOE OR SIDE OF THE SLOPE AND EXTEND UP TO THE CREST OF THE SLOPE TO FACILITATE DRAINAGE THROUGH THE FILL SECTION. THE AS-BUILT WIDTH OF THE FRENCH DRAIN SHOULD BE A FUNCTION OF THE WIDTH OF THE SPRING, SEEP OR DRAINAGE FEATURE OBSERVED DURING CONSTRUCTION.

4.THE FRENCH DRAIN SHOULD BE CONSTRUCTED TO SPAN THE ENTIRE WIDTH OF THE OBSERVED SPRING OR SEEP.

FRENCH DRAIN AND DRAINABLE FILL SECTION AT OBSERVED SEEP/SPRING OR EXISTING DRAINAGE FEATURE LOCATION



NOTE:

DRAINAGE CHANNEL DIMENSIONS AND LINING WILL BE DETERMINED BY ENGINEER AS APPLICABLE

TYPICAL ROCK LINED CHANNEL

BONDED FIBER MATRIX (HYDROMULCH)

NTS

THRASHER

IFP
ISSUED FOR PERMITTING

AFE # A05924

SUMMARY OF MATERIALS (3D)

SUMMARY OF MATERIALS (3D)

NO. DESCRIPTION QTY

REVISION

NO. DESCRIPTION DATE BY

GENERAL INFORMATION

THIS SHEET IS INTENDED TO BE PLOTTED ON ANSI D (22" X 34"). FOR REDUCTIONS, REFER TO GRAPHIC SCALE.

Antero MidstreamPartners LP

SMITHBURG TO MXP RESIDUE PIPELINE ESCP DETAILS

PROPOSED 30" HIGH PRESSURE STEEL GAS LINE DODDRIDGE COUNTY, WEST VIRGINIA

6/7/2017 AFE No.:

AS \$100M1

D. R.A. (TTG)

AR, JRH (TTG)

SHEET 22

SHT. NAME: 050-6467\MXP\ESCP10

REV. 0

LAYOUT TAB: ESCP10